

National Inventory Document 2026 – Italian Greenhouse Gas Inventory 1990-2024

National Inventory Document 2026 – Italian Greenhouse Gas Inventory 1990-2024

ITALIAN GREENHOUSE GAS INVENTORY 1990-2024

NATIONAL INVENTORY DOCUMENT 2026

Legal Disclaimer

The Institute for Environmental Protection and Research (ISPRA), together with the 21 Regional Agencies (ARPA) and Provincial Agencies (APPA) for the protection of the environment, as of 14 January 2017 is part of the National Network System for the Protection of the Environment (SNPA), established by the Law June 28, 2016, n.132.

The Institute for Environmental Protection and Research, or persons acting on its behalf, are not responsible for the use that may be made of the information contained in this report.

ISPRA - Institute for Environmental Protection and Research

Via Vitaliano Brancati, 48 – 00144 Rome

www.isprambiente.gov.it

Extracts from this document may be reproduced on the condition that the source is acknowledged

ISPRA Rapporti, 428/26

ISBN 978-88-448-0348-3

Extracts from this document may be reproduced on the condition that the source is acknowledged

Graphic design

Cover design: Alessia Marinelli - ISPRA –Area Comunicazione Ufficio Grafica

Cover image: Graphic elaboration by Angela Fiore and Luisa Mortola from ESA/NASA-S. Cristoforetti Flickr photo 281B6475 taken from the International Space Station on 12/06/2022. Creative Commons CC BY-NC-SA 2.0

Coordination of the online publication:

ISPRA – Ufficio Grafica

April 2026

Annual Report for submission under the UN Framework Convention on Climate Change and the Paris Agreement

Authors

Marina Vitullo, Daniela Romano, Antonella Bernetti, Antonio Caputo, Marco Cordella, Eleonora Di Cristofaro, Angela Fiore, Andrea Gagna, Barbara Gonella, Federica Moricci, Guido Pellis, Ernesto Taurino,

INTRODUCTION

Daniela Romano

TRENDS IN GREENHOUSE GAS EMISSIONS

Marina Vitullo

ENERGY

Ernesto Taurino

Antonella Bernetti (§3.5)

Antonio Caputo (§3.10)

Marco Cordella (§3.5, §3.6)

INDUSTRIAL PROCESSES AND PRODUCT USE

Andrea Gagna

Barbara Gonella

Ernesto Taurino

Federica Moricci

Daniela Romano (§4.5, §4.8)

AGRICULTURE

Eleonora Di Cristofaro

Angela Fiore

LAND USE, LAND USE CHANGE AND FORESTRY

Marina Vitullo

Guido Pellis

WASTE

Barbara Gonella

Ernesto Taurino

RECALCULATIONS AND IMPROVEMENTS

Daniela Romano

ANNEXES

KEY CATEGORIES AND UNCERTAINTY

Daniela Romano

Antonio Caputo

Marina Vitullo

ENERGY CONSUMPTION FOR POWER GENERATION

Ernesto Taurino

ESTIMATION OF CARBON CONTENT OF COALS USED IN INDUSTRY

Ernesto Taurino

CO₂ REFERENCE APPROACH

Ernesto Taurino

NATIONAL EMISSION FACTORS

Antonio Caputo

Ernesto Taurino

AGRICULTURE SECTOR

Eleonora Di Cristofaro

Angela Fiore

FOR-EST MODEL

Guido Pellis

Marina Vitullo

FOR-FIRES MODEL

Guido Pellis

Marina Vitullo

Contact: Marina Vitullo
E-mail marina.vitullo@isprambiente.it

ISPRA- Institute for Environmental Protection and Research
Environmental Assessment, Control and Sustainability Department
Emissions, Prevention of Atmospheric Impacts and Climate Change Area
Air Emission Inventory Unit
Via V. Brancati, 48 00144 Rome – Italy

Quote as/Citare come segue:

ISPRA (2026), Italian greenhouse gas Inventory 1990 – 2024 – National Inventory Document 2026.
Rapporti n. 428/26, ISPRA, Roma.

INDICE

Executive summary	1
Sommario (Italian)	8
1 INTRODUCTION	9
1.1 Background information on greenhouse gas inventories and climate change	9
1.2 Description of the institutional arrangement for inventory preparation	12
1.2.1 National Inventory System	12
1.3 Brief description of the process of inventory preparation	14
1.4 Brief general description of methodologies and data sources used	15
1.5 Brief description of key categories	20
1.6 Information on the QA/QC plan including verification and treatment of confidentiality issues where relevant	25
1.7 General uncertainty evaluation, including data on the overall uncertainty for the inventory totals	28
1.8 General assessment of the completeness	29
2 TRENDS IN GREENHOUSE GAS EMISSIONS	31
2.1 Description and interpretation of emission trends for aggregate greenhouse gas emissions	31
2.2 Description and interpretation of emission trends by gas	34
2.2.1 Carbon dioxide emissions	34
2.2.2 Methane emissions	35
2.2.3 Nitrous oxide emissions	36
2.2.4 Fluorinated gas emissions	37
2.3 Description and interpretation of emission trends by source	38
2.3.1 Energy	38
2.3.2 Industrial processes and product use	39
2.3.3 Agriculture	40
2.3.4 LULUCF	42
2.3.5 Waste	42
2.3.6 Indirect CO ₂ emissions	44
2.4 Description and interpretation of emission trends for indirect greenhouse gases and SO ₂	44
2.5 Indirect CO ₂ and nitrous oxide emissions	45
3 ENERGY	47
3.1 Sector overview	47
3.2 Methodology description	53
3.3 Energy industries	56
3.3.1 Public Electricity and Heat Production	56
3.3.1.1. Source category description	56
3.3.1.2. Methodological issues	57
3.3.1.3. Uncertainty and time-series consistency	58
3.3.1.4. Source-specific QA/QC and verification	58
3.3.1.5. Source-specific recalculations	58

3.3.1.6. <i>Source-specific planned improvements</i>	58
3.3.2 Refineries	58
3.3.2.1. <i>Source category description</i>	58
3.3.2.2. <i>Methodological issues</i>	58
3.3.2.3. <i>Uncertainty and time-series consistency</i>	59
3.3.2.4. <i>Source-specific QA/QC and verification</i>	60
3.3.2.5. <i>Source-specific recalculations</i>	60
3.3.2.6. <i>Source-specific planned improvements</i>	60
3.3.3 Manufacture of Solid Fuels and Other Energy Industries	60
3.3.3.1. <i>Source category description</i>	60
3.3.3.2. <i>Methodological issues</i>	61
3.3.3.3. <i>Uncertainty and time-series consistency</i>	61
3.3.3.4. <i>Source-specific QA/QC and verification</i>	62
3.3.3.5. <i>Source-specific recalculations</i>	62
3.3.3.6. <i>Source-specific planned improvements</i>	62
3.4 Manufacturing industries and construction	62
3.4.1 Sector overview	62
3.4.2 Source category description	64
3.4.3 Methodological issues	66
3.4.4 Uncertainty and time-series consistency	70
3.4.5 Source-specific QA/QC and verification	71
3.4.6 Source-specific recalculations	71
3.4.7 Source-specific planned improvements	71
3.5 Transport	72
3.5.1 Aviation	72
3.5.1.1. <i>Source category description</i>	72
3.5.1.2. <i>Methodological issues</i>	73
3.5.1.3. <i>Uncertainty and time-series consistency</i>	75
3.5.1.4. <i>Source-specific QA/QC and verification</i>	75
3.5.1.5. <i>Source-specific recalculations</i>	76
3.5.1.6. <i>Source-specific planned improvements</i>	76
3.5.2 Road Transport	76
3.5.2.1. <i>Source category description</i>	76
3.5.2.2. <i>Methodological issues</i>	77
3.5.2.3. <i>Fuel-based emissions</i>	77
3.5.2.4. <i>Biofuels used and fossil fuel fraction in biodiesel</i>	80
3.5.2.5. <i>The fuel balance process</i>	81
3.5.2.6. <i>Traffic-based emissions</i>	81
3.5.2.7. <i>Uncertainty and time-series consistency</i>	88
3.5.2.8. <i>Source-specific QA/QC and verification</i>	89

3.5.2.9. <i>Source-specific recalculations</i>	89
3.5.2.10. <i>Source-specific planned improvements</i>	91
3.5.3 Railways	91
3.5.4 Navigation	91
3.5.4.1. <i>Source category description</i>	91
3.5.4.2. <i>Methodological issues</i>	92
3.5.4.3. <i>Uncertainty and time-series consistency</i>	93
3.5.4.4. <i>Source-specific QA/QC and verification</i>	93
3.5.4.5. <i>Source-specific recalculations</i>	94
3.5.4.6. <i>Source-specific planned improvements</i>	94
3.5.5 Other transportation	94
3.5.5.1. <i>Source category description</i>	94
3.5.5.2. <i>Methodological issues</i>	94
3.5.5.3. <i>Uncertainty and time-series consistency</i>	94
3.5.5.4. <i>Source-specific QA/QC and verification</i>	95
3.5.5.5. <i>Source-specific recalculations</i>	95
3.5.5.6. <i>Source-specific planned improvements</i>	95
3.6 Other sectors	95
3.6.1 Sector overview	95
3.6.2 Source category description	96
3.6.3 Methodological issues	97
3.7 Other	99
3.7.1 Uncertainty and time-series consistency	100
3.7.2 Source-specific QA/QC and verification	101
3.7.3 Source-specific recalculations	101
3.7.4 Source-specific planned improvements	101
3.8 International bunkers	101
3.9 Feedstock and non-energy use of fuels	102
3.9.1 Source category description	102
3.9.2 Methodological issues	102
3.9.3 Uncertainty and time-series consistency	103
3.9.4 Source-specific QA/QC and verification	104
3.9.5 Source-specific recalculations	104
3.10 Fugitive emissions from solid fuels, oil and natural gas	105
3.10.1 Source category description	105
3.10.2 Methodological issues	105
3.10.3 Uncertainty and time-series consistency	112
3.10.4 Source-specific QA/QC and verification	113
3.10.5 Source-specific recalculations	114
3.10.6 Source-specific planned improvements	115

4 INDUSTRIAL PROCESSES AND PRODUCT USE	116
4.1 Sector overview	116
4.2 Mineral Products (2A)	119
4.2.1 Source category description	119
4.2.2 Methodological issues	121
4.2.3 Uncertainty and time-series consistency	126
4.2.4 Source-specific QA/QC and verification	127
4.2.5 Source-specific recalculations	127
4.2.6 Source-specific planned improvements	127
4.3 Chemical industry (2B)	128
4.3.1 Source category description	128
4.3.2 Methodological issues	131
4.3.3 Uncertainty and time-series consistency	138
4.3.4 Source-specific QA/QC and verification	140
4.3.5 Source-specific recalculations	140
4.3.6 Source-specific planned improvements	140
4.4 Metal production (2C)	140
4.4.1 Source category description	140
4.4.2 Methodological issues	142
4.4.3 Uncertainty and time-series consistency	148
4.4.4 Source-specific QA/QC and verification	149
4.4.5 Source-specific recalculations	149
4.4.6 Source-specific planned improvements	149
4.5 Non-energy products from fuels and solvent use (2D)	149
4.5.1 Source category description	149
4.5.2 Methodological issues	150
4.5.3 Uncertainty and time-series consistency	152
4.5.4 Source-specific QA/QC and verification	153
4.5.5 Source-specific recalculations	154
4.5.6 Source-specific planned improvements	155
4.6 Electronics Industry (2E)	155
4.6.1 Source category description	155
4.6.2 Methodological issues	155
4.6.3 Uncertainty and time-series consistency	156
4.6.4 Source-specific QA/QC and verification	157
4.6.5 Source-specific recalculations	157
4.6.6 Source-specific planned improvements	157
4.7 Fluorinated substitutes for ozone depleting substances (2F)	157
4.7.1 Source category description	157
4.7.2 Methodological issues	158

4.7.3	Commercial refrigeration (2.F.1.a)	162
4.7.4	Domestic refrigeration (2.F.1.b)	166
4.7.5	Industrial refrigeration (2.F.1.c)	168
4.7.6	Transport refrigeration (2.F.1.d)	171
4.7.7	Mobile air conditioning (2.F.1.e)	173
4.7.8	Stationary Air Conditioning (2.F.1.f)	175
4.7.9	Foam blowing (2.F.2)	184
4.7.10	Fire protection (2.F.3)	185
4.7.11	Aerosol (2.F.4)	188
4.7.12	Uncertainty and time-series consistency	189
4.7.13	Source-specific QA/QC and verification	192
4.7.14	Source-specific recalculation	193
4.7.15	Source-specific planned improvements	193
4.8	Other product manufacture and use (2G)	194
4.8.1	Source category description	194
4.8.2	Methodological issues	194
4.8.3	Uncertainty and time series consistency	197
4.8.4	Source-specific QA/QC and verification	198
4.8.5	Source-specific recalculation	198
4.8.6	Source-specific Planned improvements	198
4.9	Other production (2H)	199
4.9.1	Source category description	199
5	AGRICULTURE	200
5.1	Sector overview	200
5.1.1	Emission trends	200
5.1.2	Key categories	202
5.1.3	Activities	202
5.1.4	Agricultural statistics	203
5.2	Enteric fermentation (3A)	205
5.2.1	Source category description	205
5.2.2	Methodological issues	205
5.2.3	Uncertainty and time-series consistency	213
5.2.4	Source-specific QA/QC and verification	214
5.2.5	Source-specific recalculations	214
5.2.6	Source-specific planned improvements	216
5.3	Manure management (3B)	216
5.3.1	Source category description	216
5.3.2	Methodological issues	216
5.3.3	Uncertainty and time-series consistency	230
5.3.4	Source-specific QA/QC and verification	231

5.3.5	Source-specific recalculations	232
5.3.6	Source-specific planned improvements	235
5.4	Rice cultivation (3C)	237
5.4.1	Source category description	237
5.4.2	Methodological issues	237
5.4.3	Uncertainty and time-series consistency	241
5.4.4	Source-specific QA/QC and verification	242
5.4.5	Source-specific recalculations	242
5.4.6	Source-specific planned improvements	242
5.5	Agriculture soils (3D)	242
5.5.1	Source category description	242
5.5.2	Methodological issues	243
5.5.3	Uncertainty and time-series consistency	251
5.5.4	Source-specific QA/QC and verification	251
5.5.5	Source-specific recalculations	253
5.5.6	Source-specific planned improvements	255
5.6	Field burning of agriculture residues (3F)	256
5.6.1	Source category description	256
5.6.2	Methodological issues	256
5.6.3	Uncertainty and time-series consistency	258
5.6.4	Source-specific QA/QC and verification	259
5.6.5	Source-specific recalculations	259
5.6.6	Source-specific planned improvements	259
5.7	Liming (3G)	259
5.7.1	Source category description	259
5.7.2	Methodological issues	259
5.7.3	Uncertainty and time-series consistency	260
5.7.4	Source-specific QA/QC and verification	260
5.7.5	Source-specific recalculations	260
5.7.6	Source-specific planned improvements	260
5.8	Urea application (3H)	260
5.8.1	Source category description	260
5.8.2	Methodological issues	261
5.8.3	Uncertainty and time-series consistency	261
5.8.4	Source-specific QA/QC and verification	261
5.8.5	Source-specific recalculations	261
5.8.6	Source-specific planned improvements	261
5.9	Other carbon-containing fertilizers (3I)	261
5.9.1	Source category description	261
5.9.2	Methodological issues	262

5.9.3	Uncertainty and time-series consistency	262
5.9.4	Source-specific QA/QC and verification	262
5.9.5	Source-specific recalculations	262
5.9.6	Source-specific planned improvements	263
6	LAND USE, LAND USE CHANGE AND FORESTRY	264
6.1	Sector overview	264
6.2	Forest Land (4A)	269
6.2.1	Description	269
6.2.2	Information on approaches used for representing land areas and on land-use databases used for the inventory preparation	269
6.2.3	Land-use definitions and the classification systems used and their correspondence to the LULUCF categories	270
6.2.4	Methodological issues	270
6.2.5	Uncertainty and time series consistency	276
6.2.6	Category-specific QA/QC and verification	277
6.2.7	Category-specific recalculations	280
6.2.8	Category-specific planned improvements	281
6.3	Cropland (4B)	281
6.3.1	Description	281
6.3.2	Information on approaches used for representing land areas and on land-use databases used for the inventory preparation	282
6.3.3	Land-use definitions and the classification systems used and their correspondence to the LULUCF categories	282
6.3.4	Methodological issues	282
6.3.5	Uncertainty and time series consistency	288
6.3.6	Category-specific QA/QC and verification	288
6.3.7	Category-specific recalculations	288
6.3.8	Category-specific planned improvements	290
6.4	Grassland (4C)	290
6.4.1	Description	290
6.4.2	Information on approaches used for representing land areas and on land-use databases used for the inventory preparation	290
6.4.3	Land-use definitions and the classification systems used and their correspondence to the LULUCF categories	290
6.4.4	Methodological issues	291
6.4.5	Uncertainty and time series consistency	296
6.4.6	Category-specific QA/QC and verification	296
6.4.7	Category-specific recalculations	297
6.4.8	Category-specific planned improvements	298
6.5	Wetlands (4D)	298
6.5.1	Description	298

6.5.2	Information on approaches used for representing land areas and on land-use databases used for the inventory preparation	298
6.5.3	Land-use definitions and the classification systems used and their correspondence to the LULUCF categories	298
6.5.4	Methodological issues	299
6.5.5	Uncertainty and time series consistency	299
6.5.6	Category-specific QA/QC and verification	300
6.5.7	Category-specific recalculations	300
6.5.8	Category-specific planned improvements	300
6.6	Settlements (4E)	300
6.6.1	Description	300
6.6.2	Information on approaches used for representing land areas and on land-use databases used for the inventory preparation	300
6.6.3	Land-use definitions and the classification systems used and their correspondence to the LULUCF categories	300
6.6.4	Methodological issues	301
6.6.5	Uncertainty and time series consistency	303
6.6.6	Category-specific QA/QC and verification	303
6.6.7	Category-specific recalculations	303
6.6.8	Category -specific planned improvements	304
6.7	Other Land (4F)	304
6.8	Direct and indirect N ₂ O emissions from N inputs to managed soils (4(I))	304
6.9	Emissions and removals from drainage and rewetting and other management of organic and mineral soils (4(II))	305
6.9.1	Description	305
6.9.2	Methodological issues	305
6.9.3	Uncertainty	307
6.9.4	Category-specific recalculations	307
6.10	Direct and indirect N ₂ O emissions from N mineralization/immobilization associated with loss/gain of soil organic matter resulting from change of land use or management of mineral soils (4(III))	308
6.10.1	Direct N ₂ O emissions from N mineralization/immobilization	308
6.10.1.1	Description	308
6.10.1.2	Methodological issues	308
6.10.1.3	Category-specific recalculations	309
6.10.2	Indirect N ₂ O emissions from N mineralization/immobilization	310
6.10.2.1	Description	310
6.10.2.2	Methodological issues	310
6.10.2.3	Category-specific recalculations	310
6.11	Biomass Burning (4(IV))	311
6.11.1	Description	311
6.11.2	Methodological issues	311

6.11.3	Uncertainty and time series consistency	312
6.11.4	Category-specific QA/QC and verification	312
6.11.5	Category-specific recalculations	313
6.11.6	Category-specific planned improvements	314
6.12	Harvested wood products (HWP) (4G)	314
6.12.1	Description	314
6.12.2	Methodological issues	314
6.12.3	Uncertainty and time series consistency	315
6.12.4	Category-specific QA/QC and verification	315
6.12.5	Category-specific recalculations	315
6.12.6	Category-specific planned improvements	316
7	WASTE	317
7.1	Sector overview	317
7.2	Solid waste disposal on land (5A)	318
7.2.1	Source category description	318
7.2.2	Methodological issues	319
7.2.3	Uncertainty and time-series consistency	331
7.2.4	Source-specific QA/QC and verification	331
7.2.5	Source-specific recalculations	334
7.2.6	Source-specific planned improvements	335
7.3	Biological treatment of solid waste (5B)	335
7.3.1	Source category description	335
7.3.2	Methodological issues	335
7.3.3	Uncertainty and time-series consistency	337
7.3.4	Source-specific QA/QC and verification	337
7.3.5	Source-specific recalculations	337
7.3.6	Source-specific planned improvements	337
7.4	Waste incineration (5C)	338
7.4.1	Source category description	338
7.4.2	Methodological issues	338
7.4.3	Uncertainty and time-series consistency	343
7.4.4	Source-specific QA/QC and verification	344
7.4.5	Source-specific recalculations	344
7.4.6	Source-specific planned improvements	345
7.5	Wastewater handling (5D)	345
7.5.1	Source category description	345
7.5.2	Methodological issues	347
7.5.3	Uncertainty and time-series consistency	353
7.5.4	Source-specific QA/QC and verification	354
7.5.5	Source-specific recalculations	355

7.5.6	Source-specific planned improvements	355
8	RECALCULATIONS AND IMPROVEMENTS	356
8.1	Explanations and justifications for recalculations	356
8.2	Implications for emission levels	356
8.3	Implications for emission trends, including time series consistency	357
8.4	Recalculations, response to the review process and planned improvements	357
8.4.1	Recalculations	357
8.4.2	Response to the UNFCCC review process	360
8.4.3	Planned improvements (e.g., institutional arrangements, inventory preparation)	360
9	REFERENCES	362
9.1	INTRODUCTION and TRENDS IN GREENHOUSE GAS EMISSIONS	362
9.2	ENERGY	362
9.3	INDUSTRIAL PROCESSES AND PRODUCT USE	364
9.4	AGRICULTURE	369
9.5	LAND USE, LAND USE CHANGE AND FORESTRY	379
9.6	WASTE	383
9.7	ANNEX 1	388
9.8	ANNEX 2	388
9.9	ANNEX 3	388
9.10	ANNEX 4	388
9.11	ANNEX 5	388
9.12	ANNEX 6	389
9.13	ANNEX 7	389
9.14	ANNEX 11	392
9.15	ANNEX 12	392
ANNEX 1:	KEY CATEGORIES AND UNCERTAINTY	393
A1.1	Introduction	393
A1.2	Approach 1 key category assessment	393
A1.3	Uncertainty assessment (IPCC Approach 1)	400
A1.4	Approach 2 key category assessment	414
ANNEX 2:	ENERGY CONSUMPTION FOR POWER GENERATION	421
A2.1	Source category description	421
A2.2	Methodological issues	422
A2.3	Uncertainty and time-series consistency	423
A2.4	Source-specific QA/QC and verification	424
A2.5	Source-specific recalculations	424
A2.6	Source-specific planned improvements	424
ANNEX 3:	ESTIMATION OF CARBON CONTENT OF COALS USED IN INDUSTRY	425
ANNEX 4:	CO₂ REFERENCE APPROACH	429
A4.1	Introduction	429
A4.2	Comparison of the sectoral approach with the reference approach	429
A4.3	Comparison of the sectoral approach with the reference approach and international statistics	

ANNEX 5: NATIONAL ENERGY BALANCE, YEAR 2024	432
ANNEX 6: NATIONAL EMISSION FACTORS	433
A6.1 Natural gas	433
A6.2 Diesel oil, petrol and LPG	435
A6.3 Fuel oil	436
A6.4 Coal	436
A6.5 Other fuels	438
ANNEX 7: AGRICULTURE SECTOR	445
A7.1 Enteric fermentation (3A)	445
A7.2 Manure management (3B)	453
A7.3 Agricultural soils (3D)	459
ANNEX 8: ADDITIONAL INFORMATION OF THE ANNUAL INVENTORY SUBMISSION	469
A8.1 Annual inventory submission	469
ANNEX 9: OVERVIEW OF THE CURRENT SUBMISSION IMPROVEMENTS	482
A9.1 Results of the UNFCCC review process	482
A9.2 Results of the latest EU-internal inventory review process	482
ANNEX 10: REPORTING UNDER EU REGULATION 2024/1281	496
A10.1 Consistency with ETS data	496
A10.2 Consistency with energy statistics	499
ANNEX 11: FOR-EST MODEL	501
ANNEX 12: FOR-FIRES MODEL	509
A12.1 Method description	509
A12.2 Activity data	510
A12.3 Methodological issues	511

PREMESSA

Nell'ambito delle politiche e degli strumenti finalizzati al contrasto dei cambiamenti climatici, il monitoraggio delle emissioni di gas serra riveste un ruolo fondamentale.

In Italia, la predisposizione e l'aggiornamento annuale dell'inventario nazionale dei gas serra, secondo i formati richiesti a livello internazionale, sono affidati all'ISPRA su incarico del Ministero dell'Ambiente e della Sicurezza Energetica. Tale attività è disciplinata dal Decreto Legislativo n. 51 del 7 marzo 2008 e dal Decreto Legislativo n. 30 del 13 marzo 2013, che prevedono l'istituzione di un Sistema Nazionale (*National System*) per l'inventario delle emissioni di gas serra.

Inoltre, come previsto dalla Convenzione quadro sui cambiamenti climatici e dall'Accordo di Parigi, l'ISPRA illustra in un apposito rapporto, il *National Inventory Document*, le metodologie di stima adottate, fornendo anche una spiegazione degli andamenti delle emissioni osservati nel tempo.

Il *National Inventory Document* facilita i processi internazionali di verifica cui le stime ufficiali di emissione dei gas serra sono sottoposte. In particolare, viene esaminata la rispondenza alle proprietà di trasparenza, consistenza, comparabilità, completezza e accuratezza nella realizzazione, qualità richieste esplicitamente dalla Convenzione suddetta. L'inventario delle emissioni è sottoposto ogni anno ad un esame (*review*) da parte di un organismo nominato dal Segretariato della Convenzione che analizza tutto il materiale presentato dal Paese e ne verifica in dettaglio le qualità su enunciate.

Questo rapporto, accompagnato dalle relative tabelle, costituisce la comunicazione ufficiale dell'Italia in adempimento agli obblighi della Convenzione e dell'Accordo di Parigi per quanto riguarda l'inventario nazionale dei gas serra.

Inoltre, il documento rappresenta un riferimento fondamentale per la pianificazione e l'attuazione di tutte le politiche ambientali da parte delle istituzioni centrali e periferiche.

Oltre all'inventario nazionale dei gas serra, l'ISPRA redige annualmente anche l'inventario nazionale delle emissioni in atmosfera, richiesto dalla Convenzione di Ginevra sull'inquinamento atmosferico transfrontaliero a lunga distanza (UNECE-CLRTAP) e dalle direttive europee volte alla limitazione delle emissioni. Inoltre, l'intero territorio nazionale è attualmente coperto da inventari regionali delle emissioni, generalmente coerenti con l'inventario nazionale, elaborati principalmente dalle Agenzie Regionali e Provinciali per la Protezione dell'Ambiente.

Nonostante i progressi compiuti, l'attività di preparazione degli inventari continua ad affrontare nuove sfide legate alla necessità di considerare nuove sorgenti e nuovi inquinanti e di armonizzare gli inventari prodotti per diverse finalità di *policy*. Il contesto internazionale al quale fa riferimento la preparazione dell'inventario nazionale costituisce una garanzia di qualità dei dati, per l'autorevolezza dei riferimenti metodologici, l'efficacia del processo internazionale di *review* e la flessibilità nell'adattamento alle nuove circostanze.

Executive summary

ES.1. Background information on greenhouse gas inventories and climate change

The United Nations Framework Convention on Climate Change (FCCC) was ratified by Italy in the year 1994 through law no.65 of 15/01/1994.

The Kyoto Protocol, adopted in December 1997, has established emission reduction objectives for Annex B Parties (i.e., industrialised countries and countries with economy in transition): in particular, the European Union as a whole was committed to an 8% reduction within the period 2008-2012, in comparison with base year levels. For Italy, the EU burden sharing agreement, set out in Annex II to Decision 2002/358/EC and in accordance with Article 4 of the Kyoto Protocol, had established a reduction objective of 6.5% in the commitment period, in comparison with 1990 levels.

A new global agreement was reached in Paris in December 2015, for the period after 2020. The agreement aims to strengthen the global response to the threat of climate change by holding the increase in the global temperature to well below 2°C above pre-industrial levels and to pursue efforts to limit the temperature increase to 1.5 °C above pre-industrial levels, recognizing that this would significantly reduce the risks and impact of climate change. On 5th October 2016, the threshold for entry into force of the Paris Agreement was achieved and the Paris Agreement entered into force on 4th November 2016.

To fulfil the gap 2013-2020, the 'Doha Amendment to the Kyoto Protocol' was adopted on 8th December 2012. The EU and its Member States had committed to this second phase of the Kyoto Protocol and established to reduce their collective emissions to 20% below their levels in 1990 or other chosen base years; this was also reflected in the Doha Amendment. The target was to be fulfilled jointly with Iceland.

Italy was in compliance with the targets of both the Kyoto phases.

As a Party to the Convention and the Paris Agreement, Italy is committed to develop, publish and regularly update national emission inventories of greenhouse gases (GHGs) as well as formulate and implement programs to reduce these emissions.

To meet national and international reporting obligations, the national greenhouse gas (GHG) emissions inventory is compiled each year by the Institute for Environmental Protection and Research (ISPRA) and submitted to the relevant authorities following approval by the Ministry of the Environment and Energy Security (MASE). The submission is made through the completion of the Common Reporting Tables (CRTs) in accordance with the guidelines established under the United Nations Framework Convention on Climate Change. An annual GHG inventory submission comprises two main components: a National Inventory Document (NID) and the Common Reporting Tables (CRTs), as outlined in the Annex to Decision 18/CMA.1, which sets the modalities, procedures, and guidelines for the transparency framework for action and support under Article 13 of the Paris Agreement (FCCC/PA/CMA/2018/3/Add.2).

Detailed information on emission figures and estimation procedures, including all the basic data needed to carry out the final estimates, is to be provided to improve the transparency, consistency, comparability, accuracy, and completeness of the inventory provided.

The national inventory is updated annually to reflect revisions and improvements in the methodology and use of the best information available. Adjustments are applied retrospectively to earlier years, which accounts for any difference in previously published data.

This report provides an analysis of the Italian GHG emission inventory from 1990 to 2024.

Emission estimates comprise seven direct greenhouse gases under the Convention (carbon dioxide, methane, nitrous oxide, hydrofluorocarbons, perfluorocarbons, sulfur hexafluoride, nitrogen trifluoride) which contribute directly to climate change owing to their positive radiative forcing effect and four indirect greenhouse gases (nitrogen oxides, carbon monoxide, non-methane volatile organic compounds, sulfur dioxide). Italy uses the 100-year time-horizon global warming potential values, excluding the value for fossil methane, listed in Table 8.A.1 in the contribution of Working Group I to the Fifth Assessment

Report of the Intergovernmental Panel on Climate Change¹, following COP27 decision taken in 2022 on the 'Revision of the UNFCCC reporting guidelines on annual inventories for Parties included in Annex I to the Convention'.

This report, the CRT files and other related documents are available on website at the address <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.

The last official inventory submissions can be found at the UNFCCC website <https://unfccc.int/ghg-inventories-annex-i-parties/2025>.

The present submission has been communicated to the UNFCCC and the European Union according to the Regulation (EU) 2018/1999 of the European Parliament and of the Council of 11 December 2018 on the Governance of the Energy Union and Climate Action; it will be available on the UNFCCC website.

ES.2. Summary of national emission and removal related trends

Total greenhouse gas emissions, in CO₂ equivalent, excluding emissions and removals from land use, land use change and forestry, decreased by 30.2% between 1990 and 2024, varying from 521 to 363 CO₂ equivalent million tons (Mt).

CO₂, the most significant greenhouse gas, represents 81.4% of total emissions in CO₂ equivalent and has declined by 31.9% between 1990 and 2024. In the same year, CH₄ and N₂O contributed 11.8% and 3.8% of total CO₂ equivalent emissions, respectively. Between 1990 and 2024, CH₄ emissions fell by 21.8%, while N₂O emissions decreased by 39.0%. Other greenhouse gases account for smaller shares: HFCs make up 1.8% of total emissions, PFCs and SF₆ each represent about 0.1%, and NF₃ contributes less than 0.01%.

Tables ES.1 and ES.2 illustrate the national trend of greenhouse gases for 1990-2024, expressed in CO₂ equivalent terms, by gas and sector, respectively.

¹ IPCC, 2013. Climate Change 2013: The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change. TF Stocker, D Qin, G-K Plattner, et al. (eds.). Cambridge and New York: Cambridge University Press. Available at <http://www.ipcc.ch/report/ar5/wg1>

Table ES.1. Total greenhouse gas emissions and removals in CO₂ equivalent by gas [kt CO₂ eq]

GHG emissions	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ equivalent</i>										
CO ₂ excluding net CO ₂ from LULUCF	438,208	448,596	469,598	501,365	434,573	359,658	300,706	334,095	336,796	309,321	298,490
CO ₂ including net CO ₂ from LULUCF	423,941	413,046	438,806	456,835	387,059	311,845	256,426	288,796	291,187	251,103	233,880
CH ₄ excluding CH ₄ from LULUCF	55,016	57,139	57,833	54,793	52,784	49,089	47,054	46,565	45,120	44,269	43,003
CH ₄ including CH ₄ from LULUCF	55,843	57,411	58,331	55,062	53,078	49,328	47,327	47,159	45,593	44,620	43,273
N ₂ O excluding N ₂ O from LULUCF	22,603	24,213	25,018	24,404	16,631	15,091	15,277	15,210	13,558	14,268	13,789
N ₂ O including N ₂ O from LULUCF	23,094	24,468	25,331	24,609	16,850	15,220	15,503	15,621	13,909	14,570	14,061
HFCs	372	1,100	3,748	9,669	12,790	11,786	9,415	8,806	8,279	7,726	6,670
PFCs	2,615	1,351	1,363	1,759	1,377	1,540	516	413	462	297	280
Unspecified mix of HFCs and PFCs	NA,NO	24	24	24	24	24	22	25	22	29	33
SF ₆	421	700	621	565	405	483	252	282	405	367	328
NF ₃	NA,NO	77	13	33	20	28	16	15	20	20	26
Indirect CO ₂	1,391	1,296	1,173	1,155	976	815	876	858	790	843	871
Total (excluding LULUCF, with CO₂ indirect)	520,626	534,495	559,393	593,769	519,581	438,515	374,134	406,270	405,451	377,139	363,490
Total (including LULUCF, with CO₂ indirect)	507,677	499,472	529,411	549,712	472,579	391,070	330,352	361,976	360,667	319,575	299,422

Table ES.2. Total greenhouse gas emissions and removals in CO₂ equivalent by sector [kt CO₂ eq]

GHG categories	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
<i>kt CO₂ equivalent</i>											
1. Energy	426,248	438,789	460,604	488,371	428,785	358,354	298,120	330,181	333,377	305,141	294,526
2. Industrial Processes and Product Use	37,946	36,299	38,240	47,135	36,579	28,803	23,736	24,712	22,830	21,692	20,107
3. Agriculture	36,045	36,103	35,280	33,039	30,753	30,169	30,881	30,226	28,346	29,283	28,009
4. LULUCF	-12,949	-35,023	-29,981	-44,057	-47,002	-47,445	-43,782	-44,294	-44,784	-57,565	-64,068
5. Waste	18,996	22,008	24,094	24,069	22,488	20,373	20,521	20,293	20,108	20,180	19,977
6. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Indirect CO ₂ emissions	1,391	1,296	1,173	1,155	976	815	876	858	790	843	871
Total (including LULUCF)	507,677	499,472	529,411	549,712	472,579	391,070	330,352	361,976	360,667	319,575	299,422

ES.3. Overview of source and sink category emission estimates and trends

The energy sector is the largest contributor to national total GHG emissions with a share, in 2024, of 81.0%. GHG emissions from this sector decreased by 30.9% from 1990 to 2024. Substances with decrease rates were CO₂, whose levels reduced by 30.2% from 1990 to 2024 and accounts for 97.0% of the total in the energy sector, and CH₄ which showed a reduction of 58.9% but its share out of the sectoral total is only 1.8%; N₂O showed a decrease of 15.4% from 1990 to 2024, accounting for 1.2%. Specifically, in terms of total CO₂ equivalent, an increase in emissions was observed only in the transport sector (38.5% of the total energy emissions), equal to 10.9% from 1990 to 2024.

The industrial processes and product use sector accounts, in 2024, for 5.5% of total greenhouse gas emissions excluding LULUCF. Emissions showed a decrease of 47.0% from 1990 to 2024. Specifically, by substance, CO₂ accounts for 62.5% and showed a decrease by 54.8%, CH₄ decreased by 78.7%, but it accounts only for 0.1% in 2024, while N₂O, whose levels share 2.4% of total industrial emissions, decreased by 92.3%. The decrease in emissions is mostly due to a decrease in the chemical industry (due to the fully operational abatement technology in the adipic acid industry) and mineral and metal production emissions. A considerable increase was observed in F-gases emissions, whose level on total sectoral emissions is about 35.0%.

The agriculture sector accounts for 7.7% of total emissions excluding LULUCF. Emissions refer mainly to CH₄ and N₂O levels, which account for 69.2% and 29.2% of the sectoral total, respectively; accounts for the remaining 1.6% of total emissions. The decrease observed in the total GHG level of emissions (-22.3%) is mostly due to the decrease of CH₄ emissions from enteric fermentation (-21.5%) and manure management (-22.8%). The decrease of N₂O (-25.2%) from agricultural soils; in 2024 these categories account for 48.2%, 21.3% and 22.5% of the total sectoral emissions, respectively.

As regards land use, land-use change and forestry, from 1990 to 2024 total removals in CO₂ equivalent considerably increased. CO₂ accounts for 99.2% of total emissions and removals of the sector, as absolute weight. The key driver for the rise in removals is the increase of carbon stock in forest land.

Finally, emissions from the waste sector contribute to 5.5% to total emissions without LULUCF; their level increased by 5.2% from 1990 to 2024. The trend is mainly driven by the increase in emissions from solid waste disposal (12.8%), accounting for 77.2% of the sectoral total in 2024, counterbalanced by the decrease of emissions from waste-water treatment (-17.3%), accounting for 19.5%. Considering emissions by gas, the most important greenhouse gas is CH₄ which accounts for 91.4% of the sectoral total and

shows an increase of 5.4% from 1990 to 2024. N₂O levels have increased by 40.8% while CO₂ decreased by 85.1%; in 2024, these gases account for 8.3% and 0.4%, respectively.

Indirect CO₂ emissions refer to the atmospheric oxidation of NMVOC emissions from solvents and other products use. These emissions have decreased by 37.4% since 1990, the main reason being reduced use of solvent chemicals in industry.

Table ES.3 provides an overview of the CO₂ equivalent emission trends by category and gas.

Table ES.3. Summary of emission trends by category and gas in CO₂ equivalent [kt CO₂ eq.]

Category	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ equivalent</i>										
A. Energy: fuel combustion	412,012	425,367	448,484	477,764	419,122	349,698	291,961	324,575	328,355	300,637	290,075
CO ₂ : 1. Energy Industries	136,941	139,941	144,273	159,227	136,885	105,486	81,213	85,440	94,054	74,820	63,503
CO ₂ : 2. Manufacturing Industries and Construction	90,773	88,970	94,894	90,787	68,890	54,542	44,907	54,069	52,461	48,699	45,251
CO ₂ : 3. Transport	100,319	111,531	121,642	126,780	114,627	105,590	85,639	101,846	107,893	107,870	112,221
CO ₂ : 4. Other Sectors	76,042	75,580	79,169	92,324	89,783	76,111	72,715	75,437	66,632	62,611	62,478
CO ₂ : 5. Other	1,071	1,496	837	1,233	652	459	625	314	511	364	605
CH ₄	2,781	3,094	2,850	2,616	3,548	3,364	3,121	3,382	2,939	2,659	2,561
N ₂ O	4,085	4,755	4,819	4,796	4,738	4,145	3,741	4,087	3,864	3,616	3,456
1B2. Energy: fugitives from oil & gas	14,236	13,422	12,120	10,607	9,663	8,656	6,159	5,606	5,022	4,504	4,451
CO ₂	4,048	4,002	3,262	2,557	2,377	2,574	2,112	1,816	1,799	1,740	1,673
CH ₄	10,178	9,409	8,848	8,038	7,275	6,073	4,039	3,783	3,215	2,757	2,771
N ₂ O	11	10	11	12	11	9	7	8	8	8	7
2. Industrial processes	37,946	36,299	38,240	47,135	36,579	28,803	23,736	24,712	22,830	21,692	20,107
CO ₂	27,992	26,049	24,743	27,663	20,808	14,349	12,918	14,620	13,125	12,699	12,245
CH ₄	144	150	82	83	67	48	38	45	39	36	31
N ₂ O	6,402	6,848	7,646	7,338	1,088	545	559	505	480	519	495
HFCs	372	1,100	3,748	9,669	12,790	11,786	9,415	8,806	8,279	7,726	6,670
PFCs	2,615	1,351	1,363	1,759	1,377	1,540	516	413	462	297	280
Unspecified mix of HFCs and PFCs	NA,NO	24	24	24	24	24	22	25	22	29	33
SF ₆	421	700	621	565	405	483	252	282	405	367	328
NF ₃	NA,NO	77	13	33	20	28	16	15	20	20	26
3. Agriculture	36,045	36,103	35,280	33,039	30,753	30,169	30,881	30,226	28,346	29,283	28,009
CO ₂ : Liming	1	1	2	14	18	14	10	26	4	5	4
CO ₂ : Urea application	465	512	525	507	335	425	472	414	218	424	420
CO ₂ : Other carbon-containing fertilizers	44	54	44	42	28	20	22	24	14	13	14
CH ₄ : Enteric fermentation	17,174	16,796	16,631	14,521	14,125	14,310	14,815	14,695	14,518	14,314	13,488
CH ₄ : Manure management	5,308	5,057	5,017	5,147	4,939	4,740	4,549	4,457	4,471	4,519	4,098
CH ₄ : Rice Cultivation	2,102	2,228	1,855	2,078	2,255	1,943	1,696	1,677	1,547	1,510	1,793
CH ₄ : Field Burning of Agricultural Residues	15	15	15	17	13	13	12	12	11	12	10
N ₂ O: Manure management	3,076	2,959	2,897	2,685	2,536	2,203	2,078	2,017	1,982	2,002	1,863

Category	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ equivalent</i>										
<i>N₂O: Agriculture soils</i>	7,856	8,477	8,291	8,022	6,501	6,499	7,225	6,902	5,578	6,481	6,316
<i>N₂O: Field Burning of Agricultural Residues</i>	4	4	4	4	3	3	3	3	3	3	3
4A. Land-use change and forestry	-12,949	-35,023	-29,981	-44,057	-47,002	-47,445	-43,782	-44,294	-44,784	-57,565	-64,068
CO ₂	-14,267	-35,549	-30,792	-44,531	-47,514	-47,813	-44,280	-45,299	-45,609	-58,218	-64,610
CH ₄	827	271	498	269	294	239	273	594	474	351	269
N ₂ O	491	255	313	205	218	129	225	411	352	302	272
6. Waste	18,996	22,008	24,094	24,069	22,488	20,373	20,521	20,293	20,108	20,180	19,977
CO ₂	512	458	208	230	172	88	73	90	84	78	76
CH ₄	17,313	20,390	22,536	22,293	20,561	18,599	18,784	18,514	18,380	18,463	18,252
N ₂ O	1,171	1,160	1,350	1,547	1,754	1,687	1,664	1,689	1,644	1,639	1,648
Indirect CO₂ emissions	1,391	1,296	1,173	1,155	976	815	876	858	790	843	871
Total emissions (with LULUCF)	507,677	499,472	529,411	549,712	472,579	391,070	330,352	361,976	360,667	319,575	299,422
Total emissions (without LULUCF)	520,626	534,495	559,393	593,769	519,581	438,515	374,134	406,270	405,451	377,139	363,490

ES.4. Other information

In Table ES.4 NO_x, CO, NMVOC and SO₂ emission trends are summarized. All gases showed a significant reduction in 2024 as compared to 1990. SO₂ (-96.0%), NO_x levels have reduced by 74.7%, while CO and NMVOC show a decrease by 77.0% and 58.5%, respectively.

Table ES.4. Total emissions of indirect greenhouse gases and SO₂ [kt]

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt</i>										
NO _x	2,128	1,992	1,522	1,306	966	727	586	598	590	554	539
CO	6,823	7,117	4,813	3,526	3,106	2,300	1,881	2,020	1,785	1,640	1,570
NMVOC	2,008	2,080	1,662	1,375	1,154	944	885	889	825	838	843
SO ₂	1,784	1,323	757	411	222	128	85	79	86	71	70

Sommario (Italian)

Nel documento "Italian Greenhouse Gas Inventory 1990-2024. National Inventory Document 2026" si descrive la comunicazione annuale italiana dell'inventario delle emissioni dei gas serra in accordo a quanto previsto nell'ambito della Convenzione Quadro sui Cambiamenti Climatici delle Nazioni Unite (UNFCCC) e all'Accordo di Parigi. Tale comunicazione è anche trasmessa all'Unione Europea nell'ambito del Regolamento 2018/1999 del Parlamento Europeo e del Consiglio dell'11 Dicembre 2018 'Governance of the Energy Union and Climate Action'.

Ciascun Paese che aderisce alla Convenzione, oltre a trasmettere annualmente l'inventario nazionale delle emissioni di gas a effetto serra nei formati previsti, è tenuto a documentare la serie storica delle emissioni in un apposito rapporto, denominato *National Inventory Document*. Tale documentazione include una spiegazione delle tendenze osservate nelle emissioni, una descrizione dell'analisi delle principali sorgenti emissive (*key categories*) e delle relative incertezze, nonché i riferimenti alle metodologie di stima adottate, alle fonti dei dati di attività e ai fattori di emissione impiegati nelle valutazioni. Il rapporto illustra inoltre il sistema di *Quality Assurance/Quality Control* (QA/QC) applicato all'inventario e le attività di verifica condotte sui dati.

Il *National Inventory Document* facilita, inoltre, i processi internazionali di verifica cui sono sottoposte le stime di assorbimenti ed emissione dei gas serra, finalizzati a verificarne la conformità ai principi di trasparenza, coerenza, comparabilità, completezza e accuratezza. Tali criteri di qualità sono esplicitamente richiesti dalla Convenzione Quadro sui Cambiamenti Climatici. Qualora, nel corso del processo di revisione, vengano individuati errori nei formati di trasmissione dei dati oppure stime non adeguatamente supportate da documentazione e da una chiara giustificazione metodologica, al Paese interessato viene richiesto di procedere alla revisione e all'aggiornamento delle stime di emissione.

I dati di emissione dei gas-serra, i rapporti *National Inventory Report*, così come i risultati dei processi di *review*, fino al 2025, sono pubblicati sul sito web del Segretariato della Convenzione sui Cambiamenti Climatici (<https://unfccc.int/ghg-inventories-annex-i-parties/2025>; <https://unfccc.int/process-and-meetings/transparency-and-reporting/reporting-and-review/reporting-and-review-under-the-convention/greenhouse-gas-inventories-annex-i-parties/simplified-review-reports-2025>).

La presente comunicazione, completa del rapporto *National Inventory Document* e delle tabelle di stima dall'anno 1990 al 2024 (*Common Reporting Tables – CRTs*), è in accordo alla Convenzione sui Cambiamenti Climatici. I documenti sono pubblicati sul sito dell'UNFCCC.

La serie storica nazionale delle emissioni è anche disponibile sul sito web all'indirizzo: <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.

Da un'analisi di sintesi della serie storica dei dati di emissione dal 1990 al 2024, si evidenzia che le emissioni nazionali totali dei sei gas serra, espresse in CO₂ equivalente, sono diminuite del 30.2% nel 2024 rispetto al 1990. In particolare, le emissioni complessive di CO₂ sono pari all'81.4% del totale e risultano nel 2024 inferiori del 31.9% rispetto al 1990. Le emissioni di metano e di protossido di azoto sono pari a circa l'11.8% e il 3.8% del totale, rispettivamente, e presentano andamenti in diminuzione sia per il metano (-21.8%) che per il protossido di azoto (-39.0%). Gli altri gas serra, HFC, PFC, SF₆ e NF₃, hanno un peso complessivo sul totale delle emissioni che varia tra lo 0.01% e l'1.8%; le emissioni degli HFC evidenziano una forte crescita, mentre le emissioni di PFC decrescono e quelle di SF₆ e NF₃ mostrano un incremento. Sebbene tali variazioni non siano risultate determinanti ai fini del conseguimento degli obiettivi di riduzione delle emissioni, la significatività del trend degli HFC potrebbe renderli sempre più importanti nei prossimi anni.

1 INTRODUCTION

1.1 Background information on greenhouse gas inventories and climate change

In 1988 the World Meteorological Organisation (WMO) and the United Nations Environment Program (UNEP) established a scientific Intergovernmental Panel on Climate Change (IPCC) to evaluate the available scientific information on climate variations, examine the social and economic influence on climate change and formulate suitable strategies for the prevention and the control of climate change.

The first IPCC report in 1990, although considering the high uncertainties in the evaluation of climate change, emphasised the risk of global warming due to an imbalance in the climate system originated by the increase of anthropogenic emissions of greenhouse gases (GHGs) caused by industrial development and use of fossil fuels. The scientific knowledge on climate change has firmed up considerably by the IPCC Fifth Assessment Report on global warming which states that "Human influence on the climate system is clear, and recent anthropogenic emissions of greenhouse gases are the highest in history. Recent climate changes have had widespread impacts on human and natural systems." and "Warming of the climate system is unequivocal, and since the 1950s, many of the observed changes are unprecedented over decades to millennia. The atmosphere and ocean have warmed, the amounts of snow and ice have diminished, and sea level has risen." Hence the need to reduce those emissions, particularly for the most industrialised countries.

The first initiative was taken by the European Union (EU) at the end of 1990, when the EU adopted the goal of stabilisation of carbon dioxide emissions by the year 2000 at the level of 1990 and requested Member States to plan and implement initiatives for environmental protection and energy efficiency. The contents of EU statement were the base for the negotiation of the United Nations Framework Convention on Climate Change (UNFCCC) which was approved in New York on 9th May 1992 and signed during the summit of the Earth in Rio de Janeiro in June 1992. Parties to the Convention are committed to developing, publishing and regularly updating national emission inventories of greenhouse gases (GHGs) as well as formulate and implement programs addressing anthropogenic GHG emissions. Specifically, Italy ratified the Convention through law no.65 of 15/1/1994.

On 11/12/1997, Parties to the Convention adopted the Kyoto Protocol, which establishes emission reduction objectives for Annex B Parties (i.e., industrialised countries and countries with economy in transition) in the period 2008-2012. The European Union, as a whole, was committed to an 8% reduction within the period 2008-2012, in comparison with base year levels; for Italy, the EU burden sharing agreement, set out in Annex II to Decision 2002/358/EC and in accordance with Article 4 of the Kyoto Protocol, established a reduction objective of 6.5% in the commitment period, in comparison with the base 1990 levels.

Italy ratified the Kyoto Protocol on 1st June 2002 through law no.120 of 01/06/2002. The ratification law also prescribes the preparation of a National Action Plan to reduce greenhouse gas emission, which was adopted by the Interministerial Committee for Economic Planning (CIPE) on 19th December 2002 (deliberation n. 123 of 19/12/2002). The Kyoto Protocol entered into force on 16th February 2005.

The first commitment period ended in 2012, with an extension, for fulfilling commitments, to 18th November 2015, the so called *true-up period*.

In 2012 the 'Doha Amendment to the Kyoto Protocol' was adopted in relation to the period 2013-2020, including new commitments for Annex I Parties to the Kyoto Protocol and a revised list of GHGs to be reported on by Parties in the second commitment period.

During the second commitment period, Parties committed to reduce GHG emissions by at least 18% below 1990 levels in the eight-year period from 2013 to 2020. The EU and its Member States had committed to the 'Doha Amendment to the Kyoto Protocol', pledging to reduce their collective emissions to 20% below their levels in 1990 during the period 2013-2020, as reflected in the Doha Amendment. The target was to

be fulfilled jointly with Iceland. Italy deposited its instrument of ratification on 18 July 2016 and the amendment entered into force on 31 December 2020, following ratification by 147 Parties.

The EU had jointly fulfilled its UNFCCC target and implemented it internally through EU legislation in the 2020 [Climate and Energy package](#), adopted in 2009. In the package, in order to achieve the 20% reduction in 2020 compared to 1990, the EU divided the effort between the sectors covered by the [EU Emissions Trading System](#) (EU ETS) and the sectors under the [Effort Sharing Decision](#) (ESD). Legally binding target trajectories for the period 2013-2020 were enshrined in both the [EU-ETS Directive](#) (Directive 2003/87/EC and respective amendments) and the [Effort Sharing Decision](#). The Effort Sharing Decision had set annual national emission targets for all Member States for the period 2013-2020 for those sectors², excluding LULUCF, not covered by the EU emissions trading system (ETS). For Italy, the target included in the Effort Sharing Decision is equal to a GHG emissions reduction by 13% compared to 2005 levels.

The UNFCCC/CMP.17 decision, adopted at the Sharm el Sheik Conference in December 2022, set the deadline for the conclusion of the fulfilment of the Doha commitments by 2023, considering that the UNFCCC expert review process (under Article 8 of the Protocol) of the emission inventories for the last year of the commitment period (2020) was to be completed by 1 June 2023. Italy has fulfilled its reduction commitments under the agreement. The final report on the review of the report upon expiration of the additional period for fulfilling commitments for the second commitment period of the Kyoto Protocol of Italy is published on the UNFCCC website: <https://unfccc.int/documents/637791>.

A global agreement was reached in Paris in December 2015, for the period after 2020. The [Paris Agreement](#) entered into force in 2016, aims at strengthening the global response to the threat of climate change by holding the increase in the global temperature to well below 2°C above pre-industrial levels and to pursue efforts to limit the temperature increase below 1.5°C above pre-industrial levels, as this would significantly reduce the risks and impact of climate change. To achieve this long-term temperature goal, Parties aim to reach global peaking of GHG emissions as soon as possible and undertake rapid reductions to achieve a balance between anthropogenic GHG emissions and removals in the second half of this century.

In this framework, the European Union set a binding target to cut its emissions by at least 55% below 1990 levels by 2030, including the Land Use, Land-Use Change and Forestry (LULUCF) sector. A part of the emission reduction target is divided among the sectors subject to the Emissions Trading System (ETS), for which a 62% reduction from 2005 levels is required at European level. For the remaining non-ETS share, new and more ambitious national targets were defined with the approval of the Fit for 55 package (Regulation (EU) 2023/857). Italy is required an overall reduction of 43.7% in emissions compared to 2005 levels for the sectors and categories included in the EU Effort Sharing Regulation (ESR), i.e. transport, residential, agriculture, waste and industry not included under ETS. Within this framework commitments for Land use, Land-Use Change, and Forestry (LULUCF) were also revised, and defined in Regulation (EU) 839/2023 LULUCF: the target for 2030 was fixed as a net removal equal to, at least, -35.8Mt CO₂ eq. Annual binding national targets both under ESR and LULUCF. In 2025, an EU Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841 has been carried out, aimed to set out the annual emission allocations (AEAs) of Italy for the years from 2026 to 2030, as required by Article 4.3 of Regulation (EU) No 2018/842 (the 'Effort Sharing Regulation', ESR) and the annual limit values of Italy for the years from 2026 to 2030, as required by Article 4.4 of Regulation (EU) No 2018/841 (the 'LULUCF Regulation'). Implementing acts for the abovementioned EU regulations will be adopted to set out the annual AEAs and annual limit values of Italy, following the EU review process of the 2025 GHG inventory submission.

As a Party to the Convention and the Paris Agreement, Italy is committed to develop, publish and regularly update national emission inventories as well as formulate and implement programs to reduce these

² transport, buildings, agriculture, non-ETS industry and waste sectors

emissions. In order to establish compliance with national and international commitments, air emission inventories are compiled and communicated annually to competent institutions.

Specifically, the national GHG emission inventory is communicated through compilation of the Common Reporting Tables (CRTs), according to the guidelines provided by the United Nations Framework Convention on Climate Change.

The inventory is updated annually in order to reflect revisions and improvements in methodology and availability of new information. Recalculations are applied retrospectively to earlier years, which account for any difference in previously published data. The submission also provides detailed information on emission figures and estimation methodologies in the annual National Inventory Document.

As follows, this report is compiled according to the guidelines on reporting as specified in the document FCCC/PA/CMA/2018/3/Add.2, Decision 18/CMA.1. Italy, as well as all EU Member States, uses the 100-year time-horizon global warming potential values, excluding the value for fossil methane, listed in table 8.A.1 in the contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change³, following the COP27 decision taken in 2022 on the 'Revision of the UNFCCC reporting guidelines on annual inventories for Parties included in Annex I to the Convention'.

An analysis of the Italian GHG emission inventory for the year 2024, and a revision of the entire time series from 1990, communicated in the framework of the annual submission under the UNFCCC, is provided in the document.

Emission estimates comprise the six direct greenhouse gases (carbon dioxide, methane, nitrous oxide, hydrofluorocarbons, perfluorocarbons, sulphur hexafluoride) plus nitrogen trifluoride (NF₃) which contribute directly to climate change owing to their positive radiative forcing effect and four indirect greenhouse gases (nitrogen oxides, carbon monoxide, non-methane volatile organic compounds, sulphur dioxide).

The CRT files, the national inventory document and other related documents are available at the address <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.

The official inventory submissions can also be found at the UNFCCC website:

The present document is the official submission, for the year 2026, both to the UNFCCC and to the European Union according to the Regulation (EU) 2018/1999 of the European Parliament and of the Council of 11 December 2018 on the Governance of the Energy Union and Climate Action.

³ IPCC, 2013. Climate Change 2013: The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change. TF Stocker, D Qin, G-K Plattner, et al. (eds.). Cambridge and New York: Cambridge University Press. Available at <http://www.ipcc.ch/report/ar5/wg1>.

1.2 Description of the institutional arrangement for inventory preparation

1.2.1 National Inventory System

The National System for the Italian Greenhouse Gas Inventory was established by the Legislative Decree 51 of March 7th 2008 and confirmed by the Legislative Decree 30 of March 13th 2013.

Article 5.1 of the Kyoto Protocol established that Annex I Parties should have in place a National System from the end of 2006 for estimating anthropogenic greenhouse gas emissions by sources and removals by sinks and for reporting and archiving inventory information according to the guidelines specified in the UNFCCC Decision 20/COP.7. This decision is updated by Decision 24/CP19, which calls the system national inventory arrangements but does not change the basic requests of functionality and operability.

The 'National Registry for Carbon sinks', instituted by a Ministerial Decree on 1st April 2008, is part of the Italian National System. In agreement with the Ministerial decree art. 4, the Ministry for the Environment, Land and Sea is responsible for the management of the National Registry for Carbon sinks. The Decree also provides that ISPRA and the former State Forestry Service, now Carabinieri Forestali, are involved by the Ministry as technical scientific support for specific activities as defined in the relevant protocol. ISPRA is responsible for the preparation of emission and removals estimates for the LULUCF sector. Following an update of the abovementioned Ministerial Decree, in 2013, the Institute for Services on Agricultural and Agro-food Market (ISMEA⁴) has been designated for the technical coordination of the section related to cropland and grassland of the National Registry of Carbon Sinks.

In March 2006 Italy started operating a national registry under the European Emission Trading Scheme (EU ETS). Eventually, in June 2012 all national registries of the EU Member States as well as the national registries of Norway, Liechtenstein and Iceland were grouped in a single central software system managed by the European Commission.

According to [Legislative Decree N. 47 of 9 June 2020](#), enforcing European Directive 2018/410/EC, ISPRA is responsible for the administration of the Italian part of the Union Registry; the Institute performs this task under the supervision of the National Competent Authority.

ISPRA is also responsible for the national system for policies, measures and emissions and, in cooperation with the Ministry of the Environment (MASE), collects all the information and data from the competent Ministries. Article 1 of the Decree implementing law N. 79 (9th December 2016), reports the list of information and data that are to be sent by the competent ministries to MASE and ISPRA and also the timing for providing such information. With the establishment of this system, there has been a strengthening of roles and obligations for statistical data flow, some of which are useful for the inventory scope.

The Italian National System, currently in place, is fully described in the document 'National Greenhouse Gas Inventory System in Italy' (ISPRA, 2018). A summary picture is reported here below.

As indicated by art. 14 bis of the Legislative Decree, the Institute for Environmental Protection and Research (ISPRA) is the single entity in charge of the preparation and compilation of the national greenhouse gas emission inventory. The MASE is responsible for the endorsement of the inventory and for communication to the Secretariat of the Framework Convention on Climate Change. The inventory is also submitted to the European Commission.

The Institute prepares a document which describes the national system including all updated information on institutional, legal and procedural arrangements for estimating emissions and removals of greenhouse gases and for reporting and archiving inventory information. The document is updated when there is the

⁴ ISMEA is a public body, providing support to public and private sector. According to DPR 31 March 2001, n. 200, ISMEA is part of the National Statistical System – SISTAN and of the National Agricultural Information System – SIAN.

need to describe an annual change occurred in the system. The reports are publicly available at <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.

A specific unit of the Institute is responsible for the compilation of the Italian Greenhouse Gas Inventory and the Italian Atmospheric Emission Inventory in the framework of the Convention on Climate Change and the Convention on Long Range Transboundary Air Pollution, respectively. The whole inventory is compiled by the Institute.

ISPRA is responsible for the general administration of the inventory and all aspects related to its preparation, reporting and quality management. Activities include the collection and processing of data from different data sources, the selection of appropriate emissions factors and estimation methods consistent with the IPCC Guidelines, the compilation of the inventory following the QA/QC procedures, the assessment of uncertainty, the preparation of the National Inventory Document and the reporting through the ETF tool, and Common Reporting Tables, the response to the review process, the updating and data storage. Scientific and technical institutions and consultants may be engaged for ad hoc studies and research aimed at improving both activity data and emission factors, at country level, for some specific activities. Also, there are different institutions responsible for statistical basic information and data publication, primary to ISPRA for carrying out estimates. These institutions are part of the National Statistical System (Sistan), which periodically provides official statistics at national level; moreover, the National Statistical System ensures the homogeneity of the methods used for official statistics through a coordination plan, involving the entire public administration at central, regional and local levels.

The National Statistical System is coordinated by the Italian National Institute of Statistics (ISTAT); other bodies, joining the National Statistical System, are the statistical offices of ministries, national agencies, regions and autonomous provinces, provinces, municipalities, research institutes, chambers of commerce, local governmental offices, some private agencies and private subjects who have specific characteristics determined by law. The Italian statistical system was instituted on 6th September 1989 by the Legislative Decree n. 322/89, which established guiding principles and criteria for reforming public statistics. A national statistical plan which defines surveys, data elaborations and project studies for a three-year period is to be drawn up and updated annually. The plan is approved by a Prime Ministerial Decree after consideration of the Interministerial Committee for Economic Planning (CIPE). Statistical information and results deriving from the completion of the plan are of public domain and the system is responsible for wide circulation.

Ministries, public agencies and other bodies are obliged to provide the data and information specified in the annual statistical plan; the same obligations regard the private entities. All the data are protected by the principles of statistical disclosure control and can be distributed and communicated only at aggregate level even though microdata can circulate among the subjects of the Statistical System.

Sistan activity is supervised by the Commission for Guaranteeing Statistical Information (CGIS) which is an external and independent body. In particular, the Commission supervises: the impartiality and completeness of statistical information, the quality of methodologies, the compliance of surveys with EU and international directives. The Commission, established within the Presidency of the Council of Ministers, is composed of high-profile university professors, directors of statistical or research institutes and managers of public administrations and bodies, which do not participate at Sistan.

The main Sistan products, which are primarily necessary for inventory compilation, are:

- National Statistical Yearbooks, by ISTAT (National Institute of Statistics);
- National Energy Balance (annual), Petrochemical Bulletin (quarterly publication), by MASE (Ministry of Economic Development);
- Transport Statistics Yearbooks, by MIT (Ministry of Transportation);
- Annual Statistics on Electrical Energy in Italy, by Terna (National Independent System Operator);
- Annual Report on Waste, by ISPRA;

- National Forestry Inventory, by “Carabinieri Forestali”⁵.

The national emission inventory is also a Sistan product.

Other information and data sources are used to carry out emission estimates, which are generally referred to in Table 1.1 of the following section 1.4.

1.3 Brief description of the process of inventory preparation

ISPRA has established fruitful cooperation with several governmental and research institutions as well as industrial associations, which helps improving the accuracy of the estimates of some leading categories of the inventory. These activities aim at the improvement of provision and collection of basic data and emission factors, also through plant-specific data, and exchange of information on scientific studies and new sources. Moreover, when in depth investigation is needed and a high uncertainty in the estimates is present, ISPRA may commit specific sector studies to ad hoc research teams.

The final aim is for ISPRA to improve the implementation of country specific methodologies and use of national emission factors and parameters.

ISPRA also coordinates with different national and regional authorities and private institutions for the cross-checking of parameters and estimates as well as with ad hoc expert panels to improve the completeness and transparency of the inventory.

The main basic data needed for the preparation of the GHG inventory are energy statistics published by the Ministry of the Environment, in the National Energy Balance (BEN), statistics on industrial and agricultural production published by the National Institute of Statistics (ISTAT), statistics on transportation provided by the Ministry of Transportation, and data supplied directly by the relevant professional associations.

Emission factors and methodologies used in the estimation process are consistent with the IPCC Guidelines and supported by national experiences and circumstances.

In addition to a new year, the entire time series from 1990 is checked and revised during the annual compilation of the inventory to meet the requirements of transparency, consistency, comparability, completeness and accuracy. Measures to guarantee and improve these qualifications are undertaken and recalculations should be considered as a contribution to the overall improvement of the inventory.


Recalculations are elaborated on account of changes in the methodologies used to carry out emission estimates, changes due to different allocation of emissions as compared to previous submissions and changes due to error corrections. The inventory may also be expanded by including categories not previously estimated if sufficient information on activity data and suitable emission factors have been identified and collected.

Information on the major recalculations is provided every year in the sectoral and general chapters of the national inventory reports.

In Figure 1.1 the most important steps to guarantee the continuous improvement of the national GHG emission inventory are outlined.

⁵ <http://www.carabinieri.it/arma/oggi/organizzazione/organizzazione-per-la-tutela-forestale-ambientale-e-agroalimentare>

Figure 1.1 National Greenhouse Gas Inventory: annual inventory process



All the reference material, estimates and calculation sheets, as well as the documentation on scientific papers and the basic data needed for the inventory compilation, are stored and archived at the Institute. After each reporting cycle, all database files, spreadsheets and electronic documents are archived as 'read-only-files' so that the documentation and estimates could be traced back during the review process or the new inventory compilation year.

Technical reports and emission figures are publicly available on the website at the address:

<https://emissioni.sina.isprambiente.it/inventario-nazionale/>.

1.4 Brief general description of methodologies and data sources used

A detailed description of methodologies and data sources used in the preparation of the emission inventory for each sector is outlined in the relevant chapters. In Table 1.1, a summary of the activity data and sources used in the inventory compilation is reported.

Methodologies are consistent with the IPCC Guidelines and EMEP/EEA Guidebooks (IPCC, 2003; IPCC, 2006; IPCC, 2019; EMEP/EEA, 2023); national emission factors are used as well as default emission factors from international guidebooks, when national data are not available. The development of national methodologies is supported by background documents.

In Table 1.2, a summary of the methods and emission factors used in the compilation of the Italian inventory is reported.

Table 1.1 Main activity data and sources for the Italian Emission Inventory

SECTOR	ACTIVITY DATA	SOURCE
1 Energy		
1A1 Energy Industries	Fuel use	Energy Balance - Ministry of Environment Major national electricity producers European Emissions Trading Scheme
1A2 Manufacturing Industries and Construction	Fuel use	Energy Balance - Ministry of Environment Major National Industry Corporation European Emissions Trading Scheme
1A3 Transport	Fuel use Number of vehicles Aircraft landing and take-off cycles and maritime activities	Energy Balance - Ministry of Environment Statistical Yearbooks - National Statistical System Statistical Yearbooks - Ministry of Transportation Statistical Yearbooks - Italian Civil Aviation Authority (ENAC) Maritime and Airport local authorities
1A4 Residential-public-commercial sector	Fuel use	Energy Balance - Ministry of Environment
1B Fugitive Emissions from Fuel	Amount of fuel treated, stored, distributed	Energy Balance - Ministry of Environment Statistical Yearbooks - Ministry of Transportation Major National Industry Corporation
2 Industrial Processes and Product Use	Production data	National Statistical Yearbooks- National Institute of Statistics International Statistical Yearbooks-UN European Emissions Trading Scheme European Pollutant Release and Transfer Register Sectoral Industrial Associations
3 Agriculture	Agricultural surfaces Production data Number of animals Fertiliser consumption	Agriculture Statistical Yearbooks - National Institute of Statistics Sectoral Agriculture Associations
4 Land Use, Land Use Change and Forestry	Forest area, biomass increment and stock Biomass burnt	Carabinieri - National and Regional Forestry Inventory Statistical Yearbooks - National Institute of Statistics Universities and Research Institutes
5 Waste	Amount of waste	National Waste Cadastre - Institute for Environmental Protection and Research , National Waste Observatory

Table 1.2 Methods and emission factors used in inventory preparation

SUMMARY 3 SUMMARY REPORT FOR METHODS AND EMISSION FACTORS USED																
GREENHOUSE GAS SOURCE AND SINK	CO ₂		CH ₄		N ₂ O		HFCs		PFCs		SF ₆		Unspecified mix of HFCs and PFCs		NF ₃	
	Meth	EF	Meth	EF	Meth	EF	Meth	EF	Meth	EF	Meth	EF	Meth	EF	Meth	EF
1. Energy	T1,T2,T3	CS,D,M	T1,T2,T3	CR,C S,D,M	T1,T2,T3	CR,D,M										
A. Fuel combustion	T1,T2,T3	CS,M	T1,T2,T3	CR,D,M	T1,T2,T3	CR,D,M										
1. Energy industries	T3	CS	T3	CR,D	T3	CR,D										
2. Manufacturing industries and construction	T2	CS	T2	CR,D	T2	CR,D										
3. Transport	T1,T2	CS,M	T1,T2,T3	CR,D,M	T1,T2,T3	CR,D,M										
4. Other sectors	T2	CS	T2	CR	T2	CR										
5. Other	T2	CS	T2	CR	T2	CR										
B. Fugitive emissions from fuels	T1,T2	CS,D	T1,T2	CR,C S,D	T1	D										
1. Solid fuels			T1,T2	CR,D												

2. Oil and natural gas	T1,T2	CS,D	T1,T2	CR,C S,D	T1	D										
C. CO ₂ transport and storage																
2. Industrial processes	D,T1,T2, T3	CR,CS,D, M,PS	D,T1	CR,C S,D	CS,T3	CS,D,P S	CS,T2	CS,D, PS	CS,T2	CS,P S	CS,T2	CS,PS	CS	PS	T2	CS
A. Mineral industry	T2	CS,PS														
B. Chemical industry	D,T2,T3	CR,PS	D,T1	CR,C S,D	T3	D,PS	CS	PS	CS	PS						
C. Metal industry	T2	CR,CS,PS	D	CS,D			T2	PS								
D. Non-energy products from fuels and solvent use	T1,T2	D,M,PS														
E. Electronic industry							T2	CS	T2	CS	T2	CS	CS	PS	T2	CS
F. Product uses as ODS substitutes							T2	CS,D								
G. Other product manufacture and use					CS	CS					CS,T3	CS,PS				
H. Other																
3. Agriculture	T1	D	T1,T2	CS,D	D,T1,T2	CS,D										
A. Enteric fermentation			T1,T2	CS,D												
B. Manure management			T1,T2	CS,D	T2	CS,D										
C. Rice cultivation			T2	CS												
D. Agricultural soils ⁽³⁾					T1	CS,D										
E. Prescribed burning of savannas																
F. Field burning of agricultural residues			T1	CS,D	T1	CS,D										
G. Liming	T1	D														
H. Urea application	T1	D														
I. Other carbon-containing fertilizers	T1	D														
J. Other																
4. Land use, land-use change and forestry	T1,T2,T 3	CS,D	T1,T2	CS,D	T1,T2	CS,D										
A. Forest land	T1,T2,T 3	CS,D	T2	CS,D	T2	CS,D										
B. Cropland	T1,T2	CS,D	T1	D	T1	D										
C. Grassland	T1,T2,T 3	CS,D	T1	CS	T1	CS										
D. Wetlands																
E. Settlements	T1	D			T1	D										
F. Other land																
G. Harvested wood products	T2	CS														
H. Other																
5. Waste	D,T1	CS,D	D,T1, T2	CR,C S,D	D,T1	CR,CS, D										
A. Solid waste disposal			T2	CS												

B. Biological treatment of solid waste			D	CS,D	D	D													
C. Incineration and open burning of waste	D,T1	CS,D	D,T1	CR,C S,D	D,T1	CS,D													
D. Waste water treatment and discharge			T1	D	T1	CR,D													
E. Other																			
6. Other (as specified in summary 1.A)																			
Use the following notation keys to specify the method applied:																			
D (IPCC default)			T1a, T1b, T1c (IPCC Tier 1a, Tier 1b and Tier 1c, respectively)						CR (CORINAIR)			M (model)							
RA (Reference Approach)			T2 (IPCC Tier 2)						CS (Country Specific)										
T1 (IPCC Tier 1)			T3 (IPCC Tier 3)						OTH (Other)										
If using more than one method within one source category, list all the relevant methods. Explanations regarding country-specific methods, other methods or any modifications to the default IPCC methods, as well as information regarding the use of different methods per source category where more than one method is indicated, should be provided in the documentation box. Also use the documentation box to explain the use of notation OTH.																			
Use the following notation keys to specify the emission factor used:																			
D (IPCC default)			CS (Country Specific)						OTH (Other)										
CR (CORINAIR)			PS (Plant Specific)						M (model)										
Where a mix of emission factors has been used, list all the methods in the relevant cells and give further explanations in the documentation box. Also use the documentation box to explain the use of notation OTH.																			

Activity data used in emission calculations and their sources are briefly described here below.

In general, for the energy sector, basic statistics for estimating emissions are fuel consumptions provided in the Energy Balance by the Ministry of Environment. Additional information for electricity production is supplied by the major national electricity producers and by the major national industry corporation. On the other hand, basic information for road transport, maritime and aviation, such as the number of vehicles, harbour statistics and aircraft landing and take-off cycles are published by the National Institute of Statistics and the Ministry of Transportation in the relevant statistical yearbooks. Other data are communicated by different category associations.

A lot of information on productions, fuel consumptions, emission factors and emissions in specific energy and industrial sub sectors is obtained from data collected by operators under the European Emissions Trading Scheme (ETS).

The criteria of data reporting are defined by European Directive 2018/410/EC and adopted at national level by the [Legislative Decree N. 47 of 9 June 2020](#). In compliance with the above-mentioned legislation, independent certifications and verifications of activity data, emission data and emission factors are required. At national level, data verification has to be carried out by verifiers accredited by the national ETS Committee according to the ministerial decree DEC/RAS/115/2006. The verification of data submissions ensures reliability, credibility, and precision/accuracy of monitoring systems for data and any information relating to emissions by plant.

Data from the Italian Emissions Trading Scheme database are incorporated into the national inventory whenever the sectoral coverage is complete; in fact, ETS data not always entirely cover energy categories whereas national statistics, such as the national energy balance and the energy production and consumption statistics, provide the complete basic data needed for the Italian emission inventory. Nevertheless, ETS data are entirely used to develop country-specific emission factors and check activity data levels.

For the industrial sector, the annual production data are provided by national sources and industrial associations.

Emission data collected through the National Pollutant Release and Transfer Register are also used in the development of emission estimates or considered as a verification of emission estimates for some specific categories. According to the Italian Decree of 23 November 2001, data (reporting period 2002-2006) included in the Italian pollutant emissions register were validated by competent authorities within 30 June each year and communicated by ISPRA to the Ministry of the Environment every year and to the European Commission every three years according to EC Decision 2000/479. Since 2008, the national pollutant emissions register has been replaced by the national pollutant release and transfer register (the Italian PRTR) to comply with Regulation EC n.166/2006; data are collected annually at facility level and sent, after validation, by competent authorities to European Commission within 31 March every year for data referring to the previous year. These data are used for the compilation of the inventory whenever they are complete in terms of sectoral information; in fact, industries communicate figures only if they exceed specific thresholds; furthermore, basic data such as fuel consumption are not supplied, and production data are not always split by product but reported as an overall figure. In any case, the Italian PRTR is a good basis for data checks and a way to facilitate contacts with industries which, in many cases, supply, under request, additional information as necessary for carrying out sectoral emission estimates.

In addition, final emissions are checked and verified also considering figures reported by industries in their annual environmental reports.

Both for energy and industrial processes, emissions of large industrial point sources are registered individually; communication also takes place in the framework of the European Directive on Large Combustion Plants, based upon detailed information such as fuel consumption. Other small plants voluntarily communicate their emissions which are also considered individually. For solvents, the amount of solvent use is provided by environmental publications of sectoral industries and associations.

ISPRA directly collects data from the industrial associations under the ETS and other European directives, Large Combustion Plant and PRTR, and makes use of these data in the preparation of the national inventory ensuring the consistency of time series.

For the other sectors, i.e. for agriculture, annual production data and the number of animals are provided by the National Institute of Statistics and other sectoral associations.

For land use, land use change and forestry, forest areas are derived from national forest inventories provided by the Ministry of Agriculture and Carabinieri; the Carabinieri is also the provider of official statistics related to the areas subject to fires.

For waste, the main activity data are provided by the Institute for Environmental Protection and Research and the Waste Observatory.

Unpublished data are used only if supported by personal communication and confidentiality of data is respected.

As for data disclosure, the inventory team is obliged to ensure confidentiality of sensitive information by legislation when data are communicated under specific directives or confidentiality is requested by data providers. In the case of data collection under the ETS, E-PRTR, large combustion plants and other directives, the database of the complete information is available only to a specific group of authorised experts which have the legal responsibility for the respect of confidentiality issues. In other cases, each expert is responsible for the data received, and confidentiality. In any case, all data are placed on a password protected access environment at ISPRA and available only to authorised experts of the inventory team.

All the material and documents used for the inventory estimation process are stored at the Institute for Environmental Protection and Research. Activity data and emission factors as well as methodologies are referenced to their data sources.

1.5 Brief description of key categories

A key category analysis of the Italian inventory is carried out according to the Approach 1 and Approach 2 described in the 2006 IPCC Guidelines (IPCC, 2006).

Following the IPCC guidelines, a key category is defined as an emission category that has a significant influence on a country's GHG inventory in terms of the absolute level and trend in emissions and removals, or both. Key categories are those which, when summed together in descending order of magnitude, add up to over 95% of the total emissions or 90% of total uncertainty. National emissions have been disaggregated into the categories proposed in the IPCC guidelines and reflect specific national circumstances. Both level and trend analysis have been applied to the last submitted inventory; a key category analysis has also been carried out for the base year emission levels. For the year 1990, 38 key categories were individuated implementing Approach 1 and Approach 2. Including the LULUCF in the analysis, 50 categories were selected by Approach 1 and Approach 2. The description of these categories is shown in Table 1.3 and Table 1.4.

Table 1.3 Key categories (excluding LULUCF) by the IPCC Approach 1 and Approach 2. Year 1990

<i>Key categories (excluding the LULUCF sector)</i>			
1.A.1	Energy industries - CO ₂ gaseous fuels	L	L1 = level key category by Approach 1 T1 = trend key category by Approach 1 L2 = level key category by Approach 2 T2 = trend key category by Approach 2 L = level key category by Approach 1 and Approach 2 T = trend key category by Approach 1 and Approach 2
1.A.1	Energy industries - CO ₂ liquid fuels	L	
1.A.1	Energy industries - CO ₂ solid fuels	L	
1.A.2	Manufacturing industries and construction - CO ₂ gaseous fuels	L	
1.A.2	Manufacturing industries and construction - CO ₂ liquid fuels	L	
1.A.2	Manufacturing industries and construction - CO ₂ solid fuels	L	
1.A.2	Manufacturing industries and construction - N ₂ O liquid fuels	L2	
1.A.3.b	Transport - CH ₄ Road transportation	L2	
1.A.3.b	Transport - CO ₂ Road transportation	L	
1.A.3.d	Transport - CO ₂ Waterborne navigation	L1	
1.A.4	Other sectors - CH ₄ commercial, residential, agriculture biomass	L2	
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture gaseous fuels	L	
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture liquid fuels	L	
1.A.4	Other sectors - N ₂ O commercial, residential, agriculture liquid fuels	L2	
1.B.2.a	Fugitive - CO ₂ Oil and natural gas - Oil	L1	
1.B.2.b	Fugitive - CH ₄ Oil and natural gas - Natural gas	L	
1.B.2.c	Fugitive - CO ₂ Oil and natural gas - venting and flaring	L2	
1.B.2.d	Fugitive - CO ₂ Oil and natural gas - Other - flaring in refineries	L2	
2.A.1	Mineral industry- CO ₂ Cement production	L	
2.A.2	Mineral industry- CO ₂ Lime production	L1	
2.A.4	Mineral industry- CO ₂ Other processes uses of carbonates	L1	
2.B.1	Chemical industry- CO ₂ Ammonia production	L1	
2.B.2	Chemical industry- N ₂ O Nitric acid production	L1	
2.B.3	Chemical industry- N ₂ O Adipic acid production	L	
2.B.9	Chemical industry- PFCs Fluorochemical production	L2	
2.C.1	Metal industry- CO ₂ Iron and steel production	L	
2.C.3	Metal industry-PFCs Aluminium production	L2	
3.A.1	Enteric Fermentation- CH ₄	L	
3.A.2	Manure Management - CH ₄	L	
3.A.2	Manure Management - N ₂ O	L	
3.C	Rice Cultivation - CH ₄	L1	
3.B.5	Indirect N ₂ O Emissions from Manure Management	L2	
3.D.a	Direct N ₂ O Emissions from Managed soils	L	
3.D.b	Indirect N ₂ O Emissions from Managed soils	L	

Key categories (excluding the LULUCF sector)

5.A	Solid waste disposal - CH ₄	L
5.D	Wastewater treatment and discharge - CH ₄	L
5.D	Wastewater treatment and discharge - N ₂ O	L2
	Indirect CO ₂ emissions - CO ₂	L2

Table 1.4 Key categories (including LULUCF) by the IPCC Approach 1 and Approach 2. Year 1990

Key categories (excluding the LULUCF sector)

1.A.1	Energy industries - CO ₂ gaseous fuels	L
1.A.1	Energy industries - CO ₂ liquid fuels	L
1.A.1	Energy industries - CO ₂ solid fuels	L
1.A.2	Manufacturing industries and construction - CO ₂ gaseous fuels	L
1.A.2	Manufacturing industries and construction - CO ₂ liquid fuels	L
1.A.2	Manufacturing industries and construction - CO ₂ solid fuels	L
1.A.2	Manufacturing industries and construction - N ₂ O liquid fuels	L2
1.A.3.b	Transport - CH ₄ Road transportation	L2
1.A.3.b	Transport - N ₂ O Road transportation	L2
1.A.3.b	Transport - CO ₂ Road transportation	L
1.A.3.c	Transport - CO ₂ Civil Aviation	L1
1.A.3.d	Transport - CO ₂ Waterborne navigation	L1
1.A.4	Other sectors - CH ₄ commercial, residential, agriculture biomass	L2
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture gaseous fuels	L
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture liquid fuels	L
1.A.4	Other sectors - N ₂ O commercial, residential, agriculture liquid fuels	L2
1.B.2.a	Fugitive - CO ₂ Oil and natural gas - Oil	L1
1.B.2.b	Fugitive - CH ₄ Oil and natural gas - Natural gas	L
1.B.2.c	Fugitive - CO ₂ Oil and natural gas - venting and flaring	L2
1.B.2.d	Fugitive - CO ₂ Oil and natural gas - flaring in refineries	L2
2.A.1	Mineral industry- CO ₂ Cement production	L
2.A.2	Mineral industry- CO ₂ Lime production	L1
2.A.4	Mineral industry- CO ₂ Other processes uses of carbonates	L1
2.B.1	Chemical industry- CO ₂ Ammonia production	L1
2.B.2	Chemical industry- N ₂ O Nitric acid production	L1
2.B.3	Chemical industry- N ₂ O Adipic acid production	L
2.B.9	Chemical industry- PFCs Fluorochemical production	L2
2.C.1	Metal industry- CO ₂ Iron and steel production	L
2.C.3	Metal industry- PFCs Aluminium production	L
3.A.1	Enteric Fermentation- CH ₄	L
3.A.2	Manure Management - CH ₄	L
3.A.2	Manure Management - N ₂ O	L
3.C	Rice cultivations - CH ₄	L1
3.B.5	Indirect N ₂ O Emissions from Manure Management	L2
3.D.a	Direct N ₂ O Emissions from Managed soils	L
3.D.b	Indirect N ₂ O Emissions from Managed soils	L
4.A.1	Forest Land remaining Forest Land -DOM- CO ₂	L
4.A.1	Forest Land remaining Forest Land -Living biomass- CO ₂	L
4.A.2	Land converted to Forest Land - Living biomass - CO ₂	L

L1 = level key category by Approach 1
T1 = trend key category by Approach 1
L2 = level key category by Approach 2
T2 = trend key category by Approach 2
L = level key category by Approach 1 and Approach 2
T = trend key category by Approach 1 and Approach 2

<i>Key categories (excluding the LULUCF sector)</i>		
4.B.1	Cropland remaining cropland – Living biomass -CO2	L1
4(II)	Cropland remaining cropland – Organic soils -CO2	L2
4.B.2	Land Converted to Cropland – DOM- mineral soils - CO2	L2
4.C.1	Grassland Remaining Grassland – Living biomass- CO2	L
4.C.1	Grassland Remaining Grassland – Living biomass- CH4	L2
4.C.2	Land converted to Grassland – mineral soils – CO2	L2
4.E.2	Land Converted to Settlements - CO2	L2
5.A	Solid waste disposal - CH4	L
5.D	Wastewater treatment and discharge - CH4	L
5.D	Wastewater treatment and discharge - N2O	L2
	Indirect CO ₂ emissions	L

Applying the analysis to the 2024 inventory, without the LULUCF sector, 49 key categories were totally individuated, both at level and trend. Results are reported in Table 1.5.

Table 1.5 Key categories (excluding LULUCF) by IPCC Approach 1 and Approach 2. Year 2024

<i>Key categories (excluding the LULUCF sector)</i>		
1.A.1	Energy industries - CO ₂ gaseous fuels	L, T
1.A.1	Energy industries - CO ₂ liquid fuels	L, T
1.A.1	Energy industries - CO ₂ solid fuels	L, T
1.A.2	Manufacturing industries and construction - CO ₂ gaseous fuels	L, T
1.A.2	Manufacturing industries and construction - CO ₂ liquid fuels	L, T
1.A.2	Manufacturing industries and construction - CO ₂ solid fuels	L1, T
1.A.3.a	Transport – CO ₂ Civil aviation	L1, T1
1.A.3.b	Transport - CH ₄ Road transportation	T2
1.A.3.b	Transport – N ₂ O Road transportation	L2, T2
1.A.3.b	Transport - CO ₂ Road transportation	L, T
1.A.3.d	Transport - CO ₂ Waterborne navigation	L1, T1
1.A.4	Other sectors - CH ₄ commercial, residential, agriculture biomass	L, T
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture solid fuels	T1
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture gaseous fuels	L, T
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture liquid fuels	L, T
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture other fossil fuels	L1, T
1.A.4	Other sectors - CO ₂ commercial, residential, agriculture solid fuels	T1
1.A.4	Other sectors - N ₂ O commercial, residential, agriculture biomass	L2, T2
1.A.4	Other sectors - N ₂ O commercial, residential, agriculture liquid fuels	L2
1.B.2.b	Fugitive - CH ₄ Oil and natural gas - Natural gas	L, T
1.B.2.b	Fugitive - CO ₂ Oil and natural gas - Oil	T1
1.B.2.c	Fugitive – CO ₂ Oil and natural gas - Other – venting and flaring	T2
1.B.2.d	Fugitive - CH ₄ Oil and natural gas - Other - flaring in refineries	L2, T2
1.B.2.d	Fugitive - CO ₂ Oil and natural gas - Other - flaring in refineries	T2
2.A.1	Mineral industry- CO ₂ Cement production	L, T
2.A.2	Mineral industry- CO ₂ Lime production	L1
2.A.4	Mineral industry- CO ₂ Other processes uses of carbonates	T
2.B.1	Chemical industry- CO ₂ Ammonia production	T1
2.B.2	Chemical industry- N ₂ O Nitric acid production	T
2.B.3	Chemical industry- N ₂ O Adipic acid production	T
2.B.9	Chemical industry- HFCs Fluorochemical production	T2

L1 = level key category, Approach 1
T1 = trend key category, Approach 1
L2 = level key category, Approach 2
T2 = trend key category, Approach 2
L = level key category, Approach 1 and Approach 2
T = trend key category, Approach 1 and Approach 2

<i>Key categories (excluding the LULUCF sector)</i>		
2.B.9	Chemical industry- PFCs Fluorochemical production	T2
2.C.1	Metal industry- CO2 Iron and steel production	T1
2.C.3	Metal industry- PFCs Aluminium production	T
2.F.1	Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	L, T
2.F.2	Product uses as substitutes for ozone depleting substances - HFCs Foam blowing agents	T2
2.F.3	Product uses as substitutes for ozone depleting substances - HFCs Fire protection	L2, T2
3.A.1	Enteric Fermentation- CH4	L, T
3.A.2	Manure Management - CH4	L
3.A.2	Manure Management – N2O	L
3.B.5	Indirect N2O Emissions from Manure Management	L2
3.C	Rice Cultivation - CH4	L1
3.D.a	Direct N2O Emissions from Managed soils	L, T
3.D.b	Indirect N2O Emissions from Managed soils	L, T2
5.A	Solid waste disposal - CH4	L, T2
5.B	Biological treatment of Solid waste - N2O	L2, T2
5.D	Wastewater treatment and discharge - CH4	L, T2
5.D	Wastewater treatment and discharge - N2O	L2, T2
	Indirect CO2 emissions	L2

If considering emissions and removals from the LULUCF sector, 51 key categories were identified, as reported in Table 1.6.

Table 1.6 Key categories (including LULUCF) by IPCC Approach 1 and Approach 2. Year 2024

<i>Key categories (including the LULUCF sector)</i>		
1.A.1	Energy industries - CO2 gaseous fuels	L, T
1.A.1	Energy industries - CO2 liquid fuels	L, T
1.A.1	Energy industries - CO2 solid fuels	L1, T
1.A.2	Manufacturing industries and construction - CO2 gaseous fuels	L, T
1.A.2	Manufacturing industries and construction - CO2 liquid fuels	L, T
1.A.2	Manufacturing industries and construction - CO2 solid fuels	L1, T
1.A.3.a	Transport – CO2 Civil aviation	L1, T1
1.A.3.b	Transport - CO2 Road transportation	L, T
1.A.3.b	Transport – N2O Road transportation	L2
1.A.3.d	Transport - CO2 Waterborne navigation	L1, T1
1.A.4	Other sectors - CH4 commercial, residential, agriculture biomass	L, T
1.A.4	Other sectors - CO2 commercial, residential, agriculture gaseous fuels	L, T
1.A.4	Other sectors - CO2 commercial, residential, agriculture liquid fuels	L, T
1.A.4	Other sectors - CO2 commercial, residential, agriculture other fossil fuels	L1, T1
1.A.4	Other sectors - N2O commercial, residential, agriculture biomass	L2, T2
1.B.2.b	Fugitive - CH4 Oil and natural gas - Natural gas	L, T
1.B.2.c	Fugitive – CO2 Oil and natural gas - Oil	L1
1.B.2.d	Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	T2
2.A.1	Mineral industry- CO2 Cement production	L, T
2.A.2	Mineral industry- CO2 Lime production	L1
2.A.4	Mineral industry- CO2 Other processes uses of carbonates	T1
2.B.2	Chemical industry- CO2 Ammonia production	T1
2.B.2	Chemical industry- N2O Nitric acid production	T1

L1 = level key category, Approach 1
T1 = trend key category, Approach 1
L2 = level key category, Approach 2
T2 = trend key category, Approach 2
L = level key category, Approach 1 and Approach 2
T = trend key category, Approach 1 and Approach 2

<i>Key categories (including the LULUCF sector)</i>		
2.B.3	Chemical industry- N2O Adipic acid production	T
2.C.1	Metal industry- CO2 Iron and steel production	T1
2.C.3	Metal industry- PFCs Aluminium production	T
2.F.1	Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	L, T
2.F.2	Product uses as substitutes for ozone depleting substances - HFCs Foam blowing agents	T2
2.F.3	Product uses as substitutes for ozone depleting substances - HFCs Fire protection	T2
3.A.1	Enteric Fermentation- CH4	L, T
3.A.2	Manure Management - CH4	L, T1
3.A.2	Manure Management - N2O	L1
3.C.4	Direct N2O Emissions from Managed soils	L, T
3.C.5	Indirect N2O Emissions from Managed soils	L, T2
3.C.7	Rice cultivations - CH4	L1
4.A.1	Forest Land remaining Forest Land – DOM - CO2	T
4.A.1	Forest Land remaining Forest Land – Living biomass - CO2	L, T
4.A.2	Land Converted to Forest Land – DOM - CO2	L
4.A.2	Land Converted to Forest Land – Soils - CO2	L, T
4.A.2	Land Converted to Forest Land – Living biomass - CO2	L, T
4.B.1	Cropland Remaining Cropland – Living biomass - CO2	L1, T1
4.B.1	Cropland Remaining Cropland – Mineral soils - CO2	L, T
4(II)	Cropland Remaining Cropland – Organic soils - CO2	L2, T2
4.B.2	Land Converted to Cropland – Mineral soils -CO2	L2
4.C.1	Grassland Remaining Grassland – Living biomass - CO2	L, T
4.C.2	Land Converted to Grassland – Mineral soils CO2	L, T
4.E.2	Land Converted to Settlements - CO2	L, T
4.G	Harvest wood product – CO2	L, T
5.A	Solid waste disposal - CH4	L, T
5.B	Biological treatment of Solid waste - N2O	L2, T2
5.D	Wastewater treatment and discharge - CH4	L, T2
5.D	Wastewater treatment and discharge - N2O	L2, T2
	Indirect CO2 emissions	L2

The analysis of key categories is used to prioritize improvements that should be taken into account for the next inventory submissions. First of all, it is important that emissions of key categories, being the most significant in terms of absolute weight and/or combined uncertainty, are estimated with a high level of accuracy. For the Italian inventory, higher tiers are mostly used for calculating emissions from these categories as requested by the IPCC Guidelines and the use of country specific emission factors is extensive. There are only a few key categories which estimates do not meet these quality objectives, in terms of the methodology and the application of default emission factors.

Among these categories, prioritization is made on account of the actual absolute weight, the expected future relevance, the level of uncertainty and a cost-effectiveness analysis. Therefore, improvements are planned for the LULUCF sector as well as for maritime navigation category, which emissions are estimated with a Tier1 and with Tier 2 for few years and has been selected as a priority after verification of the availability of annual detailed activity data, the evaluation of the resources and cost of the database to be implemented.

In addition to this evaluation, also categories estimated with higher tiers but affected by a high level of uncertainty are considered in the prioritization plan. For instance, activities were planned and are ongoing

for HFC, PFC substitutes for ODS to improve the accuracy of the Italian inventory and reduce the overall uncertainty.

1.6 Information on the QA/QC plan including verification and treatment of confidentiality issues where relevant

ISPRA has elaborated an inventory QA/QC plan which describes specific QC procedures to be implemented during the inventory development process, facilitates the overall QA procedures to be conducted, to the extent possible, on the entire inventory and establishes quality objectives.

Particularly, an inventory QA/QC procedures manual (ISPRA, 2013) describes QA/QC procedures and verification activities to be followed during the inventory compilation and helps in the inventory improvement. Furthermore, specific QA/QC procedures and different verification activities implemented thoroughly the current inventory compilation, as part of the estimation process, are figured out in the annual QA/QC plan (ISPRA, 2026 [a]). These documents are publicly available at ISPRA website <https://emissioni.sina.isprambiente.it/inventario-nazionale/>.

Quality control checks and quality assurance procedures together with some verification activities are applied both to the national inventory as a whole and at sectoral level. Future planned improvements are prepared for each sector by the relevant inventory compiler; each expert identifies areas for sectoral improvement based on his own knowledge and in response to the UNFCCC inventory reviews and considering the result of the key category assessment.

The quality of the inventory has improved over the years, and further investigations are planned for all those sectors relevant in terms of contribution to total CO₂ equivalent emissions and with high uncertainty.

In addition to *routine* general checks, source specific quality control procedures are applied on a case-by-case basis focusing on key categories and on categories where significant methodological and data revision have taken place or on new sources. Checklists are compiled annually by the inventory experts and collected by the QA/QC coordinator. These lists are also registered in the 'reference' database. General QC procedures also include data and documentation gathering. Specifically, the inventory analyst for a source category maintains a complete and separate project archive for that source category; the archive includes all the materials needed to develop the inventory for that year and is kept in a transparent manner.

All the information used for the inventory compilation is traceable back to its source. The inventory is composed of spreadsheets to calculate emission estimates; activity data and emission factors as well as methodologies are referenced to their data sources. Attention is paid to the archiving and storing of all inventory data, supporting information, inventory records as well as all the reference documents. To this end, a major improvement which increases the transparency of the inventory has been the development of a 'reference' database. After each reporting cycle, all database files, spreadsheets and official submissions are archived as 'read-only' mode in a master computer.

Quality assurance procedures regard some verification activities of the inventory as a whole and at a sectoral level. Feedback for the Italian inventory derive from communication of data to different institutions and/or at local level. For instance, the communication of the inventory to the European Community results in a pre-check of the GHG values before the submission to the UNFCCC and relevant inconsistencies may be highlighted.

Every year, emission figures are also subjected to a process of re-examination once the inventory, the inventory related publications and the national inventory reports are posted on website, specifically www.isprambiente.gov.it, and from the communication of data to different institutions and/or at local level. In some cases, sectoral major recalculations are presented and shared with the relevant stakeholders prior to the official submission.

For the energy and industrial sectors, different meetings were held in the last years jointly with the industrial associations, the Ministries of the Environment and ISPRA in the framework of the European Emissions Trading Scheme (EU-ETS), for assessing carbon leakage in EU energy intensive industries and the definition of GHG emission benchmarks; also in this context, estimations of the emission inventory for different sectors were presented.

ISPRA collects data from the industrial associations and industrial facilities under the EU- ETS and other European legislation such as Large Combustion Plant Directive and E-PRTR Regulation. The inventory team manages all these data and makes use of them in the preparation of the national inventory, ensuring the consistency of the time series by the comparison of the information collected under the directives with other sources available before the Regulations. Emissions and activity data submitted under the ETS are mandatorily subject to verification procedures, as requested and specified by the European Directive 2003/87/EC (art. 15 and Annex V). Also, the quality of the Italian PRTR data is guaranteed by art.9 of the Regulation 2006/166/EC and by art.3(3) of the Presidential Decree n.157/2011.

ISPRA manages all this information in an informative system to help in highlighting the main discrepancies among data and improving the time series consistency. The informative system is based on identification codes to trace back individual point sources in different databases.

ISPRA is also responsible for the provincial inventory on the local scale; at now the provincial inventories at local scale for the years 1990, 1995, 2015, 2019 and 2023 are available. In fact, every 5 years, and now every 4 years, in the framework of the Protocol on Long-term Financing of the Cooperative Programme for Monitoring and Evaluation of the Long-range Transmission of Air Pollutants in Europe (EMEP) under the Convention on Long-range Transboundary Air Pollution (CLTRAP), Parties have to report their national air emissions disaggregated on a 0.1°*0.1° grid. Specifically, ISPRA has applied a top-down approach to estimate emissions at provincial areas based on proxy variables. The results were checked out by regional and local environmental agencies and authorities; data are available at ISPRA web address <https://emissioni.sina.isprambiente.it/inventari-locali/>. The last report which describes detailed methodologies to carry out estimates is available (ISPRA, 2022). Comparisons between top-down and local inventories have been carried out during the last year and will continue in the next years; results are shared among the 'local inventories' expert group leading to an improvement in methodologies for both the inventories. ISPRA has also collaborated with local authorities to assess the participation of the Italian municipalities to the Covenant of Mayors (<http://www.isprambiente.gov.it/it/pubblicazioni/rapporti/stato-di-attuazione-del-patto-dei-sindaci-in-italia>).

A specific procedure undertaken for improving the inventory regards the establishment of national expert panels (in particular, in road transport, LULUCF and energy sectors) which involve, on a voluntary basis, different institutions, local agencies and industrial associations cooperating for improving activity data and emission factors accuracy.

The quality of the inventory has also improved through organization and participation in sector-specific workshops. Follow-up processes are also set up in the framework of the WGI and WG5 under the EC Monitoring Mechanism, which addresses the improvement of different inventory sectors.

Especially in the last years, there has been an intensification of activities related to emission scenarios, and the importance of the emission inventory as a solid starting point is primary. The inventory is shared with the Ministry of the Environment, and all the relevant Ministries and local authorities.

In this context, from 2011, a report concerning the state of implementation of commitments to reduce greenhouse gases emissions, and describing emission trends and projections, is prepared by the MASE in consultation with other relevant Ministries. The report is annexed to the economy and financial document (DEF) to be annually approved by the Government.

Expert peer reviews of the national inventory occur annually within the UNFCCC process, whose results and suggestions can provide valuable feedback on areas where the inventory should be improved. The last review occurred in 2025. The final report will be available at the relevant UNFCCC web site address

<https://unfccc.int/first-biennial-transparency-reports> and details on the review processes and implementation of the comments and potential recommendations are described in Annex 10 and in relevant sections.

At European level, reviews of the European inventory are undertaken by experts from different Member States for critical sectoral categories. Moreover, in the context of the European Effort Sharing Decision (EC, 2009), in 2021, a detailed review of the Italian inventory was conducted.

An official independent review of the entire Italian greenhouse gas inventory was undertaken by the Aether consultants in 2013. Main findings and recommendations regard mostly the transparency in the NIR, the improvement of QA/QC documentation.

The preparation of environmental reports where data are needed at different aggregation levels or refer to different contexts, such as environmental and economic accounting, is also a check for emission trends. At national level, for instance, emission time series are reported in the Environmental Data Yearbooks published by ISPRA. Moreover, figures are communicated to the National Institute of Statistics to be used in the framework of the EUROSTAT NAMEA Project.

At European level, ISPRA also reports on indicators meeting the requirements of Article 13 of EU Regulation 1999/2018. Member States shall submit figures on specified indicators. These indicators are reported in the document 'Carbon Dioxide Intensity Indicators' (ISPRA, 2026 [b]).

Comparisons between emission estimates from industrial sectors and those published by industry in their Environmental reports are carried out annually to assess the quality and the uncertainty of the estimates.

Additional consistency checks of data are carried out in the context of the European Regulation No 1999/2018. EU Member States shall report in textual and tabular format on data inconsistencies.

For example, data on air pollutants estimated under the UNECE Convention on Long-range Transboundary Air Pollution and those under the UNFCCC Convention should not exceed the difference of more than $\pm 5\%$ between the total emissions for a specific pollutant otherwise text and a tabular format should be compiled by the Member State. As shown in chapter 2, para 2.4, these differences for Italy are far under the threshold.

Other relevant articles of the EU Regulation are related to the consistency of reported GHG emissions under UNFCCC with data from the EU emissions trading system by category, and to consistency of energy statistics considering the apparent consumption calculated on the basis of the data included in the GHG inventory and the reference approach calculated on the basis of the energy data reported to Eurostat.

If these differences are higher than $\pm 2\%$, in the total national apparent fossil fuel consumption at aggregate level for all fossil fuel categories, a tabular format shall also be compiled. For Italy these differences are below the determined threshold.

The detailed tables are included in Annex 10 of the NID.

A summary of all the main QA/QC activities over the past years which ensure the continuous improvement of the inventory is presented in the document 'Quality Assurance/Quality Control plan for the Italian Emission Inventory. Year 2026' (ISPRA, 2026 [a]).

A proper archiving and reporting of the documentation related to the inventory compilation process is also part of the national QA/QC programme.

All the material and documents used for the inventory preparation are stored at ISPRA. Information relating to the planning, preparation, and management of inventory activities is documented and archived. The archive is organised so that any skilled analyst could obtain relevant data sources and spreadsheets, reproduce the inventory, and review all decisions about assumptions and methodologies undertaken. A master documentation catalogue is generated for each inventory year, and it is possible to track changes in data and methodologies over time. Specifically, the documentation includes:

- electronic copies of each of the draft and final inventory report, electronic copies of the draft and final CRT tables;
- electronic copies of all the final, linked source category spreadsheets for the inventory estimates (including all spreadsheets that feed the emission spreadsheets);
- results of the reviews and, in general, all documentation related to the corresponding inventory year submission.

After each reporting cycle, all database files, spreadsheets and electronic documents are archived.

1.7 General uncertainty evaluation, including data on the overall uncertainty for the inventory totals

The 2006 IPCC Guidelines (IPCC, 2006) define two approaches to estimating uncertainties in national greenhouse gas inventories: Approach 1, based on the error propagation equations, and Approach 2, corresponding to the application of Monte Carlo analysis.

For the Italian inventory, quantitative estimates of the uncertainties are calculated using Approach 1 which application is described in Annex 1, with or without emissions and removals from the LULUCF sector. Emission categories are disaggregated into a detailed level, and uncertainties are therefore estimated for these categories.

For 2024, an uncertainty of 2.5% is estimated for total emission figures without LULUCF, whereas for the trend the analysis assesses an uncertainty of 1.5%. Including the LULUCF sector into national figures, the uncertainty is equal to 6.2% for the year 2024, whereas the uncertainty for the trend is estimated to be 3.7%. The variation in the uncertainty levels, as compared to the previous submission, is mainly due to the recalculation process and consequent different weights of the categories and relevant uncertainties. The assessment of uncertainty has also been applied to the 1990 emission levels. The results show an uncertainty of 2.1% in the combined GWP total emissions, excluding emissions and removals from LULUCF, whereas it increases to 2.4% including the LULUCF sector.

Approach 2, Montecarlo analysis, was implemented in previous submissions to estimate uncertainty of some of the key categories of the Italian inventory. Most of the results prove that both approaches (Approach 1 and 2) produce comparable results and that uncertainty values derived by Approach 2 are lower than those derived from the application of Approach 1. For the description of the categories to which the analysis was applied, reference years and other details, please consult previous NIRs (e.g. NIR, 2022).

QC procedures are also undertaken on the calculations of uncertainties to confirm the correctness of the estimates and that there is sufficient documentation to duplicate the analysis. The assumptions which uncertainty estimations are based on are documented for each category. Figures used to draw up uncertainty analysis are checked both with the relevant analyst experts and literature references and are consistent with the IPCC Guidelines. More in details, facility level data are used to check and verify information from the industrial sector; these data also include information from the European Emissions Trading Scheme and the Italian PRTR register which data are collected and elaborated by the inventory team. Most of the time there is correspondence among activity data from different databases so that the level of uncertainty could be assumed equal or lower than 3%; the same occurs for emission factors coming from measurements at plant level, and even in this case the uncertainty may be assumed lower than the predetermined level. The overall uncertainty of the Italian inventory is relatively low due to the prevalence of the energy sector sources, whose estimates derive from accurate parameters, out of the total, it has been decided to use conservative figures; this occurs especially for energy and industrial sectors. Details can be found at category level in the relevant sections.

The results of the uncertainty analysis, generally associated with a key category assessment by Approach 2, are used to prioritize improvements for the next inventory submissions. Emissions of key categories are usually estimated with a high level of accuracy in terms of the methodology used and characterized by a

low uncertainty; some exceptions may occur and categories estimated with higher tiers may be affected by a high level of uncertainty. For instance, in the agriculture sector, direct N₂O emissions from agricultural soils and indirect N₂O from nitrogen used in agriculture are affected by a high level of uncertainty especially in the emission factors notwithstanding the advanced tiers used. For the categories with a high uncertainty, further improvements are planned whenever sectoral studies can be carried out.

1.8 General assessment of the completeness

The inventory covers all major sources and sinks, as well as direct and indirect gases, included in the IPCC guidelines.

Details are reported in Table 1.7 and Table 1.8. Sectoral and background tables of the CRT are complete as far as details of basic information are available. For instance, multilateral operations emissions are not estimated because no activity data are available.

Allocation of emissions is not consistent with the IPCC Guidelines only where there is no data available to split the information. For instance, for fugitive emissions, N₂O fugitive emissions from oil refining and storage activities are reported under category 1.B.2.d other, flaring in refineries. Further investigation will be carried out closely with industry about these figures.

Table 1.7 Source and sinks not estimated in the 2024 inventory

Sources and sinks not estimated (NE)			
GHG	Sector	Source/sink category	Explanation
N ₂ O	Energy	1.B Fugitive Emissions from Fuels/ 1.B.2 Oil and Natural Gas and Other Emissions from Energy Production/ 1.B.2.d Other /Geotherm	N ₂ O emissions are negligible
CO ₂ CH ₄ , N ₂ O	Energy	1.D.2 Multilateral Operations	Information and statistical data are not available
CH ₄	Agriculture	3.D Agricultural Soils	CH ₄ emissions from managed soils have not been estimated because no methodology is available in the IPCC Guidelines.
CO ₂ CH ₄ , N ₂ O	LULUCF	4.E Settlements/4(V) Biomass Burning 4.E Settlements	Emissions are considered insignificant, below 0.05% of the national total GHG emissions, and minor than 500 kt CO ₂ eq.

Table 1.8 Source and sinks reported elsewhere in the 2024 inventory

Sources and sinks reported elsewhere (IE)				
GHG	Source/sink category	Allocation as per IPCC Guidelines	Allocation used by the Party	Explanation
CO ₂	1.AD Feedstocks, reductants and other non-energy use of fuels/Liquid Fuels/Gasoline	1.AD Liquid fuel/Gasoline/LPG/ Other Oil/Refinery feedstock/Residual oil	1.AD Liquid fuel/Naphta	National energy balances include only the input and output quantities from the petrochemical plants; so in the petrochemical transformation process the output quantity could be greater than the input quantity, in particular for light products as LPG, gasoline and refinery gas, due to chemical reactions. Therefore, it is possible to have negative values for some products (mainly gasoline, refinery gas, fuel oil). For this matter, for the reporting on CRF tables, these fuels have been added to naphtha.

Sources and sinks reported elsewhere (IE)				
GHG	Source/sink category	Allocation as per IPCC Guidelines	Allocation used by the Party	Explanation
N ₂ O	1.B Fugitive Emissions from Fuels/ 1.B.2 Oil and Natural Gas and Other Emissions from Energy Production/ 1.B.2.a Oil/ 1.B.2.a.4 Refining / Storage	1.B.2.a.4 Refining/storage	1.B.2.d flaring in refineries	No information is available to split the emissions
CO ₂	2.C Metal Industry/ 2.C.5 Lead Production	2.C.5. Lead Production	2.C.6 Zinc production	CO ₂ emissions from the sole zinc and lead integrated plant in Italy have been estimated. The available data do not allow to distinguish between zinc and lead emissions.
CO ₂	4.A Forest Land/4.A.1 Forest Land Remaining Forest Land/4(V) Biomass Burning/Wildfires	4.A.1 4(V) Biomass Burning/Wildfires	4.A.1, Carbon stock change in living biomass	CO ₂ emissions due to wildfires in forest land remaining forest land are included in table 4.A.1, Carbon stock change in living biomass, Losses
CO ₂	4.A Forest Land/4.A.2 Land Converted to Forest Land/4(V) Biomass Burning/Wildfires	4.A.2 4(V) Biomass Burning/Wildfires	4.A.2, Carbon stock change in living biomass	CO ₂ emissions due to wildfires in forest land remaining forest land are included in table 4.A.2, Carbon stock change in living biomass, Losses
N ₂ O	4.A Forest Land/4.A.1 Forest Land Remaining Forest Land/4(I) Direct N ₂ O Emissions from N Inputs to Managed Soils/Inorganic N Fertilizers	4(I) Direct N ₂ O Emissions from N Inputs to Managed Soils/Inorganic N Fertilizers	3.D.1 Direct N ₂ O emissions from managed soils	N inputs to managed soils are reported in the agriculture sector
CO ₂	4.G Harvested Wood Products/Approach B/Approach B2/Total HWP from Domestic Harvest/HWP Produced and Exported/Solid Wood/Sawnwood and Wood panels	Solid Wood/Sawnwood and Wood panels in HWP Produced and exported	Solid Wood/Sawnwood and wood panels in HWP produced and consumed domestically	HWP produced and exported are included in the HWP produced and consumed domestically

2 TRENDS IN GREENHOUSE GAS EMISSIONS

2.1 Description and interpretation of emission trends for aggregate greenhouse gas emissions

Summary data of the Italian greenhouse gas emissions for the years 1990-2024 are reported in Tables A8.1.1- A8.1.5 of Annex 8.

Total greenhouse gas emissions, in CO₂ equivalent, excluding emissions and removals from LULUCF and including indirect emissions, have decreased by 30.2% between 1990 and 2024, varying from 521 to 363 CO₂ equivalent million tons (Mt). Table 1 shows the trend of national greenhouse gases, expressed in CO₂ equivalent terms and by substance; emissions are reported excluding and including emissions and removals from LULUCF and with indirect emissions which, for Italy, equals the total emissions.


CO₂, the most significant greenhouse gas, represents 81.4% of total emissions in CO₂ equivalent and has declined by 31.9% between 1990 and 2024. Specifically, CO₂ emissions from the energy sector in 2024 are 30.9% lower than in 1990. In the same year, CH₄ and N₂O contributed 11.8% and 3.8% of total CO₂ equivalent emissions, respectively. Between 1990 and 2024, CH₄ emissions fell by 21.8%, while N₂O emissions decreased by 39.0%. Other greenhouse gases account for smaller shares: HFCs make up 1.8% of total emissions, PFCs and SF₆ each represent about 0.1%, and NF₃ contributes less than 0.01%.

Table 2.1 Greenhouse gas emissions and removals from 1990 to 2024 by gas (kt CO₂ eq.)

GHG emissions	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ equivalent</i>										
CO ₂ excluding net CO ₂ from LULUCF	438,208	448,596	469,598	501,365	434,573	359,658	300,706	334,095	336,796	309,321	298,490
CO ₂ including net CO ₂ from LULUCF	423,941	413,046	438,806	456,835	387,059	311,845	256,426	288,796	291,187	251,103	233,880
CH ₄ excluding CH ₄ from LULUCF	55,016	57,139	57,833	54,793	52,784	49,089	47,054	46,565	45,120	44,269	43,003
CH ₄ including CH ₄ from LULUCF	55,843	57,411	58,331	55,062	53,078	49,328	47,327	47,159	45,593	44,620	43,273
N ₂ O excluding N ₂ O from LULUCF	22,603	24,213	25,018	24,404	16,631	15,091	15,277	15,210	13,558	14,268	13,789
N ₂ O including N ₂ O from LULUCF	23,094	24,468	25,331	24,609	16,850	15,220	15,503	15,621	13,909	14,570	14,061
HFCs	372	1,100	3,748	9,669	12,790	11,786	9,415	8,806	8,279	7,726	6,670
PFCs	2,615	1,351	1,363	1,759	1,377	1,540	516	413	462	297	280
Unspecified mix of HFCs and PFCs	NA,NO	24	24	24	24	24	22	25	22	29	33
SF ₆	421	700	621	565	405	483	252	282	405	367	328
NF ₃	NA,NO	77	13	33	20	28	16	15	20	20	26
Indirect CO ₂	1,391	1,296	1,173	1,155	976	815	876	858	790	843	871
Total (excluding LULUCF, with CO₂ indirect)	520,626	534,495	559,393	593,769	519,581	438,515	374,134	406,270	405,451	377,139	363,490
Total (including LULUCF, with CO₂ indirect)	507,677	499,472	529,411	549,712	472,579	391,070	330,352	361,976	360,667	319,575	299,422

Figure 2.1 illustrates the national trend of greenhouse gases, expressed in CO₂ equivalent terms and by substance; total emissions do not include emissions and removals from land use, land use change and forestry.


Figure 2.1 National greenhouse gas emissions from 1990 to 2024 (without LULUCF) (Mt CO₂ eq.)



The share of the different sectors, in terms of total emissions, remains nearly unvaried over the period. Specifically, for the year 2024, the greatest part of the total greenhouse gas emissions is to be attributed to the energy sector, with a percentage of 81.0%, followed by agriculture and industrial processes and product use, accounting for 7.7% and 5.5%, respectively, and waste contributing with 5.5% to total emissions.

Total greenhouse gas emissions and removals, including LULUCF sector, are shown in Figure 2.2 subdivided by sector.

Figure 2.2 Greenhouse gas emissions and removals from 1990 to 2024 by sector (Mt CO₂ eq.)




In 2024, considering the total GHG emissions (including the absolute value of net LULUCF emissions/removals), the percentage contribution of the sectors is: 70.2% for energy, 7.4% for agriculture, 5.4% for industrial processes and product use, 12.2% for LULUCF and 4.6% for waste.

2.2 Description and interpretation of emission trends by gas

2.2.1 Carbon dioxide emissions

CO₂ emissions, without LULUCF, decreased by 31.9% from 1990 to 2024, ranging from 438 to 298 million tons. The largest sources of emissions are transport (37.5%) and energy industries (21.2%). Non-industrial combustion accounts for 20.8% and manufacturing and construction industries for 15.1%, while the remaining emissions from energy sector accounts for 0.8%. Emissions from the energy sector's other categories represent 0.8%. Industrial processes, including indirect CO₂ emissions, make up 4.4%, and the agriculture and waste sectors together contribute 0.2%.

Figure 2.3 CO₂ emissions by category from 1990 to 2024 (Mt)




The reduction in CO₂ emissions has been mainly driven by significant decreases in the energy industries and in manufacturing industries and construction categories. Between 1990 and 2024, emissions from energy industries fell by 53.6%, while those from manufacturing industries and construction declined by 50.1%. The transport sector experienced rising emissions until 2007, followed by a decline due to the economic recession and the increased adoption of low fuel-consumption vehicles; however, emissions remain higher than their 1990 levels. Non-industrial combustion emissions have decreased by 18.4% since 1990, with their trend largely influenced by annual climatic variations. Emissions from industrial processes decreased by 55.4%, mainly because of reduced cement production.

Figure 2.4 illustrates the performance of the following economic and energy indicators:

- Gross Domestic Product (GDP), market prices chain linked values 2015 (base year 1990=100);
- Total Energy Consumption;
- CO₂ emissions, excluding emissions and removals from land-use change and forests;
- CO₂ *intensity*, which represents CO₂ emissions per unit of total energy consumption.

CO₂ emissions in the 1990s essentially mirrored energy consumption. In recent years, a clear decoupling between GDP and CO₂ emissions can be observed. This trend is mainly associated with the gradual substitution of high-carbon fuels with methane gas in electricity generation and industry. In addition, the increasing penetration of renewable energy sources has contributed to a significant reduction in CO₂ intensity. The COVID-19 pandemic in 2020 caused a sharp decline in emissions and a slowdown in economic activity. In the following years, a rebound in economic growth occurred, while emissions remained comparatively lower, confirming the ongoing decoupling between economic development and carbon emissions.

Figure 2.4 Energy-related and economic indicators and CO₂ emissions



2.2.2 Methane emissions


In 2024, methane emissions, excluding LULUCF, accounted for 11.8% of total greenhouse gas emissions, amounting to 43.0 Mt CO₂ equivalent. This represents a 21.8% reduction compared to 1990 levels. In 2024, the majority of CH₄ emissions came from the agriculture sector (45.1%), followed by waste (42.4%) and energy (12.4%) sectors.

Within the agriculture sector, emissions primarily stem from enteric fermentation (69.6%) and manure management (21.1%). Overall, agricultural emissions have declined by 21.2% compared to 1990 levels, largely due to a reduction in livestock numbers and the recovery of biogas for energy use, particularly in swine and poultry farming.

In the waste-management sector, methane emissions mainly arise from the operation of dumping sites and the treatment of industrial wastewater. Compared to 1990, CH₄ emissions from this sector have increased by 5.4%. The largest share of emissions comes from solid waste disposal on land (84.5%), followed by wastewater handling (14.5%). Emissions from solid waste disposal have risen by 12.8%, whereas those from wastewater treatment have decreased by 26.0% over the same period.

In the energy sector, the reduction of CH₄ emissions (-58.9%) is the result of two contrasting factors: on the one hand there has been a considerable reduction in emissions deriving from energy industries, transport, fugitive emissions from fuels (caused by leakage from the extraction and distribution of fossil fuels, due to the gradual replacement of natural-gas distribution networks), on the other hand a strong increase in the non-industrial combustion category can be observed, as a result of the increased use of methane and biomass in heating systems. Figure 2.5 shows the emission figures by sector.

Figure 2.5 National CH₄ emissions by sector from 1990 to 2024 (kt)



2.2.3 Nitrous oxide emissions

In 2024, nitrous oxide (N₂O) emissions, excluding LULUCF, accounted for 3.8% of total greenhouse gas emissions. Between 1990 and 2024, these emissions declined by 39.0%, falling from 22.6 to 13.8 Mt CO₂ equivalent. The agricultural sector is the primary source of N₂O emissions, contributing 59.3% of the total. Emissions mainly result from the application of chemical and organic fertilizers, as well as from the management of animal waste. Over the 1990–2024 period, agricultural N₂O emissions decreased by 25.2%, largely due to a reduction in livestock numbers.


Emissions from the energy sector, which account for 25.1% of total N₂O emissions, declined by 15.4% between 1990 and 2024. This decrease is largely attributable to a 47.8% reduction in emissions from the manufacturing and construction industries, responsible for 4.5% of total N₂O emissions, mainly due to the decline in cement production in recent years. However, this downward trend has been partly offset by a 9.9% increase in emissions from the “other sectors” category, which represents 12.3% of total N₂O emissions, driven by the growing use of biomass in heating systems.

In the industrial processes sector, N₂O emissions have fallen by 92.3% between 1990 and 2024. This sharp decline is almost entirely attributable to the installation of abatement technologies in nitric and adipic acid production plants, which have substantially reduced process-related emissions. An additional contributing factor has been the reduced use of N₂O for medical purposes.

Emissions from the waste sector, which account for 12.0% of national N₂O emissions, mainly arise from the treatment of industrial and domestic wastewater, as well as from the biological treatment of solid waste.

Figure 2.6 shows national emission figures by sector.

Figure 2.6 National N₂O emissions by sector from 1990 to 2024 (kt)




2.2.4 Fluorinated gas emissions

Overall, fluorinated gases accounted for 2.0% of total greenhouse gas emissions in CO₂ equivalent in 2024, showing a marked increase compared to 1990. This overall rise reflects differing trends among the various gases. HFCs, for example, increased substantially over the 1990–2024 period, from 0.4 to 6.6 Mt CO₂ equivalent. The main emission sources include the use of HFC-134a, HFC-125, HFC-32 and HFC-143a in refrigeration and air-conditioning equipment, as well as HFC-134a in pharmaceutical aerosols. The growth in emissions is attributable both to the replacement of ozone-depleting substances and to the expanded use of air conditioning, particularly in vehicles. By contrast, PFC emissions declined by 89.4% between 1990 and 2024. In 2024, PFC emissions amounted to 0.3 Mt CO₂ equivalent, mainly arising from by-product emissions in fluorochemical production (63.9%) and from their use in semiconductor manufacturing (31.6%).

Emissions of SF₆ are equal to 0.3 Mt in CO₂ equivalent in 2024, with a decrease of 22.1% as compared to 1990 levels. In 2024, 75.3% of SF₆ emissions derive from 2.G Other product Manufacture and use category (91.3% from electrical equipment and from the use of this substance in accelerators 8.7%). The remaining 24.7% comes from the semiconductors manufacture. NF₃ emissions accounted for 0.03 Mt in CO₂ equivalent in 2024 and derive from the semiconductors industry.

Figure 2.7 National emissions of fluorinated gases by sector from 1990 to 2024 (kt CO₂ eq.)



2.3 Description and interpretation of emission trends by source

2.3.1 Energy

Emissions from the energy sector account for 81.0% of total national greenhouse gas emissions, excluding LULUCF, in 2024. Emissions in CO₂ equivalent from the energy sector are reported in Table 2.2 and Figure 2.8.

Table 2.2 Total emissions from the energy sector by category (1990-2024) (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt CO ₂ eq.										
Total emissions	426,248	438,789	460,604	488,371	428,785	358,354	298,120	330,181	333,377	305,141	294,526
Fuel Combustion (Sectoral Approach)	412,012	425,367	448,484	477,764	419,122	349,698	291,961	324,575	328,355	300,637	290,075
Energy Industries	137,667	140,676	144,963	159,922	137,478	106,064	81,646	85,870	94,527	75,206	63,857
Manufacturing Industries and Construction	92,151	90,204	96,245	92,299	70,048	55,569	45,839	55,140	53,468	49,645	46,159
Transport	102,191	114,216	123,954	128,362	115,900	106,679	86,521	102,861	108,935	108,905	113,282
Other Sectors	78,868	78,713	82,444	95,867	95,008	80,918	77,317	80,384	70,903	66,510	66,160
Other	1,136	1,559	877	1,314	688	468	638	321	521	371	617
Fugitive Emissions from Fuels	14,236	13,422	12,120	10,607	9,663	8,656	6,159	5,606	5,022	4,504	4,451
Solid Fuels	148	83	109	101	97	59	29	28	30	29	25
Oil and Natural Gas	14,088	13,339	12,012	10,506	9,566	8,597	6,130	5,578	4,992	4,475	4,426

From 2005, GHG emissions from the energy sector have been decreasing because of the policies adopted at European and national level to implement the production of energy from renewable sources. From the same year, a further shift from petrol products to natural gas in producing energy has been observed as a consequence of the starting of the EU greenhouse gas Emission Trading Scheme (EU ETS). From 2009, a further drop in the sectoral emissions is due to the economic recession; an increase is observed only from 2009 to 2010 (+2.7%) and since then, in 2020 and 2021, for the recovery from the pandemic period. Total greenhouse gas emissions, in CO₂ equivalent, show a decrease of about 30.9% from 1990 to 2024; in particular, an upward trend is noted from 1990 to 2005, with an increase by 14.4%, while between 2005 and 2024 emissions decreased by 39.6%.


The GHG with the highest impact, in the energy sector, is CO₂, accounting for 97.0% of the sectoral total, in 2024, whose levels have decreased by 30.2% from 1990 to 2024. In the same year, CH₄ emissions account for 1.8% of the sectoral total. Their trend shows a decrease of 58.9% from 1990 to 2024, driven by the combined effect of technological improvements that limit volatile organic compounds (VOCs) from tail pipe and evaporative emissions (for cars) and the expansion of two-wheelers fleet. N₂O shows a decrease of 15.4% with a share out of the total equal to 1.2%, mainly driven by the technological development in road transport and to the switch from gasoline to diesel fuel consumption.

Overall, the sector's emission reductions over the period are primarily driven by declines in the energy industries and the manufacturing and construction. In 2024, these sectors accounted for 21.7% and 15.7% of total emissions, with reductions of 53.6% and 49.9%, respectively. For manufacturing industries and construction, the decrease is largely due to lower production in certain subsectors, such as chemicals, construction materials, and steel, resulting from the economic recession, as well as improvements in efficiency, particularly in the chemical industry. Emissions also declined in the other sectors category by 16.1%, which accounted for 22.5% of total emissions in 2024. By contrast, the transport sector, representing 38.5% of emissions in 2024, experienced an increase of 10.9%.

Road transport is the most relevant source in the transport sector, accounting in 2024 for 28.8% of total national CO₂ equivalent emissions.

The increase in other sectors, which refer to emissions originated from energy use in the civil sector and from military mobile activities, is due, from 1990 to 2000, to the increase in numbers and size of building with heating, and to the trend in weather conditions, while from 2002, and especially in the last few years, to the increase in other greenhouse gas emissions than CO₂ for the growing use of woody biomass and biogas for heating. Details on these figures are described in the specific chapter.

Figure 2.8 Trend of total emissions from the energy sector (1990-2024) (kt CO₂ eq.)



2.3.2 Industrial processes and product use

Emissions from the industrial processes and product use sector account for 5.5% of total national greenhouse gas emissions, excluding LULUCF, in 2024. Emission trends from industrial processes are reported in Table 2.3 and Figure 2.9. Total emissions, in CO₂ equivalent, show a decrease of 47.0%, from 1990 to 2024. Considering emissions by substance, CO₂ and N₂O decreased by 54.8% and 92.3%, respectively, including the indirect CO₂ emissions; in terms of their weight out of the sectoral total emissions, CO₂ accounts for 62.5% and N₂O for 2.4%. CH₄ decreased by 78.7% but it accounts for only 0.1%.


The decrease in emissions is mostly to be attributed to a decrease in the mineral and chemical industries. Emissions from mineral production decreased by 54.6%, mostly for the reduction of cement production. The decrease of GHG emissions in the chemical industry (63.0%) is due to the decreasing trend of the emissions from nitric acid and adipic acid production (the last production process sharply reduced its emissions, due to a fully operational abatement technology). On the other hand, from 1990 to 2024, a considerable increase is observed in F-gas emissions (115.3%), whose share on total sectoral emissions is 35.0% in the last reporting year. The main causes of the increase are the consumptions of HFCs in refrigeration and air-conditioning devices, together with their use in pharmaceutical aerosols (see section 2.2.4). Details for industrial processes and product use emissions can be found in the specific chapter.

Table 2.3 Total emissions from the industrial processes sector by gas (1990-2024) (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ eq.</i>										
Total emissions	39,337	37,595	39,414	48,290	37,555	29,619	24,612	25,570	23,620	22,536	20,978
CO ₂	29,383	27,345	25,916	28,817	21,784	15,165	13,794	15,478	13,915	13,542	13,117
CH ₄	144	150	82	83	67	48	38	45	39	36	31
N ₂ O	6,402	6,848	7,646	7,338	1,088	545	559	505	480	519	495
F-gases	3,408	3,252	5,770	12,051	14,616	13,862	10,221	9,542	9,187	8,438	7,336
HFCs	372	1,100	3,748	9,669	12,790	11,786	9,415	8,806	8,279	7,726	6,670
PFCs	2,615	1,351	1,363	1,759	1,377	1,540	516	413	462	297	280
Unspecified mix of HFCs and PFCs	NA,NO	24.4	24.4	24.4	24.4	24.4	22.4	25.3	22.1	28.7	32.7
SF ₆	421	700	621	565	405	483	252	282	405	367	328
NF ₃	NA,NO	76.6	13.3	33.4	20.2	28.4	16.2	15.2	19.5	19.7	25.7

For the description of the sector, Indirect CO₂ emissions have been added up to CO₂ levels.

Figure 2.9 Trend of total emissions from the industrial processes sector (1990-2024) (kt CO₂ eq.)



2.3.3 Agriculture


Emissions from the agriculture sector accounted for 7.7% of total national greenhouse gas emissions, in 2024, excluding LULUCF. Emissions from the agriculture sector are reported in Table 2.4 and Figure 2.10.

Table 2.4 Total emissions from the agriculture sector by source (1990-2024) (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt CO ₂ eq.										
Total emissions	36,045	36,103	35,280	33,039	30,753	30,169	30,881	30,226	28,346	29,283	28,009
Enteric Fermentation	17,174	16,796	16,631	14,521	14,125	14,310	14,815	14,695	14,518	14,314	13,488
Manure Management	8,384	8,016	7,914	7,832	7,475	6,943	6,627	6,474	6,453	6,521	5,960
Rice Cultivation	2,102	2,228	1,855	2,078	2,255	1,943	1,696	1,677	1,547	1,510	1,793
Agricultural Soils	7,856	8,477	8,291	8,022	6,501	6,499	7,225	6,902	5,578	6,481	6,316
Field Burning of Agricultural Residues	19	18	18	22	16	16	14	15	14	15	13
Liming	1	1	2	14	18	14	10	26	4	5	4
Urea application	465	512	525	507	335	425	472	414	218	424	420
Other carbon-containing fertilizers	44	54	44	42	28	20	22	24	14	13	14

Emissions mostly refer to CH₄ and N₂O, which, in 2024, account for 69.2% and 29.2% of the total emissions of the sector, respectively. CO₂ accounts for the remaining 1.6% of total emissions. The decrease observed in total emissions (-22.3%) is mostly due to the decrease of CH₄ emissions from enteric fermentation (-21.5%) and manure management (-22.8%). The decrease of N₂O (-25.2%) from agricultural soils; in 2024 these categories account for 48.2%, 21.3% and 22.5% of the total sectoral emissions, respectively.

Figure 2.10 Trend of total emissions from the agriculture sector (1990-2024) (kt CO₂ eq.)



Main drivers behind these downward trends are the reduction in the number of animals, especially cattle, in the whole period and the reduction of the use of nitrogen fertilizers. In addition, an increase in the recovery of the biogas produced from animal manure and used in the energy sector has occurred in the last years. This biogas has been used for electricity production and the combined electricity and heat production, thus contributing to the reduction of total emissions. Detailed comments can be found in the specific chapter.

2.3.4 LULUCF


Emissions and removals from the LULUCF sector are reported in Table 2.5 and Figure 2.11.

Table 2.5 Total emissions from the LULUCF sector by source/sink (1990-2024) (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt CO₂ eq.</i>										
Total	-12,879	-35,005	-29,941	-44,040	-46,979	-47,434	-43,773	-44,285	-44,774	-57,554	-64,056
Forest land	-20,287	-34,276	-29,897	-38,898	-40,144	-42,172	-39,951	-41,834	-43,601	-52,661	-57,754
Cropland	2,035	1,347	937	-463	323	1,682	3,163	1,494	1,511	1,404	243
Grassland	4,926	-1,919	-1,395	-5,572	-8,279	-8,305	-7,217	-4,274	-3,282	-5,774	-5,660
Wetlands	NE,NO	5	8	8	130	130	32	NE,NO	NE,NO	NE,NO	NE,NO
Settlements	766	527	821	1,371	1,110	1,132	991	1,108	1,103	1,103	1,103
Other land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Harvested wood products	-389	-707	-454	-503	-142	88	-799	-787	-516	-1,637	-2,002
Other (indirect N ₂ O soils)	70	18	40	17	23	11	9	9	10	11	12

LULUCF total removals, in CO₂ equivalent, show a high variability in the period, remarkably influenced by the annual fires' occurrence and the related GHG emissions. CO₂ accounts for 99.2% of total emissions and removals of the sector, as absolute weight. The key driver for the rise in removals is the increase of carbon stock in forest land. Further details for LULUCF emissions and removals can be found in the specific chapter.

Figure 2.11 Trend of total emissions and removals from the LULUCF sector (1990-2024) (kt CO₂ eq.)



2.3.5 Waste


In 2024, emissions from the waste sector accounted for 5.5% of total national greenhouse gas emissions, excluding LULUCF. Emissions from the waste sector are shown in Table 2.6 and Figure 2.12.

Table 2.6 Total emissions from the waste sector by source (1990-2024) (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt CO ₂ eq.										
Total emissions	18,996	22,008	24,094	24,069	22,488	20,373	20,521	20,293	20,108	20,180	19,977
Solid waste disposal	13,671	16,938	19,264	19,043	17,429	15,666	15,925	15,642	15,525	15,643	15,419
Biological treatment of solid waste	23	54	232	456	577	599	560	558	529	501	505
Incineration and open burning of waste	598	547	287	331	270	185	166	184	170	166	164
Waste-water treatment and discharge	4,703	4,469	4,311	4,240	4,212	3,924	3,870	3,909	3,884	3,871	3,889

Total sectoral emissions, in CO₂ equivalent, increased by 5.2% from 1990 to 2024. The trend is mainly driven by the increase in emissions from solid waste disposal (12.8%), accounting for 77.2% of the sectoral total in 2024, counterbalanced by the decrease of emissions from waste-water treatment (-17.3%), accounting for 19.5%. Considering emissions by gas, the most important greenhouse gas is CH₄ which accounts for 91.4% of the sectoral total and shows an increase of 5.4% from 1990 to 2024. N₂O levels have increased by 40.8% while CO₂ decreased by 85.1%; in 2024, these gases account for 8.3% and 0.4%, respectively. Further details can be found in the specific chapter.

Figure 2.12 Trend of total emissions from the waste sector (1990-2024) (kt CO₂ eq.)



2.3.6 Indirect CO₂ emissions

The contribution of indirect CO₂ emissions from atmospheric oxidation of NMVOCs to the greenhouse gas emissions is small, about 0.2% of the total greenhouse gas emissions. Since these emissions are originated from the solvent use category and are part of the national total emissions, they have been included and discussed under CO₂ trend and the industrial process and product use sector.

2.4 Description and interpretation of emission trends for indirect greenhouse gases and SO₂

Emission trends of NO_x, CO, NMVOC and SO₂ from 1990 to 2024 are presented in Table 2.7 and Figure 2.13.


Table 2.7 Total emissions without LULUCF for indirect greenhouse gases and SO₂ (1990-2024) (kt)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt										
NO _x	2,128	1,992	1,522	1,306	966	727	586	598	590	554	539
CO	6,823	7,117	4,813	3,526	3,106	2,300	1,881	2,020	1,785	1,640	1,570
NMVOC	2,008	2,080	1,662	1,375	1,154	944	885	889	825	838	843
SO ₂	1,784	1,323	757	411	222	128	85	79	86	71	70

All gases show a significant reduction in 2024 as compared to 1990 levels. The highest reduction is observed for SO₂ (- 96.0%), NO_x levels have reduced by 74.7%, while CO and NMVOC show a decrease by 77.0% and 58.5%, respectively. A detailed description of the trend by gas and sector can be found in the Italian Informative Inventory Report (ISPRA, 2026 [c]).

The most relevant reductions occurred because of the Directive 75/716/EC, and successive ones related to the transport sector, and of other European Directives which established maximum levels for sulfur content in liquid fuels and introduced emission standards for combustion installations. Therefore, in the combustion processes, oil with high sulfur content and coal have been substituted with oil with low sulfur content and natural gas.

Figure 2.13 Trend of total emissions for indirect greenhouse gases and SO₂ (1990-2024) (kt)



It should be noted that these figures are different from the national totals reported under the *United Nations Economic Commission for Europe (UNECE) Convention on Long Range Transboundary Air Pollution (CLRTAP)*. If total emissions are assessed excluding the LULUCF sector, the differences are to be attributed to the different accounting of emissions from the civil aviation sector. In the national totals under CLRTAP, emissions from aviation are calculated considering all LTO (*Landing and Take-Off*) cycles, both domestic and international, while completely excluding emissions from the cruise phase. When LULUCF is included in national figures, discrepancies are also linked to the treatment of fires. In the UNFCCC national total with LULUCF, emissions from fires in forests, grasslands, and croplands are included. By contrast, these fire-related emissions are not counted in the CLRTAP national total.

Emission trends of NO_x, CO, NMVOC and SO₂, excluding LULUCF, communicated under UNECE CLRTAP are presented in Table 2.8. In the context of the Regulation (EU) 2018/1999 of the European Parliament and of the Council of 11 December 2018 on the Governance of the Energy Union and Climate Action, EU Member States shall report on the consistency of data on air pollutants under the UNECE Convention on Long-range Transboundary Air Pollution and those under the UNFCCC. Differences in percentage terms between figures, without LULUCF, between the two Conventions are illustrated in Table 2.9.

Table 2.8 Total emissions for indirect greenhouse gases and SO₂ (1990-2024) (kt) under UNECE CLRTAP

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt										
NO _x	2,125	1,988	1,516	1,302	961	723	590	609	599	560	543
CO	6,824	7,118	4,814	3,526	3,106	2,301	2,023	2,423	2,091	1,846	1,709
NMVOC	2,008	2,080	1,663	1,375	1,154	944	898	924	852	856	855
SO ₂	1,784	1,322	756	411	222	127	86	82	89	73	71

Table 2.9 Percentage differences between total emissions for indirect greenhouse gases and SO₂ under the UNFCCC and UNECE CLRTAP Conventions (1990-2024)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	%										
NO _x	0.17	0.17	0.41	0.34	0.58	0.46	0.35	0.49	0.61	0.51	0.37
CO	-0.01	-0.01	-0.02	-0.01	0.00	-0.04	0.01	0.03	0.00	-0.03	-0.07
NMVOC	0.00	0.00	-0.01	-0.01	-0.01	-0.01	0.00	0.01	0.00	-0.01	-0.02
SO ₂	0.01	0.02	0.05	0.08	0.17	0.15	0.16	0.28	0.31	0.31	0.21

2.5 Indirect CO₂ and nitrous oxide emissions

Indirect emissions originate from the atmospheric oxidation of CH₄, CO and NMVOCs. CO₂ emissions from the oxidation of NMVOCs from solvent use are reported separately, as indirect CO₂ emissions, following the recommendations of different UNFCCC reviews. Details on how NMVOCs are converted into indirect CO₂ can be found in the sections on indirect CO₂ emissions from non-energy-related products from fuels and solvents in Section 4.5.

Indirect emissions of N₂O take place because of two different nitrogen loss pathways. These pathways are the volatilization/emission of nitrogen as NH₃ and NO_x and the subsequent deposition of these forms of nitrogen as ammonium (NH₄⁺) and oxidized nitrogen (NO_x) on soils and waters, and the leaching and runoff of nitrogen from synthetic and organic nitrogen fertilizer inputs, crop residues, mineralization of nitrogen through land use change or management practices, and urine and dung deposition from grazing animals, into groundwater, riparian areas and wetlands, rivers. All NH₃ or NO_x anthropogenic emissions are potential sources of N₂O emissions. Indirect N₂O emissions are estimated according to Equation 7.1 of the 2006 IPCC Guidelines (IPCC, 2006) based on NO_x and NH₃ national emissions disaggregated at sectoral level (ISPRA, 2021 [a]) and reported as memo item in the relevant sectors, except for the agriculture sector where emissions are already included in the national totals. This method assumes that N₂O emissions from

atmospheric deposition are reported by the country that produced the original NO_x and NH₃ emissions. The ultimate formation of N₂O may occur in another country due to atmospheric transport of emissions. Also, the method does not account for the probable lag time between NO_x and NH₃ emissions and subsequent production of N₂O in soils and surface waters. This time lag is expected to be small related to an annual reporting cycle.

As already stated, total GHG emissions include indirect CO₂ emissions for Italy.

3 ENERGY

3.1 Sector overview

For the pollutants and sources discussed in this section, emissions result from the combustion of fuel. The pollutants estimated are: carbon dioxide (CO₂), NO_x as nitrogen dioxide, nitrous oxide (N₂O), methane (CH₄), non-methane volatile organic compounds (NMVOC), carbon monoxide (CO), sulfur dioxide (SO₂) and ammonia (NH₃). The sources covered are:

- Energy industries (public electricity and heat production, petroleum refining, manufacture of solid fuels and other energy industries);
- Manufacturing industries and construction (iron and steel, non-ferrous metals, chemicals, pulp, paper and print, food processing, beverages and tobacco, non-metallic minerals and other);
- Transport (aviation, road transportation, railways, navigation and other transportation);
- Other sectors (commercial/institutional, residential and agriculture/forestry/fishing);
- Fugitive emissions from fuels.

The national emission inventory is prepared using energy consumption information available from national statistics and an estimate of the use of the fuels.

Estimates for a particular source sector are calculated by applying an emission factor to an appropriate statistic. That is:

$$\text{Total Emission} = \text{Emission Factor} \times \text{Activity Data}$$

Emission factors are typically derived from measurements on several representative sources and the resulting factor applied to the whole country. For some categories, emissions data are available at individual sites. Hence, emissions for a specific category can be calculated as the sum of the emissions from these point sources. That is:

$$\text{Emission} = \sum \text{Point Source Emissions}$$

However, it is necessary to carry out an estimate of the fuel consumption associated with these point sources, so that emissions from non-point sources can be estimated from fuel consumption data without double counting. In general, a point source approach is applied to specific point sources (e.g. power stations, cement kilns, refineries). Most non-industrial sources are estimated using emission factors.

For most of the combustion source categories, emissions are estimated from fuel consumption data reported in the National Energy Balance (BEN) and in the joint questionnaire IEA/EUROSTAT/UNECE and from an emission factor appropriate to the type of fuel. Thus, the estimate from fuel consumption emission factors refers to stationary combustion in boilers and heaters. The other categories are estimated by more complex methods discussed in the relevant sections. However, for these processes, where emissions arise from fuel combustion for energy production, these are reported under IPCC Table 1A. The fuel consumption of Other Industry is estimated so that the total fuel consumption of these sources is consistent with the national energy balance.

Fugitive emissions are estimated and reported under 1B category, and the relevant information is provided in paragraph 3.10.

Emissions from CO₂ storage and distribution category do not occur in Italy, yet.

According to the IPCC 2006 Guidelines (IPCC, 2006), electricity generation by companies primarily for their own use is auto-generation, and the emissions produced should be reported under the industry concerned. However, most national energy statistics (including Italy) report emissions from electricity generation as a

separate category. The Italian inventory makes an overall calculation and then attempts to report as far as possible according to the IPCC methodology:

- auto-generators are reported in the relevant industrial sectors of section “1.A.2 Manufacturing Industries and Construction”, including sector “1.A.2.g Other”;
- refineries auto-generation is included in section 1.A.1.b;
- iron and steel auto-generation is included in section 1.A.1.c;
- autogeneration of energy and heat in the incinerators is reported in 1.A.4.a.

These reports are based on TERNA estimates of fuel used for steam generation connected with electricity production (TERNA, several years).

Emissions from waste incineration facilities with energy recovery are reported under category 1.A.4.a (Combustion activity, commercial/institutional sector), for the fossil and biomass fraction of waste incinerated in the other fuel and biomass subcategories respectively, whereas emissions from other types of waste incineration facilities are reported under category 5.C (Waste incineration). In fact, energy recovered by these plants is mainly used for district heating of commercial buildings or is auto consumed in the plant. For 2024, almost 99% of the total amount of waste incinerated is treated in plants with an energy recovery system. The available literature (ENEA-federAmbiente, 2012) provides that in 2010 the gross electricity production by urban waste incinerators was equal to 3887 GWh (net 3190 GWh) and the amount sent to the network was equal to only 121 GWh. To estimate CO₂ emissions, considering the total amount of waste incinerated in plants with energy recovery, carbon content is calculated, as described in paragraph 7.4.2, in the waste chapter. Different emission factors for municipal, industrial and oils, hospital waste, and sewage sludge are applied, as reported in the waste chapter, Tables 7.19-7.23. Waste amount is then converted into energy content applying the conversion factor resulting from data provided by TERNA and equal in 2024 to 11.2 GJ/t of waste. In 2024, the resulting average emission factor for the fossil part of waste is equal to 81.1 kg CO₂/GJ while for the biomass is equal to 188.4 kg CO₂/GJ.

Recovered landfill gas is used for heating and power in commercial facilities, the resulting emissions are reported under 1.A.4.a in biomass. In 2024, the resulting average emission factor is equal to 50.5 kg CO₂/GJ. Biogas recovered from the anaerobic digester of animal waste is used for utilities in the agriculture sector and relative emissions are reported under 1.A.4.c in biomass. In 2024, the resulting average emission factor is equal to 54.1 kg CO₂/GJ. Italy allocates these emissions to the 1.A.4 category because the energy produced in these plants, incinerators or landfills, as well as energy produced by biogas collection from manure and agriculture residue, is prevalently auto-consumed for heating and electricity of the buildings or animal recoveries, and only a few amount of energy produced goes to the electrical grid.

Emission trends

In 2024, the energy sector accounts for 95.4% of CO₂ emissions, 12.4% of CH₄ and 25.1% of N₂O. In terms of CO₂ equivalent, the energy sector shares 81.0% of total national greenhouse gas emissions excluding LULUCF. Emission trends of greenhouse gases from the energy sector are reported in Table 3.1.

Table 3.1 GHG emission trends in the energy sector 1990-2024 (Mt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total Energy	426.2	438.8	460.6	488.4	428.8	358.4	298.1	330.2	333.4	305.1	294.5
CO₂	409.2	421.5	444.1	472.9	413.2	344.8	287.2	318.9	323.4	296.1	285.7
CH₄	13.0	12.5	11.7	10.7	10.8	9.4	7.2	7.2	6.2	5.4	5.3
N₂O	4.1	4.8	4.8	4.8	4.7	4.2	3.7	4.1	3.9	3.6	3.5

The emission trend is generally driven by economic indicators as already shown in chapter 2. Since 2005, GHG emissions from the sector have been decreasing because of the policies adopted at European and national level to implement the production of energy from renewable sources. From the same year, a

further shift from petrol products to natural gas in producing energy has been observed because of the starting of the EU greenhouse gas Emission Trading Scheme (EU ETS) on January 1st 2005. From 2009, a further drop in the sectoral emissions is due to the economic recession. In general, from 2005 a decrease is observed in total GHG emissions and annual variations are always negative except for 2010, for the recovery of the economy after the economic recession, and 2015, where emissions increase of 3.5% with respect to 2014 due to a reduction in energy production by hydroelectric which resulted in an increase of energy production from thermoelectric plants to satisfy the energy demand. From 2016 the main driver of the decrease of emissions is the shift from coal to natural gas fuel consumption for energy production. In 2020 there is a further significant decrease in emissions due to the pandemic and the consequent lock-down regime to which the country has been subjected. In 2021 the end of the pandemic and recovery of economy resulted in an increase of emissions with respect to the previous year but the political crisis and the outbreak of conflict in Europe have strongly affected some production sectors.

In Table 3.2, the electricity production distinguished by source for the whole time series is reported based on data supplied by the national grid operator (ENEL, several years; TERNA, several years). From 2010 to 2014 a drop in electricity generation from fossil fuels has been observed in Italy. The drop has been driven both by the economic recession and by the increase of renewable sources for energy production. The use of natural gas and coal is generally driven by the market; in 2011, from one side there was a minor availability (and higher prices) of natural gas imported by pipelines from Algeria and Libya, due to the “spring revolutions” occurring in these countries in that year, on the other side a new coal power plant, one of the largest in Italy, was fully operative with a production of around 12500 GWh explaining the increasing trend of electricity production from solid fuels. In “other fuels” a multitude of fuels are included, as biomass, waste, biogas from agriculture residues and waste and synthesis gases from heavy residual or chemical processes. The breakdown is available to the inventory expert allowing emission estimations, but it is confidential and not published by the owner of the information, TERNA.

Table 3.2 Production of electricity by sources 1990-2024 (GWh)

Source	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	GWh										
Hydroelectric	35,079	41,907	50,900	42,927	54,407	46,970	49,495	47,478	30,291	42,068	54,757
Thermoelectric	178,590	196,123	220,455	253,073	231,248	192,054	181,307	189,711	199,210	162,588	152,080
- solid fuels	32,042	24,122	26,272	43,606	39,734	43,201	13,380	14,022	22,607	13,220	3,948
- natural gas	39,082	46,442	97,607	149,259	152,737	110,860	133,683	143,998	141,445	118,987	118,554
- derivated gases	3,552	3,443	4,252	5,837	4,731	2,220	1,697	1,947	1,614	1,181	839
- oil products	102,718	120,783	85,878	35,846	9,908	5,620	3,175	3,851	4,953	3,622	2,527
- other fuels	1,196	1,333	6,446	18,525	24,138	30,151	29,373	25,893	28,591	25,578	26,212
Geothermic	3,222	3,436	4,705	5,325	5,376	6,185	6,026	5,914	5,837	5,692	5,675
Eolic and Photovoltaic	0	14	569	2,347	11,032	37,786	43,703	45,966	48,616	54,352	58,315
Total	216,891	241,480	276,629	303,672	302,062	282,994	280,531	289,069	283,954	264,700	270,827

Source: TERNA

More in general, the share of the total energy consumption by primary sources in the period 1990- 2024, reported in Table 3.3, shows an evident change from oil products and solid fuels to natural gas and renewables while the share of consumption of electricity is variable and driven by the market.

Table 3.3 Total energy consumptions by primary sources 1990-2024 (%)

Sources	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	%										
renewable	0.7	0.9	1.1	2.0	4.3	8.8	11.5	11.1	10.8	10.7	10.9
solid fuels	9.6	7.9	6.9	8.6	8.0	8.0	3.6	3.6	5.1	3.4	1.7
natural gas	23.7	25.7	31.4	36.0	36.2	35.8	41.5	40.9	38.4	36.0	36.3
crude oil	56.2	54.9	49.5	43.1	38.5	36.7	32.0	33.4	35.2	37.3	37.5
primary electricity	9.8	10.5	11.1	10.3	13.1	10.8	11.4	11.0	10.6	12.6	13.6

Source: Ministry of Environment

Further analysis on the electricity generation time series and CO₂ emission factors are available at the following web address: <https://emissioni.sina.isprambiente.it/inventario-nazionale/>.

Recalculations

In 2026 submission some recalculations occurred as in the following.

In 1A1a Recalculations occurred in 2021-2022-2023 as a consequence of an ETS power plant that has become part of a refinery plant as a hydrogen production unit and has therefore been excluded from 1A1a.

In 1A2 the main recalculations occur for the last three years because of the update of different activity data in the National Energy Balance resulting in small differences with respect to the previous submission, in particular CO₂ emissions show a change of +1.1% in 2021, -2.3% in 2022 and -1.7% in 2023. These differences are mainly due to:

- Update of coal consumption in 2023 for integrated plants (1A2a -20.1%);
- Update of liquid consumptions of other oil products in chemical and petrochemical for 2022 and 2023 resulting in some change in CO₂ emissions from 1A2c (-28.5%, -2.3%);

Update of natural gas consumptions data with the reallocation of emissions in 1A2g (+5.9%, +4.3% and 3.9% in 2021, 2022 and 2023) in place of 1A1a.

As regards 1.A.3.b., electricity road consumptions estimations have been revised as a result of the update of the energy consumptions factors reported in the Road transport emission factors Appendix 4 (2025 update) of the EMEP/EEA air pollutant emission inventory guidebook 2023. Italian road vehicles electricity consumption data derive from Eurostat database (<https://ec.europa.eu/eurostat/data/database>). COPERT input road electricity consumption data have been calibrated based on the vehicles categories using electricity included in COPERT classification. National data regarding density and energy content about natural gas road consumption have been updated since 2023. Average net calorific value for biogasoline has been updated since 2020 according to data reported for Italy in the IEA Eurostat UNECE Questionnaire 2024. Biogas road consumption, included in COPERT model in the total road natural gas consumption, has been considered in the Inventory, reported only since 2020 in the IEA - Eurostat – UNECE Energy Questionnaire (about 11%, 15%, 26%, 33% and 36% of total road natural gas consumption in 2020, 2021, 2022, 2023 and 2024 respectively).

Based on the above revisions, updates have been applied to the mileage estimates in the historical series, in accordance with fuel balance constraints, to maintain consistency, at trend level over the years, with national statistics updates.

For 1.A.3.a., in this submission estimates of CH₄ and N₂O have been recalculated by Eurocontrol from 2002, due to a new evaluation of taxi times.

As regards 1.A.4., recalculations occur from 2010 because of an updated distribution of biogenic/fossil activity data from waste sector which, in turn, has impact over the heating sector. The comparison between the estimates and recent ETS data allow Italy to improve waste characterization for non-urban waste burnt in the municipal plants. Only certain categories (specific EER code, i.e., residues from waste treatment can

be incinerated in those plants) and it is correct that such waste is considered the same as municipal waste, 50% fossil and 50% biogenic. Using this assumption since 2020, the inventory estimates and the ETS data have a better match. In 2024, the ETS estimates show approximately 3.7 kt fossil CO₂ with 32 reporting facilities, while the inventory estimates show 3.9 kt fossil CO₂ with four additional facilities. Between 2010 and 2020, linear smoothing was applied, considering the evolution of waste composition and assuming a regular trend. This led to a recalculation of -1.2% in 2010 to -2.8% in 2023.

Table 3.4 Emission recalculations in the energy sector 1990-2023 (%)

Year	GHG	CO ₂	CH ₄	N ₂ O
1990	0.01	0.00	0.25	0.00
1991	0.01	0.00	0.33	0.00
1992	0.01	0.00	0.35	0.00
1993	0.01	0.00	0.42	0.00
1994	0.01	0.00	0.46	0.00
1995	0.01	0.00	0.37	0.00
1996	0.01	0.00	0.31	0.00
1997	0.00	0.00	0.12	0.00
1998	0.01	0.00	0.19	0.00
1999	0.01	0.00	0.21	0.00
2000	0.01	0.00	0.26	0.00
2001	0.01	0.00	0.29	0.00
2002	0.00	0.00	-0.14	-0.05
2003	-0.01	0.00	-0.22	-0.05
2004	0.00	0.00	-0.13	-0.05
2005	0.00	0.00	-0.09	-0.05
2006	0.00	0.00	-0.10	-0.05
2007	0.00	0.00	-0.14	-0.05
2008	0.00	0.00	-0.11	-0.05
2009	0.00	0.00	-0.10	-0.06
2010	-0.26	-0.26	-0.13	-0.03
2011	-0.15	-0.15	-0.15	-0.03
2012	-0.21	-0.21	-0.15	-0.02
2013	-0.30	-0.31	-0.18	-0.02
2014	-0.40	-0.41	-0.23	-0.02
2015	-0.44	-0.45	-0.24	-0.16
2016	-0.52	-0.53	-0.07	-0.18
2017	-0.51	-0.53	-0.06	-0.19
2018	-0.55	-0.57	-0.02	-0.11
2019	-0.59	-0.60	-0.07	-0.18
2020	-0.64	-0.65	-0.48	-0.11
2021	-0.59	-0.56	-1.47	-0.66
2022	-1.09	-1.01	-4.20	-3.06
2023	-1.19	-1.02	-7.22	-4.96

Key categories

Key category analysis, for 2024, identified 25 categories at level assessment with Approach 1 and Approach 2 in the energy related emissions. In the case of the energy sector in Italy, a sector-by-sector analysis instead of a source-by-source analysis will better illustrate the accuracy and reliability of the emission data, given the interconnection between the underlying data of most key categories. In the following box, key categories for 2024 are listed, referring to the section of the text where they are quoted.

Key-categories identification in the energy sector with the IPCC Approach 1 and Approach 2 for 2024

KEY CATEGORIES	without LULUCF	with LULUCF	Relevant paragraphs	Notes
1 Transport - CO ₂ Road transportation	L,T	L,T	3.5.2	Tables 3.21-3.29
2 Other sectors - CO ₂ commercial, residential, agriculture gaseous fuels	L,T	L,T	3.6	Tables 3.32-3.35
3 Energy industries - CO ₂ solid fuels	L1,T	L1,T	3.3	Tables 3.6-3.9
4 Energy industries - CO ₂ gaseous fuels	L,T	L,T	3.3	Tables 3.6-3.9
5 Manufacturing industries and construction - CO ₂ gaseous fuels	L,T	L,T	3.4	Tables 3.10-3.13
6 Energy industries - CO ₂ liquid fuels	L,T	L,T	3.3	Tables 3.6-3.9
7 Other sectors - CO ₂ commercial, residential, agriculture liquid fuels	L,T	L,T	3.9	Tables 3.32-3.35
8 Manufacturing industries and construction - CO ₂ liquid fuels	L,T	L,T	3.4	Tables 3.10-3.13
9 Fugitive - CH ₄ Oil and natural gas - Natural gas	L,T	L,T	3.9	Tables 3.40-3.46
10 Other sectors - CH ₄ commercial, residential, agriculture biomass	L,T	L,T	3.6	Tables 3.32-3.35
11 Manufacturing industries and construction - CO ₂ solid fuels	L1,T	L1,T	3.4	Tables 3.10-3.13
12 Other sectors - CO ₂ commercial, residential, agriculture other fossil fuels	L1,T	L1,T1	3.6	Tables 3.32-3.35
13 Other sectors - N ₂ O commercial, residential, agriculture biomass	L2,T2	L2,T2	3.6	Tables 3.32-3.35
14 Transport - CO ₂ Waterborne navigation	L1, T1	L1, T1	3.5.4	Table 3.30
15 Fugitive - CO ₂ Oil and natural gas – venting and flaring	T2			Tables 3.40-3.46
16 Other sectors - N ₂ O commercial, residential, agriculture liquid fuels	L2		3.6	Tables 3.32-3.35
17 Other sectors - CO ₂ commercial, residential, agriculture solid fuels	T1		3.6	Tables 3.32-3.35
18 Transport - CH ₄ Road transportation	T2		3.5.2	Tables 3.21-3.29
19 Fugitive - CH ₄ Oil and natural gas - Other - flaring in refineries	L2, T2	T2	3.9	Tables 3.40-3.46
20 Fugitive - CO ₂ Oil and natural gas - Other - flaring in refineries	T2		3.9	Tables 3.40-3.46
21 Transport – CO ₂ Civil aviation	L1, T1	L1, T1	3.5.1	Tables 3.15-3.19
22 Transport - N ₂ O Road transportation	L2, T2		3.5.2	Tables 3.21-3.29
23 Manufacturing industries and construction - CH ₄ biomass	T2		3.4	Tables 3.10-3.13
24 Fugitive - CO ₂ Oil and natural gas - Oil	T1	L1		
25 Fugitive - CO ₂ Oil and natural gas - Other - flaring in refineries	T2			

With reference to the box, fourteen key categories (n. 2-8, 10-13, 16-17, 23) are linked to stationary combustion and to the same set of energy data: the energy sector CRT Table 1.A.1, the industrial sector, Table 1.A.2 and the civil sector Tables 1.A.4a and 1.A.4b. Ten out of fourteen key categories refer to CO₂ emissions, two categories refer to CH₄ and N₂O emissions from the use of biomass in the residential sector, one to CH₄ emissions from manufacturing industries using biomass and the last category refers to N₂O emissions from liquid fuels in other sectors.

All these sectors refer to the national energy balance (MASE, several years [a]) for the basic energy data and the distribution among various subsectors, even if more accurate data for the electricity production sector can be found in TERN publications (TERNA, several years). Evolution of energy consumptions/emissions is linked to the activity data of each sector; see paragraph 3.3, 3.4 and 3.6 and Annex 2 for the detailed analysis of those sectors. Electricity production is the most “dynamic” sector and the energy emissions trend, for CO₂, N₂O and CH₄, is mainly driven by thermoelectric production, see Tables A2.1 and A2.4 for more details.

In the following table emissions in kt of CO₂ equivalent for stationary combustion key categories at level assessment are summarized. From 1990 to 2024, an increase in use of natural gas instead of fuel oil and gas oil in stationary combustion plants is observed; it results in a decrease of CO₂ emissions from combustion of liquid fuels and an increase of emissions from gaseous fuels used in the different sectors. Coal and coke for residential heating have been banned and reduced to 0. The increase in CH₄ emissions from other sectors reflects the increase in the use of biomass for residential heating.

Table 3.5 Stationary combustion, GHG emissions in 1990 and 2024 (kt CO₂ eq)

	1990	2024
Energy industries - CO ₂ liquid fuels	81,197	14,986
Energy industries - CO ₂ solid fuels	38,647	4,951
Other sectors - CO ₂ commercial, residential, agriculture liquid fuels	38,274	10,757
Other sectors - CO ₂ commercial, residential, agriculture gaseous fuels	36,338	47,800
Manufacturing industries and construction - CO ₂ liquid fuels	32,806	10,266
Manufacturing industries and construction - CO ₂ gaseous fuels	32,234	30,122
Manufacturing industries and construction - CO ₂ solid fuels	25,732	4,338
Energy industries - CO ₂ gaseous fuels	16,954	43,455
Other sectors - CH ₄ commercial, residential, agriculture biomass	1,116	1,903
Other sectors - CO ₂ commercial, residential, agriculture other fossil fuels	530	3,921

Source: ISPRA elaborations

Another group of key categories (n. 1, 14, 18, 21-22) referred to the transport sector, with basic total energy consumption reported in the national energy balance and then subdivided in the different subsectors with activity data taken from various statistical sources; see paragraph 3.5, transport, for an accurate analysis of these key sources. This sector also shows a remarkable increase in emissions in the '90s, CO₂ from air transport and road transport, as can be seen in Table 3.19 and Table 3.27, respectively. In the last years CO₂ emissions from road transport started to decrease as a consequence of the economic crisis and the reduction of the average fuel consumption per kilometer of new vehicles. The trend of N₂O and CH₄ emissions is linked to technological changes that occurred in the period.

Finally, the last four key categories (n. 9, 15, 19,20, 24 and 25) refer to oil and gas operations. For this sector basic overall production data are reported in the national balance but emissions are calculated with more accurate data published or delivered to ISPRA by the relevant operators, see paragraph 3.10.

Most of the categories described are also key categories for the years 1990 and 2024 considering LULUCF emissions and removals.

3.2 Methodology description

Emissions are calculated by the equation:

$$E_{p,s,f} = A_{s,f} * e_{p,s,f}$$

where

$E_{p,s,f}$ = Emission of pollutant p from source s from fuel f (kg)

$A_{s,f}$ = Consumption of fuel f by source s (TJ-t)

$e_{p,s,f}$ = Emission factor of pollutant p from source s from fuel f (kg/TJ-kg/t)

The fuels covered are listed in Table A2.2 in Annex 2, though not all fuels occur in all sources. Sector specific tables specify the emission factors used. Emission factors are expressed in terms of kg pollutant/ TJ based on the net calorific value of the fuel. The carbon factors used are based on national sources and are

appropriate for Italy. Most of the CO₂ emission factors have been crosschecked with the results of specific studies that evaluate the carbon content of the imported/produced fossil fuels at national level. A comparison of the current national factors with the IPCC ones has been carried out; the results suggest quite limited variations in liquid fuels and some differences in natural gas, explained by basic hydrocarbon composition, and in solid fuels.

Monitoring of the carbon content of the fuels nationally used is an ongoing activity at ISPRA. The principle is to analyse regularly the chemical composition of the used fuel or relevant activity statistics, to estimate the carbon content and the emission factor. National emission factors are reported in Table 3.12 and Table 3.20. The specific procedure followed for each primary fuel (natural gas, oil, coal) is reported in Annex 6. In particular:

- transportation fuels have shown significant variation around the year 2000 due to the reformulation of gasoline and diesel to comply with the EU directive, see Table 3.20;
- the most important imported fuels, natural gas, fuel oil and coal show variations of carbon content from year to year, due to changes in the origin of imported fuel supply; a methodology has been set up to evaluate annually the carbon content of the average fuel used in Italy, see Annex 6 for details;
- derived gases produced in refineries, as petcoke, refinery gas and synthesis gas from heavy residual fuel, in iron and steel integrated plants, as coke oven gas, blast furnaces gas and oxygen converter gas, and in chemical and petrochemical plants have been calculated from 2005 on the basis of the analysis of information collected by the plants in the framework of EU ETS, see Annex 6 for details.

The activity statistics used to calculate emissions are fuel consumptions provided annually by the Ministry of Environment (MASE) in the National Energy Balance (MASE, several years [a]), by Terna (Terna, several years) for the power sector and some additional data sources to characterize the technologies used at sectoral level, quoted in the relevant sections.

Activity data collected in the framework of the EU ETS scheme does not cover the overall energy sector, whereas the official statistics available at national level, such as the National Energy Balance (BEN) and the energy production and consumption statistics supplied by Terna, provide the complete basic data needed for the emission inventory. Italian energy statistics are mainly based on the National Energy Balance thanks to the transmission of the joint questionnaires IEA/EUROSTAT/UNECE. The report is reliable, by international standards, and it may be useful to summarize its main features:

- it is a balance, every year national experts from the Ministry of the Environment carry out the exercise balancing final consumption data with import-export information;
- the balance is made on the energy value of energy carriers, considering transformations that may occur in the energy industries (refineries, coke plants, electricity production);
- data are collected regularly by the Ministry of Environment, monthly, from industrial subjects;
- oil products, natural gas and electricity used by industry, civil or transport sectors are taxed with excise duties linked to the physical quantities of the energy carriers; excise duties are differentiated in products and final consumption sectors (i.e. diesel oil for industrial use pays duties lower than for transportation use and higher than for electricity production);
- concerning energy consumption information, this scheme produces highly reliable data: BEN is based on registered quantities of energy consumption and not on estimates;

-
- coal is an exception to this rule, it is not subject to excise duties; consumption information is estimated; anyway, it is nearly all imported and a limited number of operators use it and the Ministry of Environment monitors all of them monthly.

The energy balances of fuels used in Italy, published by the Ministry of Environment (MASE, several years [a]), compare total supply based on production, exports, imports, stock changes and known losses with the total demand; the difference between total supply and demand is reported as “statistical difference”. 2024 data communicated by Italy to the Joint Questionnaire IEA/EUROSTAT/UNECE in the format revisited by EUROSTAT are available on website: <https://sisen.mase.gov.it/dgsaie/>. Some differences between data communicated to the international organizations and EUROSTAT publication have been observed and are under investigation; they are mainly due to the use of default instead of country specific energy conversion factors and different classification criteria for fuels. Data submitted by the Ministry of Environment to the Joint Questionnaire IEA/ EUROSTAT/UNECE have been used for solid, liquid and gaseous fuel consumptions. Some inconsistencies have been found in data communicated at Eurostat and referring to the ninety years, especially in the sectoral distribution of fuels; in these cases, the information already available in the national energy balances has been maintained because of considered more reliable and consistent in the time series. In addition to fossil fuels, the Joint Questionnaire provides estimates for energy use from commercial wood and straw combustion, as well as biodiesel and biogas. Carbon dioxide emissions from biomass combustion are not included in the national total as suggested in the IPCC Guidelines (IPCC, 2006) but emissions of other GHGs and other pollutants are included. CORINAIR methodology (EMEP/EEA, 2023) includes emissions from the combustion of wood in the industrial and domestic sectors as well as the combustion of biomass in agriculture.

The inventory also includes emissions from the combustion of lubricants based on data collected from waste oil recyclers and quoted in the energy balance. According to the IPCC 2006 Guidelines (IPCC, 2006), only emissions from the combustion of lubricants in two strokes engines are reported in the energy sector while the other emissions are reported in the IPPU sector.

Currently, a review process of the national energy balance is underway with Eurostat and involves the various interested parties (TERNA, GSE, MASE, Acquirente Unico) in Italy. In a first step, those responsible for the National Energy Balance implemented methodological changes for 2022 and subsequently applied these changes to 2021 to make it consistent. ISPRA is following this process closely to know the details and optimize the estimates. This change in methodology has caused a break in the series for some fuels and it is necessary further work to improve the time series consistency, and it will probably take a few years to also reconstruct the historical series of fuels according to the new definitions. In this submission shift of other oil products from energy to no-energy consumptions thanks to a discussion with Federchimica (national association of chemical industries) for the years from 2021 to 2024 and the introduction of data concerning hydrogen production, at the moment, only for 2024.

3.3 Energy industries

A detailed description of the methodology used to estimate greenhouse gas emissions from electricity production under 1.A.1.a, 1.A.1.b and 1.A.1.c is reported in Annex 2. Basic data, methodology and emission factors used to estimate emissions are derived from the same sources. In the following sub-paragraphs additional information on the specific categories is supplied.

In this category, gaseous fuels refer to natural gas while solid fuels mainly to coal used to produce energy and derived gases used in the integrated iron and steel plants; liquid fuels include residual oil fuel consumption used for energy production in power plants and different fuels used in refineries. The CO₂ implied emission factor trend for the sector is driven by the liquid fuel consumption in the petroleum refining industry (97% of the total of liquid) where many fuels, with very different emission factors, are used, such as refinery gas, that have an average emission factor value equal to 56.1 t/TJ, and petroleum coke with an average emission factor equal to 95.3 t/TJ. In the last years, a reduction in the consumption of synthesis gas from heavy residual fuels (in 2024 the average emission factors t CO₂/TJ values are about 81.0 and 98.1 for heavy residual fuels and synthesis gas respectively) is observed, resulting in interannual variations. Emission factors time series for these fuels are reported in Annex 6.

3.3.1 Public Electricity and Heat Production

3.3.1.1. *Source category description*

This paragraph refers to the main electricity producers that produce electricity for the national grid. From 1998 onwards, the expansion of the industrial cogeneration of electricity and the split of the national monopoly have transformed many industrial producers into “independent producers”, regularly supplying the national grid. These producers account in 2024 for 91.1% of all electricity produced with combustion processes in Italy (TERNA, several years).

In Italy, only limited data does exist about producers working for district heating grids; most of the cogenerated heat is produced and used on the same site by industrial operators. Therefore, data on heat production is prevalently reported in Table 1.A(a)s2 for industry and Table 1.A(a)s4 for district heating. In TERNA yearly publication, heat cogenerated while producing electricity is reported separately. Unfortunately, no details are reported on the final use of cogenerated heat, so it can be used in inventory preparation just to cross check the total fuel amount with other sources, such as EU ETS or the consumption of fuels in the industry reported in the national energy balance.

Under biomass, wood and charcoal consumption and relevant emissions are reported until 2007; CO₂ emission factor is shown in Table 3.12 while CH₄ and N₂O emission factors are equal to 30 g/GJ and 4 g/GJ respectively. From 2008 also bioliquid fuel is used and included under biomass (CH₄ and N₂O emission factors equal to 12 g/GJ and 2 g/GJ respectively), resulting in the decrease of the average emission factor.

Other fuels subcategory refers mainly to fuel consumptions of other liquid, solid and gaseous fuels such as industrial wastes, that are more than half of the total TJ of the subcategory, as plastics, rubber, and solvents, synthesis gas from heavy residual (98.1 tCO₂/TJ in 2024) and other liquid fuels (76.5 tCO₂/TJ in 2024); the average CO₂ emission factor has been calculated for the whole time series and it is equal to 89.1 t/TJ in 2024.

CO₂ implied emission factor trend of liquid fuels for this category is driven by the mix of high and low sulfur fuel oil consumptions that is changed in the years as a consequence of the adoption of air quality European Directives introducing air pollutants ceilings at the stacks, and the policies at national level which established stringent ceiling for new and old plants and a timing scheduled for their implementation. The CH₄ implied emission factor is the weighted average of gasoil and residual oil emission factors equal to 1.5 g/GJ and 3 g/GJ respectively. The general decreasing trend is due to the minor use of fuel oil for energy

production, at the minimum in the last years, while the amount of gasoil, which is related to the start-up of power plants and to the gasoil used in stationary engines, has a more stable trend.

3.3.1.2. Methodological issues

The data source on fuel consumption is the annual report “Statistical data on electricity in Italy - Production” (“Dati statistici sull’energia elettrica in Italia - Produzione”), edited from 1999 by the Italian Independent System Operator (TERNA, several years). The report refers to the total of producers and the estimate of the part belonging to public electricity production is made by the inventory team based on detailed electricity production statistics by industrial operators. Data on total electricity production for the year 2024 is reported in Annex 2. For the time series, see previous NIR reports. The emission factors used are listed in Table 3.12.

Another source of information is the National Energy Balance (MASE, several years [a]), which contains data on the total electricity producing sector. The data of the national energy balance (BEN) are also used to address the statistical survey of international organizations, IEA, Eurostat and UNECE. Both BEN and TERNA publications could be used for the inventory preparation, as they are part of the national statistical system and published regularly. Currently, a review process of the national energy balance is underway with Eurostat and involves the various interested parties (TERNA, GSE, MASE, Acquirente Unico) in Italy.

A detailed analysis of both sources is reported in Annex 2. From the year 2005 onwards, a valuable source of information is given by the reports prepared for each industrial installation subject to EU ETS scheme. These reports are prepared by independent qualified verifiers and concern the CO₂ emissions, emission factors and activity data, including fuel used. ISPRA receives copies of the reports from the competent authority (Ministry of Environment) and can extract the information related to electricity production. The information available is very useful but does not fully cover the electricity production sector or the public electricity production. The EU ETS does not include all installations, only those above 20 MWt, it is made on a point source basis so the data include electricity and heat production while the corresponding data from TERNA, concerning only the fuel used for electricity production, are commercially sensitive, confidential and they are not available to the inventory team. Anyway, the comparison of data collected by TERNA with those submitted to the EU ETS allows identifying possible discrepancies in the different datasets and thus providing the Ministry of Environment experts with useful suggestions to improve the energy balance.

In Table 3.6, fuel consumptions and emissions of 1.A.1.a category are reported for the time series. Table 3.6 shows a decrease in fuel consumption and an overall decrease in GHG emissions. However, a slower increase is observed in CH₄ emissions due to the increase in use of natural gas and biomass.

Table 3.6 Public electricity and heat production: Energy data (TJ) and GHG emissions, 1990-2024

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
Fuel consumption (TJ)	1,441,741	1,472,753	1,554,810	1,709,208	1,480,778	1,205,336	1,056,626	1,160,711	896,102	802,736
GHG (kt CO ₂ eq.)	109,050	110,709	109,527	115,827	97,534	79,317	60,209	71,339	53,490	43,843
CO ₂ (kt)	108,670	110,335	109,193	115,445	97,195	78,922	59,922	71,031	53,262	43,638
CH ₄ (kt)	3.8	4.0	3.6	4.0	3.6	4.2	4.1	3.9	3.1	3.2
N ₂ O (kt)	1.0	1.0	0.9	1.0	0.9	1.0	0.7	0.7	0.5	0.4

Source: ISPRA elaborations

In the last two years, there was a significant drop in consumption linked to the face-out of coal but also to a reduction in natural gas consumption. Moreover, it has been possible to observe a shift from coal to natural gas for energy production in the last years. As the main data source refers to the whole electricity

production sector, the uncertainty and time-series consistency, source-specific QA/QC and verification, recalculations and planned improvements are all addressed in Annex 2.

3.3.1.3. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from public electricity and heat production is estimated to be about 4.2% in annual emissions; a higher uncertainty, equal to 50.1%, is calculated for CH₄ and N₂O emissions because of the uncertainty levels attributed to the related emission factors. A summary of the results is reported in Annex 1.

3.3.1.4. Source-specific QA/QC and verification

Basic data to estimate emissions have been reported by the national energy balance and the national grid administrator. Data collected under other reporting obligations that include refineries (EU ETS, LCP and E-PRTR databases) have been used to cross-check the energy balance data, fuels used and emission factors. Differences and problems have been analyzed in detail and solved together with the experts of the Ministry of Environment, who are in charge of preparing the National Energy Balance.

3.3.1.5. Source-specific recalculations

Recalculations occurred in 2021-2022-2023 as a consequence of an ETS power plant that has become part of a refinery plant as a hydrogen production unit and has therefore been excluded from 1A1a.

3.3.1.6. Source-specific planned improvements

For the next submissions, the adaptation of the estimation methodologies to the changes in the energy balance is planned.

3.3.2 Refineries

3.3.2.1. Source category description

This subsector covers the energy emissions from the national refineries (14 operating plants in 2024), including the energy used to generate electricity for internal use and exported to the national grid by power plants that directly use off-gases or other residues of the refineries. These power plants are generally owned by other companies but are located inside the refinery premises or just sideways. In 2024 the power plants included in this source category have generated 7.3% of all electricity produced with combustion processes in Italy. Energy consumption and emissions are reported in CRT Table 1.A.1.b. Parts of refinery losses, flares, are reported in CRT Table 1.B.2.a and c.

3.3.2.2. Methodological issues

The consumption data used for refineries comes from BEN (MASE, several years [a]); the same data are also reported by Unione Energia per la Mobilità, the industrial category association (UNEM, several years). From 2005 onwards, also the EU ETS “verified reports” cover almost the entire sector, for energy consumptions, combustion emissions and process emissions. Other sources of information are the annual reporting requirements for the large combustion plants under the European Directive (LCP) and the E-PRTR Regulation; both data sets include most refineries, but not all the emission sources.

For the part of the energy and related emissions due to the power plants, the source is TERNA (see Annex 2 for further details). The quota of total energy consumption from electricity production included in category 1.A.1.b is estimated by the electricity production model based on fuels used and plant location.

All the fuel used in boilers and processes, the refinery “losses” and the reported losses of crude oil and other fuels (that are mostly due to statistical discrepancies) are considered to calculate emissions. Fuel lost in the distribution network is accounted for here and not in the individual end use sector. From 2002 particular attention has been paid to avoid double counting of CO₂ emissions, checking if the refinery reports of emissions already include losses in their energy balances. IPCC Tier 2 emission factors and national emission factors are used as reported in Table 3.12.

From 2008, TERNA modified the detailed table of fuel consumption and related energy production introducing a more complete list of fuels. The aim of the change was to revise the consumption values of waste fuels which are very important for estimating the contribution of renewable to electricity production and consequently greenhouse gases.

In Table 3.7, a sample calculation for the year 2024 is reported, with energy and emission data.

Table 3.7 Refineries, CO₂ emission calculation, year 2024

	Consumption, TJ				CO ₂ emissions, kt			
REFINERIES	Petroleum coke	Ref. gas	Liquid fuels	Natural gas	Petroleum coke	Ref. gas	Liquid fuels	Natural gas
energy		717	45,733	46,450		40	3,878	2,745
furnaces	19,562	105,852	14,396		1,864	5,935	1,034	
TOTAL				232,709				15,497

Source: ISPRA elaborations

From 2005, the weighted average of CO₂ emission factor reported by operators in the context of the EU ETS scheme is used for petroleum coke, refinery gas and synthesis gas from heavy residual fuels. The trend of the implied emission factor is driven by the mix of the fuels used in the sector. The main fuels used are refinery gases, fuel oil and petroleum coke, which have very different emission factors, and every year their amount used changes resulting in an annual variation of the IEF. The increase in the last years, with respect to the nineties, of the consumption of fuels with higher carbon content, as petroleum coke and synthesis gas obtained from heavy residual fuels, explains the general growth of the IEF for liquid fuel reported in the CRT for this sector.

In the following box, liquid fuel consumptions of 1.A.1.b category disaggregated by fuel are reported.

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Refinery gas	119,123	136,305	124,549	153,036	153,739	132,688	111,499	112,318	126,906	129,828	106,569
Naphta	218	784	4,441	2,613	3,353	87	3	0	0	0	0
Pet coke	28,495	28,634	40,623	50,180	49,415	30,094	20,427	28,200	28,241	25,700	19,562
Synthesis gas	0	0	36,425	65,021	78,628	61,763	56,735	42,353	55,217	47,636	45,671
Fuel oil	76,881	89,310	84,589	75,301	49,442	16,435	3,684	5,380	8,162	6,283	7,912
LPG	1,243	1,151	2,026	3,408	2,717	1,704	2,497	3,463	7,812	10,213	6,110
Gasoil	43	43	5,338	11,317	897	0	0	7	416	5,563	436
Gasoline	0	0	0	0	0	0	0	0	0	0	0
Total	226,003	256,228	297,992	360,875	338,191	242,771	194,846	191,720	226,754	225,223	186,260

Liquid fuel consumptions in petroleum refining (TJ), 1990-2024

3.3.2.3. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from refineries is estimated to be about 4.2% in annual emissions; a higher uncertainty, equal to 50.1%, is calculated for CH₄ and N₂O emissions because of the uncertainty levels attributed to the related emission factors. Montecarlo analysis has been carried out to estimate uncertainty of CO₂ emissions from stationary combustion of solid, liquid and gaseous fuels emissions, resulting in 5.1%, 3.3% and 5.8%, respectively. Normal distributions were assumed for all the parameters. A summary of the results is reported in Annex 1. In Table 3.8 GHG emissions from the sector in the years 1990, 1995, 2000, 2005, 2010, 2015, 2020-and 2022-2024 are reported.

Table 3.8 Refineries, GHG emission time series

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
CO ₂ emissions, Mt	15.8	18.0	22.2	27.9	28.3	20.9	17.4	19.0	18.2	17.2
CH ₄ emissions, kt	0.40	0.46	0.59	0.69	0.69	0.48	0.39	0.43	0.39	0.42
N ₂ O emissions, kt	0.45	0.51	0.60	0.73	0.69	0.51	0.41	0.48	0.47	0.43
Refinery, total, Mt CO ₂ eq	15.9	18.1	22.4	28.1	28.5	21.1	17.6	19.2	18.4	17.3

Source: ISPRA elaborations

An upward trend in emission levels is observed from 1990 to 2010 explained by the increasing quantities of crude oil processed and the complexity of process used to produce more environmentally friendly transportation fuels. Liquid fuel consumptions have reached a plateau in 2010 and they are now in a downward trend that is expected to continue, due to the reduced quantities of crude oil processed and electricity produced and to the gradual substitution with natural gas fuel consumption.

3.3.2.4. Source-specific QA/QC and verification

Basic data to estimate emissions have been reported by the national energy balance and the national grid administrator. Data collected under other reporting obligations that include refineries (EU ETS, LCP and E-PRTR databases) have been used to cross-check the energy balance data, fuels used and emission factors. Differences and problems have been analyzed in detail and solved together with the experts of the Ministry of Environment, who are in charge of preparing the National Energy Balance.

3.3.2.5. Source-specific recalculations

No recalculations occurred.

3.3.2.6. Source-specific planned improvements

For the next submissions, the adaptation of the estimation methodologies to the changes in the energy balance is planned.

3.3.3 Manufacture of Solid Fuels and Other Energy Industries

3.3.3.1. Source category description

In Italy, a few coke and “manufactured gas” producing plants were operating in the early nineties and they have been reported here. Only one manufactured gas producing plant is still in operation from 2002.

In this section, emissions from power plants, which use coal gases, are also reported. In 2024 the power plants included in this source category have generated about 1.6% of all electricity produced with combustion processes in Italy.

Regarding the manufacture of other solid fuels, in Italy, charcoal was produced in the traditional way until the sixties while now it is prevalently produced in modern furnaces (e.g. with the VMR system) where exhaust gases are collected and recycled to produce the energy for the furnace itself. This system ensures good management of the exhausts and the temperature, so that any waste of energy is prevented, and emissions are kept to a minimum. Analysing the issue with the 2019 IPCC Refinements results in an available methodology (IPCC, 2019) and Italy made an estimate for the previous submission producing time series emissions for CH₄ and N₂O.

3.3.3.2. Methodological issues

Fuel consumption data for the sector are reported in the BEN (MASE, several years [a]). Fuels used to produce energy are also reported with more detail as for fuel disaggregation level by TERNA (TERNA, several years). From 2005 onwards, also the EU ETS “verifier’s reports” cover almost the entire sector, for energy consumptions, combustion emissions and process emissions. Other sources of information are the yearly reporting obligations for the large combustion plants under European Directive (LCP) and for facilities under the E-PRTR Regulation; both reporting obligations include most of the iron and steel integrated plants and the only coke producing plant but not all the emission sources.

A carbon balance is done, as suggested by the IPCC good practice guidance, to avoid over or under estimation from the sector. In Annex 3 further details on carbon balances of solid fuels and derived gases used are reported.

The high-implied emission factor for solid fuels is due to the large use of derived steel gases and in particular blast furnace gas to produce energy. These gases have been assimilated to the renewable sources and incentives are still provided for their use.

Other fuels are used in co-combustion with coal gases to produce electricity and they are reported by TERNA, see Annex 2. From 2008, natural gas and fuel oil consumptions reported in the CRT for this sector, are those communicated by the operators of the plants included in the sector in the framework of the EU ETS scheme. Fuel consumption reported in the sector is subtracted from the total fuel consumption to produce energy, guaranteeing that over and under estimation are avoided.

CH₄ emissions from coke ovens are estimated based on production data to consider additional volatile emissions due to the specific process. Average emission factors are calculated based on information communicated by the four (two in the last years) plants under the E-PRTR registry.

3.3.3.3. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from integrated iron and steel plants is estimated to be about 4.2% in annual emissions; a higher uncertainty, equal to 50.1%, is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors. Montecarlo analysis has been carried out to estimate uncertainty of CO₂ emissions from stationary combustion of solid, liquid and gaseous fuels emissions, resulting in 5.1%, 3.3% and 5.8%, respectively. Normal distributions have been assumed for all the parameters. A summary of the results is reported in Annex 1. In Table 3.9 GHG emissions from the sector are reported.

Table 3.9 Manufacture of solid fuels, GHG emission time series

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂ emissions, Mt	12.5	11.6	12.9	15.9	11.4	5.6	3.8	4.7	4.0	3.3	2.7
CH ₄ emissions, kt	6.5	6.4	5.5	2.4	1.0	0.9	0.7	0.7	0.7	0.7	0.6
N ₂ O emissions, kt	0.12	0.11	0.10	0.12	0.08	0.04	0.03	0.03	0.03	0.02	0.02
Total, Mt CO ₂ eq	12.7	11.8	13.0	16.0	11.5	5.7	3.9	4.7	4.0	3.3	2.7

Source: ISPRA elaborations

The trend of CO₂ and N₂O emissions is driven by the production trends combined with an increase in energy consumption required by more energy intensive products. In 2009 a strong reduction of emissions is observed because of the economic recession that in 2010 and 2011 have partially recovered. In 2012 a further drop occurred for the economic crisis and by environmental constraints of the main iron and steel integrated plants that should reduce its productions. In 2015 a drop is still observed (around 1.7 Mt CO₂) consistently with the production activities reduction of the main iron and steel integrated plants.

The trend of CH₄ emissions is driven by the coke production trend, which decreased from 6.4 Mt in 1990 to less than 2 Mt in 2024 and by the renewal of the production plants. In particular, the strong reduction of CH₄ emissions in the last years is the result of the renewal of the coke production plants in Taranto, which started in 2005, and the implementation of best available technologies to reduce volatile organic compounds. In 2009, as well as in 2013, national coke production has reduced by about 40% with respect to the previous year, determining a loss in efficiency of the production plants and an increase of emissions by product unit (IEF) for those years. The production regime of the largest Italian steel plant in the last years, in particular 2023, reached historic lows, inducing the massive recovery of derived gases within the same plant. This situation had repercussions on the nearby thermoelectric plant which instead had to resort almost exclusively to natural gas and all this is very well reflected in the variations undergone by the coal FE.

3.3.3.4. Source-specific QA/QC and verification

Basic data to estimate emissions have been reported by the national energy balance and the national grid administrator. Data collected under other reporting obligations that include integrated iron and steel plants, such as EU ETS Directive, LCP and E-PRTR databases, have been used to cross-check the energy balance data, fuels used and emission factors. Differences and problems have been analyzed in detail and solved together with Ministry of Environment experts, which are in charge of preparing the National Energy Balance. In the national PRTR register the integrated plants report every year the CO₂ emitted at each stage of the process, coke production, sinter production and iron and steel production, which result from separate carbon balances calculated in each phase of the production process. Moreover, total CO₂ emissions reported in the E-PRTR by the operators are equal to those reported under the EU ETS scheme.

The detailed analysis and comparison of the different data reported improved the allocation of fuel consumption and CO₂ emissions between 1.A.1.c and 1.A.2.a sectors. From the 2010 submission, in fact, coking coal losses for transformation process and related emissions have been reallocated under 1.A.1.c instead of 1.A.2.a.

3.3.3.5. Source-specific recalculations

No recalculations occurred.

3.3.3.6. Source-specific planned improvements

No specific improvements are planned for the next submission.

3.4 Manufacturing industries and construction

3.4.1 Sector overview

Included in this category are emissions which originate from energy use in the manufacturing industries included in category 1.A.2. Where emissions are released simultaneously from the production process and from combustion, as in the cement, lime and glass industry, these are estimated separately and included in category 2.A. All greenhouse gases as well as CO, NO_x, NMVOC and SO₂ emissions are estimated. In 2024, energy use in industry accounted for 15.1% of total national CO₂ emissions, 0.7% of CH₄, 4.5% of N₂O. In terms of CO₂ equivalent, the manufacturing industry shares 12.2 % of total national greenhouse gas emissions.

Two key categories have been identified for this sector in 2024, for level and trend assessment, using both the IPCC Approach 1 and Approach 2:

Manufacturing industries and construction - CO₂ gaseous fuels (L, T);

Manufacturing industries and construction - CO₂ liquid fuels (L, T).

Manufacturing industries and construction - CO₂ solid fuels is a key category at trend assessment both with and without uncertainty while, at level assessment, is a key category only with Tier 1. A fourth category is added to these three: Manufacturing industries and construction - CH₄ biomass key category at trend assessment but only with the uncertainty while N₂O from liquid fuels, is key category for 1990 only including the uncertainty estimates.

In the following Table 3.10, GHG emissions connected to the use of fossil fuels, excluded process emissions, are reported. Industrial emissions show oscillations related to economic cycles.

Table 3.10 Manufacturing industry, GHG emission time series

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂ emissions, kt	90,773	88,970	94,894	90,787	68,890	54,542	44,907	54,069	52,461	48,699	45,251
CH ₄ emissions, kt	6.69	6.92	6.01	6.48	5.68	11.21	11.01	11.61	11.17	10.50	10.22
N ₂ O emissions, kt	4.49	3.92	4.46	5.02	3.77	2.69	2.36	2.81	2.62	2.46	2.35
Industry, total, kt CO ₂ eq	92,151	90,204	96,245	92,299	70,048	55,569	45,839	55,140	53,468	49,645	46,159

In Table 3.11 emissions are reported by pollutants, for all the subsectors included in the sector.

Table 3.11 Trend in greenhouse gas emissions from the manufacturing industry sector, 1990-2024

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂ (kt)											
1.A.2.a Iron and Steel	25,255	24,201	22,537	19,289	15,708	10,629	8,004	9,437	8,766	7,997	7,674
1.A.2.b Non-Ferrous Metals	735	879	1,249	1,176	1,105	999	1,036	1,326	1,133	1,087	1,033
1.A.2.c Chemicals	21,429	18,659	18,104	17,241	16,395	11,132	9,137	9,813	8,476	7,991	7,058
1.A.2.d Pulp, Paper and Print	3,108	4,185	4,253	5,457	5,148	4,872	4,665	5,011	4,535	3,950	3,794
1.A.2.e Food	3,891	5,095	6,282	6,017	4,132	3,444	3,472	3,651	3,377	3,305	3,189
1.A.2.f Non-metallic minerals	21,045	17,461	21,407	25,271	18,099	14,007	10,348	11,017	11,389	10,304	10,387
1.A.2.g Other	15,310	18,490	21,062	16,338	8,303	9,460	8,245	13,814	14,785	14,064	12,115
CH₄ (t)											
1.A.2.a Iron and Steel	3,795	4,226	3,093	3,304	2,880	2,062	1,449	1,593	1,394	1,248	1,036
1.A.2.b Non-Ferrous Metals	13	15	26	24	19	18	18	23	19	18	17
1.A.2.c Chemicals	876	725	643	533	542	327	237	266	233	214	176
1.A.2.d Pulp, Paper and Print	77	93	115	154	92	107	98	121	121	116	114
1.A.2.e Food	105	127	174	429	731	7,639	8,238	8,389	8,173	7,727	7,764
1.A.2.f Non-metallic minerals	1,412	1,276	1,463	1,624	1,197	842	779	891	849	812	815
1.A.2.g Other	408	461	493	412	219	215	191	327	382	364	293
N₂O (t)											
1.A.2.a Iron and Steel	411	414	366	396	294	200	148	183	160	131	129
1.A.2.b Non-Ferrous Metals	13	16	24	23	20	18	18	23	19	19	18
1.A.2.c Chemicals	404	322	314	317	328	207	134	147	132	122	100

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
1.A.2.d Pulp, Paper and Print	64	82	80	102	90	86	81	86	78	69	66
1.A.2.e Food	52	53	76	87	47	172	180	184	178	170	170
1.A.2.f Non-metallic minerals	2,644	2,285	2,630	2,986	2,183	1,427	1,286	1,464	1,368	1,338	1,358
1.A.2.g Other	906	751	974	1,110	807	579	508	728	686	612	504

Source: ISPRA elaborations

A general trend of reduction in emissions is observed from 1990 to 2024; some sub sectors reduced sharply (iron and steel, chemicals, non-metallic minerals), other sub sectors (non-ferrous metals, pulp and paper) increased their emissions. In 2009 an overall reduction of emissions for all the sectors occurred due to the effects of the economic recession. In 2010 production levels restored for iron and steel, but a further significant drop is noted in 2013 due to environmental constraints of the main integrated iron and steel plant in Italy, located in Taranto, which had to reduce its steel production level. Non-metallic minerals emission trend is driven by the cement industry which strongly reduced its production levels in 2009 and further in 2013, in relation to the economic recession and the crisis of building construction sector; a further decrease of this sector is observed in 2016 and 2017. The increasing trend of CH₄ emissions in the last years, especially for food industry, is driven by the increase of biomass used as a fuel in this sector with a peak in 2014 and in 2019-2021. The decreasing trend of CO₂ and N₂O in the last years is driven by the trend of non-metallic minerals industry emissions due to the reduction trend of cement productions.

3.4.2 Source category description

The category 1.A.2 comprises seven sources: 1.A.2.a Iron and Steel, 1.A.2.b Non-Ferrous Metals, 1.A.2.c Chemicals, 1.A.2.d Pulp, Paper and Print, 1.A.2.e Food, 1.A.2.f Non-metallic minerals, 1.A.2.g Other.

Iron and steel

The main processes involved in iron and steel production are those related to sinter and blast furnace plants, to basic oxygen and electric arc furnaces and to rolling mills. Most of emissions are connected to the integrated steel plants, while for the other plants, the main energy source is electricity (accounted for in 1.A.1.a) and the direct use of fossil fuels is limited to heating – re heating of steel in the intermediate part of the process.

There were four integrated steel plants in 1990 that from 2005 are reduced to two, with another plant that still has a limited production of pig iron. Nevertheless, the steel production in integrated plants did not change significantly in the 1990-2008 period due to an expansion in capacity of the two operating plants. From 2015 only one integrated plant remains in operation. The maximum production was around 11 Mt/y in 1995 and in 2005-2008, with lower values in other years and the lowest of 2.0 Mt in 2024.

It has to be underlined that the integrated steel plants include also the cogeneration of heat and electricity using the recovered “coal gases” from various steps of the process, including steel furnace gas, BOF gas and coke oven gas. All emissions due to the “coal gases” used to produce electricity are included in the electricity grid operator’s yearly reports and are accounted in the category 1.A.1.c. No detailed information is available about the heat produced, so the emissions are included in source category 1.A.2.a.

With the aim of avoiding double counting, process emissions resulting from the iron and steel subcategory are reported in the industrial processes sector. CH₄ emissions are estimated for each emitting activities according to the classification of activities described in the EMEP/EEA guidebook and, consequently, allocated to the combustion or industrial processes sector, in consideration of the relevant methodological issues. More in detail, CH₄ process emissions for pig iron and steel production are already allocated to the industrial processes sector as well as fugitive CH₄ emissions from coke production, that are reported under fugitive emissions, while CH₄ emissions from the combustion of fuels are allocated to the energy sector.

This subsector is one of the most important of 1.A.2 category and accounts, in 2024, for 16.8% of total 1.A.2 GHG emissions, and 2.1% of total national emissions.

Non-Ferrous Metals

In Italy, the production of primary aluminium stopped in 2013 (and was 232 kt in 1990) while secondary aluminium accounts for 350 kt in 1990 and 664 kt in 2024. These productions, however, use electricity as the primary energy source so the emissions due to the direct use of fossil fuels are limited. The sub sector comprises also the production of other non-ferrous metals, both primary and secondary copper, lead, zinc and others; but those productions have also a limited share of emissions. Magnesium production is not occurring. The bulk of emissions are due to foundries that prepare mechanical pieces for the engineering industry or the market, using all kinds of alloys, including aluminum, steel and iron.

Chemicals

CO₂, CH₄ and N₂O emissions from chemical and petrochemical plants are included in this sector.

In Italy, there are petrochemical plants integrated with a nearby refinery as well as stand-alone plants that get the inputs from the market. Main products are Ethylene, Propylene, Styrene. Ethylene and propylene are produced in petrochemical industry by steam cracking. Ethylene is used to manufacture ethylene oxide, styrene monomer and polyethylene. Propylene is used to manufacture polypropylene but also acetone and phenol. Styrene, also known as vinyl benzene, is produced on an industrial scale by catalytic dehydrogenation of ethyl benzene. Styrene is used in the rubber and plastic industry to manufacture through polymerization processes such products as polystyrene, ABS, SBR rubber, SBR latex. Except for ethylene oxide, whose production has stopped in 2002, the other productions of the above-mentioned chemicals still occur in Italy. Activity data are stable from 1990 to 2012, with limited yearly variations along the time series and a reduction in the last years.

Chemical industry includes non-organic chemicals such as chlorine/soda, sulfuric acid, nitric acid, and ammonia. A limited production of fertilizers is also present in Italy. From 1990 to 2024 the sum of production of this source category was greatly reduced: in 2024 it was less than half of the production in 1990.

This source category does include some emissions from the cogeneration of electricity. Due to the transformation of some of those plants in power plants directly connected to the grid and so reported in category 1.A.1.a, the percentage of the category 1.A.2.c CO₂ emissions due to electricity generation has reduced from 1990 to 2024.

This subsector accounts, in 2024, for 15.4% of total 1.A.2 GHG emissions, and 2.0% of total national emissions.

Pulp, Paper and Print

Emissions from the manufacturing of paper are included in this source category. In Italy the manufacture of virgin paper pulp is rather limited, with a production feeding less than 5% of the paper produced in 2019. Most of the pulp was imported in 1990, while in 2024 half of the pulp used is produced locally from recycled paper. Paper production is expanding, and activity data (total paper produced) were 6.2 Mt in 1990 and 8.0 Mt in 2024. The printing industry represents a minor part of the source category emissions.

This source category includes also emissions from the cogeneration of electricity. Due to the transformation of some of those plants into power plants directly connected to the grid (and so reported in category 1.A.1.a), the percentage of the category 1.A.2.d CO₂ emissions due to electricity generation has strongly reduced from 1990 to 2024. This subsector accounts, in 2024, for 8.3% of total 1.A.2 GHG emissions, and 1.0% of total national emissions.

Food

Emissions from food production are included in this source category. In Italy the food production industry is expanding. A comprehensive activity data for this sector is not available; more in detail while energy data are those reported in the national energy balance for this sector, information at subsector and technological level is not available and only few plants are part of the ETS; energy fuel consumption was estimated to be 62 PJ in 1990 and 104 PJ in 2024, almost half of energy consumptions in 2024 derives from biomass.

This source category also includes emissions from the cogeneration of electricity. Due to the transformation of those plants into power plants directly connected to the grid and so reported in category 1.A.1.a, the percentage of the category 1.A.2.e CO₂ emissions due to electricity generation has reduced from 1990 to 2024.

Non-metallic minerals

This sector, which refers to construction materials, is quite significant in terms of emissions due to the energy intensity of the processes involved. Construction materials subsector includes the production of cement, lime, bricks, tiles and glass. It comprises thousands of small and medium-sized enterprises, with only a few large operators, mainly related to cement production. Some of the products are also exported. The description of the process used to produce cement, lime and glass is reported in chapter 4, industrial processes.

Brick manufacturing is a common process in most countries and requires no further explanation; the primary fossil fuel used is natural gas. A distinctive national feature, however, is tile production, which is concentrated in numerous specialized "industrial districts." These clusters consist of many independent small- and medium-sized enterprises that collectively produce world-class products in terms of both quality and design, exporting them globally. Since 2000, the processes adopted in this sector have been relatively efficient compared to the European average and rely primarily on natural gas as the main fossil energy source. Industrial activity data vary widely across subsectors serving diverse markets, making it difficult to identify a common trend. From an emissions perspective, cement, lime, and glass production are the most significant contributors. This subsector is among the most important within category 1.A.2, accounting in 2024 for 23.3% of total 1.A.2 greenhouse gas emissions and 3.0% of overall national emissions.

Other

This category includes emissions from a wide range of industrial subsectors, several of which are particularly important in Italy in terms of both value added and export performance. The engineering sector (vehicle and machinery manufacturing) is the main industrial subsector by value added and export revenues, while textiles ranked second until 2000. The remaining "other industries" category encompasses furniture production and various other "Made in Italy" goods, which together contribute a non-negligible share of emissions. This category also includes emissions from the cogeneration of electricity. Due to the transformation of some of those plants into power plants directly connected to the grid, reported in category 1.A.1.a, the percentage of the category 1.A.2.g CO₂ emissions due to electricity generation has reduced in the last years. This subsector accounts, in 2024, for 26.6% of total 1.A.2 GHG emissions, and 3.4% of total national emissions.

3.4.3 Methodological issues

Energy consumption data comprise specification of consumption for 13 sub-sectors and more than 25 fuels. These very detailed data, combined with industrial production data, allow for a good estimation of all the fuel used by most industrial sectors, with the details required by CRT format. With reference to coal used in the integrated steel production plants, the quantities reported in BEN are not used as such, but a procedure has been elaborated to estimate the carbon emissions linked to steel production and those attributable to the coal gases recovered for electricity generation, as already mentioned in paragraph 3.4.1.

The detailed calculation procedure is described in Annex 3. Moreover, a part of the fuel input is considered in the estimation of process emissions, see chapter 4 for further details.

The balance of fuel (total consumption minus industrial processes consumption) is considered in the emission estimate; CO₂ emission factors used for 2024 are listed in Table 3.12. The procedure used to estimate the national emission factors is described in Annex 6. These factors account for the fraction of carbon oxidised equal to 1.00 for solid, liquid and gaseous fuels, as suggested by the IPCC 2006 guidelines (IPCC, 2006).

For some fuels such as natural gas, coal and residual oil, country specific emission factors are available for the whole time series; so, their time series considers different oxidation factors according to the improvement of combustion efficiency occurred in the nineties but considering the value equal to 1.00 from 2005.

For petroleum coke, synthesis gas from heavy residual, refinery gases, iron and steel derived gases, coking coal, anthracite, coke oven coke from 2005, and for residual gases from chemical processes, from 2007, CO₂ emission factors have been calculated based on the data reported by operators under the EU ETS scheme. See Annex 6 for further details. For the other fuels, where national information was not available, default emission factors provided by the IPCC 2006 Guidelines have been used (IPCC, 2006).

Table 3.12 Emission Factors for Power, Industry and Civil sector

	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Liquid fuels			
Crude oil	73.300	3.101	3.069
Jet gasoline	70.000	3.101	2.931
Jet kerosene	71.500	3.153	2.994
Petroleum Coke in industry*	93.880	3.129	3.931
Petroleum Coke in refineries*	95.308	3.380	3.990
Gasoil	74.100	3.186	3.102
Orimulsion	77.000	2.118	3.224
Fuel oil*	76.475	3.143	3.202
Heavy residual in refineries*	81.026	3.155	3.392
Synthesis gas from heavy residual*	98.130	0.953	4.108
Residual gases from chemical processes*	50.150	2.202	2.100
Other chemical gases*	53.877	2.296	2.256
Gaseous fuels			
Natural gas*	59.089	2.026 (Sm ³)	2.474
Solid fuels			
Steam coal*	92.227	2.318	3.861
"sub-bituminous" coal	96.100	1.816	4.024
Lignite	101.000	1.202	4.229
Coking coal*	93.490	2.906	3.914
Anthracite*	101.001	2.942	4.229
Coke oven coke*	105.305	3.085	4.409
Biomass			
Solid Biomass*	(94.600)	(0.962)	(3.961)
Derived Gases			
Refinery Gas*	56.070	2.651 (sm ³)	2.348
Coke Oven Gas*	44.857	0.748 (sm ³)	1.878
Oxygen converter Gas*	199.535	1.283 (sm ³)	8.354
Blast furnace*	246.717	0.908 (sm ³)	10.330
Other fuels (fossil)			
Municipal solid waste*	67.231	0.523	2.815
Industrial solid waste*	79.529	2.005	3.330

*country specific emission factors

Source: ISPRA elaborations

Other sources of information are the yearly survey performed for the E-PRTR, since 2003, and the EU ETS; both surveys include main industrial operators, but not all emission sources. From 2005 onwards, the

detailed reports by operators subject to EU ETS constitute a valuable source of data, as already said above, with reference to oxidation factors and average emission factors.

In general, in the industrial sector, the ETS data source is used for cross checking BEN data. Energy/emissions data from the EU ETS survey of industrial sectors should be normally lower than the corresponding BEN data because only part of the installations / sources of a certain industrial sub sector are subject to EU ETS. In case of missing sources or lower figures in the BEN than ETS, at fuel level, a verification procedure is carried out.

Since 2007 data, ISPRA verifies data from both sources and communicates potential discrepancies to MASE. Thus, a verification procedure has started that could lead to a change of data in the energy balance. However, it is necessary to underline that EU ETS data does not include all industrial installations and cannot be used directly to estimate sectoral emissions for a series of reasons that will be analyzed in the following, sector by sector.

Biomass fuel consumption in the sector is driven by the use of wood in the non-metallic subcategory and biogas from agriculture residues in the food subcategory. The trend of the implied emission factors is driven in the last years by the exponential increase of the biogas fuel consumption, observed mainly in the food processing industry, and the strong increase of wood consumption in industry, as supplied by the national energy balance (MASE, several years [a]).

Other fuels include industrial waste fuel consumption reported in the non-metallic mineral subcategory. The use of industrial waste in manufacturing industries is linked to the use in the last 15/20 years in cement production plants and refers to the consumption of RDF (Refuse-derived Fuel), plastics, tyres, waste oils and solvents. The average emission factor time series is reported in Table A6.12 of Annex 6 and it has been derived from data reported to the ETS by the plants using that fuel.

Iron and steel

For this sector, all main installations are included in EU ETS, but only from 2013 all sources of emissions are included. In the previous years, only part of the processes of integrated steel making was subject to EU ETS, in particular the manufacturing process after the production of row steel was excluded up to 2007 and only the lamination processes have been included from 2008.

So, the EU ETS data has been of limited use for this subsector and the procedure set up starting from the total carbon input to the steel making process, is the most comprehensive one to estimate the emissions to be reported in 1.A.2.a, see Annex 3 for further details. Of course, data available from EU ETS is used for cross-checking the national energy balance data, with an aim to improve the consistency of the data set. These plants are also reported in E-PRTR, but not all sources are included.

The low implied emission factors and annual variations in the average CO₂ emission factor for solid fuel are due to the fact that both activity data and emissions reported under this category include the results of the carbon balance (see Annex 3 for further details). The implied emission factor for 2024 is equal to 64.9 t/TJ. CH₄ implied emission factor is equal to 15.4 kg/TJ in 2024, and it is higher than the default emission factors because of the specificities of the in-process combustion activities. The sintering process is a pre-treatment step in the production of iron in which metal ores, coke and other materials are roasted under burners, involving the mixing of combustion products and/or the fuel with the product or raw materials (EMEP/EEA, 2019). Apart from combustion emissions, the heating of plant feedstock and product can lead to substantial CH₄ emissions which are to be accounted for in the combustion process.

Non-Ferrous Metals

These plants are mostly excluded from EU ETS; primary aluminum producing plants should have been included from 2013, but the only Italian plant closed in the same year. These production processes are also in the scope of the E-PRTR survey, which collects also information concerning emissions to air, but since these facilities usually do not exceed the emission thresholds for mandatory reporting the information regarding emissions to air is not reported by the operators.

Chemicals

The use of EU ETS data for this subsector is rather complex because generally chemical plants are excluded from EU ETS while petrochemical plants, which report also under the E-PRTR, are included from 2013. In this case, the data set is used for cross checking BEN data. As mentioned in paragraph 3.4.1, also a small amount of emissions connected to the production of electricity for the onsite use is reported in source 1.A.2.c, basic data are taken from TERN reports and the relative subsector amount is estimated with a model. In this category, biomass refers to the steam wood fuel consumption as available in the BEN. The relevant CO₂ emission factor is reported in Table 3.12 above.

Fuel consumptions of derived chemical and petrochemical fuels, which could be considered as petrol derived fuels, were reported in the past in the "other fossil fuels" category for chemicals industries. With the aim of improving the comparison between reference and sectoral approaches, these fuels have been reported under the liquid fuel category. The average CO₂ emission factor at sectoral level for liquid fuels is driven by the weight of synthesis gases from chemical processes fuel consumptions. The relevant CO₂ emission factor is reported in Table 3.12 above.

Pulp, Paper and Print

Most of the operators in the paper and pulp sector are included in EU ETS, while only a few of the printing installations are included.

CH₄ and N₂O emissions from biomass fuel consumption in the sector are included in the inventory based on the biomass fuel consumption reported in the annual environmental report by the industrial association (ASSOCARTA, several years) and to the EU ETS. Statistics on biomass fuel consumption appear from 1998. According to the information supplied by the industrial association of the sector, ASSOCARTA, a few plants started to use biomass in 1998. The use of biomass increased till 2008, while in 2009 the use of biomass sharply reduced with a further reduction in the following years to return in the last years to the same level of 2009. From 2008 information is directly reported by the production plants in the framework of the EU ETS and a reduction in the IEF is observed as a consequence of increase in energy efficiency of the biomass fuel used. For the years from 1990 to 1997 the use of biomass for energy purposes in the pulp and paper industry has been assumed not occurring. Biomass fuel consumption includes especially black liquor, from 1998 to 2007, but also industrial sludge and biogas from industrial organic wastes. From 2013 only biogas is included and, in 2024, CO₂ emission factor is equal to 56.7 t/TJ.

Food

Emissions from food production are included in this source category. Comprehensive activity data for this sector is not available; the subsector comprises many small and medium-sized enterprises, with thousands of different products. Only limited info on this sector can be found in the ETS survey, the sector is not included in the scope of ETS.

Liquid fuel refers to fuel oil and LPG fuel consumption driving the variability of the average emission factors. For the years up to 2002, solid fuel consumption was mainly related to the consumption of coke and small amount of lignite. Biomass includes fuel consumption of steam wood and biogas from food industrial residual. The CH₄ implied emission factor time series is driven by the mix of these fuels. In this sector, emissions are prevalent from biogas from food industry residual or in the paper industry, with an EF of CH₄ equal to 153 kg/TJ, while in the other manufacturing industries biomass refers to wood and similar with an emission factor for CH₄ equal to 28 kg/TJ.

CH₄ emissions from biogas fuel combustion consider the technology used to produce energy and heat from biogas combustion, usually stationary engines, which is not fully efficient and results in higher emissions of VOC, CO and PM. The emission factor is reported in the EMEP/CORINAIR Guidebook (EMEP/CORINAIR, 2007) as the maximum for stationary engines. The relevant information is planned to be collected at plant level to update this emission factor considering the improvement in technology in the last years with respect to the nineties. Biogas has an emission factor for N₂O, equal to 3 kg/TJ.

Non-metallic minerals

This sector comprises emissions from many different industrial subsectors, some of which are subject to EU ETS and some not. Construction material subsector is energy intensive, and it is subject to EU ETS. In the national energy database, the data for construction material are reported separately and they can be cross checked with ETS survey. However, in the construction material subsector, there are many small and medium size enterprises, so the operators subject to ETS are only a part of the total.

Biomass includes wood fuel consumption and other non-conventional fuels especially used in the construction material subsector. CH₄ emission factor is equal to 28 kg/TJ and refers to the use of these non-conventional fuels for cement production (EMEP/CORINAIR, 2007).

Industrial waste fuel consumption is also included in this subcategory; CH₄ and N₂O emission factors are equal to 3 kg/TJ and 15 kg/TJ respectively.

Other

This sector comprises emissions from many different industrial subsectors, mainly not subject to EU ETS.

3.4.4 Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions for this category is estimated to be about 4% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors and the difference in emission factors between the industrial subsectors, sources 1.a.2.a-g. Time series of the industrial energy consumption data are contained in the BEN time series and in the CRTs and are reported in the following table.

Table 3.13 Fuel consumptions for Manufacturing Industry sector, 1990-2024 (TJ)

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
1.A.2 Manufacturing Industries and Construction	1,367,598	1,393,148	1,506,841	1,464,862	1,116,067	913,182	794,893	887,401	816,363	773,096
a. Iron and Steel	397,841	378,482	373,499	371,192	299,536	182,846	139,913	152,542	126,490	123,296
b. Non-Ferrous Metals	11,916	14,708	20,276	19,774	18,537	16,968	17,309	18,847	18,011	17,321
c. Chemicals	320,112	288,273	279,930	257,657	241,530	169,118	144,585	130,049	123,368	111,916
d. Pulp, Paper and Print	50,730	70,189	73,713	94,498	88,256	83,986	80,591	77,214	66,464	64,230
e. Food Processing, Beverages and Tobacco	62,370	84,987	103,004	99,007	73,493	108,704	113,441	110,551	105,904	104,405
f. Non-metallic minerals	278,929	255,293	306,930	363,170	261,735	201,447	163,314	172,990	158,954	159,861
g. Other	245,699	301,216	349,489	259,564	132,980	150,113	135,741	225,209	217,174	192,066

Source: ISPRA elaborations

Emission levels observed from 1990 to 2005 are nearly constant with some oscillations, linked to the economic cycles and reflecting the development of national sectoral industries, such as paper and food. After the year 2005 the general trend is downward, with oscillations due to the economic cycles industries but also reflecting the delocalization of production in some specific sectors like chemicals and textile industry, see Table 3.11 above. The underlining reason for the reduced emissions is the reduced industrial output, and the increase in energy efficiency. For the iron and steel sector as well as for the non-metallic minerals sector, a drop is observed in the last years coherent with the reduction of the production activities in the main national iron and steel integrated plants and in the cement production industry respectively.

3.4.5 Source-specific QA/QC and verification

Basic data to estimate emissions have been reported by the national energy balance and the national grid administrator. Data collected by other surveys that include EU-ETS and E-PRTR surveys have been used to cross – check the energy balance data, fuels used and EFs. Differences and problems have been analyzed in detail and solved together with MASE experts.

The energy data used to estimate emissions reported in Table 1.A.2 have two different levels of accuracy:

- in general, they are quite reliable, and their uncertainty is the same of the BEN; as reported in Annex 4 the BEN survey covers 100% of import, export and production of energy; the total industrial consumption estimate is obtained subtracting from the total the known energy quantities (obtained by specialized surveys) used in electricity production, refineries and the civil sector.
- the energy consumption at sub sectoral level (sources 1.A.2.a-g) is estimated by MASE on the basis of sample surveys, actual production and economic data; therefore, the internal distribution of energy consumption does not have the same degree of accuracy as the higher level.

3.4.6 Source-specific recalculations

In 1A2 the main recalculations occur for the last three years because of the update of different activity data in the National Energy Balance resulting in small differences with respect to the previous submission, in particular CO₂ emissions show a change of +1.1% in 2021, -2.3% in 2022 and -1.7% in 2023. These differences are mainly due to:

- Update of coal consumption in 2023 for integrated plants (1A2a -20.1%);
- Update of liquid consumptions of other oil products in chemical and petrochemical for 2022 and 2023 resulting in some change in CO₂ emissions from 1A2c (-28.5%, -2.3%);

Update of natural gas consumptions data with the reallocation of emissions in 1A2g (+5.9%, +4.3% and 3.9% in 2021, 2022 and 2023) in place of 1A1a.

3.4.7 Source-specific planned improvements

To improve comparability with international statistics and the relevant definition and classification of fuels emission inventory, the latter has been progressively updated using the energy balance activity data provided by the Italian Ministry of Environment to the international organization, after verification that these time series data reflect the relevant emission inventory categories.

A revision of biomass and waste fuel consumption time series is planned for the next submission on the basis of energy data communicated by the Ministry of Environment to the Joint Questionnaire IEA/EUROSTAT/UNECE, after a verification and comparison with data up to now used and available in the National Energy Balance reports (MASE, several years [a]). National Energy Balances are available in Italy from 1970, with the same format and comparable data. The submissions to the international questionnaire in some cases follow different rules and different allocation of fuel consumptions. The comparison is intended to prevent the use of international statistical data from resulting in a loss of information already used for the emissions inventory.

3.5 Transport

This category shows an increase in emissions, reflecting the trend observed in fuel consumption for road transportation, which in 2024 accounts for about 92.7% of GHG sectoral emissions. The mobility demand and, particularly, the road transportation share keeps above 90% over the years. A growth is observed, although since 2008 emissions from transport begin to decrease. Due to the pandemic during the year 2020, the mobility demand sharply lowered, mainly corresponding to the lockdown periods. Since 2021, the sector has shown a recovery and, in 2024, it is responsible for 31.2% of total national GHG emissions and 38.5% of the GHG energy sector emissions.

In 2024, the GHG emission shares of the different transport modes are: 2.1% for domestic aviation, 92.7% for road transportation, 0.02% for railways (diesel oil), 4.5% for domestic navigation, and 0.7% for pipeline transport.

Emissions increase of about 26.8% from 1990 to 2007 and show a decrease of about 18.0% from 2007 to 2019; despite an inversion of the trend between 2013 and 2014, a further reduction is observed between 2015 and 2017, while 2018-2019 emissions show an upward trend because of a general growth of economy. 2024 is 4% higher than 2023, 6.6% higher than 2019 and 10.9% higher than 1990. In 2012 a drop is observed in CO₂ emissions due to a sharp reduction of gasoline and diesel fuel consumption for road transport, explained mainly by the economic crisis, contributing to the reduction of movements of passengers and goods, and in a minor way the penetration in the market of low consumption vehicles.

The time series of CO₂, CH₄ and N₂O emissions, in Mt CO₂ equivalent, is reported in Table 3.14; figures comprise all the emissions reported in table 1.A.(a)s3 of the CRT. Emission estimates are discussed below for each sub sector. The trend of CH₄ and N₂O emissions is impacted by the evolution of the technologies in the road transport sector and the distribution between the different fuels consumption.

Table 3.14 GHG emissions for the transport sector (Mt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂ Mt CO ₂ eq	100.32	111.53	121.64	126.78	114.63	105.59	85.64	101.85	107.89	107.87	112.22
CH ₄ Mt CO ₂ eq	1.01	1.13	0.86	0.56	0.33	0.24	0.16	0.17	0.16	0.17	0.17
N ₂ O Mt CO ₂ eq	0.86	1.55	1.45	1.01	0.95	0.85	0.72	0.85	0.88	0.89	0.89
Total, Mt CO₂ eq.	102.19	114.22	123.95	128.36	115.90	106.68	86.52	102.86	108.93	108.91	113.28

Source: ISPRA elaborations

CO₂ from road vehicles is key category both in 1990 and 2024, in level and trend (Tier 1 and Tier 2) with and without LULUCF. CO₂ from waterborne navigation is key category both in 1990 and 2024, in level (Tier 1) with and without LULUCF, in trend (Tier 1) with and without LULUCF and in 2024 in level (Tier 2) without LULUCF. CO₂ from civil aviation is key category in level (Tier 1) in 1990 with LULUCF, in 2024 in level (Tier 1) with and without LULUCF, in trend (Tier 1) with and without LULUCF.

3.5.1 Aviation

3.5.1.1. Source category description

The IPCC methodology requires the estimation of emissions for 1.A.3.a.i category (International Aviation) and 1.A.3.a.ii (Domestic Aviation), including figures both for the cruise phase of the flight and the landing and take-off cycles (LTO). Emissions from international aviation are reported as a memo item and are not included in national totals.

Civil aviation contributes mainly to CO₂ emissions. CH₄ and N₂O emissions also occur and are estimated in this category but their contribution is insignificant. In 2024, total GHG emissions from this source category

were about 2.1% of the national total emissions from transport, and about 0.7% of the GHG national total (in terms of CO₂ only, the share is almost the same).

GHG emissions from aviation from 1990 to 2024 show an increase of about 62%. From 1990 to 2019, GHG emissions from the sector increased by 59%, due to the expansion of the aviation transport mode. Considering the sharp reduction of movements that occurred in 2020 due to the global pandemic, the aviation sector decreased by 20% in comparison with 1990. From 2010 to 2019, a reduction is observed in GHG emissions equal to -19.6% due both to the reduction of domestic flights and to an increase of energy efficiency in new aircraft. Considering the year 2024, the total reduction amounts to -18.3%, in comparison with 2010 emissions. Focusing on the period 2010-2021, after the minimum GHGs emissions registered in the years 2015-2016, there is a rise in the emissions from aviation in the years 2017-2019, related to the growth rates in the number of domestic flights. Years 2020 -2021 are to be considered apart because of the exceptional global conditions. GHG emissions in 2024 are 102.5% higher in comparison to 2020: there is a full recovery from the first year of pandemic, and emissions are 1.7% higher than in 2019. CO₂ emissions deriving from civil aviation represent a key category in level (Tier 1) in 1990 with LULUCF, in 2024 in level (Tier 1) with and without LULUCF, in trend (Tier 1) with and without LULUCF.

3.5.1.2. *Methodological issues*

The methodology to estimate emissions is in line with the IPCC Guidelines (IPCC, 2006) and the EMEP/EEA Guidebook (EMEP/EEA, 2023).

Activity data comprises both fuel consumption and aircraft movements, which are available at different level of aggregation and derive from different sources as specified below:

- Total inland deliveries of aviation gasoline and jet fuel are provided in the national energy balance (MASE, several years [a]). This figure is the best approximation of aviation fuel consumption, for international and domestic use, but it is reported as a total and not split between domestic and international and includes fuel used for engines and airframe testing.
- Data on annual arrivals and departures of domestic and international landing and take-off cycles at Italian airports are reported by different sources: National Institute of Statistics in the statistics yearbooks (ISTAT, several years [a]), Ministry of Transport in the national transport statistics yearbooks (MIT, several years), the Italian civil aviation in the national aviation statistics yearbooks (ENAC/MIT, several years), which report total national and international commercial air traffic, scheduled and not scheduled flights including charter and air taxi, EUROCONTROL flights data time series 2002 – 2023 (EUROCONTROL, several years). Along the time series, data from ENAC have been used (ENAC/MIT, several years) from 1990 to 2001, whereas, EUROCONTROL flights data are used from 2002, considering departures from and arrivals to all airports in Italy, regarding flights flying under instrument flight rules (IFR), including civil helicopters flights and excluding flights flagged as military.

As for the emission and consumption factors, values, from 1990 to 1999, are derived by the EMEP/CORINAIR guidebook (EMEP/CORINAIR, 2007), both for LTO cycles and cruise phases, considering national specificities. These specificities derived from the results of a national study which, considering detailed information on the Italian air fleet and the origin-destination flights for the year 1999, calculated national average values for both domestic and international flights (Romano et al., 1999; ANPA, 2001) based on the default EMEP/CORINAIR emission and consumption factors (EMEP/CORINAIR, 2007). The resulting national average emission and consumption factors were therefore used to estimate emissions for LTO cycles and cruise both for domestic and international flights from 1990 to 1999.

Specifically, for the year 1999, a tier 3 method was applied. In fact, figures on the number of flights, destination, aircraft fleet and engines were provided by the local airport authorities, national airlines and EUROCONTROL, covering about 80% of the national official statistics on aircraft movements for the relevant year. Data on 'Times in mode' was also supplied by the four principal airports and estimates for the other minor airports have been carried out based on previous sectoral studies at local level.

Emissions were estimated from the number of aircraft movements broken down by aircraft and engine type (derived from ICAO database if not specified) at each of the principal Italian airports; information about whether the flight is international or domestic and the related distance travelled was also considered.

Based on sample information, estimates have been carried out at national level from 1990 to 1999 considering the official statistics on movements of the aviation sector (ENAC/MIT, several years) and applying the national average consumption and emission factors, as previously described. From 2005, EUROCONTROL provides emission estimates from the aviation sector of each EU Member State under both the UNFCCC and LRTAP conventions, both for LTO cycles and cruise phases, domestic and international, including data on fuel consumption and emission factors, and the number of flights which are also available for 2002-2004. The Advanced Emissions Model (AEM) was applied by EUROCONTROL to derive these figures, according to a Tier 3 methodology (EMEP/EEA, 2023). For the period between 1999 and 2005, linear interpolation was applied to calculate consumption and emission parameters. In general, to carry out national estimates of greenhouse gases and other pollutants for LTO cycles, both domestic and international, consumption and emissions are calculated using the average consumption and emission factors multiplied by the total number of flights. The same method is used to estimate emissions for domestic cruise. On the other hand, for international cruise, consumption is derived by difference from the total fuel consumption reported in the national energy balance and the estimated values as described above and emissions are therefore calculated.

Data on domestic and international aircraft movements from 1990 to 2024 are shown in Table 3.15 where domestic flights are those entirely within Italy.

Table 3.15 Aircraft Movement Data (LTO cycles)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Domestic flights	172,148	185,220	319,748	350,140	354,520	280,645	151,156	209,721	286,496	286,194	296,868
International flights	147,875	198,848	303,608	381,206	406,990	425,410	172,835	232,750	419,862	485,543	535,833

Source: ISTAT, several years [a]; ENAC/MIT, several years; Eurocontrol, several years.

Emission factors are reported in Table 3.16 and Table 3.17. CO₂ and SO₂ emission factors (in kg/TJ) depend on the fuel quality, and according to the information available in literature it has been assumed that the quality of jet fuel does not change in the period. CO₂ emission factors are those in the 2006 IPCC Guidelines (IPCC, 2006), while SO₂ emission factor is equal to 1 kg/t of fuel. For N₂O, because of emission factors are not available at engine/airplane level in the relevant EMEP and IPCC Guidelines which are based on the ICAO database, the 2006 IPCC Guidelines default value has been used, equal to 2 kg/TJ (IPCC, 2006). For the other gases, including CH₄, emission factors depend on the technologies and vary in the time series according to the surveys as already described in this paragraph.

Table 3.16 CO₂ and SO₂ emission factors for Aviation (kg/t) 1990-2024

	CO ₂ ^a	SO ₂
Aviation jet fuel	849	1.0
Aviation gasoline	839	1.0

a Emission factor as kg carbon/t.

Table 3.17 Non-CO₂ emission factors for Aviation (2023)

	Units	CH ₄	N ₂ O	NO _x	CO	NMVOC	Fuel
Domestic LTO	kg/LTO	0.129	0.053	7.960	5,911	0.756	604.496
International LTO	kg/LTO	0.165	0.067	11.261	7.004	0.807	769.934
Domestic Cruise	kg/t fuel	-	0.087	14.206	4.468	0.505	-
International Cruise	kg/t fuel	-	0.080	14.754	2.254	0.215	-
Aircraft Military ^a	kg/t fuel	0.400	0.200	15.800	126.000	3.600	-

Source: (°)EMEP/CORINAIR, 2007; EMEP/EEA 2023; Eurocontrol, several years

Total fuel consumption, both domestic and international, is reported by LTO and cruise in Table 3.18.

Table 3.18 Aviation jet fuel consumption for domestic and international flights (kt)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	<i>kt</i>										
Domestic LTO	111	120	208	233	227	168	89	123	176	173	179
International LTO	130	175	258	269	296	328	130	162	301	361	413
Domestic cruise	357	384	654	666	704	526	291	421	620	584	595
International cruise	1,246	1,688	2,297	2,456	2,534	2,745	1,087	1,432	2,625	3,366	3,724

Source: ISPRA elaborations

Emissions from military aircraft are also estimated and reported under category 1.A.5.b Other. The methodology to estimate military aviation emissions is simpler than the one described for civil aviation since LTO data are not available in this case. As for activity data, total consumption for military aviation is published in the petrochemical bulletin (MASE, several years [b]) by fuel. Emission factors are those provided in the EMEP/CORINAIR guidebook (EMEP/CORINAIR, 2007). CO₂ and SO₂ emission factors depend on fuel properties; as regards CO₂, emission factors have been calculated assuming that 100% of the fuel carbon is oxidized to CO₂. Therefore, emissions are calculated by multiplying military fuel consumption data for the EMEP/CORINAIR default emission factors shown in Table 3.17.

3.5.1.3. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from aviation is estimated to be about 3% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors. Time series of domestic emissions from the aviation sector is reported in Table 3.19. An upward trend in emission levels is observed from 1990 to 2019 which is explained by the increasing number of LTO cycles. Nevertheless, the propagation of more modern aircraft in the fleet slows down the trend in the most recent years. In 2020, the lowest emissions level due to the pandemic is observed. By the year 2024, emissions increased and reached higher levels in comparison with 2019.

Table 3.19 GHG emissions from domestic aviation

		1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂	<i>kt</i>	1,493.1	1,588.5	2,718.2	2,839.4	2,958.5	2,166.8	1,194.8	1,703.4	2,484.6	2,358.8	2,418.6
CH ₄	<i>t</i>	26.9	27.7	47.9	47.2	49.2	34.6	17.0	23.1	33.1	32.7	34.3
N ₂ O	<i>t</i>	41.8	44.4	76.0	70.7	77.0	57.5	28.4	40.5	60.2	58.0	59.6

Source: ISPRA elaborations

3.5.1.4. Source-specific QA/QC and verification

Data used for estimating emissions from the aviation sector derive from different sources: local airport authorities, national airlines operators, EUROCONTROL and official statistics by different Ministries and national authorities. Different QA/QC and verification activities are carried out for this category.

As regards past years, the results of the national studies and methodologies applied at national and airport level, were shared with national experts in the framework of an *ad hoc* working group on air emissions instituted by the National Aviation Authority (ENAC). The group, chaired by ISPRA, included participants from ENAC, Ministry of Environment, Ministry of Transport, national airlines and local airport authorities. The results reflected differences between airports, aircraft used and times in mode spent on each operation. Currently, verification and comparison activities regard activity data and emission factors. In particular, the number of flights has been compared considering different sources: ENAC, ASSAEROPORTI, ISTAT, EUROCONTROL and verification activities have been performed based on the updated EUROCONTROL data on fuel consumption and emission factors resulting in an update and improvement of the national

inventory. Furthermore, there is an ongoing collaboration and data exchange with regional environmental agencies on this issue.

3.5.1.5. *Source-specific recalculations*

In this submission estimates of CH₄ and N₂O have been recalculated by Eurocontrol from 2002, due to a new evaluation of taxi times.

3.5.1.6. *Source-specific planned improvements*

Improvements for the next submissions are planned based on the outcome of the ongoing quality assurance and quality control activities, regarding the results of investigation into data and information deriving from different sources, in particular further assessment of EUROCONTROL data, and comparison with ISTAT information.

3.5.2 Road Transport

3.5.2.1. *Source category description*

This section addresses the estimation of emissions related to category 1.A.3.b Road transportation. In 2024, total GHG emissions from this category were about 92.7% of the total national emissions from transport, 35.7% of the energy sector and about 28.9% of the GHG national total.

From 1990 to 2024, GHG emissions from the sector increased by 11.7%. This trend is explained by multiple factors: on one side, a strong increase starting from 1990 until 2007 (27.7%) due to the increase of vehicle fleet, total mileage and consequently fuel consumptions; on the other side, in the last years, from 2007 onwards, a decrease in fuel consumption and emissions basically due to the economic crisis (emissions from 2007 to 2019 decrease of about -18.8%); then from 2019 to 2020, there has been a sharp reduction in emissions, amounting to approximately -19.4%, as a result of the pandemic crisis; the post pandemic recovery in mobility and consumption from 2020 to 2021 has led to an increase in GHG emissions of about 21.5% and from 2021 to 2022 of about 5.0%. Finally, during last two years, increases in emissions of about 0.5% in 2023 and 4.1% in 2024 have been observed.

CO₂ emissions from road transport have been identified as a key category, both in 1990 and in 2024, with approach 1 and approach 2, with and without LULUCF, at level and trend assessment. CH₄ emissions are key category: in 1990 in level with approach 2 with and without LULUCF; in trend with approach 1 and with approach 2 without LULUCF. N₂O emissions are key categories in 1990 in level with approach 2 with LULUCF, in 2024 in level with approach 2 without LULUCF, in trend with approach 2 without LULUCF.

Emissions from road transport are calculated either from a combination of total fuel consumption data and fuel properties or from a combination of drive-related emission factors and road traffic data.

Emissions from biomass fuel consumption are included and reported as follows: biodiesel is accounted for under the diesel fuel category, bioethanol under the gasoline fuel category, and biogas under the natural gas fuel category. Biomass fuels mainly refer to the use of biodiesel blended with diesel fuel, bioethanol blended with gasoline, and biogas blended with natural gas.

CO₂ emissions are calculated based on the carbon content of the fuel. In the emission calculation model, fuel consumption used as input, balanced with the fuel consumption estimated by the model, includes both fossil and biofuels. CO₂ emissions associated with biomass are subsequently subtracted from the total to be reported separately under the biomass subcategory. CH₄ and N₂O emissions depend on vehicle technology and are estimated using more detailed information on vehicle types, technologies, and the corresponding fuel consumption. The trend in methane emissions reflects the combined effect of technological improvements aimed at reducing VOC emissions from vehicle tailpipes and the expansion of

the vehicle fleet. It should also be noted that Italy has a large fleet of motorcycles and mopeds (about 10.7 million vehicles in 2024) using gasoline, which has increased by about 62.4% since 1990. A share of this fleet does not fully comply with the most stringent VOC emission standards.

3.5.2.2. *Methodological issues*

According to the IPCC Guidelines (IPCC, 2006) and the EMEP/EEA air pollutant emission inventory guidebook 2023 (EMEP/EEA, 2023), a national methodology has been developed and applied to estimate emissions; COPERT methodology is used and country specificities are taken into account according to Tier 3 of IPCC Guidelines, such as the physic-chemical characterization of fossil fuels used in Italy and the peculiar structure of the circulating fleet.

In general, the annual update of the model is based on the availability of new measurements and studies regarding road transport emissions (for further information see: <https://www.emisia.com/utilities/copert/>). The model COPERT 5 (updated version 5.8.1, September 2024) has been used and applied for the whole time series in 2026 and 2025 submission. COPERT 5 introduced over the years upgrades both from software and methodological point of view (<https://www.emisia.com/utilities/copert/versions/>). Several new methodological features have been introduced with respect to the previous model COPERT 4. As regards fuel, updates concerned: fuel energy instead of fuel mass calculations; distinction between primary and end (blends) fuels, automated energy balance. Regarding vehicle types, updated vehicle category naming, new vehicle types and emission control technology level, have been introduced. As regards emission factors, one function type and the possibility to distinguish between peak/off-peak urban, have been implemented.

Main methodological innovations introduced in version 5.8.1 respect to the previous version 5.7.3 relate: the introduction of Euro 7 vehicles; the introduction of Euro VI CNG & LNG HDVs; the revision of CO, EC, SPN23, NO_x of Euro 6 HEV/PHEV; the revision of VOCs speciation of Euro 5/6 petrol & diesel LDVs; the revision of EC of BEVs; the revision of cold PM & BC of Euro 5/6 petrol, diesel & CNG LDVs; the revision of EC of Euro 6 LPG cars; the revision of Euro 5 motorcycles.

As regards the software, revisions relate: the extension of the functionalities of the Command Line Interface regarding ability to point to an existing .cop file, all pollutants, mileage degradation; Energy Consumption from A/C for battery electric cars. In addition, the following bugs have been solved: share of cold CH₄ and NMVOC over VOC for Euro 6 LDVs; hot CH₄ emission factors of LPG cars; PM, PN emission factor of CNG/LPG Euro 5 & 6 vehicles; minor issues. The following vehicle categories have been introduced since 2025 submission: Battery electric Light Commercial Vehicles, CNG and LNG Heavy Duty Trucks, Battery electric Buses.

Italian road vehicles electricity consumption data, introduced recently in COPERT in relation to the evolution of the fleet, derive from Eurostat database (<https://ec.europa.eu/eurostat/data/database>).

As regards CO₂ emissions from catalytic converters using urea (reported under category 2.D.3), Italian road transport emissions estimation about CO₂ from urea-based catalysts is implemented in the model used. For diesel passenger cars Euro 6 and light duty trucks Euro 6, the consumption of urea is assumed to be equal to 2% of fuel consumption; for diesel heavy duty trucks and buses, the consumption of urea is assumed to be equal to 6% of fuel consumption at Euro 4 and Euro 5 level and equal to 3.5% at Euro 6 level. Regarding the purity (the mass fraction of urea in the urea-based additive), the default value of thirty-two and half percent has been used (IPCC, 2006).

Methodologies are described in the following, distinguishing emissions calculated from fuel consumption and traffic data.

3.5.2.3. *Fuel-based emissions*

Emissions of carbon dioxide and sulfur dioxide from road transport are calculated from the consumption of gasoline, diesel, liquefied petroleum gas (LPG) and natural gas and the carbon or sulfur content of the

fuels consumed. Consumption data has been updated according to data officially communicated to the Joint Questionnaire OECD/IEA/EUROSTAT.

Consumption data for the fuel consumed by road transport in Italy are taken from the national energy balance (MASE, several years [a]), in physical units (considering the use in road transportation, in machinery as regards gasoline, in commercial and public service, and subtracting the quantities for military use in diesel oil and off-road uses in petrol).

Monitoring of the carbon content of the fuels used in Italy is an ongoing activity at ISPRA (Italian Institute for Environmental Protection and Research). The purpose is to regularly analyze the chemical composition of the used fuels or relevant commercial statistics to estimate the carbon content/emission factor (EF) of the fuels.

With reference to the whole inventory, for each primary fuel, a specific procedure has been established.

As regards road transport, Italy country-specific CO₂ emission factors values for gasoline, diesel fuel and LPG, derive from ad hoc studies about the properties of transportation fuels sold in Italy and whose results are representative and applicable with reference to four different time phases: 1990 – 1999; 2000 – 2012; 2013 – 2019; since 2020 (Innovhub – Fuel Experimental Station surveys, several years).

As regards natural gas, the national market is characterized by the commercialization of gases with different chemical composition in variable quantities from one year to the other. The methodology used to estimate the average EF for natural gas per year is based on the available consumption data, referring to the lower heat value (each year the quantities of natural gas imported or produced in Italy are published on <https://sisen.mase.gov.it/dgsaie/>, Ministry of Environment, Ministry of Industry, several years).

Emissions of CO₂, expressed as kg carbon per ton of fuel, are based on the H/C and O/C ratios of the fuel. The increase in fuel consumption due to air conditioning use implies that extra CO₂ emissions in g/km are calculated as a function of temperature and relative humidity; nevertheless, because of CO₂ emissions depend on total statistical fuel consumption, there is no impact on the CO₂ officially reported but instead on other pollutants.

Emissions of SO₂ are based on the sulfur content of the fuel, on the assumption that all the sulfur in the fuel is transformed completely into SO₂. As regards heavy metals (exhaust emissions of lead have been dropped because of the introduction of unleaded gasoline), apparent fuel metal contents (COPERT default) are used in the emissions calculation; for the non-exhaust share, values consider also of lubricant content and engine wear (EMEP/EEA, 2023).

Fuel consumption data derive basically from the national energy balance (MASE, several years [a]); supplementary information is taken from the Oil Bulletin (MASE, several years [b]). As regards biofuels, the consumption has increased in view of the targets to be respected by Italy and set in the framework of the European directive 20-20-20. The trend of biodiesel is explained by the fact that this biofuel has been tested from 1994 to 1996 before entering in production since 1998. Country specific values obtained for biodiesel in 2020 National survey have been used to update the entire fuel specifications historical series (previously, in the absence of country specific parameters, Eurostat Energy Balance parameters were used). The consumption of bioethanol has been introduced since 2008, according to data resulting in the energy balance. Values of the fuel-based emission factors for CO₂ from consumption of petrol and diesel fuels are shown in Table 3.21. These factors account for the fraction of oxidized carbon for liquid fuels equal to 1, as suggested by the 2006 IPCC guidelines (IPCC, 2006). From the nineties, different directives regulating the fuel quality in Europe have been implemented (Directive 93/12/EC, Directive 98/70/EC, Directive 2003/17/EC and Directive 2009/30/EC), in parallel with the evolution of vehicle fleet technologies; this resulted in remarkable differences in the characteristics of the fuels, including the content of carbon, hydrogen and oxygenates, parameters needed to derive the CO₂ emission factors. The final reports on the physico-chemical characterization of fossil fuels used in Italy, carried out by the Fuel Experimental Station, that is an Italian Institute operating in the framework of the Department of Industry, are used, with the aim

to improve fuel quality specifications. Fuel information is also updated based on the annual reports published by ISPRA about the fuel quality in Italy.

In consequence of the removal of CO₂ correction tool in COPERT model, previously aimed at CO₂ correction based on type approval CO₂ emission factors, referred to gasoline and diesel passenger cars from Euro 4 onwards, OBFCM data at Country level (https://climate-energy.eea.europa.eu/topics/transport/real-world-emissions/additional_information) have been considered in the COPERT efficiency improvement tool.

A specific survey was also conducted to characterize the national fuel used in 2000-2001.

Regarding 1990-1999, a study was carried out to evaluate the use of the default emission factors reported in the IPCC Guidelines 1996 in consideration of the available information on national fuels. Emission factors from the Guidelines have been considered representative for diesel and LPG while for gasoline a country specific emission factor has been calculated considering the IPCC default values and the specific energy content of the national fuels. For further details see the relevant paragraph in Annex 6.

Values for SO₂ vary annually as the sulfur-content of fuels change and are calculated every year for gasoline and gas oil and officially communicated to the European Commission in the framework of European Directives on fuel quality (ISPRA, several years); these figures are also published by the refinery's industrial association (UNEM, several years). The Directive 2003/17/EC introduced for 2005 new limit for S content in the fuels, both gasoline and diesel, 50% lower than the previous ones.

Table 3.20 Fuel-Based Emission Factors for Road Transport

National emission factors	Mg CO ₂ /TJ	Mg CO ₂ /Mg
Mtbe	73.072	-
Gasoline, 1990-'99, interpolated emission factor	71.034	3.123
Gasoline, test data, 2000-2012 ^{b,c}	71.864	3.143
Gasoline, test data, 2013-2019 ^c	73.338	3.140
Gasoline, test data, since 2020 ^c	73.081	3.152
Gas oil, 1990-'99, IPCC OECD ^a	73.274	3.129
Gas oil, engines, test data, 2000-2012 ^{b,c}	73.892	3.171
Gas oil, engines, test data, 2013-2019 ^c	73.648	3.151
Gas oil, engines, test data, since 2020 ^c	73.510	3.150
LPG, 1990-'99, IPCC ^a Europe	64.350	3.000
LPG, test data, 2000-2019 ^{b,c}	65.592	3.026
LPG, test data, since 2020 ^c	65.984	3.026
Natural gas (dry) 1990	55.822	-
Natural gas (dry) 2024	59.089	-

a IPCC, 1997. Revised 1996 IPCC Guidelines for National GHG Inventories, Reference Manual, ch1, tables 1-36 to 1-42

b APAT, 2003

c Emission factor in kg carbon/ton, based on Fuel Experimental Station (Innovhub, several years)

CO₂ and SO₂ emissions can be disaggregated by vehicle type using estimated fuel consumption factors and traffic data, following an approach similar to that adopted for the traffic-based estimation of other pollutants described below. In the current inventory, fuel consumption factors expressed in grams of fuel per kilometre were applied for each vehicle type, together with average speeds derived from the emission functions and speed coefficients provided by the COPERT 5 model (EMISIA SA, 2024). The mileage and fuel consumption values calculated using COPERT functions are reported in Table 3.21 for each vehicle category, fuel type, and road type in Italy in 2024.

Table 3.21 Average fuel consumption and mileage for main vehicle category and road type, year 2024

		Fuel Consumption (TJ)				Mileage (kveh_km)			
		Urban	Rural	Highway	TOTAL	Urban	Rural	Highway	TOTAL
Passenger Cars	Petrol	89,412	133,668	51,787	274,868	23,487,178	65,228,074	24,001,556	112,716,808
Passenger Cars	Petrol Hybrid	20,358	19,750	7,450	47,557	8,153,525	11,647,893	3,494,368	23,295,786
Passenger Cars	Petrol PHEV	2,820	2,625	1,008	6,454	1,261,274	1,801,819	540,546	3,603,639
Passenger Cars	Diesel	112,663	250,686	135,889	499,238	34,752,808	118,667,487	63,113,126	216,533,421
Passenger Cars	Diesel Hybrid	4,190	3,518	1,745	9,453	1,679,463	2,399,234	719,770	4,798,467
Passenger Cars	LPG Bifuel	25,438	27,473	19,060	71,971	7,031,296	13,836,756	7,158,264	28,026,316
Passenger Cars	CNG Bifuel	9,444	6,771	4,589	20,804	2,129,054	3,051,644	1,916,149	7,096,847
Passenger Cars	Battery electric	913	1,368	585	2,866	1,500,441	2,143,487	643,046	4,286,973
Light Commercial Vehicles	Petrol	2,210	2,036	724	4,970	388,075	853,765	310,460	1,552,300
Light Commercial Vehicles	Diesel	58,456	81,400	37,520	177,376	13,536,884	29,781,145	10,829,507	54,147,536
Light Commercial Vehicles	Battery electric	100	150	67	317	136,432	194,903	58,471	389,806
Heavy Duty Trucks	Petrol	2	5	2	9	253	758	253	1,264
Heavy Duty Trucks	Diesel	33,559	69,676	173,165	276,400	2,551,598	8,232,823	19,584,451	30,368,872
Heavy Duty Trucks	Natural Gas	420	1,051	3,094	4,565	21,048	113,908	286,011	420,968
Buses	Diesel	6,633	8,540	24,362	39,535	424,957	873,743	2,986,507	4,285,207
Buses	Diesel Hybrid	990	68	-	1,058	92,923	10,325	-	103,248
Buses	Natural Gas	6,362	389	-	6,751	299,515	33,279	-	332,795
Buses	Battery electric	563	60	-	623	106,013	11,779	-	117,793
Mopeds	Petrol	2,083	893	-	2,976	2,874,888	1,232,095	-	4,106,983
Motorcycles	Petrol	22,448	11,057	1,967	35,472	14,858,874	8,667,676	1,238,239	24,764,789

Source: ISPRA elaborations

Notes: Biodiesel included in diesel; bioethanol included in gasoline; biogas included in natural gas.

3.5.2.4. Biofuels used and fossil fuel fraction in biodiesel

In Italy, biodiesel, biogasoline and biogas are used in road transportation, and the respective emissions have been estimated in the inventory. As regards biodiesel and biogasoline, over the years, almost all commercial gasoline has been substantially E0, but in 2023 biogasoline consumption has more than doubled respect to 2022, the share respect to the total road gasoline consumption is about 1.0% in 2023 and 1.1% in 2024. The distributed diesel over the last years reached up to 5-7% by volume of biodiesel in diesel fuel, in 2023 the share of biodiesel is 5.4%, respect to the total road diesel consumption, but in 2024 a decrease is observed being the share of biodiesel equal to 3.3%. The trends over the years are explained by the decision of the Italian producers/refineries, since the beginning of the introduction of the obligations on biofuels, to focus on biodiesel rather than ethanol to comply with the European/Italian obligations to introduce biofuels on the market.

To date, biogasoline represents a minimum percentage out of the total gasoline including biogasoline consumption. According to the Renewable energy Directive (2009/28/EC) the amount of biogasoline reported in the Energy balance is equal to the renewable part of the fuel, calculated as 37% of the total volume placed on the market. Biodiesel has been tested from 1994 to 1996 before entering in production since 1998. CO₂ emissions from fossil fuel content of biofuels in Italy have been estimated by the implementation of the COPERT tool "fossil fuel fraction in biodiesel". In particular, the estimation is based on the country specific data regarding the share of FAME in biodiesel (equal to 94.3% in 2023), deriving from data and information reported by Italy under Council Directive (EU) 2015/652 laying down calculation

methods and reporting requirements pursuant to Directive 98/70/EC of the European Parliament and of the Council relating to the quality of petrol and diesel fuels. Moreover, biogas road consumption has been considered, representing about 36.0% of total road natural gas consumption in 2024. It is reported since 2020 in the IEA - Eurostat – UNECE Energy Questionnaire.

3.5.2.5. *The fuel balance process*

COPERT 5 includes an automated fuel consumption balancing procedure designed to ensure that the breakdown of fuel consumption by vehicle type, calculated based on fuel consumption factors and then aggregated, matches the BEN data on total fuel consumption in Italy (adjusted for off-road consumption).

This simulation is started up having the target to equalize calculated and statistical consumptions, separately for fuel, at national level, with the aim to obtain final estimates as accurately as possible. Once all data and input parameters have been inserted and all options have been set reflecting the peculiar situation of the Country, emissions and consumptions are calculated by the model, in the detail of the vehicle category legislation standard; then, the aggregated consumption values derived are compared with the input statistical national aggregated values (deriving basically from the National Energy Balance, as described above), with the aim to minimize the deviation.

3.5.2.6. *Traffic-based emissions*

Emissions of NMVOC, NO_x, CO, CH₄ and N₂O are calculated from emission factors, expressed in grams per kilometer, and road traffic statistics estimated by ISPRA on the basis of data released from: Ministry of Transport (MIT, several years), the Automobile Club of Italy (ACI, several years), the National Association of Cycle-Motorcycle Accessories (ANCMA, several years), the National Institute of Statistics (ISTAT, several years [b]), the National Association of concessionaries of motorways and tunnels (AISCAT, several years).

The emission factors are based on experimental measurements of emissions from in-service vehicles of different types driven under test cycles with different average speeds calculated from the emission functions and speed-coefficients provided by COPERT 5 (EMISIA SA, 2024). This source provides emission functions and coefficients relating emission factors (in g/km) to average speed for each vehicle type and Euro emission standard derived by fitting experimental measurements to polynomial functions. These functions were then used to calculate emission factor values for each vehicle type and Euro emission standard at each of the average speeds of the road and area types.

Country specific hot emission factors for Euro 6 Small and Medium LPG passenger cars, deriving from tests on five Euro 6 b/c bifuel LPG passenger cars (national survey carried out by Innovhub (Innovhub, 2018), are implemented in COPERT 5.

N₂O emission factors derive from the application of COPERT 5 v. 5.8.1 model (EMISIA SA, 2024). Tier 3 is implemented, according to which N₂O is connected to the aftertreatment devices, such as catalytic converters and diesel particle filters. N₂O emissions are significant for catalyst vehicles, in particular when the catalyst is under partially oxidizing conditions, when the catalyst has not reached its light-off temperature yet or when the catalyst is aged. So N₂O emissions depend on the vehicle age or cumulative mileage. Moreover, aftertreatment ageing depends upon the fuel sulfur level. Hence, different emission factors are explained by the variation in fuel sulfur content and in the driving conditions (EMEP/EEA, 2023). COPERT model version 5.8.1 reports an emission factor equal to 0 for conventional LPG passenger cars, for conventional diesel passenger cars and light duty vehicles, while for the other vehicle categories, emission factors are available in the model. Because of those zero values, noticeable variations may appear between IEF referred to consecutive years where the fleet consists just of conventional vehicles and Euro 1 vehicles; such differences are then explained by the different share of Euro 1 vehicles out of the total. As regards newer vehicles, N₂O emissions may derive as a byproduct from SCR systems, this issue needs to be monitored to reveal how much this could be a problem in real world conditions (EMEP/EEA, 2023).

The road traffic data used are vehicle kilometer estimates for the different vehicle types and different road classifications in the national road network. This data have to be further broken down by composition of each vehicle fleet in terms of the fraction of vehicles on the road powered by different fuels and in terms of the fraction of vehicles on the road relating to the different emission regulations which applied when the vehicle was first registered. These are related to the age profile of the vehicle fleet.

In brief, the emissions from motor vehicles fall into three different types calculated as hot exhaust emissions, cold-start emissions, and evaporative emissions for NMVOC; in addition, not exhaust emissions for PM, BC and heavy metals deriving from road vehicle tyre and brake wear and road abrasion are contemplated. Hot exhaust emissions are emissions from the vehicle exhaust when the engine has warmed up to its normal operating temperature. Emissions depend on the type of vehicle, type of fuel the engine runs on, the driving profile of the vehicle on a journey and the emission regulations applied when the vehicle was first registered as this defines the type of technology the vehicle is equipped with.

For a particular vehicle, the driving cycle over a journey is the key factor which determines the amount of pollutant emitted. Key parameters affecting emissions are acceleration, deceleration, steady speed and idling characteristics of the journey, as well as other factors affecting load on the engine such as road gradient and vehicle weight. However, studies have shown that for modelling vehicle emissions over a road network at national scale, it is sufficient to calculate emissions from emission factors in g/km related to the average speed of the vehicle in the drive cycle (EMISIA, 2024). Emission factors for average speeds on the road network are then combined with national road traffic data. Emissions are calculated from vehicles of the following types:

- Gasoline passenger cars
- Diesel passenger cars
- LPG passenger cars
- CNG passenger cars
- Petrol Hybrid passenger cars
- Petrol PHEV passenger cars
- Diesel Hybrid passenger cars
- Battery electric passenger cars
- Gasoline Light Commercial Vehicles (Gross Vehicle Weight (GVW) $\leq$ 3.5 tonnes)
- Diesel Light Commercial Vehicles (Gross Vehicle Weight (GVW) $\leq$ 3.5 tonnes)
- Battery electric Light Commercial Vehicles (Gross Vehicle Weight (GVW) $\leq$ 3.5 tonnes)
- Diesel, Gasoline, Natural Gas Rigid-axle Heavy Duty Trucks (GVW $>$ 3.5 tonnes)
- Diesel, Natural Gas Articulated Heavy Duty Trucks (GVW $>$ 3.5 tonnes)
- Diesel Buses and coaches
- Diesel Hybrid Buses
- CNG Buses
- Battery electric Buses
- Mopeds and motorcycles.

Basic data derives from different sources. Detailed data on the national fleet composition are found in the yearly report from ACI (ACI, several years), used from 1990 to 2006, except for mopeds for which estimates have been elaborated based on National Association of Cycle-Motorcycle Accessories data on mopeds fleet composition and mileages (ANCMA, several years).

Specific fleet composition data were provided by the Ministry of Transport for all vehicle categories from 2007 onwards. The Ministry of Transport in the national transport yearbook (MIT, several years) reports mileages time series. Furthermore, since 2015 the Ministry of Transport supplies information on the distribution of old gasoline cars over the detailed vehicles categories (PRE ECE; ECE 15/00-01; ECE 15/02; ECE 15/03; ECE 15/04; information obtained from the registration year; data used for the updating of the time series since 2007).

Since 2014, the Ministry of Transport supplies updated information on the reallocation of not defined vehicles categories (data used for the updating of the time series since 2007). Ministry of Transport data have been used for: the passenger cars ("Petrol Hybrid" passenger cars category are introduced from 2007 onwards, the mini petrol (Gasoline < 0.8 l) passenger cars subsector is introduced since 2012 and diesel small (Diesel<1.4 l) subsector since 2007 onwards, in addition to the gasoline, diesel, LPG, CNG traditional ones); the diesel and gasoline light commercial vehicles; the breakdown of the heavy duty trucks, buses and coaches fleet according to the different weight classes and fuels (for HDT almost exclusively diesel, a negligible share consists of gasoline HDT vehicles; diesel for coaches; diesel, diesel hybrid and CNG for buses); the motorcycles fleet in the detail of subsector and legislation standard of both 2-stroke and 4-stroke categories.

Fleet values for urban buses have been updated according to the update of the data on urban public buses, published on CNIT (MIT, several years). The National Institute of Statistics carries out annually a survey on heavy goods vehicles, including annual mileages (ISTAT, several years [b]). The National Association of concessionaries of motorways and tunnels produces monthly statistics on highway mileages by light and heavy vehicles (AISCAT, several years). The National General Confederation of Transport and Logistics (CONFETRA, several years) and the national Central Committee of road transporters (Giordano, 2007) supplied useful information and statistics about heavy goods vehicles fleet composition and mileages.

In Tables 3.22, 3.23, 3.24 and 3.25 detailed data on the relevant vehicle mileages in the circulating fleet are reported, subdivided according to the main emission regulations.

Table 3.22 Passenger Cars technological evolution: circulating fleet calculated as stock data multiplied by effective mileage (%)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
a. Gasoline cars technological evolution											
PRE ECE, pre-1973	0.04	0.03	0.01	0.01	0.002	0.002	0.002	0.002	0.002	0.002	0.001
ECE 15/00-01, 1973-1978	0.10	0.04	0.01	0.005	0.003	0.002	0.002	0.002	0.002	0.002	0.002
ECE 15/02-03, 1978-1984	0.30	0.15	0.03	0.01	0.01	0.01	0.01	0.005	0.005	0.004	0.004
ECE 15/04, 1985-1992	0.55	0.55	0.28	0.10	0.04	0.03	0.02	0.02	0.02	0.01	0.01
PC Euro 1 - 91/441/EEC, from 1/1/93	0.00	0.24	0.27	0.17	0.05	0.02	0.01	0.01	0.01	0.01	0.01
PC Euro 2 - 94/12/EEC, from 1/1/97	-	-	0.39	0.32	0.21	0.11	0.06	0.05	0.04	0.04	0.04
PC Euro 3 - 98/69/EC Stage2000, from 1/1/2001	-	-	-	0.31	0.20	0.15	0.08	0.07	0.07	0.06	0.05
PC Euro 4 - 98/69/EC Stage2005, from 1/1/2006	-	-	-	0.09	0.44	0.41	0.27	0.25	0.24	0.22	0.20
PC Euro 5 - EC 715/2007, from 1/1/2011	-	-	-	-	0.04	0.21	0.17	0.17	0.17	0.16	0.15
PC Euro 6 (Since EC 715/2007, from 9/1/2015)	-	-	-	-	-	0.06	0.24	0.23	0.23	0.22	0.21
- Euro 6 a/b/c											
- Euro 6 d-temp (2019 - 2020)	-	-	-	-	-	-	0.14	0.14	0.13	0.13	0.12
- Euro 6 d (since 2021)	-	-	-	-	-	-	-	0.05	0.09	0.13	0.20
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
b. Diesel cars technological evolution											
Conventional, pre-1993	1.00	0.92	0.35	0.05	0.01	0.004	0.002	0.002	0.002	0.001	0.001
PC Euro 1 - 91/441/EEC, from 1/1/93	-	0.08	0.10	0.03	0.01	0.002	0.001	0.001	0.001	0.001	0.001
PC Euro 2 - 94/12/EEC, from 1/1/97	-	-	0.55	0.23	0.08	0.02	0.005	0.006	0.005	0.003	0.003
PC Euro 3 - 98/69/EC Stage2000, from 1/1/2001	-	-	-	0.56	0.33	0.16	0.08	0.06	0.05	0.05	0.04
PC Euro 4 - 98/69/EC Stage2005, from 1/1/2006	-	-	-	0.13	0.50	0.43	0.25	0.21	0.20	0.19	0.14
PC Euro 5 - EC 715/2007, from 1/1/2011	-	-	-	-	0.07	0.35	0.28	0.28	0.27	0.25	0.26

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
PC Euro 6 (Since EC 715/2007, from 9/1/2015)											
- Euro 6 a/b/c	-	-	-	-	0.00	0.05	0.28	0.29	0.29	0.30	0.31
- Euro 6 d-temp (2019 - 2020)	-	-	-	-	-	-	0.10	0.11	0.11	0.11	0.12
- Euro 6 d (since 2021)	-	-	-	-	-	-	-	0.03	0.06	0.09	0.12
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
c. Lpg cars technological evolution											
Conventional, pre-1993	1.00	0.90	0.71	0.47	0.04	0.01	0.01	0.01	0.01	0.01	0.01
PC Euro 1 - 91/441/EEC, from 1/1/93	-	0.10	0.20	0.26	0.02	0.01	0.004	0.004	0.003	0.003	0.003
PC Euro 2 - 94/12/EEC, from 1/1/97	-	-	0.09	0.19	0.08	0.03	0.01	0.01	0.01	0.01	0.01
PC Euro 3 - 98/69/EC Stage2000, from 1/1/2001	-	-	-	0.06	0.08	0.05	0.02	0.02	0.02	0.02	0.02
PC Euro 4 - 98/69/EC Stage2005, from 1/1/2006	-	-	-	0.01	0.75	0.46	0.29	0.26	0.24	0.22	0.20
PC Euro 5 - EC 715/2007, from 1/1/2011	-	-	-	-	0.03	0.36	0.26	0.25	0.24	0.22	0.21
PC Euro 6 (Since EC 715/2007, from 9/1/2015)											
- Euro 6 a/b/c	-	-	-	-	-	0.08	0.13	0.12	0.12	0.11	0.11
- Euro 6 d-temp (2017-2019)	-	-	-	-	-	-	0.22	0.21	0.21	0.20	0.19
- Euro 6 d (2020 and later)	-	-	-	-	-	-	0.05	0.10	0.15	0.21	0.26
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
d. CNG cars technological evolution											
PC Conventional - Euro 4	1.00	1.00	1.00	1.00	0.91	0.58	0.42	0.39	0.37	0.36	0.35
PC Euro 5 - EC 715/2007, from 1/1/2011	-	-	-	-	0.09	0.32	0.29	0.28	0.28	0.29	0.29
PC Euro 6 (Since EC 715/2007, from 9/1/2015)											
- Euro 6 a/b/c	-	-	-	-	-	0.10	0.14	0.13	0.14	0.14	0.14
- Euro 6 d-temp (2017-2019)	-	-	-	-	-	-	0.12	0.12	0.12	0.12	0.13
- Euro 6 d (2020 and later)	-	-	-	-	-	-	0.04	0.07	0.09	0.09	0.09
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
	2007	2008	2009	2010	2015	2020	2021	2022	2023	2024	
e. Hybrid Gasoline cars technological evolution (from 2007 onwards)											
PC Euro 4 - 98/69/EC Stage2005, from 1/1/2006		1.00	1.00	0.65	0.54	0.11	0.01	0.01	0.004	0.002	0.002
PC Euro 5 - EC 715/2007, from 1/1/2011		-	-	0.35	0.46	0.74	0.07	0.04	0.03	0.02	0.01
PC Euro 6 (Since EC 715/2007, from 9/1/2015)											
- Euro 6 a/b/c		-	-	-	-	0.15	0.35	0.21	0.14	0.10	0.07
- Euro 6 d-temp (2019 - 2020)		-	-	-	-	-	0.57	0.32	0.22	0.16	0.12
- Euro 6 d (since 2021)		-	-	-	-	-	-	0.42	0.61	0.72	0.79
Total		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
	2013	2014	2015	2020	2021	2022	2023	2024			
f. Petrol PHEV cars technological evolution											
- Euro 6 a/b/c				1.00	1.00	1.00	0.33	0.02	0.01	0.01	0.01
- Euro 6 d-temp (2019 - 2020)				-	-	-	0.67	0.29	0.17	0.12	0.09

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
- Euro 6 d (since 2021)				-	-	-	-	0.69	0.82	0.87	0.90
Total				1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
	2007	2008	2009	2010	2015	2020	2021	2022	2023	2024	
g. Hybrid Diesel cars technological evolution (from 2007 onwards)											
PC Euro 6 (Since EC 715/2007, from 9/1/2015)											
- Euro 6 a/b/c		1.00	1.00	1.00	1.00	1.00	0.09	0.04	0.02	0.01	0.01
- Euro 6 d-temp (2019 - 2020)		-	-	-	-	-	0.91	0.41	0.26	0.17	0.12
- Euro 6 d (since 2021)		-	-	-	-	-	-	0.55	0.71	0.81	0.86
Total		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Source: ISPRA elaborations on ACI and Ministry of Transport data

Table 3.23 Light Commercial Vehicles technological evolution: circulating fleet calculated as stock data multiplied by effective mileage (%)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
a. Gasoline Light Commercial Vehicles technological evolution											
Conventional, pre 10/1/94	1.00	0.93	0.63	0.35	0.08	0.05	0.03	0.03	0.03	0.02	0.02
LCV Euro 1 - 93/59/EEC, from 10/1/94	-	0.07	0.21	0.17	0.10	0.05	0.02	0.02	0.02	0.01	0.01
LCV Euro 2 - 96/69/EEC, from 10/1/98	-	-	0.16	0.15	0.30	0.17	0.05	0.04	0.04	0.04	0.03
LCV Euro 3 - 98/69/EC Stage2000, from 1/1/2002	-	-	-	0.31	0.26	0.20	0.10	0.07	0.08	0.07	0.06
LCV Euro 4 - 98/69/EC Stage2005, from 1/1/2007	-	-	-	0.01	0.25	0.31	0.23	0.20	0.17	0.15	0.14
LCV Euro 5 - 2008 Standards 715/2007/EC, from 1/1/2012	-	-	-	-	0.004	0.21	0.16	0.15	0.13	0.11	0.10
LCV Euro 6 (Since 2007/715/EC, from 9/1/2016)											
- Euro 6 a/b/c	-	-	-	-	-	0.02	0.10	0.09	0.08	0.07	0.07
- Euro 6 d-temp (2018 - 2020)	-	-	-	-	-	-	0.30	0.31	0.26	0.23	0.21
- Euro 6 d (since 2021)	-	-	-	-	-	-	-	0.09	0.20	0.29	0.36
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
b. Diesel Light Commercial Vehicles technological evolution											
Conventional, pre 10/1/94	1.00	0.92	0.54	0.22	0.07	0.03	0.01	0.01	0.01	0.01	0.01
LCV Euro 1 - 93/59/EEC, from 10/1/94	-	0.08	0.22	0.10	0.05	0.03	0.01	0.005	0.004	0.004	0.003
LCV Euro 2 - 96/69/EEC, from 10/1/98	-	-	0.24	0.21	0.17	0.09	0.01	0.01	0.01	0.01	0.01
LCV Euro 3 - 98/69/EC Stage2000, from 1/1/2002	-	-	-	0.46	0.33	0.22	0.05	0.05	0.04	0.04	0.03
LCV Euro 4 - 98/69/EC Stage2005, from 1/1/2007	-	-	-	0.01	0.38	0.33	0.18	0.18	0.16	0.14	0.13
LCV Euro 5 - 2008 Standards 715/2007/EC, from 1/1/2012	-	-	-	-	0.01	0.30	0.29	0.26	0.24	0.22	0.21
LCV Euro 6 (Since 2007/715/EC, from 9/1/2016)											
- Euro 6 a/b/c	-	-	-	-	0.00	0.01	0.16	0.14	0.13	0.12	0.11
- Euro 6 d-temp (2018 - 2020)	-	-	-	-	-	-	0.29	0.26	0.25	0.23	0.21
- Euro 6 d (since 2021)	-	-	-	-	-	-	-	0.09	0.16	0.23	0.30
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Source: ISPRA elaborations on ACI and Ministry of Transport data

Table 3.24 Heavy Duty Trucks and Buses technological evolution: circulating fleet calculated as stock data multiplied by effective mileage (%)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
a. Heavy Duty Trucks technological evolution											
Conventional, pre 10/1/93	1.00	0.90	0.68	0.37	0.20	0.02	0.01	0.01	0.01	0.01	0.01
HDT Euro I - 91/542/EEC Stage I, from 10/1/93	-	0.10	0.10	0.07	0.04	0.01	0.003	0.004	0.004	0.004	0.004
HDT Euro II - 91/542/EEC Stage II, from 10/1/96	-	-	0.22	0.28	0.15	0.08	0.04	0.04	0.04	0.03	0.03
HDT Euro III - 2000 Standards, 99/96/EC, from 10/1/2001	-	-	-	0.28	0.36	0.34	0.20	0.18	0.17	0.16	0.15
HDT Euro IV - 2005 Standards, 99/96/EC, from 10/1/2006	-	-	-	-	0.07	0.09	0.07	0.06	0.06	0.05	0.05
HDT Euro V - 2008 Standards, 99/96/EC, from 10/1/2009	-	-	-	-	0.18	0.39	0.32	0.30	0.27	0.25	0.23
HDT Euro VI (Since 2009/595/EC, from 12/31/2013)											
- Euro VI A/B/C	-	-	-	-	-	0.07	0.23	0.22	0.20	0.19	0.18
- Euro VI D/E (2019 and later)	-	-	-	-	0.001	0.003	0.13	0.19	0.25	0.30	0.35
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
b. Diesel Buses technological evolution											
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Conventional, pre 10/1/93	1.00	0.93	0.65	0.34	0.13	0.01	0.005	0.004	0.004	0.003	0.002
Buses Euro I - 91/542/EEC Stage I, from 10/1/93	-	0.07	0.07	0.08	0.04	0.01	0.01	0.004	0.004	0.003	0.001
Buses Euro II - 91/542/EEC Stage II, from 10/1/96	-	-	0.28	0.32	0.27	0.14	0.07	0.06	0.05	0.04	0.02
Buses Euro III - 2000 Standards, 99/96/EC, from 10/1/2001	-	-	-	0.26	0.34	0.38	0.26	0.21	0.19	0.17	0.10
Buses Euro IV - 2005 Standards, 99/96/EC, from 10/1/2006	-	-	-	-	0.12	0.13	0.11	0.10	0.09	0.09	0.07
Buses Euro V - 2008 Standards, 99/96/EC, from 10/1/2009	-	-	-	-	0.11	0.28	0.25	0.26	0.26	0.25	0.26
Buses Euro VI (Since 2009/595/EC, from 12/31/2013)											
- Euro VI A/B/C	-	-	-	-	-	0.05	0.20	0.21	0.20	0.19	0.22
- Euro VI D/E (2019 and later)	-	-	-	-	-	-	0.10	0.15	0.19	0.24	0.33
	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
c. CNG Buses technological evolution											
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Urban CNG Buses Conventional, pre 10/1/93; Urban CNG Buses Euro I - 91/542/EEC Stage I, from 10/1/93	1.00	1.00	0.11	0.01	0.003	0.003	0.001	0.001	0.001	0.0004	0.0002
Urban CNG Buses Euro II - 91/542/EEC Stage II, from 10/1/96	-	-	0.89	0.20	0.10	0.05	0.01	0.01	0.004	0.002	0.001
Urban CNG Buses Euro III - 2000 Standards, 99/96/EC, from 10/1/2001; Urban CNG Buses Euro IV - 2005 Standards, 99/96/EC, from 10/1/2006	-	-	-	0.79	0.09	0.07	0.05	0.04	0.03	0.02	0.02
Urban CNG Buses Euro V - 2008 Standards, 99/96/EC, from 10/1/2009; EEV (Enhanced environmentally friendly vehicle; ref. 2001/27/EC and 1999/96/EC line C, optional limit emission values).	-	-	-	-	0.81	0.84	0.58	0.53	0.39	0.29	0.20

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Urban CNG Buses Euro VI D/E (since 2013)	-	-	-	-	-	0.03	0.35	0.42	0.57	0.68	0.78
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

d. Diesel Hybrid Buses technological evolution (from 2007 onwards)

	2007	2008	2009	2010	2015	2020	2021	2022	2023	2024
Buses Euro VI (Since 2009/595/EC, from 12/31/2013)										
- Euro VI A/B/C	1.00	1.00	1.00	1.00	1.00	0.16	0.10	0.08	0.04	0.03
- Euro VI D/E	-	-	-	-	-	0.84	0.90	0.92	0.96	0.97
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Source: ISPRA elaborations on ACI and Ministry of Transport data

Table 3.25 Mopeds and motorcycles technological evolution: circulating fleet calculated as stock data multiplied by effective mileage (%)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Mopeds and motorcycles - Conventional	1.00	1.00	0.88	0.43	0.18	0.12	0.09	0.09	0.09	0.08	0.08
Mopeds and motorcycles - Euro 1	-	-	0.12	0.30	0.20	0.14	0.10	0.09	0.09	0.08	0.07
Mopeds and motorcycles - Euro 2	-	-	-	0.22	0.35	0.32	0.22	0.20	0.19	0.18	0.16
Mopeds and motorcycles - Euro 3	-	-	-	0.04	0.27	0.41	0.40	0.38	0.36	0.33	0.30
Mopeds and motorcycles - Euro 4	-	-	-	-	-	-	0.18	0.18	0.17	0.16	0.16
Mopeds and motorcycles - Euro 5	-	-	-	-	-	-	0.01	0.05	0.10	0.16	0.23
Total	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Source: ISPRA elaborations on ACI, ANCMA and Ministry of Transport data

Average emission factors are calculated for average speeds by three driving modes: urban, rural and motorway, combined with the vehicle kilometres travelled and vehicle categories. ISPRA estimates total annual vehicle kilometres for the road network in Italy by vehicle type, see Table 3.26, based on data from various sources:

- Ministry of Transport (several years) for rural roads and on other motorways; the latter estimates are based on traffic counts from the rotating census and core census surveys of ANAS (ANAS, several years);
- highway industrial association for fee-motorway (AISCAT, several years);
- local authorities for built-up areas (urban).

Table 3.26 Evolution of fleet consistency and mileage

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
All passenger vehicles (including moto), total mileage (10 ⁹ veh-km/y)	350	412	454	446	438	437	342	416	428	431	434
Car fleet (10 ⁶)	27	30	32	34	36	37	40	40	40	41	42
Moto, total mileage (10 ⁹ veh-km/y)	30	41	42	42	34	32	23	23	23	26	29
Moto fleet (10 ⁶)	7	7	9	9	9	10	10	10	10	11	11
Goods transport, total mileage (10 ⁹ veh-km/y)	69	76	81	103	76	63	56	69	77	79	87
Truck fleet (10 ⁶), including LDV	2	3	3	4	5	5	5	5	5	5	5

Source: ISPRA elaborations

Notes: The passenger vehicles include passenger cars, buses and moto; the moto fleet includes mopeds and motorcycles; in the goods transport light commercial vehicles and heavy-duty trucks are included.

When a vehicle engine is cold, it emits at a higher rate than when it has warmed up to its designed operating temperature. This is particularly true for gasoline engines, and the effect is even more severe for cars fitted with three-way catalysts, as the catalyst does not function properly until the catalyst is also warmed up.

Emission factors have been derived for cars and LCVs from tests performed with the engine starting cold and warmed up. The difference between the two measurements can be regarded as an additional cold-start penalty paid on each trip a vehicle is started with the engine (and catalyst) cold.

Evaporative emissions of gasoline fuel vapour from the tank and fuel delivery system in vehicles constitute a significant fraction of total NMVOC and methane emissions from road transport. Nevertheless, the contribution of evaporative emissions to total NMVOC emissions decreased significantly since the introduction of carbon canisters. Breathing losses through the tank vent and fuel permeations and leakages are considered the most important sources of evaporative emissions. The estimation of evaporative emissions considers three different mechanisms: diurnal emissions (depending on daily temperature variations), running losses (during the vehicles use) and hot soak emissions (following the vehicles use). The process of fuelling of vehicles is not considered here. The procedure for estimating evaporative emissions of NMVOCs takes account of gasoline volatility, the absolute ambient temperature and temperature changes, the characteristics of vehicles design; the driving pattern is also significant for hot soak emissions and running losses (EMEP/EEA, 2023).

3.5.2.7. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from road transport is estimated to be about 4% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions because of the uncertainty levels attributed to the related emission factors.

The following Table 3.27 summarizes the time series of GHG emissions in CO₂ equivalent from road transport, highlighting the evolution of this source, characterized by an upward trend in CO₂ emission levels from 1990 to 2007, which is explained by the increasing of the fleet, total mileages, and fuel consumptions and by a decreasing trend from 2007 onwards, due, on one side, to the economic crisis, and on another side, to the propagation of the number of vehicles with low fuel consumption per kilometre. In subsequent years, with respect to 2007, a reduction in total mileages, fuel consumptions (gasoline and diesel) and consequently CO₂ emissions have been noted. Since 2017 emissions increase until 2019. Then from 2019 to 2020 there has been a sharp reduction in emissions, amounting to approximately -19.4% because of the pandemic crisis. Then from 2020 to 2021 a recovery of about +21.5%, from 2021 to 2022 an increase of about 5.0%, from 2022 to 2023 an increase of about 0.5% have been observed. Finally, during last year 2023 – 2024 GHG emissions increase of about 4.1%.

CH₄ and N₂O emission trends are consequence of the penetration of new technologies according to the main emission regulations. Specifically, CH₄ and more in general VOC emissions have reduced along the time series due to the introduction of VOC abatement devices on vehicles, in agreement with the legislation emission limits, and the rate of penetration of the new vehicles into the national fleet. The time series of N₂O emissions and implied emission factors are prevalently driven by the fleet composition and the penetration rate of the new vehicles/technologies. Moreover, in the COPERT model, N₂O emission factors depend also on the sulphur content of the fuel. Significant drops of emissions and implied emission factors are observed in 1999-2000 and in 2004-2005 which are explained by the different fuel specifications in those years due to the application of the relevant European Directives on fuel quality. The sulphur content (%wt) in gasoline was 0.04 and 0.007 respectively in 1999 and 2000, 0.0055 and 0.0025 respectively in 2004 and 2005, 0.0012 and 0.0005 in 2008 and 2009 and for diesel oil changed from 0.0226 in 2004 to 0.0035 in 2005 and from 0.0028 in 2008 to 0.0008 in 2009.

Table 3.27 GHG emissions from road transport (kt CO₂ equivalent)

		1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂	kt	92,331.7	103,532.1	111,523.9	117,112.0	104,657.4	98,349.2	77,836.5	94,633.6	99,432.5	99,916.2	104,024.7
CH ₄	kt CO ₂ eq	969.1	1,090.1	814.6	533.3	309.8	219.2	137.2	145.1	145.5	148.6	149.7
N ₂ O	kt CO ₂ eq	746.0	1,434.4	1,336.9	908.6	835.5	789.6	651.7	785.7	811.3	806.0	829.8
Total	kt CO ₂ eq	94,046.8	106,056.7	113,675.4	118,553.8	105,802.7	99,358.0	78,625.5	95,564.4	100,389.3	100,870.8	105,004.3

Source: ISPRA elaborations

3.5.2.8. *Source-specific QA/QC and verification*

Data used for estimating emissions from the road transport sector derive from different sources, including official statistics providers and industrial associations. A specific procedure undertaken for improving the inventory in the sector regards the establishment of a national expert panel in road transport which involves, on a voluntary basis, different institutions, local agencies and industrial associations cooperating for improving activity data and emission factors accuracy. In this group, emission estimates are presented annually, and new methodologies are shared and discussed. Reports and data of the meetings can be found at the following address: http://groupware.sinanet.isprambiente.it/expert_panel/library. Last meeting has been held in 2024 in Rome (Automobile Club of Italy, <https://aci.gov.it/attivita-e-progetti/iniziative-e-progetti/>). In addition, road transport emission factors are shared and publicly available on the website <https://fetransp.isprambiente.it/#/>.

Besides, time series resulting from the recalculation due to the application of COPERT have been discussed over time with national experts in the framework of an ad hoc working group on air emissions inventories. The group is chaired by ISPRA and includes participants from the local authorities responsible for the preparation of local inventories, sectoral experts, the Ministry of Environment, and air quality model experts. Recalculations are comparable with those resulting from application of the model at local level. Top-down and bottom-up approaches have been compared with the aim to identify the major problems and future possible improvements in the methodology to be addressed (emission estimates at the link: <https://emissioni.sina.isprambiente.it/inventario-nazionale/>).

3.5.2.9. *Source-specific recalculations*

The annual update of the road transport emissions time series involves a periodic review process. In the 2026 submission, the historical time series has been revised from 2015 onwards following the availability of new data and updated information. In particular, the number of buses used in urban public transport services for the year 2023 has been revised based on updated national statistics reported in the CNIT and published by the Ministry of Transport in 2025.

Estimates of electricity consumption in road transport have also been revised following the update of the energy consumption factors reported in *Road Transport Emission Factors*, Appendix 4 (2025 update) of the *EMEP/EEA Air Pollutant Emission Inventory Guidebook 2023*. Italian road vehicle electricity consumption data are derived from the Eurostat database (<https://ec.europa.eu/eurostat/data/database>). The electricity consumption values used as input in COPERT have been calibrated according to vehicle categories, using the electricity classification adopted in COPERT.

National data on density and energy content for natural gas used in road transport have been updated starting from 2023. In addition, the average net calorific value for biogasoline has been revised from 2020 onwards, based on data reported for Italy in the IEA–Eurostat–UNECE Questionnaire 2024.

The COPERT efficiency improvement tool has been applied since 2025 submission (OBFCM data at country level https://climate-energy.eea.europa.eu/topics/transport/real-world-emissions/additional_information), also to compensate the removal of CO₂ correction tool in COPERT model, previously referred to gasoline and diesel passenger cars from Euro 4 onwards.

Biogas road consumption, included in COPERT model in the total road natural gas consumption, has been considered in the Inventory, reported only since 2020 in the IEA - Eurostat – UNECE Energy Questionnaire (about 11%, 15%, 26%, 33% and 36% of total road natural gas consumption in 2020, 2021, 2022, 2023 and 2024 respectively).

According to the 2006 IPCC Guidelines, emission estimates from lubricants have been reported under IPPU except lubricants used in two stroke engines in road transport; so, CO₂ emissions from lubricants have been detailed and attributed just to the two stroke engines in road transport ("1.A.3.b.iv, Other liquid fuels"), calculated by COPERT model, while the remaining share has been considered in the IPPU sector.

Based on the above revisions, updates have been applied to the mileage estimates in the historical series, in accordance with fuel balance constraints, to maintain consistency, at trend level over the years, with national statistics updates, in particular taking into account the downward revision of tonne-kilometres data for total national road freight transport (not less than 50 km) for the year 2023 (ISTAT, Ministry of Transport, several years).

Differences between 2026 and previous submission, for road transport GHG emissions, account for 0.00% in 1990 and -0.004% in 2023; the recalculations registered for the driver carbon dioxide values are 0.00% in 1990 and 0.01% in 2023; as regards methane, discrepancies vary from 0.00% in 1990 to -0.82% in 2023; emissions of nitrous oxide show variations of 0.00% in 1990 and -1.47% in 2023. In Table 3.28 the recalculation time series is reported for all gases.

Table 3.28 Emission recalculations in road transport 1990 - 2023 (%)

Year	GHG	CO ₂	CH ₄	N ₂ O
1990	0.00%	0.00%	0.00%	0.00%
1991	0.00%	0.00%	0.00%	0.00%
1992	0.00%	0.00%	0.00%	0.00%
1993	0.00%	0.00%	0.00%	0.00%
1994	0.00%	0.00%	0.00%	0.00%
1995	0.00%	0.00%	0.00%	0.00%
1996	0.00%	0.00%	0.00%	0.00%
1997	0.00%	0.00%	0.00%	0.00%
1998	0.00%	0.00%	0.00%	0.00%
1999	0.00%	0.00%	0.00%	0.00%
2000	0.00%	0.00%	0.00%	0.00%
2001	0.00%	0.00%	0.00%	0.00%
2002	0.00%	0.00%	0.00%	0.00%
2003	0.00%	0.00%	0.00%	0.00%
2004	0.00%	0.00%	0.00%	0.00%
2005	0.00%	0.00%	0.00%	0.00%
2006	0.00%	0.00%	0.00%	0.00%
2007	0.00%	0.00%	0.00%	0.00%
2008	0.00%	0.00%	0.00%	0.00%
2009	0.00%	0.00%	0.00%	0.00%
2010	0.00%	0.00%	0.00%	0.00%
2011	0.00%	0.00%	0.00%	0.00%
2012	0.00%	0.00%	0.00%	0.00%
2013	0.00%	0.00%	0.00%	0.00%
2014	0.00%	0.00%	0.00%	0.00%
2015	0.00%	0.00%	-0.39%	0.33%
2016	0.00%	0.00%	0.00%	0.00%
2017	0.00%	0.00%	0.00%	0.00%
2018	0.00%	0.00%	0.00%	0.00%
2019	0.00%	0.00%	0.22%	-0.14%
2020	0.00%	0.00%	0.00%	0.00%
2021	0.00%	0.00%	-1.90%	-0.03%
2022	-0.02%	0.00%	-4.07%	-1.04%
2023	0.00%	0.01%	-0.82%	-1.47%

Source: ISPRA elaborations

3.5.2.10. Source-specific planned improvements

Improvements for the next submission will be connected to the possible new availability of data and information regarding activity data, calculation factors and parameters, new developments of the methodology and the update of the software.

3.5.3 Railways

Electricity used by railways for electric traction is supplied through the public distribution system; therefore, the emissions associated with its generation are reported under category 1.A.1.a *Public Electricity*. Emissions from diesel-powered trains are reported under category 1.A.3.c *Railways*. These estimates are based on gasoil consumption for railways reported in the National Energy Balance (BEN) (MASE, several years [a]), applying the Tier 1 methodology and the emission factors provided in the *EMEP/EEA Emission Inventory Guidebook 2023* (EMEP/EEA, 2023). Emissions related to lubricants in diesel locomotives in the railway sector are reported under the IPPU sector. An exception is represented by lubricants used in two-stroke engines in road transport, which are instead accounted for within the energy sector.

Fuel consumption data are collected by the Ministry of Economic Development, responsible for the energy balance, from the companies with diesel railways. The activity is present only in those areas without electrified railways, which are limited in the national territory. The trend reflects the decrease in the use of these railways. Because of low values, emissions from railways do not represent a key category.

Carbon dioxide and sulfur dioxide emissions are calculated on fuel-based emission factors using fuel consumption data from the energy balance. The CO₂ emission factors for diesel fuel derive from ad hoc studies about the properties of transportation fuels sold in Italy, performed by ISPRA since the nineties, and whose results are representative and applicable with reference to three different time phases: 1990 – 1999; 2000 – 2011; 2012 – 2019; since 2020 (Innovhub, several years).

Values for SO₂ vary annually according to the variation of the Sulphur-content of fuels produced, imported and commercialized, and it is yearly monitored according to legislative constraints; moreover, it is officially communicated to the European Commission in the framework of European Directives on fuel quality (ISPRA, several years). Emissions of CO, NMVOC, NO_x, N₂O and methane are based on the EMEP/EEA methodology (EMEP/EEA, 2023) considering the implementation of the relevant European Directives to reduce atmospheric pollutants. The emission factors shown in Table 3.29 are aggregate factors so that all factors are reported on the common basis of fuel consumption.

Table 3.29 Emission factors for railway in 2024 (kg/t)

	CO ₂	CH ₄	N ₂ O	NO _x kg/t	CO	NMVOC	SO ₂
Diesel trains	3,140	0.18	1.24	52.4	10.7	4.65	0.015

Source: EMEP/EEA,2023; IPCC, 2006

GHG emissions from railways accounted in 2024 for about 0.02% of the total transport emissions. No recalculation occurred in this submission. No specific improvements are planned for the next submission.

3.5.4 Navigation

3.5.4.1. Source category description

This source category includes all emissions from fuels delivered to water-borne navigation. Mainly CO₂ emissions derive from this category, whereas CH₄ and N₂O emissions are less important. Emissions from

navigation constituted 4.5% of the total GHG in the transport sector in 2024 and about 1.4% of the national total. GHG emissions from navigation in 2024 are 8.6% lower than in 1990. GHGs emissions from national navigation are 8.7% higher in 2024, compared to 2023. CO₂ from waterborne navigation is key category both in 1990 and 2024, in level (Tier 1) with and without LULUCF, in trend (Tier 1) with and without LULUCF and in 2024 in level (Tier 2) without LULUCF.

3.5.4.2. *Methodological issues*

Emissions of the Italian inventory from the navigation sector are carried out according to the IPCC Guidelines (IPCC 2006) and the EMEP/EEA Guidebook (EMEP/EEA, 2023). A national methodology has been developed following the EMEP/EEA Guidebook which provides details to estimate emissions from domestic navigation, specifying recreational craft and inland waterways, ocean-going ships by cruise and harbor activities; emissions from international navigation are also estimated and included as memo item (EMEP/EEA, 2023). Inland, coastal, and deep-sea fishing are estimated and reported under 1.A.4.c. International inland waterways do not occur in Italy. The methodology developed to estimate emissions is based on the following assumptions and information.

Activity data comprises both fuel consumption and ship movements, which are available in different level of aggregation and derive from different sources as specified here below:

- Total deliveries of fuel oil, gas oil and marine diesel oil to marine transport are given in national energy balance (MASE, several years (a)). The split between domestic and international is not provided.
- Naval fuel consumption for inland waterways, ferries connecting mainland to islands and leisure boats, is also reported in the national energy balance as it is the fuel for shipping (MASE, several years (a)).
- Data on annual arrivals and departures of domestic and international shipping calling at Italian harbors are reported by the National Institute of Statistics in the statistics yearbooks (ISTAT, several years (a)) and Ministry of Transport in the national transport statistics yearbooks (MIT, several years).

As for emission and consumption factors, figures are derived from national studies. The first study assessed detailed information on the Italian marine fleet and the origin-destination movement matrix for the year 1997, and calculated national average values, both for recreational and harbor activities and national cruise, considering specificities of national harbors including typical times for maneuvering and time spent in the harbor as well as the distribution of ships in terms of ferries, container ships, cargo (ANPA, 2001). Based on this information and the default emission and consumption factors reported in the EMEP/CORINAIR guidebook (EMEP/CORINAIR, 2007), national average figures were estimated for harbor and cruise activities both for domestic and international shipping from 1990 to 1999. The study was repeated for the years 2004, 2005 and 2006 to consider more recent trends in the maritime sector both in terms of modelling between domestic and international consumption and improvements of operational activities in harbor (TECHNE, 2009). Based on the results, national average emissions and consumption factors were updated and applied from 2000. Specifically, for the years referred to in the surveys, the current method estimates emissions from the number of ships movements broken down by ship type at each of the principal Italian ports considering the information of whether the ship movement is international or domestic, the average tonnage and the relevant distance travelled. For those years, in fact, figures on the number of arrivals, destination, and fleet composition were provided by the local port authorities and by the National Institute of Statistics, covering about 90% of the official national statistics on ship movements. Consumption and emission factors are those derived from the EMEP/CORINAIR guidebook (EMEP/CORINAIR, 2007) and refer to the Tier 3 ship movement methodology that considers origin-destination ship movements matrices as well as technical information on the ships, as engine size, gross tonnage of ships and operational times in harbors. Based on sample information, estimates have been carried out at national level for the relevant years considering the official statistics of the maritime sector. Moreover, a recent study has been conducted

in some Italian ports, which allows to update emission factors in ports, where hoteling emission factors have been updated from year 2008 (ISPRA, 2023).

In general, national estimates of greenhouse gases and other pollutants in the Italian inventory for harbor and domestic cruise activities are obtained by calculating consumptions and emissions across the time series. This is done by applying average consumption and emission factors to the total number of movements. For international cruise, consumption is derived by subtracting the estimated values as described above from the total fuel consumption reported in the national energy balance; emissions are then calculated based on this derived consumption.

The composition of the fleet of gasoline-fueled recreational craft distinguished in two strokes and four strokes engine distribution is provided by the industrial category association (UCINA, several years); the trend of the average emission factors considers the switch from two strokes to four strokes engines of the national fleet due to the introduction in the market of new models. In 2000, the composition of the fleet was 90% of two strokes' engines equipped and 10% of four strokes while in the last year four strokes' engines are about 53% of the fleet. Gasoline fuel consumption for recreational crafts is not available on the National Energy balance for the last years, so it is estimated based on the fleet which has not significantly changed in the last years.

3.5.4.3. Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from maritime is estimated to be about 3% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors. Estimates of fuel consumption for domestic use, in the national harbors or for travel within two Italian destinations, and bunker fuels used for international travels are reported in Table 3.30. Time series of domestic GHG emissions for waterborne navigation are also shown in the same table. An upward trend in emission levels is observed from 1990 to 2000, explained by the increasing number of ship movements. Nevertheless, the operational improvements in harbor activities and a reduction in ship domestic movements inverted the tendency in the last years.

Table 3.30 Marine fuel consumptions in domestic navigation and international bunkers (kt) and GHG emissions from domestic navigation (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Gasoline for recreational craft (kt)	182	210	213	199	169	90	86	84	67	64	74
Diesel oil for inland waterways (kt)	20	23	20	77	62	54	19	22	21	22	21
Fuels used in domestic cruise navigation (kt)	778	706	811	740	725	525	667	511	571	530	574
Fuel in harbours (dom+int ships) (kt)	748	693	818	759	844	733	1,054	807	903	837	907
Fuel in international Bunkers (kt)	1,348	1,241	1,214	2,095	2,562	1,563	1,321	1,774	1,571	1,452	1,327
Emissions from National Navigation (kt)											
CO ₂ (kt)	5,470	5,163	6,103	5,623	5,705	4,448	5,798	4,540	4,959	4,613	5,012
CH ₄ (kt CO ₂ eq.)	39	42	43	38	33	20	22	19	17	16	18
N ₂ O (kt CO ₂ eq.)	34	31	37	35	36	29	38	30	33	31	33
Total (kt CO₂ eq.)	5,543	5,236	6,183	5,696	5,774	4,497	5,858	4,588	5,009	4,660	5,064

Source: ISPRA elaborations

3.5.4.4. Source-specific QA/QC and verification

Basic data to estimate emissions are reconstructed starting from information on ship movements and fleet composition coming from different sources. Data collected from the local port authorities was compared with the official statistics supplied by ISTAT, collected from maritime operators with a yearly survey and communicated at international level to EUROSTAT. Differences and problems were analyzed in detail and solved together with ISTAT experts. Different sources of data are usually used and compared during the compilation of the annual inventory. Besides, time series resulting from the recalculation have been

presented to the national experts and regional environmental agencies in the framework of an ad hoc working group on air emissions inventories. Top-down and bottom-up approaches have been compared with the aim of identifying the potential problems and future improvements to be addressed.

3.5.4.5. *Source-specific recalculations*

Recalculations, respect to the previous submission occurred. ISTAT reviewed the number of ships arriving in Italian ports in 2023; therefore, emissions have been updated accordingly.

3.5.4.6. *Source-specific planned improvements*

Further, improvements will regard verification of activity data on ship movements and emission estimates with regional environmental agencies, especially with those more affected by maritime pollution. We plan to build a tool which calculate every year emissions at harbor level taking in account of the information officially provided by Italy to Eurostat per type of ship, class of tonnage and movement statistics.

3.5.5 Other transportation

3.5.5.1. *Source category description*

This category includes all emissions from fuels delivered to the transportation by pipelines and storage of natural gas. Mainly CO₂ emissions derive from this category, as well as the other relevant pollutants typical of a combustion process, such as SO_x, NO_x, CO and PM. CH₄ and N₂O emissions are also estimated.

3.5.5.2. *Methodological issues*

Emissions from pipeline compressors are carried out according to the IPCC Guidelines and are estimated based on natural gas fuel consumption used for the compressors and the relevant emission factors. The amount of fuel consumption is estimated on the basis of data supplied for the whole time series by the national operators of natural gas distribution (SNAM, several years; STOGIT, several years) and refers to the fuel consumption for the gas storage and transportation; this consumption is part of the fuel consumption reported in the national energy balance in the consumption and losses sheet (MASE, several years [a]). Emission factors are those reported in the EMEP/EEA Guidebook for gas turbines (EMEP/CORINAIR, 2007), except for CO₂ for natural gas which is the country specific value used for the whole energy sector reported in Table 3.12. Emissions communicated by the national operators in their environmental reports are also considered to estimate air pollutants.

3.5.5.3. *Uncertainty and time-series consistency*

The combined uncertainty is estimated to be about 3% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors. Fluctuations and time series are driven both by the general trend of total natural gas fuel consumed (and transported) and by the annual fluctuation of the storage activities, which are driven by the price fluctuation of the natural gas. Natural gas fuel consumption for pipeline compressors increased from 7,359 TJ in 1990 to 12,645 TJ in 2024 with a peak of 19,098 TJ in 2010. GHG emissions follow the same trend of fuel consumption.

Table 3.31 Pipelines transport consumptions (TJ) and GHG emissions (kt CO₂ eq.)

Pipeline transport	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Consumption (TJ)	7,359	11,556	15,367	15,940	19,098	9,662	11,646	14,549	16,664	15,971	12,645
Emissions from Pipelines (kt)											
CO ₂ (kt CO ₂ eq.)	410.78	646.63	864.51	900.21	1,106.63	556.84	674.45	851.19	981.68	945.57	747.54

Pipeline transport	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CH ₄ (kt CO ₂ eq.)	0.52	0.81	1.08	1.12	1.34	0.68	0.82	1.02	1.17	1.12	0.89
N ₂ O (kt CO ₂ eq.)	5.85	9.19	12.22	12.67	15.18	7.68	9.26	11.57	13.25	12.70	10.05
Total (kt CO ₂ eq.)	417.15	656.62	877.80	914.00	1,123.15	565.20	684.52	863.78	996.09	959.38	758.48

Source: ISPRA elaborations

3.5.5.4. Source-specific QA/QC and verification

Basic data to estimate emissions are reconstructed starting from information on fuel consumptions coming from different sources. Fuel consumption reported by the national operators for this activity is compared with the amount of natural gas internal consumption and losses reported in the energy balance. Starting from the length of pipelines, the average energy consumption by kilometer is calculated and used for verification of data collected by the operators. Energy consumption and emissions by kilometer calculated based on data supplied by the main national operator (SNAM, several years) are used to estimate the figures for the other operators when their annual data are not available.

3.5.5.5. Source-specific recalculations

No specific recalculations were made concerning this source.

3.5.5.6. Source-specific planned improvements

No further improvements are planned.

3.6 Other sectors

3.6.1 Sector overview

In this paragraph sectoral emissions are reported, which originate from energy use in the civil sector included in category 1.A.4. Commercial, institutional, residential, agriculture/forestry/fisheries, and emissions from military mobile activities which are also included in category 1.A.5. All greenhouse gases as well as CO, NO_x, NMVOC and SO₂ emissions are estimated.

In 2024, sectors 1.A.4 and 1.A.5 accounted for 21.1% of CO₂, 4.6% of CH₄, 12.2% of N₂O of total national emissions. In terms of CO₂ equivalent, other sectors share 22.3% of total national greenhouse gas emissions and 22.7% of total GHG emissions of the energy sector. The trend of greenhouse gas emissions is summarized in Table 3.32 A general increase in emissions is observed from 1990 to 2000, due to the increase in activity data (number and size of building with heating); a sharp increase of CO₂ emissions is observed in 2005 due to exceptionally cold weather conditions. CH₄ and N₂O emissions increase in the period is due to the growing use of woody biomass and biogas for heating. CH₄ and N₂O emissions of category 1.A.4.c are driven by the use of biomass in the agriculture sector, both wood and biogas, for heating of greenhouse and aquaculture plants; according to the national energy balance, wood biomass fuel started to be consumed in 2000 while biogas from agriculture residues sharply increased in the last years. Details on the total amount of crop residues generated and the share of the crop residue amounts used for different purposes (for energy referring to permanent crops residues) are reported in Annex 7, Figure A.7.1.

Table 3.32 Trend in greenhouse gas emissions from the other sectors, 1990-2024

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂ (kt)											
1.A.4a. Commercial/ Institutional	11,902	14,070	17,230	23,424	27,170	21,194	21,581	19,898	17,611	19,128	19,342
1.A.4b. Residential	55,788	52,756	53,824	60,441	55,267	47,982	44,069	48,073	41,775	36,519	36,812
1.A.4c. Agriculture/ Forestry/ Fisheries	8,352	8,754	8,115	8,459	7,345	6,935	7,065	7,465	7,246	6,964	6,323
1.A.5 Other (Not elsewhere specified)	1,071	1,496	837	1,233	652	459	625	314	511	364	605
CH₄ (t)											
1.A.4a. Commercial/ Institutional	604	879	1,993	3,068	3,976	4,473	4,225	4,173	3,911	3,812	3,790
1.A.4b. Residential	43,781	50,032	52,554	55,508	98,593	87,873	82,508	91,168	76,164	67,821	64,442
1.A.4c. Agriculture/ Forestry/ Fisheries	1,264	946	669	592	774	2,383	2,792	2,839	2,752	2,649	2,548
1.A.5 Other (Not elsewhere specified)	173	223	126	160	65	54	79	39	65	46	78
N₂O (t)											
1.A.4a. Commercial/ Institutional	311	413	614	911	1,164	1,143	1,146	1,117	1,062	1,101	1,106
1.A.4b. Residential	3,014	3,172	3,303	3,521	5,261	4,659	4,348	4,783	4,021	3,572	3,427
1.A.4c. Agriculture/ Forestry/ Fisheries	2,515	2,757	2,610	2,685	2,373	2,327	2,413	2,393	2,282	2,193	1,886
1.A.5 Other (Not elsewhere specified)	225	215	135	291	131	28	39	19	32	23	39

Source: ISPRA elaborations

Seven key categories have been identified for this sector in 2024, for level and trend assessment, using both the IPCC Approach 1 and Approach 2:

- Other sectors - CO₂ commercial, residential, agriculture gaseous fuels (L, T);
- Other sectors - CO₂ commercial, residential, agriculture liquid fuels (L, T);
- Other sectors - CO₂ commercial, residential, agriculture other fossil fuels (L1, T);
- Other sectors - CO₂ commercial, residential, agriculture solid fuels (T1);
- Other sectors - CH₄ commercial, residential, agriculture biomass (L, T);
- Other sectors - N₂O commercial, residential, agriculture biomass (L2, T2);
- Other sectors - N₂O commercial, residential, agriculture liquid fuels (L2).

All these categories, except N₂O commercial, residential, agriculture liquid fuels and CO₂ commercial, residential, agriculture solid fuels, are also key categories including the LULUCF estimates in the key category assessment.

3.6.2 Source category description

This category includes: 1.A.4.a. Commercial/ Institutional, 1.A.4.b. Residential, 1.A.4.c. Agriculture/ Forestry/ Fisheries and 1.A.5 Other (Military). The estimation procedure follows that of the basic combustion data sheet. Emissions are estimated from the energy consumption data and the emission factor illustrated in Table 3.12. Emissions from off-road sources are estimated and they are reported under the relevant sectors. The methodology of these estimates is discussed in the next paragraph 3.6.3 *Others*.

Commercial/ Institutional

Emissions from this sector arise from the energy used directly in the institutional, service and commercial buildings, mainly for heating. Additionally, this category includes all emissions due to the non-renewable part of waste used in electricity generation.

In the other fuel subcategory, the amount of fossil waste burnt in incinerators with energy recovery is reported. Emissions from these plants are allocated in the commercial/institutional category because of the final use of heat and electricity production which is mainly used for district heating of commercial buildings

or is auto consumed in the plant. In fact, until the early 2000s, electricity and heat produced by incinerators have been prevalently used to satisfy the energy demand from connected activities: heating of buildings, domestic hot water, and electricity for offices. This is still true for industrial and hospital incinerators, meanwhile municipal solid waste incinerators have increased the amount of energy provided to the grid from the early 2000s until now. Although there are no data or a robust estimate of the share of waste used to produce electricity, the available literature (ENEA-federAmbiente, 2012) provides that in 2010 the gross electricity production by urban waste incinerators was equal to 3,887 GWh (net 3,190 GWh) and the amount sent to the network was equal to only 121 GWh.

Biomass refers to: consumption of biomass waste, biogas recovered for energy purposes from landfill, sludge treatments, wood and steam wood; from 2002 to 2005 minor amounts of biodiesel fuel consumption are also included. In Table 7.12 of the waste sector chapter, the amount of waste and biogas fuel consumptions for 2024 are reported. In 2024, this sector has a share of 5.4% of total GHG national emissions excluding LULUCF.

Residential

Emissions from this sector arise from the energy used directly in residential buildings, mainly for heating. The sector includes emission from households and gardening machinery. Biomass refers to wood and steam wood fuel consumption. In 2024, this sector has a share of 10.9% of total GHG national emissions, excluding LULUCF.

Agriculture/ Forestry/ Fisheries

This subsector includes all emissions due to the direct fossil fuel use in agriculture, mainly to produce mechanical energy, the fuel used in fisheries and for the machinery used in the forestry sector.

Up to 1999, biomass included only biogas recovered for energy purposes from the storage of animal manure and agriculture residuals, while from 2000, as reported in the National Energy Balance, a huge amount of wood has been consumed affecting implied emission factors. In 2024, this sector has a share of 1.9% of total GHG national emissions, excluding LULUCF.

Others

Emissions from military aircraft and naval vessels are reported under 1A.5.b Mobile. The methods of estimation are discussed in paragraphs 3.5.1 and 3.5.4 for aviation and maritime respectively. In 2024, this sector has a share of 0.2% of total GHG national emissions, excluding LULUCF.

3.6.3 Methodological issues

For this sector, energy consumption is reported in the national energy balance separating commercial and public services, residential and agriculture-fisheries. Emissions from 1.A.4.b Residential and 1.A.4.c Agriculture/Forestry/Fishing are disaggregated into those arising from stationary combustion and those from off-road vehicles and other machinery. Emissions estimations from off-road sources are discussed later in the following paragraph. Emissions from fishing vessels are estimated from fuel consumption data (MASE, several years [a]). Emission factors are shown in Table 3.12.

As already reported, in the category 1.A.4.a. emissions from incinerators' energy recovery have been reported. While the possible reallocation of these emissions to other categories (i.e., 1A1) is being studied, this submission enabled us to improve the estimates thanks to comparison with data submitted under the ETS and through a meeting with trade associations. The comparison between the estimates and recent ETS data highlighted a good correspondence in total CO₂ emissions but a clear evolution in the ratio between biogenic and fossil CO₂. The inventory considers five types of waste: urban, "special", sludge, waste oils and hospital waste. Until now, "special" waste has been considered 100% fossil. However, the "special" waste that can be burned in municipal waste incinerators in Italy must be "similar" to municipal waste. Therefore, only certain categories (specific EER code, i.e., residues from waste treatment such as off-specification

compost) can be incinerated in those plants, and it is correct that they be considered 50% fossil and 50% biogenic like municipal waste. Using this assumption since 2020, the inventory estimates and the ETS data have a better match. In 2024, the ETS estimates show approximately 3.7 kt fossil CO₂ with 32 reporting facilities, while the inventory estimates show 3.9 kt fossil CO₂ with four additional facilities. Between 2010 and 2020, linear smoothing was applied, considering the evolution of waste composition and assuming a regular trend.

In the solid fuel subcategory, the following fuels are included: steam coal, coke oven coke and gas work gas. Since the eighties, there has been a sharp reduction in the use of these fuels due to air quality national legislation (in 1990 they accounted for about 1.1% of total energy consumption of 1.A.4 category) and a further decrease is observed between 1997 and 1998 in consequence of the banning of coal used in residential heating in urban areas.

CH₄ emission factors used are those reported in the 1996 CORINAIR handbook, vol.1, for coal, equal to 200 kg/TJ (EMEP/CORINAIR, 1996), and in the EMEP/CORINAIR Guidebook for coke oven coke, equal to 15 kg/TJ (EMEP/CORINAIR, 2007) which is the maximum value of emission factor for solid fuels without specification, and gas work gas, equal to 5 kg/TJ (IPCC, 2006). No more solid fuels are used for heating purposes from 2013.

For non-CO₂ GHG emissions, at the detailed level of fuel and technology, EMEP/EEA remains the best source of information. For liquid fuel, the average emission factors are driven by the mix of fuel consumptions used in heating boilers, prevalently LPG, but also gasoil and fuel oil which was used especially in the past. For these fuels the respective CH₄ emission factors have been used: LPG 1 kg/TJ, fuel oil 3 kg/TJ and gasoil 7 kg/TJ. Regarding natural gas, the country specific CH₄ emission factor is equal to 2.5 kg/TJ.

All these emission factors have been calculated based on the default and range emission factors published in the Guidebook EMEP/CORINAIR 2007, considering country specific circumstances by means of the type of boilers where these fuels are burnt. In the 2006 IPCC Guidelines emission factors for residential/commercial/institutional boilers are equal to those reported for manufacturing industrial boilers (e.g., natural gas default emission factors are equal to 1 for all the sources of combustion) while it is assumed that these emissions should be different according to the technology and size of the boilers.

In the following box the default emission factors reported in the Guidebook EMEP/CORINAIR 2007 are shown and compared with the national ones.

Liquid and gaseous fuel CH₄ default emission factors(kg/TJ) (EMEP/CORINAIR, 2007)

Fuel	EMEP/CORINAIR default EF	Range	IPCC default EF	National EF
LPG	-	1 - 2.5	1	1
Gasoil	0.6	0.1 - 8	3	7
Fuel oil	1.6	0.1 - 10	3	3
Natural gas	1.2	0.3 - 4	1	2.5

Average implied emission factors for other fuels, which refer to fossil waste, vary on an annual basis. For CO₂, the variation occurs from 1990, as a consequence of the mix of wastes used in incinerators, such as urban wastes, industrial, hospital, and oil wastes; for non-CO₂ gases, emission factors reported in EMEP/EEA (EMEP/EEA, 2016) applied at plant level have been considered, specifically for CH₄ and N₂O emission factors are equal to 5.3 kg/TJ and 8.9 kg/TJ, respectively. In 2024 CO₂ implied emission factor from other fossil fuels was equal to 66.2 kg/GJ. Regarding biomass fuel consumption, CO₂, CH₄ and N₂O emission factors used in the national inventory for the different types of fuels are reported in the following box. CH₄ and N₂O emission factors derive from the EMEP/CORINAIR Guidebook (EMEP/CORINAIR, 2007), and the implied emission factors fluctuate as a function of the mix of fuels (wood, biogas, waste and biodiesel).

Regarding CO₂ from waste, fossil fraction emissions are distinguished by biomass to include them in the national totals. CO₂ emission factors are built based on carbon content in each type of waste: municipal

waste, industrial waste, oil, sludge and hospital. Biogas emission factors are calculated starting from the stoichiometric carbon value equal to 750 kg C/t and annual energy efficiencies provided by Terna (Terna, several years) for the respective use in commercial and agriculture sectors. Wood and steam wood average CO₂ emission factors are derived considering the typical national wood used and it is applied for the whole time series. Implied emission factors result from the mix of biomass fuels used for each category (1A4a, 1A4b, 1A4c).

Biomass CO₂, CH₄ and N₂O emission factors for 2024 (kg/TJ)

Fuel	CO ₂	CH ₄	N ₂ O
Wood	94,600	320	14
Biogas landfills and sludge treatment	50,544	153	3
Biogas agriculture residues	54,118	153	3
Waste	153,843	5	9
Biodiesel	79,600	12	2

3.7 Other

In this paragraph, the methodology used to estimate emissions vehicles and mobile machinery used within the agriculture, forestry, industry (including construction and maintenance), residential, and sectors, such as airport ground support equipment, agricultural tractors, chain saws, forklifts, snowmobiles. Engine types typically used in this off-road equipment include compression-ignition (diesel) engines, spark-ignition (motor gasoline), 2-stroke engines, and motor gasoline 4-stroke engines. Estimates are calculated based on the Tier 3 method (equation 3.3.3 of the 2006 IPCC Guidelines (IPCC, 2006). This involves the estimation of emissions from different classes of off-road sources using the following equation for each class:

$$E_j = N_j * H_j * P_j * L_j * W_j * \left(1 + Y_j * \frac{a_j}{2}\right) * e_j$$

Where:

E_j = Emission of pollutant from class j (kg/y)

N_j = Population of class j

H_j = Annual usage of class j (hours/year)

P_j = Average power rating of class j (kW)

L_j = Load factor of class j

Y_j = Lifetime of class j (years)

W_j = Engine design factor of class j

a_j = Age factor of class j (y⁻¹)

e_j = Emission factor of class j (kg/kWh)

For gasoline engine sources, evaporative NMVOC emissions are also estimated as:

$$E_{vj} = N_j * H_j * e_{vj}$$

Where:

E_{vj} = Evaporative emission from class j (kg)

e_{vj} = Evaporative emission factor for class j (kg/h)

Population data are based on a survey of machinery sales (Frustaci, 1999). Machinery lifetime is estimated on the European averages, see EMEP/CORINAIR (EMEP/CORINAIR, 2007), the annual usage data were taken either from industry or published data (EEA, 2000). The emission factors used came mostly from EMEP/CORINAIR and from Samaras (EEA, 2000). The load factors were taken from Samaras (EEA, 2000). It was possible to calculate fuel consumptions for each class based on fuel consumption factors given in EMEP/CORINAIR (EMEP/CORINAIR, 2007).

Estimates were derived from fuel consumption for the years 1990-2024 for each of the main subcategories:

- Agricultural power units: gas oil consumption was taken from the energy balance (MASE, several years [a]). The consumption of gasoline was estimated using the energy balance (MASE, several years [a]) and subtracting the amount of fuel estimated for domestic house & garden based on the population approach for 1995.
- Industrial off-road: gas oil consumption was calculated from the Ministry of Environment data (MASE, several years [a]).
- Domestic house & garden: gasoline consumption was estimated from the population approach for 1995. Time series is reconstructed in relation to the fuel use in agriculture.

3.7.1 Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions in “Other sectors” is estimated to be about 3% in annual emissions; a higher uncertainty is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors. Estimates of fuel consumption used by other sectors in 2024 are reported in Table 3.33.

Table 3.33 Trend in fuel consumption for the other sector, 1990-2024 (TJ)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
TJ											
1.A.4a. Commercial/ Institutional	206,427	247,440	306,088	419,507	488,708	400,595	402,359	370,344	326,336	352,098	357,233
1.A.4b. Residential	1,002,597	1,004,192	1,037,175	1,172,398	1,222,588	1,078,886	997,341	1,085,887	929,580	813,283	810,058
1.A.4c. Agriculture/ Forestry/ Fisheries	114,638	121,163	111,486	116,933	103,172	107,101	111,540	118,784	115,695	111,100	102,719
1.A.5 Other	14,840	20,814	11,595	16,947	9,001	6,388	8,733	4,385	7,139	5,084	8,456

Source: ISPRA elaborations

In the following Table 3.34, total GHG emissions connected to the use of fossil fuels and waste derived fuels are reported for the whole time series. An increase in emissions is observed from 1990 to 2000, due to the increase in activity data (numbers and size of buildings with heating); a sharp increase can be observed in 2005 due to exceptionally cold weather conditions. CH₄ and N₂O emissions increased in the period due to the growing use of woody biomass for heating.

Table 3.34 Other sectors, GHG emission time series 1990-2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO ₂ (kt)	77,113	77,076	80,006	93,557	90,434	76,751	73,340	75,752	67,143	62,974	63,083
CH ₄ (t)	45,822	52,079	55,342	59,329	103,407	94,784	89,604	98,219	82,892	74,328	70,858
N ₂ O (t)	6,065	6,557	6,662	7,408	8,929	8,156	7,947	8,313	7,397	6,889	6,457
GHG (kt CO ₂ eq)	80,003	80,272	83,321	97,181	95,696	81,386	79,955	80,704	71,424	66,881	66,778

Source: ISPRA elaborations

In Table 3.35, other sectors emissions are summarized. From 1990 to 2024, an increase in the use of natural gas instead of fuel oil and gas oil in stationary combustion plants is observed; it results in a decrease of CO₂ emissions from combustion of liquid fuels and an increase of emissions from gaseous fuels. CH₄ and N₂O emissions increased due to the increasing use of woody biomass for heating.

Table 3.35 Other sectors, GHG emissions in 1990 and 2024

		1990	2024
CO ₂ other sectors liquid fuels	kt	39,346	11,361
CO ₂ other sectors solid fuels	kt	899	0
CO ₂ other sectors gaseous fuels	kt	36,338	47,800
CO ₂ other sectors other fuels	kt	530	3,921
CH ₄ other sectors	t	45,822	70,858
N ₂ O other sectors	t	6,065	6,457

Source: ISPRA elaborations

3.7.2 Source-specific QA/QC and verification

Basic data to estimate emissions are reported in the national energy balance and the national grid administrator (for the waste used to generate electricity). The energy data used reported in table 1.A.4 have different levels of accuracy:

- the overall sum of residential and institutional/service/commercial energy consumption is quite reliable, and their uncertainty is the same as the BEN; the quantities of fuels used for those economic sectors are reported by main suppliers and the data are well documented;
- the energy consumption for agriculture and fisheries is also routinely reported by energy statistics, the underlying data are quite reliable because the energy use for those sectors has special taxation regimes and they are accounted for separately;
- the energy use for military and off roads is instead partly reported and partly estimated with models, as described in paragraph 3.6.3 others.

3.7.3 Source-specific recalculations

Recalculations occur from 2010 because of an updated distribution of biogenic/fossil activity data from waste sector which, in turn, has impact over the heating sector. The comparison between the estimates and recent ETS data allow Italy to improve waste characterization for non-urban waste burnt in the municipal plants. Only certain categories (specific EER code, i.e., residues from waste treatment can be incinerated in those plants, and it is correct that such waste be considered the same as municipal waste, 50% fossil and 50% biogenic. Using this assumption since 2020, the inventory estimates and the ETS data have a better match. In 2024, the ETS estimates show approximately 3.7 kt fossil CO₂ with 32 reporting facilities, while the inventory estimates show 3.9 kt fossil CO₂ with four additional facilities. Between 2010 and 2020, linear smoothing was applied, considering the evolution of waste composition and assuming a regular trend. This led to a recalculation of -1.2% in 2010 to -2.8% in 2023.

3.7.4 Source-specific planned improvements

The implementation of updated emission factors from small combustion of biomass is planned.

3.8 International bunkers

The methodology used to estimate the quantity of fuels used by international bunkers in aviation and maritime navigation has been illustrated in the relevant transport paragraphs, 3.5.1 and 3.5.4. The methodology implements the IPCC guidelines according to the available statistical data.

3.9 Feedstock and non-energy use of fuels

3.9.1 Source category description

In Table 3.36 and 3.37, detailed data on petrochemical and other non-energy use for the year 2024 are given. The tables refer to all products produced starting from fossil fuels, solid, gas or liquid, and used for “non energy” purposes. A national methodology is used for the reporting and estimation of avoided emissions.

3.9.2 Methodological issues

The quantities of fuel stored in products in petrochemical plants are calculated based on information contained in a detailed yearly report, the petrochemical bulletin, by the Ministry of Environment (MASE, several years [b]).

The national petrochemical balance includes information on petrochemical input entering the process and used to produce petrochemical products, and petrochemical plants output, returns to the market, losses and internal consumption. Due to chemical reactions in the petrochemical transformation process, the output quantity of some fuels could be greater than the input quantity; in particular, it occurs for light products such as LPG, gasoline and refinery gas, and for fuel oil. Therefore, for these fuels it is possible to have negative values of the balance. For this matter, with the aim of allowing reporting on CRT tables, these fuels have been added to naphtha. The amount of fuel recovered from the petrochemical processes and returning to the market is considered as an output, because it is consumed for transportation or in the industrial sectors, and no carbon is stored.

In Table 3.36 and Table 3.37 the overall results and details by product are reported respectively. In Table 3.36 the breakdown of total petrochemical process is reported; the percentages referring to the “net” input are calculated based on the total input subtracting the quantity of fuels as gasoil, LPG, fuel oil and gasoline which return on the market because produced from the petrochemical processes. In Table 3.37 the input to the petrochemical processes in petrochemical plants and the relevant losses, internal consumption and return to the market are reported, at fuel level, allowing the calculation of the quantity stored in products, subtracting the output (returns to the market, losses and internal consumption) from the input (petrochemical input). Carbon stored, for all the fuels, is therefore calculated from the amounts of fuels stored (in tonnes) multiplied by the relevant emission factors (tC/t) reported in Table 3.37.

An assessment was made to estimate the quantities stored in products according to the IPCC 1996 Guidelines, Reference Manual, ch1, tables 1-5 (IPCC, 1997), multiplying the IPCC percentage values in tables 1-5 of the Guidelines by the amount of fuel reported as “petrochemical input” in Table 3.37. The resulting estimate of about 4,172 kt of products, for the year 2024, is significantly larger than the quantities reported, 816 Gg.

Non-energy products amount stored from refineries, and other manufacturers, are reported in the national energy balance (MASE, several years [a]) and the carbon stored is estimated with emission factors reported in Table 3.38. For lubricants the net carbon stored results from the difference between the amount of lubricant and the amount of recovered lubricant oils. The energy content has been calculated based on the IPCC default values. Minor differences in the overall energy content of these products occur if the calculation is based on national parameters instead of IPCC default values.

In the CRT tables the fuel input amount is reported so that the fractions of carbon stored could be derived. As these fractions are derived from actual measurements, they do not correspond to any default values and may vary over time.

Table 3.36 Other non-energy uses: breakdown of total petrochemical flow for 2024

	Petrochemical Input	Returns to refinery/market	Internal consumption / losses	Quantity stored in products
ALL ENERGY CARRIERS, kt	4121.15	1922.73	1382.16	816.26
% of total input		46.7%	33.5%	19.8%
% of net input			62.9%	37.1%

Source: ISPRA elaborations

Table 3.37 Petrochemical, detailed data from MASE, year 2024 (MASE, detailed petrochemical breakdown)

FUEL TYPE	Petroch. Input	Returns to refinery/market	Internal consumption / losses	Quantity stored in products	% on total input	% on net input	Emission factor (IPCC) t C / t
	kt	kt	kt	kt			
LPG	296	287	9	0			0.8136
Refinery gas	740	185	457	98			0.7772
Virgin naphtha	0	0	0	0			0.8900
Gasoline	1462	1283	2	177			0.8373
Kerosene	321	0	0	321			0.8600
Gas oil	166	166	0	0			0.8686
Fuel oil	159	2	93	64			0.8524
Petroleum coke	0	0	0	0			0.8666
Others (feedstock)	211	0	54	157			0.8709
Losses			0	0			0.8709
Natural gas	767	0	767	0			0.7763
total	4121	1923	1382	816	20%	37%	

Source: ISPRA elaborations

Table 3.38 Other non-energy uses, year 2024, MASE several years [a]

NON ENERGY FROM REFINERIES	Quantity stored in products	Energy content IPCC '96	Total energy content	Emission factor
	kt	TJ/Gg	PJ	kt C / kt
Bitumen + tar	2,731.0	40.19	109.76	0.8844
lubricants	651.5	40.19	26.18	0.8038
recovered lubricant oils	185.0	40.19	7.44	0.8038
paraffin	62.3	40.19	2.50	0.8368
others (benzene, others)	542.5	40.19	21.80	0.8368
Totals	4,172.3		167.7	

Source: ISPRA elaborations

At national level, this methodology seems the most accurate according to the available data.

3.9.3 Uncertainty and time-series consistency

In Annex 4, the time series for comparison between reference and sectoral approaches are reported showing percentage differences in a limited range.

3.9.4 Source-specific QA/QC and verification

Basic data to estimate emissions are directly provided to ISPRA by MASE. The energy data used to estimate emissions have a high level of accuracy because they summarize the results of a 100% legally binding monthly survey of all the operators concerned.

3.9.5 Source-specific recalculations

Recalculations occur because of the implementation of the updated national energy balance data.

3.10 Fugitive emissions from solid fuels, oil and natural gas

3.10.1 Source category description

Fugitive GHG emissions occur throughout the stages of fuel production, from extraction of fossil fuels to their final use. These emissions mainly result from leaks or other irregular releases of gases during the production and processing of solid fuels, oil and gas extraction, gas transmission and distribution and from oil refining. The solid fuels category primarily generates methane emissions, whereas oil and natural gas activities also produce carbon dioxide and nitrous oxide. In 2024, GHG emissions from this category accounted for 1.2% out of the total emissions and 1.5% of emissions within the energy sector. Trends in fugitive emissions are summarized in Table 3.46, while the results of key category analysis are shown in the following box.

Key-category identification in the fugitive sector with the IPCC Approach 1 and Approach 2*

Year	IPCC category		without LULUCF	with LULUCF
2024	CH ₄	Oil and natural gas - Natural gas	L, T	L, T
	CH ₄	Oil and natural gas – Flaring in refineries	L2, T2	-
	CO ₂	Oil and natural gas – Flaring in refineries	T2	-
	CO ₂	Oil and natural gas – Oil	T1	L1
	CO ₂	Oil and natural gas – Other – Flaring in refineries	T2	T2
	CO ₂	Oil and natural gas – Venting and flaring	T2	-
1990	CH ₄	Oil and natural gas - Natural gas	L	L
	CO ₂	Oil and natural gas – Oil	L1	L1
	CO ₂	Oil and natural gas - Venting and flaring	L2	L2
	CO ₂	Oil and natural gas – Flaring in refineries	L2	L2

* L = key category in level assessment under both Approach 1 and 2

T = key category in trend assessment under both Approach 1 and 2

L1, T1 = key category in level or trend assessment under Approach 1 only

L2, T2 = key category in level or trend assessment under Approach 2 only

Fugitive CH₄ and CO₂ emissions reported in 1.B.1 refer to coal mining for only two mines with very low production in the last ten years. One mine is underground and produces coal and the other one, a surface mine, produces lignite. The underground mine stopped the extraction activities between 1994 and 1999, whereas the surface mine stopped the activity in 2001. CH₄ emissions from solid fuel transformation refer to fugitive emission from coke production in the iron and steel industry, which is also decreasing in the last years. N₂O emissions from 1.B.1 are not occurring. Fugitive CO₂ emissions reported in 1.B.2 refer prevalently to fugitive emissions in refineries during petroleum production processes, e.g. fluid catalytic cracking and sulfur recovery plants and flaring, but also include emissions from the exploration, production, transport and distribution of oil and natural gas. CH₄ emissions reported in 1.B.2 refer mainly to the production of oil and natural gas and to the transmission in pipelines and distribution of natural gas, while N₂O emissions refer to flaring in the production of oil and natural gas and in refineries and emission from exploration. For the completeness of the related CRT tables, particularly 1.B.2, the N₂O emissions in refining and storage are reported under flaring in refineries as shown in the following Table 3.39.

Table 3.39 Completeness of N₂O fugitive emissions

1.B. 2.a. Oil		
iv. Refining/storage	N ₂ O	Included in 1.B.2.d flaring in refineries

3.10.2 Methodological issues

Coal mining and handling

CH₄ emissions from coal mining have been estimated based on activity data published on the national energy balance (MASE, several years [a]) and emission factors provided by the IPCC guidelines (IPCC, 2006). Mining and post mining emissions have been calculated. As for CH₄ emissions from mining and post mining

the average emission factors of the 2006 IPCC Guidelines (IPCC, 2006) have been selected, 18m³/t and 2.5m³/t, respectively. Concerning CO₂ emissions, the calculations have been carried out considering the species profile in coal mine gas by literature data (EMEP/CORINAIR, 2007). The coal gas composition considered is 80% of CH₄ and 6% of CO₂ by volume (Williams, 1993).

As for closed or abandoned mines, there are no methods for estimating emissions from surface mines at present (IPCC, 2006). The only one underground mine was closed from 1994 to 1999, it was reopened in 2000 and definitively closed since 2016. No data are available for a country-based approach to estimate fugitive emissions during the closure period. The emission estimations are carried out applying Tier 2 of the 2006 IPCC Guidelines for bituminous mines with 100% of gassy parameter. When the mine was open the emissions were due to mine activities and not occurring as abandoned mine.

Solid fuel transformation

CH₄ emissions from coke production have been estimated on the basis of activity data published in the national statistical yearbooks (ISTAT, several years [a]) and emission factors reported in the EMEP/CORINAIR Guidebook (EMEP/CORINAIR, 2007) taking in account the information provided by the relevant operators in the framework of the EPTR registry and the ETS, as addressed in paragraph 3.3.3 of this chapter.

Regarding the manufacture of other solid fuels, in Italy charcoal was produced in the traditional way until the sixties while now it is prevalently produced in modern furnaces (e.g. with the VMR system) where exhaust gases are collected and recycled to produce the energy for the furnace itself. This system ensures good management of the exhausts and the temperature, so that any waste of energy is prevented, and emissions are kept to a minimum. So CH₄ emissions from the production of charcoal are not accounted for also considering that the emission factor available in the Revised 1996 IPCC Guidelines, in Table 1-14 vol.3 (IPCC, 1997), refers to production processes in developing countries not applicable to our country anymore. Moreover, in the IPCC Good Practice Guidance as well as in the IPCC 2006 Guidelines no guidance is supplied for charcoal production.

Oil transport and storage and refining

Fugitive emissions from oil refining are estimated starting from the total crude oil losses as reported in the national energy balance. Emissions have been reported in the Refining/Storage category (1.B.2.a.iv); they occur prevalently from processes in refineries. Fugitive emissions from oil transport have been calculated according with the amount of transported oil (MIT, several years) and emission factors published on the IPCC guidelines (IPCC, 2006). Most of the crude oil is imported in Italy by shipment and delivered at the refineries by pipelines as offshore national production of crude oil. Table 3.40 provides the length of pipelines for oil and the amount of oil products transported since 1990.

Table 3.40 Length of pipelines for oil transport (km) and amount of transported oil products (Gg)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024*
Length of pipelines (km)	4,140	4,235	4,346	4,328	4,291	4,022	3,931	3,935	3,948	3,983	3,983
Amount transported (Gg)	94,600	102,274	116,803	133,024	128,854	110,369	99,295	106,610	109,303	108,641	110,596

Source: MIT

*provisional values

Emissions in refineries have been estimated on the basis of activity data published in the national energy balance (MSE, several years [a]) or supplied by oil and gas industry association (UNEM, several years) and operators especially in the framework of the European Emissions Trading Scheme (EU-ETS), and emission factors published on the IPCC Guidelines (IPCC, 2006).

Fugitive CO₂ emissions in refineries are mainly due to catalytic cracking production processes, sulfur recovery plants, flaring and emissions by other production processes including transport of crude oil and oil products. Emissions are based on the total crude oil losses reported in the national energy balance. These emissions are then distributed among the different processes according to the average emission factors agreed and verified by the association of industrial operators (UP) and yearly updated, from 2000, following data supplied by the plants in the framework of the European Emissions Trading Scheme. In the EU-ETS context, refineries report CO₂ emissions for flaring and for processes separately.

In Table 3.41, the time series of crude oil losses published in the BEN and crude oil processed in Italian refineries are shown.

Table 3.41 Refineries activities and losses

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Crude Oil losses (Mg)	1,004	937	757	576	584	664	550	474	475	464	465
Crude oil processing (Gg)	93,711	91,014	98,003	106,542	94,944	79,148	65,517	70,550	74,650	72,247	68,588

Source: MSE, UP

Oil and gas exploration

CO₂, CH₄, and N₂O fugitive emissions from oil and natural gas exploration have been calculated according to the number of exploration wells (MASE, several years [c]) and emission factors published on the IPCC Good practice Guidance (IPCC, 2000) as no emission factors for number of wells were available in 2006 IPCC guidelines. There are no EFs in the 2006 IPCC Guidelines, where the only activity data available is the number of wells. In the IPCC good practice guidance, the tier 1 methodology and default EFs are based on the number of wells, whereas in the 2006 IPCC Guidelines, they are based on the volume of oil production. If overall oil production were used as a proxy in estimating emissions from oil and gas exploration, there would be an overestimation. Moreover, current oil production is mainly onshore, while exploration is now being done offshore, and the methodology in the 2006 IPCC Guidelines does not reflect this situation. The relationship between exploration/drilling activity and production volume applies when the two activities occur within the same bed. In the case of onshore production and offshore exploration, the onshore production is not necessarily related to the exploration, and only offshore exploration is recorded. Emissions factors for drilling, testing and servicing have been used for productive wells, while only emissions factors for drilling have been used for non-productive wells.

Oil and gas production and processing, venting and flaring

CH₄ emissions from the production of oil and natural gas as well for natural gas processing have been calculated according with activity data published on national energy balance (MASE, several years [a]), data by oil and gas industry association (UNEM, several years), data supplied by operators, and emission factors published on the IPCC guidelines (IPCC, 2006).

CH₄ emission factors for the whole time series have been calculated considering this information also for oil & gas venting and flaring. For CO₂, the IPCC default emission factor has not been modified for each category, as no specific information is available. The emissions of N₂O from flaring for oil and gas production are estimated according to the activity production data and emission factors reported in the IPCC guidelines (IPCC, 2006).

As regards the decline of CH₄ IEF for natural gas production and processing, gas companies stated that there has been an increasing awareness of reducing GHG emissions and new emergency management systems have been implemented periodically to reduce emissions from venting. Moreover, with the updating of management systems, more accurate methods to estimate vented gas have been adopted by the main gas company at regular intervals. Since 2016 the national oil&gas operator has implemented new standards to drastically reduce the fugitive emissions from its oil production sites. Since 2016 EFs were

calculated according to the amount of gas produced and fugitive leakage, as communicated by the main gas operators. The leakage rate from oil operation sites has significantly changed from 2016 onwards.

In 2024, pursuant the obligations under the Regulation (EU) 2024/1787 on the reduction of methane emissions in the energy sector, all national oil&gas operators have submitted a report to the competent authority (MASE) "containing the quantification of source-level methane emissions estimated using at least generic emission factors for all sources." The CH₄ emissions provided in the reports are the national CH₄ emissions by upstream sector. The detailed emissions by source allowed the revision of the time series of emissions for oil and gas venting, assigned entirely to oil up to 2024 submissions, as well as the time series of emissions for oil and gas flaring.


The allocation of CH₄ emissions between oil and gas has been carried out according to the share of oil and gas production for fugitive emissions and flaring, while the emissions by venting are allocated according to the percentage of emission sources of the main national operators (11.4% by oil and 88.6% by gas), applied to the whole time series. The allocation of fugitive emissions by gas between production and processing has been carried out according to the share of fugitive emission factors in IPCC 2019. In Table 3.42, the national production of oil and gas is reported. Natural gas production should be further reduced in the next years, as shown in Figure 3.1.

Table 3.42 National production of oil and natural gas

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Oil (Gg)	4,668	5,236	4,586	6,111	5,106	5,470	5,424	4,914	4,518	4,313	2,759
Natural gas (Mm³)	17,296	20,383	16,766	11,962	8,265	6,877	4,417	3,499	3,405	3,040	2,882

Source: MASE

Figure 3.1 Trend of the national production of oil and gas. The dotted line is the 10-year moving average of oil production



Natural gas transmission and distribution

CH₄ and CO₂ emissions from the transmission in pipelines and distribution of natural gas estimates are based on activity data published by industry, the national authority, and information collected annually by the Italian gas operators. In other words, the most relevant information is the amount of natural gas transmitted & distributed, and the methane emissions reported by operators in their environmental reports or communicated to ISPRA. The emissions communicated by main operators are estimated separately for

transmission/distribution considering known lengths and materials of pipelines just to calibrate the model used to estimate fugitive emissions from minor operators.

Emission estimates take into account the information on: the amount of natural gas distributed (ENI, several years [a]; SNAM, several years); length of pipelines, distinct by low, medium and high pressure and by type, cast iron, grey cast iron, steel or polyethylene pipelines (AEEG, several years); natural gas losses reported in the national energy balance (MASE, several years [a]); methane emissions reported by operators in their environmental reports (ENI, several years [b]; EDISON, several years; SNAM, several years).

CO₂ emissions have been calculated considering CO₂ content in the leaked natural gas. The average natural gas chemical composition has been calculated from the composition of natural gas produced and imported. Main parameters of mixed natural gas, as calorific value, molecular weight, and density have been calculated as well. Data on chemical composition and calorific value are supplied by the main national gas providers for domestic natural gas and for each country of origin.

Table 3.43 shows average data for national pipelines natural gas.

Table 3.43 Average composition for pipelines natural gas and main parameters

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HCV (kcal/m³)	9,156	9,193	9,215	9,261	9,325	9,303	9,340	9,377	9,428	9,438	9,438
NCV (kcal/m³)	8,255	8,290	8,320	8,354	8,412	8,391	8,432	8,467	8,515	8,524	8,523
Molecular weight	17.03	17.19	17.37	17.45	17.46	17.34	17.33	17.48	17.56	17.56	17.53
Density (kg/Sm³)	0.72	0.73	0.74	0.74	0.74	0.73	0.73	0.74	0.74	0.74	0.74
CH₄ (molar %)	94.30	93.36	92.22	91.93	92.04	92.72	92.79	91.97	91.49	91.37	91.56
NMVOC (molar %)	3.45	4.09	4.84	5.35	5.74	5.26	5.63	6.21	6.74	6.89	6.79
CO₂ (molar %)	0.22	0.20	0.18	0.49	0.75	0.70	0.88	0.91	0.83	0.74	0.76
Other no carbon gas (molar %)	2.03	2.34	2.76	2.24	1.48	1.32	0.70	0.91	0.94	1.00	0.89
CH₄ (weight %)	88.83	87.14	85.16	84.53	84.54	85.81	85.88	84.39	83.59	83.49	83.77
NMVOC (weight %)	7.33	8.62	10.00	10.73	11.27	10.34	10.78	11.91	12.89	13.11	12.95
CO₂ (weight %)	0.57	0.51	0.47	1.23	1.89	1.78	2.25	2.29	2.09	1.86	1.92
Other no carbon gas (weight %)	3.27	3.74	4.37	3.51	2.30	2.08	1.09	1.41	1.43	1.54	1.36

The emissions are estimated starting from natural gas leakage provided by the main operators for natural gas transmission and distribution and information about network working pressure (low, medium and high) and material (cast iron, grey cast iron, steel or polyethylene) provided by ARERA: the National Authority for Energy, Networks and Environment. A spreadsheet model has been developed to estimate total emissions.

SNAM is the main operator for national gas transmission and import-export, while ITALGAS, 2iRetegas, and Unareti are the main operators for gas distribution. They publish annual environmental reports with the amount of natural gas conveyed and total leaks. Moreover, SNAM provides ISPRA the chemical composition and energy content of national gas imported and produced. In 2024, SNAM accounted for about 93% of national pipelines' length and about 99% of transported gas. ITALGAS, 2iRetegas, and Unareti accounted for about 55% of distribution network length and about 56% of distributed gas. According to ARERA, there are 183 operators distributing natural gas. Starting from 2000, ARERA issues a yearly report with information on pipelines and network length, operating pressure, and network type concerning pipelines material. Table 3.44 provides the trend of natural gas distribution network length for each pipeline material and the average CH₄ emission factor.

Table 3.44 Length of low and medium pressure distribution network (km) and network emission factors for CH₄

Material	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Steel and cast iron (km)	102,061	131,271	141,848	154,886	198,706	203,116	208,044	208,935	209,740	210,737	211,255
Grey cast iron (km)	24,164	23,229	21,314	15,080	4,658	2,398	2,061	2,060	2,060	1,965	1,833
Polyethylene (km)	775	7,300	12,550	31,530	49,663	56,943	59,854	61,325	61,441	61,881	62,446

Material	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total (km)	127,000	161,800	175,712	201,496	253,027	262,457	269,959	272,320	273,241	274,583	275,534
EF (kg/km)	1,958	1,417	1,228	1000	703	540	350	333	278	234	232

The estimation model calibrated on the main operators was used to estimate fugitive emissions from minor operators. Natural gas leaks by main operators and average composition of natural gas are used to estimate fugitive emissions. For minor operators, lower quality standard and higher specific emission factors for network material, venting, and other accidental losses were considered. So EFs for distribution are generated by combining measured data obtained directly from the main gas operators with calibrated estimates from smaller operators.

Emissions are estimated separately for the different network segments: transmission in primary pipelines and distribution in low, medium, and high-pressure network, losses in pumping stations and in reducing pressure stations (including venting and other accidental losses) with their relevant emission factors, considering also information regarding the length of the pipelines and their type. Emissions from low pressure distribution also include the distribution of gas at industrial plants and in residential and commercial sectors; data on gas distribution are only available at an aggregate level thus not allowing separate reporting. In addition, emissions from the use of natural gas in housing are estimated and included. Emissions calculated are compared and balanced with emissions reported by the main distribution operators. Finally, the emission estimates for the different segments are summed up and reported in the most appropriate category (transmission/distribution).

In 2024, pursuant the obligations under the beforementioned Regulation (EU) 2024/1787, all national operators for gas transmission and distribution have submitted a report to the competent authority (MASE) "containing the quantification of source-level methane emissions estimated using at least generic emission factors for all sources." The estimation model has been integrated with data provided by the reports to reproduce the methane emissions resulting from operators. The pipelines emission factors for transmission and distribution used for emission estimates are reported in the following box:

Leakage emission factors of natural gas for transmission and distribution in pipelines by material and pressure (2024)

Material	Pressure		
	High	Medium	Low
	m ³ /km		
Steel	54.2	254.8	161.3
Cast iron	-	306.0	255.0
Grey cast iron	-		5,503.0
Polyethylene	-		157.5

High pressure natural gas leakage factor concerns transmission network. Medium and low-pressure leakage factors concern distribution network. To take account of different sources of emissions (LNG regasification plants, compression stations, pipeline import/transmission and distribution, venting, and other accidental losses) the total leaks communicated by main operators and those estimated for minor operators are distributed resulting in implied emission factors for the other sources of emissions than transmission and distribution.

In the following box, implied emission factors for transmission and distribution sources are reported:


Implied emission factors (2024)

Transmission	LNG regasification	0.28 Mm ³ NG / Gm ³ NG imported
	Pipeline compression station	0.15 Mm ³ NG / Gm ³ NG transported
	Pipeline	54.2 m ³ /km (See previous table for high-pressure pipelines)
	Venting and other accidental losses	0.082 Mm ³ NG / Gm ³ NG transported
Distribution	Pipeline	See previous table for medium and low-pressure pipelines
	Venting and other accidental losses	0.225 Mm ³ NG / Gm ³ NG distributed

Furthermore, fugitive emissions due to the use of natural gas at home are considered and estimated with an emission factor equal to $36 \text{ kg CH}_4 / \text{TJ}$ natural gas distributed. The estimation model used to estimate fugitive emissions is updated every year considering data published by ARERA on pipelines and it is calibrated with annual leakage data published by main operators in their environmental reports.


The next graph shows the CH_4 emission factors time series since 1990 for natural gas transmission and distribution compared with the respective default EFs provided by IPCC guidelines (2006). As for the transmission, the national EFs are between the range of default values. The national distribution emission factors are approaching the default value that includes fugitive and venting sources but are still more than three times higher.

Figure 3.2 Trend of CH_4 emission factors for natural gas transmission and distribution compared with the respective default EFs (IPCC, 2006).



However, it should be considered that a significant share of natural gas does not go through the distribution network but is instead directly transported to industrial sites, including power plants. According to ARERA gas distribution is also fulfilled by network operating at pressure between 5 and 24 bar, which is part of the transmission network. This configuration explains why the amount of natural gas being distributed is less than 50% of the natural gas transmitted in the whole time series and shows how it is more useful to consider the matched EFs for transmission and distribution as illustrated in the next graph.

Figure 3.3 Trend of the matched CH₄ emission factors for transmission and distribution of natural gas



The different trends between the two units of measures are explained by variable composition of natural gas along the time series as CH₄ content and average density.

Geothermal energy

Geothermal fluids can, depending on the site, contain greenhouse gases such as CO₂ and CH₄ and other minor gases such as H₂S, H₂, NH₃ and N₂. According to CO₂ measurements carried out on the geothermal fields before the 1990 (EnelGreenPower, 1996), the CO₂ emissions by geothermal energy are considered not additive to the natural ground source, so while CO₂ emissions are not accounted the CH₄ emissions are evaluated.

In Italy, the geothermal energy extraction for electricity production occurred up to now only in Tuscany. CH₄ emissions have been estimated for the whole time series according to monitoring data of the environmental agency of Tuscany (ARPAT, several years). ARPAT issues a yearly report with CH₄ flux measures (kg/h) on a sample of power plants. There are no data on the operating hours for each plant, so the flux measures are summed up and multiplied by the average operating hours for all geothermal plants, the only available data, to obtain the total emitted amount for the sampled plants. To smooth the sampling distortion (i.e., in some years only plants with higher flux are sampled that would give an overestimation of emissions) for each year the average flux measures of the previous three years are considered for not sampled plants so obtaining an extended sample. The total emitted amount for all plants is calculated dividing the estimated amount for the extended sample plants by their power and multiplying such quantity by the total operating power.

3.10.3 Uncertainty and time-series consistency

The uncertainty in CO₂, CH₄, and N₂O emissions is quite differentiated for sources as shown in Table 3.45.

Table 3.45 Activity data (AD) and emission factor (EF) uncertainties for CO₂, CH₄, and N₂O emissions

	CO ₂		CH ₄		N ₂ O	
	AD	EF	AD	EF	AD	EF
Solid fuels	3%	10%	3%	50%	NA	NA
Oil and natural gas – Oil					3%	50%
Oil and natural gas – Natural gas					NA	NA
Oil and natural gas – Venting and flaring	50%	10%	50%	50%	50%	50%
Oil and natural gas – Flaring in refineries					50%	50%

Fugitive emissions, in CO₂ equivalent, account for 1.5% out of the emissions in the energy sector in 2024. CH₄, CO₂, and N₂O emissions show a reduction from 1990 to 2024 by 72.8%, 58.7%, and 34.6% respectively. The overall decrease of CO₂ fugitive emissions is mainly driven by the reduction in crude oil losses in refineries, also gas venting and flaring contributes to the decreasing trend. The trend of CH₄ and CO₂ fugitive emissions from solid fuels is related to the extraction of coal and lignite that in Italy has always been quite low, zero from 2015, and abandoned mines. The decrease of CH₄ fugitive emissions from oil and natural gas is due to the reduction of losses for gas transportation and distribution, because of the gradual replacement of old grey cast iron pipelines with steel and polyethylene pipelines for low and medium pressure network. The CH₄ fugitive emissions from geothermal energy extraction show a relevant increase since 1990 (+109.4%) due to the entry into operation of bigger plants with higher flux values. As regards N₂O emissions, the main source, flaring in refineries, shows a reduction since 1990 by 32.8%.

Fugitive emissions since 1990 are reported in Table 3.46.

Table 3.46 Fugitive emissions from solid fuels and oil & gas (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂											
Solid fuels	0.4	0.1	0.3	0.3	0.3	0.2	0.0	0.0	0.0	0.0	0.0
Oil and natural gas	4,047	4,002	3,262	2,557	2,377	2,574	2,112	1,816	1,799	1,740	1,673
CH₄											
Solid fuels	148	83	108	101	96	59	29	28	30	29	25
Oil and natural gas	9,816	9,098	8,428	7,563	6,763	5,478	3,436	3,274	2,712	2,272	2,300
Geothermal energy	213	228	312	374	416	536	575	481	473	456	447
N₂O											
Oil and natural gas	11	10	11	12	11	9	7	8	8	8	7
Total emissions	14,236	13,422	12,120	10,607	9,663	8,656	6,159	5,606	5,022	4,504	4,451

3.10.4 Source-specific QA/QC and verification

Different data sources are used for fugitive emissions estimates: official statistics by the Ministry of Environment (MASE, several years [a], [c]), Ministry of Transport (MIT, several years); national authorities (ARERA, several years; ISTAT, several years [a]), gas operators (ENI, several years [b]; EDISON, several years; SNAM, several years), and industrial association for oil and gas (UNEM, several years).

CH₄ flux data to estimate fugitive emissions from geothermal energy extraction are yearly registered by regional environmental agency of Tuscany for a sample of geothermal power plants (ARPAT, several years). Concerning CO₂ fugitive emissions from refineries activities, the estimates are balanced with the amount of crude oil losses reported in the national energy balance (MASE, several years [a]). CH₄ emissions from transmission and distribution of natural gas are verified considering emission factors reported in literature and detailed information supplied by the main operators (ENI, several years [b]; Riva, 1997).

3.10.5 Source-specific recalculations

Important recalculations occurred for oil&gas venting and flaring (1.B.2.c.), due to new information about source specific CH₄ emissions. The information are provided by national oil&gas operators, both for upstream and for transmission and distribution supply chains, in the frame of the mandatory commitments of Regulation (EU) 2024/1787. Pursuant the Regulation, all national operators had to submit to the competent authority (MASE) a report in 2025 "containing the quantification of source-level methane emissions estimated using at least generic emission factors for all sources."

According to the reports mentioned, the allocation of CH₄ emissions by venting (1.B.2.c.i) has been revised. Up to previous submission, the CH₄ emissions from this source have been entirely allocated to oil, while for venting by gas the notation key NA was used, because no quantitative information for venting by gas was available in IPCC guidelines (2006) to allocate emissions in 1.B.2.c.i.2. The allocation of CH₄ emissions has been carried out according to the percentage of emission sources of the main national operators (11.4% by oil and 88.6% by gas), applied to the whole time series.

As for CH₄ emissions by flaring (1.B.2.c.ii.) the allocation between oil and gas has been carried out according to the annual share of oil and gas production, while up to the previous submission about 75% of emissions were assigned to oil, according to the emission factors by energy for oil production and gas production and processing in IPCC Good Practice Guidance (2000).

Fugitive emissions by gas have been allocated between production and processing according to the share of fugitive emission factors in IPCC 2019, while up to the previous submission were allocated according to production and processing emission factors in IPCC 2006.

The recalculation affects the whole series of CH₄ emissions in the sectors:

- 1.B.2.b.ii. Production and gathering
- 1.B.2.b.iii. Processing
- 1.B.2.c.i. Venting > 1.B.2.c.i.1. Oil
- 1.B.2.c.i. Venting > 1.B.2.c.i.2. Gas
- 1.B.2.c.ii. Flaring > 1.B.2.c.ii.1. Oil
- 1.B.2.c.ii. Flaring > 1.B.2.c.ii.2. Gas

Minor recalculations occurred also in all sectors involved in the upstream supply chain for the revision of oil and gas production share of the main operator, which provides ISPRA with emissions data used to estimate the national emission factors. The revision has occurred for all years since 2020 for gas and since 2021 for oil.

The recalculation affects the emissions in the sectors:

- 1.B.2.a.ii. Production and upgrading – since 2021
- 1.B.2.b.ii. Production and gathering – since 2020
- 1.B.2.b.iii. Processing – since 2020
- 1.B.2.c.ii. Flaring > 1.B.2.c.ii.1. Oil - since 2021
- 1.B.2.c.ii. Flaring > 1.B.2.c.ii.2. Gas – since 2020

The recalculations affect the whole fugitive emissions sector since 1990, with average CH₄ emissions by oil lower by 3.07 kt and average CH₄ emissions by gas higher by 3.14 kt compared to the previous submission. Delving into greater details, the next table shows the percentage change for each source category in the upstream sectors with a 5-year pace up to 2020 and every year up to 2023.

Table 3.47 Percentage change of CH₄ emissions by upstream source compared to the previous submission

Souces	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
1.B.2.a.i. Exploration	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
1.B.2.a.ii. Production and upgrading	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	-32.1%	-24.7%	-24.2%
1.B.2.b.i. Exploration	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
1.B.2.b.ii. Production and gathering	32.5%	32.5%	32.5%	32.5%	32.5%	32.5%	31.0%	32.9%	33.1%	33.8%
1.B.2.b.iii. Processing	-72.6%	-72.6%	-72.6%	-72.6%	-72.6%	-72.6%	-72.9%	-72.5%	-72.5%	-72.3%
1.B.2.c.i. Venting > 1.B.2.c.i.1. Oil	-88.6%	-88.6%	-88.6%	-88.6%	-88.6%	-88.6%	-88.6%	-92.2%	-92.2%	-92.1%
1.B.2.c.i. Venting > 1.B.2.c.i.2. Gas	#	#	#	#	#	#	#	#	#	#
1.B.2.c.ii. Flaring > 1.B.2.c.ii.1. Oil	-57.4%	-57.4%	-57.4%	-49.9%	-49.9%	-49.9%	-21.6%	-43.9%	-44.5%	-42.8%
1.B.2.c.ii. Flaring > 1.B.2.c.ii.2. Gas	184.6%	184.6%	184.6%	160.6%	160.6%	160.6%	67.7%	56.6%	62.4%	56.7%
Total	1.9%	2.6%	2.3%	-1.0%	-2.1%	-3.5%	-19.4%	-36.8%	-29.5%	-31.1%

The reversal of change in total emissions by upstream sectors occurs in 2002 and is driven by the decreasing trend of gas production.

The recalculations affect total CO₂eq emissions in the fugitive sector by +0.28%±0.09% from 1990 to 2001 and -0.23%±0.21% from 2002 to 2023 compared to the previous submission.

3.10.6 Source-specific planned improvements

No further improvements are planned for the next submission.

4 INDUSTRIAL PROCESSES AND PRODUCT USE

4.1 Sector overview

By-products or fugitive emissions, which originate from industrial processes, are included in this sector. Where emissions are released simultaneously from the production process and from combustion, as in the cement industry, these are estimated separately and included in category 1.A.2. All greenhouse gases as well as CO, NO_x, NMVOC and SO₂ emissions are estimated. N₂O emissions are also estimated, which arise from chemical industry (2B), from "other product manufacture and use (2G) and this submission includes also N₂O emissions from electronic industry (2E). As for category 2G, the use of N₂O occurs in medical applications, such as anesthesia, and in the food industry, where N₂O is used as a propelling agent in aerosol cans, specifically those for whipped cream. Emissions from the use of N₂O in explosives are also included.

CO₂ emissions related to NMVOC from solvent use in paint application, degreasing and dry cleaning, chemical products manufacturing or processing and other use, are estimated and reported separately, as indirect emissions. These emissions are described under the section 'Solvent use and indirect CO₂ emissions'.

In 2024, industrial processes and product use accounted for 4.1% of CO₂ emissions, 0.07% of CH₄, 3.59% of N₂O, 100.0% of F gases. In terms of CO₂ equivalent, industrial processes and product use contribute 5.5% to the total national greenhouse gas emissions. The trends of greenhouse gas emissions from the industrial processes sector are summarized in Table 4.1. Emissions are reported in kt for CO₂, CH₄ and N₂O and in kt CO₂ equivalent for F-gases. An increase in HFCs emissions is observed from 1990 to 2024, while CO₂ emissions from chemical and metal and mineral industry reduced sharply in the period.

Table 4.1 Trend in GHG emissions from the industrial processes and product use sector, 1990-2024 (kt)

Gas/Subcategory	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂ (kt)	27,992.0	26,049.3	24,742.8	27,662.5	20,807.5	14,349.1	12,917.9	14,620.1	13,125.0	12,698.8	12,245.0
2A. Mineral Products	20,720.5	20,239.7	20,749.0	23,304.7	17,341.5	11,291.2	9,862.2	11,149.7	10,155.0	9,757.2	9,402.4
2B. Chemical Industry	2,524.2	1,584.0	1,356.4	1,635.0	1,361.9	1,219.7	1,358.5	1,427.6	1,093.9	1,149.4	1,145.2
2C. Metal Production	4,377.9	3,902.7	2,305.3	2,419.4	1,833.8	1,562.9	1,428.2	1,738.3	1,589.0	1,485.3	1,384.5
2D. Non-energy products from fuels and solvent use	369.5	322.9	332.0	303.4	270.3	275.4	269.1	304.5	287.2	306.9	312.9
CH₄ (kt)	5.2	5.4	2.9	3.0	2.4	1.7	1.4	1.6	1.4	1.3	1.1
2B. Chemical Industry	2.5	2.7	0.3	0.2	0.2	0.2	0.1	0.1	0.1	0.1	0.1
2C. Metal Production	2.7	2.7	2.6	2.7	2.2	1.5	1.2	1.5	1.3	1.2	1.0
N₂O (kt)	24.2	25.8	28.9	27.7	4.1	2.1	2.1	1.9	1.8	2.0	1.9
2B. Chemical Industry	21.5	23.4	25.5	25.0	2.1	0.5	0.4	0.2	0.1	0.2	0.1
2G. Other product manufacture and use	2.6	2.5	3.3	2.7	2.0	1.6	1.7	1.7	1.7	1.8	1.8
2E. Electronic Industry	-	-	-	-	-	-	-	-	-	0.03	0.01
HFCs (kt CO₂ eq.)	372.0	1,099.5	3,747.6	9,669.0	12,789.7	11,785.8	9,415.0	8,806.2	8,278.8	7,725.7	6,669.5
2B. Chemical Industry	372.0	471.5	24.6	22.8	0.8	1.1	0.8	0.9	0.9	0.7	0.6
2C. Metal Production	-	-	-	-	1.9	9.2	4.9	4.4	3.5	4.1	3.9

Gas/Subcategory	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
2E. Electronics Industry	-	6.1	8.7	7.2	10.7	9.5	7.8	7.8	8.7	7.0	5.4
2F. Product Uses as Substitutes of ODS	-	621.9	3,714.3	9,639.1	12,776.2	11,766.0	9,401.6	8,793.2	8,265.7	7,713.9	6,659.6
PFCs (kt CO₂ eq.)	2,615.0	1,350.9	1,363.3	1,759.4	1,376.6	1,539.8	515.6	413.1	462.0	297.2	279.7
2B. Chemical Industry	836.5	934.9	889.5	1,388.3	1,166.9	1,392.3	374.6	261.2	300.3	173.0	177.0
2C. Metal Production	1,778.5	315.0	207.6	190.7	89.2	-	-	-	-	-	-
2E. Electronics Industry	-	101.0	266.2	180.4	120.6	136.4	124.1	134.1	142.8	105.0	88.5
SF₆ (kt CO₂ eq.)	420.9	700.1	621.0	565.1	404.9	483.5	251.7	282.4	404.6	366.7	328.0
2B. Chemical Industry	117.5	117.5	-	-	-	-	-	-	-	-	-
2C. Metal Production	-	-	169.2	83.3	17.2	-	-	-	-	-	-
2E. Electronics Industry	-	14.9	61.9	57.2	30.6	47.3	36.9	40.8	54.5	48.0	81.1
2G. Other Products Manufacture and Use	303.4	567.7	389.9	424.7	357.2	436.2	214.8	241.6	350.1	318.7	246.9
NF₃ (kt CO₂ eq.)	-	76.6	13.3	33.4	20.2	28.4	16.2	15.2	19.5	19.7	25.7
2E. Electronics Industry	-	76.6	13.3	33.4	20.2	28.4	16.2	15.2	19.5	19.7	25.7
Unspecified mix of HFCs and PFCs (kt CO₂ eq.)	-	24.4	24.4	24.4	24.4	24.4	22.4	25.3	22.1	28.7	32.7

Thirteen key categories have been identified for this sector, for level and trend assessment, with and without LULUCF, using both Approach 1 and Approach 2. The results for 2024 are reported in the following Table 4.2.

Table 4.2 Key-category identification in the industrial processes sector with the IPCC Approach 1 and Approach 2 for 2024

KEY CATEGORIES			without LULUCF	with LULUCF
2A	CO ₂	Emissions from cement production	L, T	L, T
2A	CO ₂	Emissions from lime production	L1	L1
2A	CO ₂	Emissions from other process uses of carbonates	T	T1
2B	CO ₂	Emissions from ammonia production	T1	T1
2B	N ₂ O	Emissions from adipic acid production	T	T
2B	N ₂ O	Emissions from nitric acid production	T	T1
2B	HFCs	Emissions from fluorochemical productions	T2	-
2B	PFCs	Emissions from fluorochemical productions	T2	-
2C	CO ₂	Emissions from iron and steel production	T1	T1
2C	PFC	Emissions from Aluminum production	T	T
2F	HFCs	Emissions from substitutes for ODS- Refrigeration and air conditioning	L, T	L, T
2F	HFCs	Emissions from substitutes for ODS- Foam blowing agents	T2	T2
2F	HFCs	Emissions from substitutes for ODS- Fire protection	L2, T2	T2
Indirect CO ₂			L2	L2

CO₂ emissions from cement, lime and other carbonate uses are included in category 2A; N₂O emissions from adipic acid, nitric acid and CO₂ emissions from ammonia refer to 2B; CO₂ emissions from iron and steel production and PFC emissions from aluminum production are included in 2C; HFCs from substitutes for ODS are included in 2F and HFC and PFC emissions from fluorochemical production are included in 2B. Methane emissions from the sector are not a key source. CO₂ from Ammonia production, Iron and steel, Cement production, Lime production and Other processes uses of carbonates; N₂O from Adipic acid production and Nitric acid production; PFCs from Fluorochemical production are also key categories in the 1990 assessment.

For the industrial processes sector, emissions and background data collected in the framework of the European Emissions Trading Scheme, the National Pollutant Release and Transfer Register (Italian PRTR) have been used either directly in the estimation process or as verification of emission estimates, improving national emissions factors as well as activity data.

Emissions and activity data submitted under the ETS are mandatorily subject to verification procedures, as requested and specified by the European Directive 2003/87/EC (art. 15 and Annex V). In compliance with the above-mentioned legislation, independent certifications and verifications of activity data, emission data and emission factors are required. At national level, data verification must be carried out by verifiers accredited by the national ETS Committee. The verification of data submissions ensures reliability, credibility, and precision/accuracy of monitoring systems for data and any information relating to emissions by plant. The guidelines for reporting under ETS are aligned to the 2006 IPCC Guidelines.

The Italian legislation implementing EPER Decision included a legislative decree and a Ministry decree providing guidelines for reporting by the Italian EPER facilities. The Italian legislation implementing Regulation (EC) 166/2006 is a Decree of the President of the Republic (DPR n.157/2011). Annexed to the DPR n.157/2011 is a guideline for the reporting by the operators of the Italian PRTR facilities. Both guidelines for the reporting by the Italian EPER/PRTR facilities provide the list and description of the information to be reported, which includes: activity data (mandatory), total releases exceeding the reporting threshold values (mandatory); total off-site transfers of pollutant exceeding the reporting thresholds (mandatory); total off site transfers of waste exceeding the reporting thresholds (mandatory). Releases/transfers information to be reported by facility operators can be based (in compliance with national and EU legislation) on measurement, calculation, and estimation. In the case that operators report information based on measurements/calculation they are requested to communicate also what methodology has been applied to measure/calculate total releases/transfers.

As for activity data reporting under the national PRTR, no detailed requirements have been included in the national PRTR legislation and guidelines, although some general guidance is provided and followed by operators. The operator is expected to report the best available information concerning activity data for each reporting year, basically the amount produced, manufactured or treated in the reporting year shall be reported. It is appropriate to consider also that most facilities in the scope of EPER/PRTR are also in the scope of EU and national legislation concerning the permitting procedures, monitoring and control obligation for industrial facilities larger in size. The quality of information reported by the facilities under the national EPER/PRTR is assessed by the competent authorities, the same authorities are usually involved also in the permitting procedure of these facilities, thus cross checks of information concerning AD and emissions are expected by the national legal framework.

Since emissions data reported under the national PRTR can be measured, calculated or estimated, the European PRTR Guidance Document and the national guideline for reporting to the national PRTR include also references to the IPCC Guidelines methodologies.

The collection of facility reports under the national EPER/PRTR is a task that ISPRA has to carry out by law. The national inventory team is in the same unit of ISPRA where the national EPER/PRTR is managed, the inventory team has full access to the whole national dataset of the Italian EPER/PRTR without restrictions on the type of information (AD and emissions of each reporting facilities are available for the inventory

team). Italian EPER/PRTR data (emissions and transfers of pollutants, transfers of wastes) are publicly available on the internet at the European Industrial Emissions Portal <https://industry.eea.europa.eu/industrial-emissions> (in compliance with the legislation, activity data of the reporting units are not disclosed to the public). Data from the ETS and PRTR databases are incorporated into the national inventory whenever the sectoral coverage is complete; in fact, not always data entirely cover the relevant categories whereas national statistics provide the complete basic data needed for the Italian emission inventory. Nevertheless, these data are entirely used to develop country-specific emission factors and check activity data levels.

4.2 Mineral Products (2A)

4.2.1 Source category description

In this sector CO₂ emissions from the following processes are estimated and reported: cement production, glass production, lime production and other processes uses of carbonates.

Cement

Cement production (2A1) is the main source of CO₂ emissions in this sector. As already mentioned, it is a key source both at level and trend assessment with and without LULUCF, also considering uncertainty, and accounts for 2.27% of the total national emissions.

During the last 15 years, in Italy, changes in cement production sector have occurred, leading to a more stable structure. The oldest plants were closed, wet processes were abandoned in favor of dry processes so as to improve the implementation of more modern and efficient technologies. The effects of the global recession period have led at national level to facilities closedowns and many conversions from full cycle to grinding plants. Since 2011 Italy has become the second cement producer country in the EU 27 because of the reduction of clinker production in the last years.

The picture of the cement sector in 2024 has 16 companies (50 plants of which: 30 full cycle and 20 grinding plants, i.e. in 2024 the picture is basically the same as the one in 2022) operating in Italy: multinational companies and small and medium size enterprises (operating at national or only at local level) are present in the country. The operating plants are located as follows: 44.0% is in northern Italy, 14% is in the central regions of the country and 42% is in the southern regions and in the islands. The active sintering rotary kilns belong to the "dry" or of "semidry" types. In Italy different types of cement are produced; Federbeton/AITEC, the national cement association, has characterised the national production in 2024 as follows: 65% is CEM II (Portland composite cement); 10% is CEM I (ordinary Portland cement); 15% is CEM IV (pozzolanic cement), 9% is CEM III (blastfurnace cement) and the remaining 1% is CEM V. Clinker production has been decreasing since 2007, although from 2016 to 2019 the production values have kept very close to the amount manufactured in 2016, in 2020 clinker production shows -6.0% compared to 2019 (Federbeton/AITEC [a], several years) due to pandemic, while in 2024 clinker production was -0.5% compared to 2023. Clinker demand in cement production was about 67.5% in 2024 (consumption of clinker out of production of cement).

Lime

In 2024, CO₂ emissions from lime production have been identified as a key source at level assessment, with and without LULUCF, following the Approach 1.

CO₂ emissions occurring from processes where lime is produced account for 0.53% of the total national emissions. Lime production can also occur, beside lime industry, in different industrial sectors such as iron and steel making, pulp and paper production, soda ash production, sugar production; lime can also be used in a number of processes concerning wastewater treatment, agriculture and the neutralization of acidic emissions in the industrial flue gases. In particular, the other relevant lime productions accounted for in Italy are those occurring in the iron and steel making process and in the sugar production process (although lime production&use at sugar mills occurs without release of CO₂, since CO₂ released from decarbonization is used with lime in the purification of the sugar molasses).

Lime is basically produced by calcination of limestone (calcium carbonate) or dolomite (calcium/magnesium carbonate) at 900°C. The process leads to quicklime and CO₂ emissions according to the following reaction:



CO₂ is released because of the process reaction itself and also because of combustion to provide energy to the process. CaO and MgO are called quicklime. Quicklime, together with water, gives another product of the lime industry which is called calcium hydroxide Ca(OH)₂. CO₂ emissions estimation is related to lime production in mineral industry, and it also includes the production of lime to feed other industrial processes (e.g. iron and steel making facilities).

The number of lime production facilities has been relevantly changing over the years as shown in Table 4.3.

Table 4.3 Lime production facilities (number)

	1990	2003	2010	2014	2015	2016	2019	2020	2021	2022	2023	2024
Lime facilities (n.)	85	46	35	29	25	26	23	23	21	21	21	20

Figures from 2010 onwards are based on the number of facilities reporting under the EU-ETS. Moreover, 36% of the plants are in the southern regions and in the islands, 50% are in the northern regions and 14% in the central regions. The number of operating kilns has also decreased significantly through the years (about 171 in 1990, 75 in 2003 and 20 at present). During the nineties, lime industry invested in technology implementation to replace the old kilns with regenerative and high efficiency kilns, rotary kilns are no longer used.

Concerning lime industry fuel consumptions, based on TJ reported to the national ETS system, the main energy carriers in 2024 are solid biomass (66%) burnt in the kilns, natural gas (27%) mainly for thermal uses, oil and diesel oil account for less than 2%, coke and pet-coke account for 4.5%. In 2013 biomass burnt in the kilns was 5.3%, natural gas 47.1%, coke and petcoke accounted for 21.8% and anthracite was 7.4%, while in 2005 natural gas provided 78.4% of total energy input, pet-coke 13.8% and oil 4.9%.

Other processes uses of carbonates (limestone and dolomite use in brick and tiles; fine ceramics; paper industry and power plants)

This category is a key source at trend assessment, without LULUCF, following the Approach 1 and Approach 2 and with LULUCF following Approach 1.

CO₂ emissions are also related to the use of carbonates in different industrial processes, and they account for 0.18% of the total national emissions. Limestone or dolomite can be added in different steps of the production process to obtain the desired product features (i.e., colour, porosity). Sometimes carbonates in limestone and dolomite may have to be calcined ("dead burned") in order to be added to the manufacturing process. Limestone and dolomite are also used in paper production process and in the treatment of power plants flue gases. A steep decrease in the production processes and the relevant use of limestone can be observed between 2007 and 2009; use of limestone has been decreasing more gradually since 2009; the overall decrease being mainly driven by limestone and dolomite use in the brick

and tiles sector. Mineral (stone) wool production which occurred in Italy along the years 1993-2009 is included in emission estimates for the energy sector. Stone wool has not been produced in Italy since 2009. This category also includes the time series for CO₂ emissions from other uses of soda ash.

Glass production

Glass industry in Italy can be characterized regarding four glass product types: flat glass, container glass, borosilicate and lead/crystal glass. Flat glass is produced in facilities mainly located in the North; container glass is produced in facilities located all over the country; glass fibers and wool are produced in the North. About 70 companies carry out, currently, activities related to glass industry in Italy, out of these approximately 27 companies carry out glass production processes in about 55 production units. Concerning glass chemical composition, the national glass production consists of 95% soda-lime glass, 4% borosilicate glass and 1% lead/crystal glass. The main steps of the production process in the glass industry are the following:

- raw materials storage and batch formulation;
- melting of the formulated batch at temperature ranging from 1400°C to 1600°C, in different furnaces according to the type of glass product;
- forming into glass products at specific temperature ranges;
- annealing of glass products to prevent weak glass due to stress.

The formulated batch is generally melted in continuous furnaces, whose size and features are related to the types of glass production. In Italy glass industry production is basically fueled using natural gas and low sulphur content oil (in 2024, more than 98% of energy input came from natural gas and less than 1% from oil; while in 2005 natural gas share and oil share were 84% and 16% respectively). Emissions are basically released by the high temperature melting step and depend on the type of glass product, raw materials and furnaces involved in the production process. Main pollutants are: dust, NO_x, SO_x, CO₂; occasionally and depending on the specific production process, heavy metals, fluorides and chlorides gases could be released. CO₂ emissions are mainly related to the decarbonisation of carbonates used in the process (soda ash, limestone, dolomite) during the melting phase, accounting for 0.15% of the total national emissions. The use of scrap glass (recycled cullets) in the production processes has been increasing in Italy since 1998 thus contributing to the reduction of emissions from decarbonation and from the melting phase.

In Table 4.4, values of the rate of glass recycling from 1998 are reported (CoReVe, several years).

Table 4.4 Rate of glass recycling

	1998	2000	2005	2010	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Rate of glass recycling (%)	38.8	46.9	57.2	58.4	70.9	71.4	73.9	73.4	77.4	78.6	76.6	80.8	77.4	80.3

4.2.2 Methodological issues

The IPCC Guidelines are used to estimate emissions from this sector (IPCC, 2006). Activity data are supplied by industries and/or provided in the national statistical yearbooks (ISTAT, several years [a]). Emission factors are those provided by the IPCC Guidelines (IPCC, 1997; IPCC, 2000; IPCC, 2006), by other international Guidebooks (EMEP/EEA, 2023; USEPA, 1997), or they are derived by data communicated at plant level.

Cement

CO₂ emissions from cement production are estimated using the IPCC Tier 2 approach.

Activity data derived from different official sources throughout the time series. More in detail, from 1990 to 2008 official statistics provided by ISTAT were used (ISTAT, several years [a]). From 2009, data on clinker and cement production, based on a monthly plant-by-plant collection, were officially provided by the Ministry for Economic Development, at national and regional level (MSE, several years).

These production data were cross checked with EPRTTR and ETS data and with ISTAT statistics when available. From 2017, activity data referring to cement/clinker production have been taken from the data reported to the national ETS.

Emission factors are estimated based on information provided by the Italian Cement Association (Federbeton/AITEC, several years[a]) and by cement facilities in the framework of the European pollutant release and transfer register (E-PRTR) and the European emissions trading scheme (EU-ETS). In this latter context, cement production facilities reported fuel consumption, raw materials and emissions, split between combustion process and decarbonising process and complying with a clinker kiln input method which is based on IPCC methodology.


From 1990 to 2000 the resulting emission factor for cement production is equal to 532 kg CO₂/t clinker, based on the average CaO content in the clinker and considering the contribution of carbonates and additives. This value was assumed as representative of the Italian clinker manufacturing process by AITEC (AITEC, 2004) and officially reported to the Italian Ministry of Environment in order to set the national circumstances for the implementation of the European-Emissions Trading Scheme (EU-ETS) in our country. The value was calculated by the industrial association based on a tool provided by the World Business Council for Sustainable Development, which was available on the WBCSD (no longer available since the document has been updated in the last years) and data from some large Italian plants.

From 2001 to 2004, emission factors are the result of a linear interpolation of CO₂ IEF for 2000 and 2005.

From 2005, emission factors are based on the data reported within the frame of the EPER/EPRTTR and EU-ETS. Based on emissions and activity data (which includes the average CaO content in the clinker produced and the use of carbonates and additives), reported and verified under the EU-ETS, the resulting emission factor has been fluctuating as shown in Figure 4.1: it resulted in a minimum equal to 518 kg CO₂/t clinker in 2008, and a maximum equal to 531 kg CO₂/t clinker in 2007. From 2016 to 2023 the CO₂ IEF has been ranging between 520÷525 kg CO₂/t clinker, while 517 kg CO₂/t clinker is observed in 2024. The average emission factor varies year per year also as a consequence of the different operating circumstances (e.g. quality of the raw materials and operating conditions) at the Italian clinker facilities. The present submission includes the correction of the strong decrease in the CO₂ IEF values for the years 2022 and 2023 which resulted from a mistake in the interpretation of the activity data reported by a group of clinker facilities owned by the same company.

The information related to activity data and emissions for the clinker facilities reporting to the national ETS system have been processed. The range of uncertainty based on data communicated by the plants is about 5% in the period 2005-2009, about 4% in the period 2010-2015, about 4.6% in the period 2016-2021, 42% in 2022 and 44% in 2023. The same calculation performed separately on data referred to the two subgroups of cement facilities in 2022 results in uncertainty values comparable to those of previous years.

Figure 4.1 CO₂ IEF from decarbonation in clinker production, 1990-2024



In addition to this, Federbeton/AITEC has been reporting the overall consumption of natural raw materials by the national cement industry and also the replacement of natural raw material (either in the raw meal for the clinker manufacture or in the ground mix for the different cement types) with alternative materials in the Italian cement facilities, so:

- Specific consumption of natural raw materials has been varying for the last years;
- The rate of replacement of natural raw materials has been varying for the last years.

In 2024, approximately 8.0% of natural raw material was replaced by about 2.08 Mt non raw materials (0.52 Mt non hazardous wastes and 1.56 Mt secondary raw material) (Federbeton/AITEC[b], several years). Most of the alternative materials consist of already decarbonized materials. The use of decarbonized material in amounts varying year by year in clinker kilns contributes to explaining the fluctuations in the trend of the CO₂ IEF from decarbonization.

In Table 4.5, the amounts of natural raw material consumption for the years 2009-2024 have been reported together with the amounts of secondary raw materials and the replacement rates.

Table 4.5 Replacement of natural raw materials by secondary raw materials at the Italian cement facilities

RAW MATERIALS DEMAND	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Natural raw materials (Mt)	43.6	43.4	40.4	34.2	29.8	25.1	23.5	25.4	27.5	25.4	23.7	21.6	24.4	23.5	23.4	25.9
Secondary raw materials (Mt)	1.9	1.8	1.9	2.3	1.9	1.7	1.5	1.6	1.8	1.5	1.6	1.5	1.7	1.8	1.9	2.1
Natural raw material/clinker (t/t)	1.7	1.7	1.7	1.8	1.8	1.6	1.5	1.7	1.8	1.7	1.6	1.6	1.6	1.5	1.6	1.9
Replacement of natural raw material (%)	4.0	4.3	4.3	6.8	6.7	6.3	6.5	6.4	6.7	6.0	6.7	7.0	7.0	7.8	8.3	8.0

(source: Federbeton/AITEC, several years[b])

Regarding industry data verification, the available activity data for the cement/clinker production in Italy are consistent to the information supplied by the Italian cement industry association, to data reported under the national PRTR and also to data collected in the frame of the national ETS. Emission values reported under the different obligations are in accordance with all the facilities. The number of clinker

facilities reporting under EPRTTR and ETS are shown in Table 4.6 together with the corresponding number of operating facilities according to the cement association (AITEC).


Table 4.6 Clinker facilities reporting under EPRTTR and ETS

Clinker facilities	2005	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Reporting to the national PRTR (n)	52	53	50	50	51	47	37	34	32	30	30	29	27	28	29	29	29
Reporting under the national ETS (n)	52	52	52	51	51	48	39	36	32	32	31	31	29	28	29	29	29
Number of clinker manufacturers in Italy (AITEC)	59	58	58	57	56	50	40	37	33	33	32	32	30	28	29	29	30
PRTR/AITEC (%)	88	91	86	88	91	94	93	92	97	94	94	91	90	100	100	100	97
ETS/AITEC (%)	88	90	90	89	91	96	98	97	97	97	97	97	97	100	100	100	97

In the framework of the EU-ETS register, 29 cement facilities reported referred to 2024 and 29 reported releases to air under the EPRTTR register. These figures, out of 30 operating facilities according to Federbeton/AITEC, represent the whole national clinker production. Generally, when the number of ETS clinker facilities is lower than Federbeton/AITEC figure, information concerning localization and production capacity is available for the facilities out of the scope of EU-ETS. Federbeton/AITEC reports every year the number of operating cement/clinker facilities in Italy and the cement production of the whole sector. Under the EU-ETS, cement plants communicate emissions and activity data split between energy and processes phases and specifying the amount of carbonates and additives which are constituents of the raw meal complying with a “clinker kiln input” approach; both activity data and emissions are independently verified and certified as requested by the EU-ETS directive. The implied CO₂ emission factor is applied to the total national clinker production.

Basically, CO₂ emissions time series is related to clinker production time series. Specifically, main decreases in the national production of cement industry, which well reflects the trend of the national economy, can be observed for the years 1992-1994; an increase in production can be observed from 1996 to 2001 and from 2002 to 2007, while a significant decrease in the production is observed for 2007- 2009 and 2011-2017 due to the effects of the economic crisis and the significant reduction in the number of authorizations to build between 2005 and 2015 (-84%). A weak increase in the number of new permits to build was recorded also in 2019, whilst a decrease is observed in 2020. Practically, the same variations can be observed in CO₂ emissions trend. Clinker production and CO₂ emissions time series are shown in Figure 4.2.

Figure 4.2 Trend of clinker production and CO₂ emissions 1990-2024 (kt)



Lime

CO₂ emissions from lime have been estimated based on production activity data supplied by ISTAT up to 2008 (ISTAT, several years [a]) and by operators under the ETS reporting obligations from 2009.

ISTAT data included only marketed lime, so non-marketed lime productions were added to these data, where non-marketed lime is equal to the manufacture of lime at iron & steel sites and sugar mills. The information referring to the annual amount of non-marketed lime is supplied by the operators of such facilities under the national pollutant release and transfer register (PRTR).

ETS data has been used since 2009. All the national lime production plants are part of the EU-ETS.

CO₂ emissions from lime production and use in other industrial processes (e.g. iron and steel production, sugar mills) have been also considered. Emission factors have been based on detailed information supplied by lime facilities in the framework of the European emission trading scheme and by the national lime industrial association (CAGEMA, 2005). Specifically, the value of the emission factor from 1990-2000 has been officially supplied to the Italian Ministry of Environment by the industrial association (CAGEMA, 2005), in order to set the national circumstances for the implementation of the European-Emissions Trading Scheme (EU-ETS).

From 2001 to 2004, emission factors are the result of a linear interpolation of CO₂ IEF for 2000 and 2005. From 2005, in the frame of the ETS reporting obligation activity data (including fuels and raw materials such as carbonates and additives, in compliance with a "lime kiln input" approach) were available at facility level together with CO₂ emissions (combustion and process emissions). Both activity data and CO₂ emissions are certified and independently verified as requested by the EU-ETS legislation.

The CO₂ implied emission factor varies year by year because of the natural raw material fed to the kilns at facility level including different CaO and MgO contents. In Table 4.7, CaO and MgO contents for the years 2009-2024 are reported; these figures refer only to the production plants, excluding self-production of lime in other manufacturing processes.

Table 4.7 CaO and MgO oxides content for lime production (%)

%	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
CaO content	96.9	96.7	96.2	93.6	94.4	89.8	90.7	97.1	97.7	95.5	88.8	84.1	82.3	83.2	79.8	80.3
MgO content	3.1	3.3	3.8	6.4	5.6	10.2	9.3	2.9	2.3	4.5	11.2	15.9	17.7	16.8	20.2	19.7

Other processes uses of carbonates (Limestone and dolomite)

CO₂ emissions from other process uses of carbonates are related to the use of limestone and dolomite in bricks, tiles and ceramic production, paper production and in the treatment of flue gases from power plants. In Italy only limestone is used for the activities included in this category, brick and tiles, fine ceramic, and pulp and paper production and power plant flue gases treatment, while no dolomite use is documented. CO₂ emissions from other uses of soda ash are included under this category, based on the activity data and emissions information reported by facilities in the scope of the national ETS. In 2024, about 90.1% of the total carbonates accounted for in this category has been used in the production processes of bricks and tiles, about 3.9% for the fine ceramic material, 4.4% in the treatment of flue gases in the power plants, about 0.3% in the paper industry and 1.3% is the share of the other uses of soda ash.

CO₂ emissions have been estimated based on the IPCC default value for limestone equal to 0.44 t/t; the overall CO₂ emission time series is mainly driven by the CO₂ emissions from the use of limestone in the bricks and tiles sector. In the CRTs, the total amount of carbonates accounted for in this category is reported.

Detailed production, consumption, activity data and emission factors have been supplied in the framework of the European emissions trading scheme and relevant data are annually provided by the Italian bricks

and tiles industrial association and by the Italian ceramic industrial associations (ANDIL, 2000; ANDIL, several years; ASSOPIASTRELLE, several years; ASSOPIASTRELLE, 2004; Confindustria Ceramica, several years). Even though the EU ETS has not been in operation for the whole time-series relevant information concerning the use of carbonates was made available in the communications to the Italian Ministry of Environment to get the overview of the sector for the national ETS to be implemented.

Mineral (stone) wool production has been also considered, and CO₂ emissions have been estimated but they are included in the Energy sector because it is not possible to identify the share of emissions related to the process and to the energy aspects. Mineral wool production in Italy took place in Sardinia at one facility from 1993 to 2009, then the production was considered not profitable any longer and the facility was closed down.

Glass

CO₂ emissions from glass production have been estimated taking into account, from 1990 to 2004, production data published by ISTAT on the National Statistical Yearbooks (ISTAT, several years [a]); from 2005 ISTAT statistics have not been available anymore and consistent figures published by the national glass industry association have been used (Assovetro, several years). Glass wool production is included for the whole time series.

In Table 4.8, the complete time series of the national inventory for glass production is reported for the different types of glass.

Table 4.8 Glass production time series (Mg)

Type	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Flat glass	816,406	879,750	1,009,367	1,183,310	921,619	838,019	965,859	1,190,251	1,155,728	1,066,862	982,188
Container glass	2,609,826	3,094,893	3,417,851	3,716,509	3,656,425	3,936,885	4,429,110	4,702,984	4,773,762	4,521,808	4,367,279
Glass wool	105,029	119,120	139,421	129,958	115,332	86,929	88,319	105,574	104,898	82,915	74,140
Other glass	247,684	165,213	362,970	298,000	369,730	381,900	392,316	454,572	457,532	405,980	412,903

Since 2000, information provided by operators under the national ETS has been used to develop emissions estimation and relevant CO₂ emission factors. CO₂ emissions from decarbonation, considering the national circumstances concerning the use of cullets (recycled scrap glass which does not cause CO₂ emissions) in the production processes, have been estimated. In 2024, CO₂ emission factor has been estimated equal to 92 t CO₂/t, based on the information supplied under the European emissions trading scheme by 48 out of 53 facilities.

4.2.3 Uncertainty and time-series consistency

The uncertainty in CO₂ emissions from cement, lime, other process uses of carbonates and glass production is estimated to be equal to 10.4% from each activity, resulting from 3% and 10% for activity data and emission factor, respectively. Official statistics of activity data for these categories are quite reliable when compared to the activity data reported by facilities under different data collections, thus leading to the considered uncertainty level for the activity data. The uncertainty level for emission factors is equal to the maximum level reported in the IPCC Good Practice Guidance (IPCC, 2000) for the cement production; this is a conservative estimation because the range of values of the emission factors of the Italian cement plants would lead to a lower uncertainty level. In Tables 4.9 and 4.10, the production of mineral products and CO₂ emission trend are reported.

Table 4.9 Production of mineral products, 1990 – 2024 (kt)

Activity data	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt										
Clinker production (decarbonizing)	29,786	28,778	29,816	33,122	25,239	15,527	13,389	15,165	13,600	13,150	13,084
Glass (decarbonising)	3,779	4,259	4,930	5,328	5,063	5,244	5,876	6,453	6,487	6,078	5,837
Lime (decarbonising)	2,583	2,873	2,760	3,447	2,789	2,348	2,178	2,628	2,679	2,428	2,250
Other processes use of carbonates (Limestone and dolomite use)	5,781	5,292	5,143	6,087	3,580	1,886	1,230	1,385	1,465	1,214	1,195

Table 4.10 CO₂ emissions from mineral products, 1990 – 2024 (kt)

CO ₂ emissions	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt										
Clinker production (decarbonizing)	15,846	15,310	15,862	17,403	13,276	8,196	7,059	7,919	7,095	6,860	6,762
Glass (decarbonizing)	453	511	611	768	559	534	569	614	592	584	534
Lime (decarbonizing)	1,877	2,090	2,013	2,456	1,932	1,731	1,693	2,003	1,824	1,780	1,580
Other processes use of carbonates (Limestone and dolomite use)	2,544	2,328	2,263	2,678	1,575	830	541	609	644	534	526

Emission trends are generally related to the production level, which has been decreasing for the last years mainly because of the economic recession. In particular, the trend of carbonates used in power plants for flue gases treatment is driven by the use of coal in the operating power plants.

4.2.4 Source-specific QA/QC and verification

CO₂ emissions have been checked with the relevant industrial associations. Both activity data and average emission factors are also compared every year with data reported in the national EPER/E-PRTR registry and in the European emissions trading scheme (EU-ETS). Under the EU-ETS, operators are requested to report activity data and CO₂ emissions as information verified and certified by auditors who check for consistency to the reporting criteria.

Activity data and emissions reported under EU-ETS and EPER/EPTR are compared to the information provided by the industrial associations. Comparisons have been carried out for cement, lime, limestone and dolomite, and glass sectors. The general outcome of this verification step shows consistency among the information collected under different legislative frameworks and the information provided by the relevant industrial associations. Information reported under the EU-ETS has allowed for estimating CO₂ emissions from other uses of soda ash, the whole time series is included in the present submission and allocated under the "Other processes use of carbonates" category.

4.2.5 Source-specific recalculations

Recalculations occurred for clinker production for the years 2021-2023 for the update of the activity data (0.0002%; -0.02%; -1.70% respectively) lime production" in 2021-2023 for the update of the activity data (+0.20%; +0.26% and 0.28% respectively); for "Glass production" in 2023 (0.84%) for the update of CO₂ EF for this inventory submission.

4.2.6 Source-specific planned improvements

Further investigations concerning the replacement of natural raw material in lime production are planned.


4.3 Chemical industry (2B)

4.3.1 Source category description

CO₂, CH₄, N₂O, HFCs and PFCs emissions from chemical productions are estimated and included in this sector.

Adipic acid

Adipic acid production is a multistep process which starts with the oxidation of cyclohexanol using nitric acid and Cu catalysts according to the following reaction:



Adipic acid is then used to produce nylon or is fed to other production processes. Together with adipic acid, N₂O is produced and CO₂ is one of the by-products (Radici Chimica, 1993).

Emissions data from adipic acid production are provided and referenced by one plant, which is the only producer in Italy (Radici Chimica, several years). Specifically, for N₂O, in 2022, adipic acid production is a key source at trend assessment, both with Approach 1 and Approach 2, with and without LULUCF. These emissions accounted for 21% of total N₂O emissions in 2005, 2.4% in 2010, 0.6% in 2015, 0.4% in 2020, 0.09% in 2022 and 0.04% in 2024; the notable decrease in share is since the technology to reduce N₂O emissions has become fully operational at the existing producing facility since 2007.

N₂O emissions have relevantly decreased thanks to the implementation of a catalytic abatement system (pilot scale plant). The use of thermally stable catalysts in the pilot plant has allowed the treatment of highly N₂O concentrated flue gas from the adipic acid production plant, reducing the volume of treated gas and the size of the pilot plant itself. The abatement system is generally run together with the adipic acid production process. In 2004 this system was tested for one month resulting in complete decomposition of N₂O; in 2005 the catalytic process was started only at the end of the year because of technical changes in the system; in 2006 the abatement system had been operating continuously for 9 months (3 months were needed for maintenance and technical changes) leading to the decomposition of 92% (efficiency of the abatement system while in operation) of N₂O emissions. Since 2007 the operating time has been about 11 months (about one month was needed for maintenance operations) and the N₂O emissions abatement system while in operation has reached an efficiency exceeding 98% (Radici Chimica, several years). In 2011 further emissions reduction was achieved thanks to technical improvements implemented in the production process during 2010:

- the number of scheduled outages of the adipic acid production process is reduced (from about 1/month to 2/year);
- the abatement system is set to reach the operating level more quickly than in previous years.

These two achievements allow reducing the significance of N₂O peak emissions related to the start&stop phases. Moreover, an emission monitoring and recording system was implemented in compliance with Decision 2007/589/EC (Radici Chimica, 2013).

Also, CO₂ emissions are estimated from this source.

Ammonia production

In 2024 CO₂ emissions from ammonia production are a key source, at trend assessment with the Approach 1 with and without LULUCF.

In Italy only one facility has been producing ammonia since 2009 because of the resizing of the production at national level after the crisis of the largest fertilizer producer, Enichem Agricoltura, and as a consequence

of the international financial crisis in the last years. Two facilities had been producing ammonia in Italy up to 2008, in 2009 one plant stopped the production and was decommissioned in the following years. Ammonia is obtained after processing in ammonia converters a "synthesis gas" which contains hydrogen and nitrogen. CO₂ is also contained in the synthesis gas, but it is removed in the decarbonising step within the ammonia production process. Part of CO₂ is recovered as a by-product and part is released to the atmosphere. Recovered CO₂ can either be used as input for different production processes (e.g. urea or calcium nitrate lines; liquefaction of CO₂ plant) on site or can be sold to technical gas manufacturers. The amount of recovered CO₂ from ammonia production which is fed to urea production processes is also reported (YARA, several years). Since 2021 ammonia manufacturing process has been experiencing planned shutdowns at plant level due to the rising costs of energy and natural gas as a consequence of Russia-Ukraine war.

Nitric acid

In the early nineties, seven facilities manufactured nitric acid, but since 2003 production has been carried on only in three plants. In 2008 another plant stopped the production of nitric acid, so since 2009 nitric acid production has been carried out in two plants only. Nitric acid is produced from ammonia by catalytic oxidation (with air) of NH₃ to NO₂ and subsequent reaction with water. Currently the reactions involved take place in low and medium pressure processes.

In 2024, N₂O emissions from nitric acid production are a key source for trend assessment with Approach 1 with LULUCF, and for trend with Approach 1 and Approach 2 without LULUCF, as they show a relevant decrease in emissions from 1990 due to a reduction in production. Moreover, as far as YARA facility is concerned, the decrease in N₂O emissions is also related to the implementation of catalytic N₂O decomposition in the oxidation reactors a YARA De-N₂O patented technology, based on the use of CeO₂ catalyst (YARA, several years), while the improvements in the monitoring system of N₂O emissions at the other facility has been affecting N₂O emissions estimation time series for the very last years.

Carbon black

Three facilities have been carrying out this production which consists basically on cracking of feedstock oil (a mixture of PAH) at 1200 – 1900 °C. Together with black carbon, tail gas is a byproduct of the process. Tail gas is a mixture of CO, H₂, H₂O, NO_x, SO_x and H₂S; it is generally burnt to reduce the emissions to air and to recover energy to be used in the production process.

CO₂ emissions from carbon black production have been estimated based on information supplied directly by the Italian production plants also in the framework of the EU ETS for the last years.

Ethylene, Ethylene oxide, Propylene, Styrene

Ethylene, ethylene oxide, propylene and styrene productions belong to the organic chemical processes. Ethylene is produced in petrochemical industry by steam cracking to manufacture ethylene oxide, styrene monomer and polyethylenes. Ethylene oxide is obtained via oxidation of ethylene, and it is largely used as precursor of ethylene glycol and in the manufacture of surfactants and detergents. Propylene is obtained by cracking of oil, and it is used to manufacture polypropylene but also acetone and phenol. Styrene, also known as vinyl benzene, is produced on industrial scale by catalytic dehydrogenation of ethyl benzene. Styrene is used in the rubber and plastic industry to manufacture through polymerisation processes such as polystyrene, ABS, SBR rubber, SBR latex.

Except for ethylene oxide production, which stopped in 2002, the other productions of the above-mentioned chemicals still occur in Italy.


As far as ethylene, ethylene oxide and propylene are concerned, Syndial Spa (former Enichem) and Polimeri Europa (Syndial, several years; Polimeri Europa, several years) were the main producers in Italy up to 2006. Since 2007 Polimeri Europa (the parent company name changed into Versalis in 2012) has become the main producer for those products in Italy, while it has been the main producer of styrene since 2002.

Titanium dioxide

Titanium dioxide (TiO₂) is the most used white pigment especially for paint and plastic industries. As described also in the IPCC Guidelines, two main production routes are available:

- the chloride route, which has both "combustion" and "process" emissions;
- the sulphate process, whose emissions are only related to the combustion of fuels.

In Italy there is only one facility where this production occurs, and titanium dioxide is produced through the sulphate process. The "sulphate process" involves the use of sulphuric acid to concentrate the input raw mineral in terms of titanium dioxide content, then selective precipitation and calcination allow getting the final product. Main process chemical reactions can be summarized as in the following box:




Therefore, no process emissions originate by the sulphate production process.

Caprolactame production

Caprolactame is a monomer used in the industrial production of nylon-6. It can be obtained by catalytic oxidation of toluene and cyclohexane. The process releases N₂O. N₂O emissions from caprolactame production have been estimated and reported and are related to only one producing plant, which closed in 2003.

Calcium carbide production and use

Calcium carbide production process takes place in electric furnaces, CaO and coke are fed to the furnace and the product is obtained according to the following reaction:



CARBITALIA S.p.A. is the only facility which can operate calcium carbide production in Italy. It produced calcium carbide up to 1995, when it stopped production because of the increasing price of electricity. The plant still exists and it is maintained, but since 1995 it has just been supplying calcium carbide bought abroad. About 95% of the total CaC₂ sold in Italy is used to manufacture acetylene, the remaining share is bought by foundries for the desulphuration of steel or spheroidal pig iron (CARBITALIA S.p.A., several years). CO₂ emissions from manufacture and use of calcium carbide are estimated.

Soda Ash production and use

In Italy only one facility operates soda ash production via Solvay process. Solvay process allows producing soda ash through the conversion of sodium chloride into sodium carbonate using calcium carbonate and ammonia. CO₂ is released and calcium chloride is the waste. Up to the second half of the year 2000 in the unit for the production of peroxidates there was one sodium carbonate line and a sodium perborate line

which was then converted to sodium carbonate production. Soda ash is also used in glass production processes.

Fluorochemical production

The sub-sector fluorochemical production consists of two sources, "By-product emissions" and "Fugitive emissions". PFCs and HFCs emissions from fluorochemical production are a key source at trend assessment using Approach 2 without LULUCF.

The production of halocarbons and SF₆ took place in two facilities in Italy up to 2008 (Spinetta Marengo and Porto Marghera). Since 2005, the plant in Spinetta Marengo has not produced SF₆ any longer. In the first quarter of 2008 the production plant at Porto Marghera stopped its activity. Then there is only one facility in Italy where HCFC22 is produced.

Within by-product emissions, HFC23 emissions are released from HCFC22 manufacture, CF₄ emissions are released from SF₆ and HCFC22/TFM productions, whereas C₂F₆ and HFC143a emissions are released from the production of C₃F₈ (and also CFC115) and HFC134a, respectively. Production of CFC115 was carried out only in one facility and stopped in 1998. Production of HFC125, HFC134a, HFC227ea and SF₆ lead to fugitive emissions of the same gases. Production of HFC227ea only occurred in 1999. The share of F-gas emissions from the fluorochemical production in the national total of F-gases was 38.9% in 1990 and 1.8% in 2023.

4.3.2 Methodological issues

Adipic acid

Italian production figures and emission estimates for adipic acid have been provided by the process operator (Radici Chimica, several years) for the whole time series. Emissions estimates provided by the operator are based on the IPCC default EF, so the values provided and the estimates in the Italian emissions inventory are, basically, the result of the same methodology.

More specifically, N₂O emissions from adipic acid production (category 2B3) have been estimated using the default IPCC emission factor equal to 0.30 kg N₂O/kg adipic acid produced, from 1990 to 2003.

Since 2004 the operator has started to study how to introduce an abatement system; although emission estimates provided by the operator have still been based on the IPCC default emission factor (0.30 kg N₂O/kg adipic acid produced), the operating hours of the abatement system and the abatement rates have also been included in the estimation process. The abatement system is generally run together with the adipic acid production process. In 2004, the N₂O catalytic decomposition abatement technology has been tested so that the value of emission factor has been reduced considering the efficiency and the time, one month, that the technology operated.

Since the end of 2005 the abatement technology is fully operational; the average emission factor in 2006 is equal to 0.05 kg N₂O/kg adipic acid produced and the abatement system had been operating continuously for 9 months; since 2007 the average emission factor has been 0.03 kg N₂O/kg adipic acid produced and the operating time of the abatement system has been 11 months.

Technical improvements in operating the production process and the abatement system have allowed achieving significant reduction in N₂O emissions since 2009 (Radici Chimica, 2013): in 2010 the average emission factor was 0.018 kg N₂O/kg adipic acid produced while in 2011-2013 the average EF is around 0.005 kg N₂O/kg adipic acid produced with the abatement rate exceeding 98%.

In 2015 the average EF is around 0.0045 kg N₂O/kg adipic acid while in 2023 it is 0.0015 kg N₂O/kg adipic acid.

Thus, from 1990 to 2011, default EF has been used when no abatement system was operational; and abatement rates have been considered. The operator reports also under EPER/E-PRTR both adipic acid production and the N₂O emissions related to this production; adipic production and N₂O emissions have been also reported by the operator to the national competent authority for the ETS (the facility was included in the ETS system in 2013) together with additional information such as abatement rates and operating times. Since 2011 the implementation of a new monitoring system has also enabled the reporting of better-quality emissions data in terms of nitrogen and nitrous oxides emissions.

Based on information from the national PRTR and ETS, for verification purposes, EFs are calculated for the plant, considering the IPCC default EFs, the abatement technology rate and the operating time of the abatement technology at the facility according to the formula in Table 4.11.

The EFs submitted for the adipic acid production in the CRF and the EFs calculated for the plant in Table 4.11 are practically the same throughout those years.

Table 4.11 N₂O emission factors submitted vs calculations based on efficiency and utilization details.

Parameter/Year	2005	2006	2007	2008	2009	2010	2011
EFp (IPCC default)	0.3	0.3	0.3	0.3	0.3	0.3	0.3
A	0.925	0.9212	0.965	0.986	0.986	0.986	0.986
T	0.14	0.8825	0.93	0.91	0.91	0.952	0.999
EFs (average EF)	0.26	0.056	0.031	0.031	0.031	0.019	0.005

Values resulting according to the following formula

$$(1-A*T)*EFp = EFs$$

Where:

A= Abatement rate provided by the operator

EFp= N₂O Emission Factor for Adipic Acid production (kg N₂O /kg adipic acid prod)

T = operating time of the abatement system/ operating time of the adipic acid production line

EFs = N₂O actually released Emission Factor submitted (kg N₂O released/kg adipic acid prod)

CO₂ emissions from this source have been estimated according to the information communicated by the operator. Tier 2 is implemented up to 2012 estimates while Tier 3 is reported for the estimates related to the last part of the time series (from 2013 onwards), because AD and CO₂ emissions reported by the operator in the framework of the national ETS have been used. Measurements of plant specific information under the national ETS are not available for the period 1990-2012, so Tier 3 cannot be implemented for the whole time series, but the consistency of the time series is not affected because there is only one operator for the national production of adipic acid in Italy.

Ammonia

Ammonia production data are published in the international industrial statistical yearbooks (UN, several years), national statistical yearbooks (ISTAT, several years [a]) and from 2002 they have been checked with information reported in the national EPER/E-PRTR registry. More in detail for 1990-1999 the amount of ammonia produced was published on the UN "Industrial Commodity Statistics Yearbook" (UN, several years), while for the years 2000 and 2001 production indexes published by ISTAT were applied. Since 2002 national production of ammonia in Italy has been collected at facility level. The number of ammonia facilities in Italy is known along the whole time series so it is possible to make sure that the national emissions estimation from this source is consistent to the sum of emissions from the ammonia facilities.

Since 2009 only one facility has been producing ammonia in Italy and reporting data to the national PRTR.

Recovered CO₂ has been investigated with the cooperation of the operators, and the resulting information has been used to revise the whole CO₂ emission time series and the emission factors. The analysis has allowed understanding that CO₂ emissions recovered from ammonia production are used to produce urea and technical gases. According to 2006 IPCC Guidelines the CO₂ recovered for technical gases should be

accounted for emission and included in the estimate while that for producing urea should be reported in the relevant consumption categories. For the years 1990-2001, CO₂ emission factor has been calculated based on information reported by production plants for 2002 and 2003 in the framework of the national EPER/E-PRTR registry and considering also the amounts of CO₂ recovered since the beginning of recovery operations. CO₂ reported to the national EPER/E-PRTR registry has been used for the previous years under the assumption, verified with the operator, that no change in technology at facilities have occurred throughout the period (YARA, 2007). Since 2002, the average emission factors result from data reported by the plants in the national EPER/E-PRTR and calculated considering the gas consumed for the reforming process; the plant supplies the recovered CO₂ detailed data allowing the proper application of the IPCC methodology.

Production of Urea and Ammonia are separate processes, so when they are carried out in the same facility the CO₂ EF for Ammonia production, according to the IPCC 2006 GL, is based on the amount of CO₂ released from the production of ammonia, the amount of CO₂ recovered and sold as technical gas and the amount of ammonia produced. The recovery of CO₂ fed to Urea production, instead, has to be subtracted in the calculation of the EF. The resulting CO₂ EF could vary according to the decision of the operators in terms of increase/decrease of recovered CO₂ to be sold as technical gas or fed to Urea production. For example, in 2013-2015 the amounts of CO₂ fed to Urea production and the amount of CO₂ for technical gas decreased, consequently the overall amount of CO₂ released from ammonia production increased; moreover the fluctuation of ammonia manufactured in the same years has to be considered: production of ammonia increased in 2014, then it fell in 2015 while in 2019 the amount produced was the same as in 2013. Since last quarter of 2021 the rising price of natural gas resulted in extraordinary plant shutdowns which contributed also to the fluctuation of the CO₂ IEF. Table 4.12 shows the time series for the average CO₂ emission factor.

Table 4.12 Ammonia production, time series for the average CO₂ EF (t CO₂/t ammonia production)

	1990-2001	2005	2010	2011	2012	2013	2014	2015	2020	2021	2022	2023	2024
EF (t CO ₂ /t ammonia production)	1.30	1.32	1.27	1.18	1.08	1.16	1.17	1.25	1.10	1.19	1.27	1.23	1.08

Italy investigated the differences between apparent consumption of urea and the final uses of urea at national level. Apparent consumption can be calculated starting from the production, import and export of urea at national level, according to the equation $P+I-E=\text{apparent consumption}$ (where: P is production; I mean imports and E are the exports). The total amount of urea manufactured is supplied by the operator, while the amounts referring to imports and exports can be obtained from the national institute of statistics dataset regarding the statistics about the foreign commercial exchange.

The operator of the facility producing ammonia and urea has provided us with the final markets of urea in Italy and an estimation of those market shares in 2017: SCR engines (7.6%); NOx abatement systems (2.8%); Industry ("industry-no-glue", such as cosmetics and instant cold packs, and "industry-glue", 15.1%) and fertilizers (74.5%). The review of the final urea market uses has been carried out also for the subsequent years, the exercise confirmed the completeness of the Italian inventory. As for 2021, the urea final market uses were: SCR engines (14.2%); NOx abatement systems (2.7%); Industry ("industry-no-glue", mainly instant cold packs, and "industry-glue", 8.1%) and fertilizers (74.5%).

About 95% of total natural gas consumption of ammonia production plants is used as feedstock in the production process while the remaining 5% is used as fuel input. The amount of fuel used is included in the energy balance under the no energy final consumption sector (see Annex 5), therefore double counting does not occur.

Nitric acid

Regarding nitric acid production (2B2), production figures at national level are published in the national statistical yearbooks (ISTAT, several years [a]), while at plant level they have been collected from industry (Norsk Hydro, several years; YARA, several years; Radici Chimica, several years). The number of nitric acid facilities in Italy is known along the whole timeseries, so it is possible to make sure that the national emissions estimation from this source is consistent to the sum of emissions from the nitric acid facilities. In 1990 there were seven production plants in Italy; three of them closed between 1992 and 1995, and another one closed in 2004, one more closedown in 2008 has left two plants still operating.

The N₂O average emission factors are calculated from 1990 on the basis of the emission factors provided by the existing production plants in the national EPER/E-PRTR registry, applied for the whole time series, and default IPCC emission factors for low and medium pressure plants attributed to the plants, now closed, where it was not possible to collect detailed information. Thus, N₂O emissions are estimated at plant level also considering the operating unit level, if necessary. Activity data have been collected at plant level for the whole timeseries. Unit specific default IPCC EFs have been used for plants closed in the nineties because it was not possible to collect more detailed information. For the other plants, data supplied in the framework of the EPER/EPTR registry have been used: for the years 1990-2000 EFs at unit level have been calculated as an average of 2001-2004 data provided by operators in the EPER/EPTR register. For the years 2001-2012 EPTR data were used to calculate the national EF; the activity data and the emissions reported under ETS have been used from 2013 onwards thus moving from a Tier 2 approach to a Tier 3 approach. Tier 3 cannot be implemented along the whole timeseries because the nitric acid facilities entered the national ETS in 2013 and there isn't enough information available to support Tier 3 for years before 2013. The implementation of different Tiers along the time series does not affect the consistency of the time series because there are only two operators for the national production of nitric acid in Italy both reporting the same AD under the national EPTR and ETS registers.

Table 4.13 Nitric acid production, time series for the average N₂O EF (kg N₂O/t nitric acid production)

	1990	2008	2010	2011	2012	2013	2014	2015	2017	2018	2020	2021	2022	2023	2024
EF (kg N ₂ O/Mg nitric acid)	6.49	2.29	1.21	1.32	1.11	0.86	0.40	0.31	0.49	0.42	0.29	0.22	0.23	0.29	0.24

Relevant reductions in N₂O emissions have been observed since 2008. Specifically, in 2008 the implementation of catalyst N₂O abatement technology in one of the major production plants (i.e. in one unit of that plant) has led to a significant decrease in total N₂O emissions from nitric acid production, consequently a relevant reduction in the IEF can be observed too (YARA, several years) as shown in table 4.13: the implied emission factor for 2008 is in fact 2.29 kg N₂O/Mg nitric acid production (the abatement rate in one plant was 82% so far); in 2010 the implied emission factor is 1.21 kg N₂O/Mg nitric acid production and in 2024 it is 0.24 kg N₂O/Mg nitric acid; the relevant decrease is due to the installation of the abatement technology in the other unit of the same producing facility (YARA, several years) and to the technical improvements implemented in 2011 as far as monitoring of emissions is concerned at the second nitric acid facility (Radici Chimica, 2013). Sampling circumstances at the facility may affect the reported N₂O emission values: sampling in times very close to catalyst exhaustion generally leads to higher N₂O concentration in the process flue gases, this seems to have occurred for N₂O emissions in 2011 according to the operator (Radici Chimica, several years).

Caprolactame

N₂O emissions from caprolactame have been estimated based on information supplied by the only plant present in Italy, production activity data published by ISTAT (ISTAT, several years [a]) and production and emission data reported in the national EPER/E-PRTR registry. For the years 2002 and 2003 activity data and

emissions were reported by the operators to the national EPER register. For 1990-2001 no facility level specific information was available for the inventory team, only the amount of caprolactame manufactured in Italy was known. Based on the 2002 emission factor and after discussion with the technical expert at the facility an emission factor equal to 0.3 kg N₂O/Mg caprolactame production was assumed for 1990-2001. The plant closed in 2003.

Carbon Black

CO₂ and CH₄ emissions from carbon black production process have been estimated with a Tier 2 approach and plant specific data. Plant specific information (AD and emissions) has been supplied by the Italian production facilities in the framework of the national EPER/E-PRTR registry and the European emissions trading scheme, total AD and total emissions allow for calculating the EFs values to be used in the estimation process.

In 1996 a change in the production technology in the existing plants caused a reduction of CH₄, NMVOC, NO_x, SO_x and PM₁₀ emissions. As for CH₄ emissions, the 2006 IPCC Guidelines default value for CH₄ emission factor (manufacturing process with thermal treatment) has been applied for this category and considered for the years since 1996. Table 4.14 includes the values of the implied emission factor for CO₂ (t CO₂/t carbon black production) from 2005 to 2024.

Table 4.14 Carbon black production, time series for the average CO₂ EF (t CO₂/t carbon black production)

	2005	2010	2013	2014	2015	2019	2020	2021	2022	2023	2024
EF (t CO ₂ /t Carbon black)	2.56	2.48	2.46	2.32	2.24	2.26	2.27	2.33	2.45	2.30	2.17

Ethylene, Ethylene oxide, Propylene, Styrene

Ethylene, ethylene oxide, propylene and styrene productions belong to the organic chemical processes, which are sources of methane emissions.

For ethylene activity data have been provided by the Italian producers, specifically: for 1990-2001 by the sectoral industrial association (UNEM, several years) and since 2002 by the manufacturing companies (Syndial, several years; Polimeri Europa, several years; Versalis, several years). For ethylene oxide activity data have been provided by the manufacturing company for the whole time series (Enichem, several years); this production stopped in 2001. Propylene production activity data are reported in the UN "Industrial Commodity Statistics Yearbook" (UN, several years) for the years 1990-1994; since 1995 data have been provided by the manufacturing companies (Enichem, several years; Syndial, several years; Polimeri Europa, several years; Versalis, several years). Regarding Styrene, for the years 1990-1994, UN international statistics have been used (UN, several years). From 1995 the amount of styrene is supplied every year to the inventory team by the Italian producer at plant level (Enichem, several years; Polimeri Europa, several years; Versalis, several years).

For ethylene and propylene production, CH₄ emission factor is calculated, for the whole time series, based on the EPRTR data submitted by the plants. In the framework of the E-PRTR registry, facilities manufacturing ethylene in Italy reported activity data and emissions following the E-PRTR classification. For these plants, CH₄ emissions, for these productions, were below the reporting threshold (which for methane is set to 100 t/year). Assuming that emissions of each plant were equal to the maximum value (threshold), 100 t/year, the emission factor resulted in 0.085 kg/t; this value has been used along the whole time series.

For Styrene CH₄ emissions, no specific information concerning the years 1990-1994 was available, so the EMEP/CORINAIR default emission factor (EMEP/EEA, 2007) has been applied (0.025 kg/t equal to 10% of total VOC emissions). Based on the information included in the Environmental Reports by the Italian producer (Enichem, several years), and confirmed by the operators, CH₄ emissions did not occur from 1995.

Methane emission factor for ethylene oxide production used for the whole time series (1990-2001) is equal to 6.841 kg/t as supplied by the air and waste management association (APEM, 1992).

Titanium dioxide

In Italy there is only one facility where titanium dioxide production occurs. As previously reported, because of the implementation of the sulphate process, no CO₂ process emissions occur. CO₂ emissions from fuel combustion in titanium dioxide production via the sulphate process do occur; however, they are accounted for under the “Energy” sector.

Calcium carbide

CO₂ emissions from calcium carbide production process and use have been estimated on the basis of the activity data provided by the sole Italian producer/retailer (CARBITALIA SPA, several years). Activity data relating to the manufacture of calcium carbide are referred to the years from 1990 to 1995 when the production stopped; activity data concerning the use of calcium carbide have been provided for the whole time series too. The default IPCC CO₂ emission factors (IPCC, 2006) have been used to estimate the emissions from the manufacture and use along the whole time series.

Soda ash

CO₂ emissions from soda ash production have been estimated using available information on the Solvay process (Solvay, 2003), which is the technology employed in Italy. Emissions from the use of soda ash, on the other hand, are accounted for under glass production. In Italy, soda ash production has been carried out at a single facility, which falls within the scope of the national EPER/PRTR. As a result, data on activity levels and emissions for this plant are available from 2002 onwards. For the period 1990–2001, production data were sourced from the United Nations’ Industrial Commodity Statistics Yearbook (UN, several years). For those earlier years, the CO₂ emission factor was derived from the methodology used in Spain’s GHG inventory, incorporating information provided by Solvay for a plant using the same technology as the Italian facility. From 2002 onwards, the emission factor is based on data annually reported by the Italian operator under the national EPER/PRTR and the EU Emissions Trading System (ETS), including preliminary data for 2005–2009 and official data from 2013 onward.

Fluorochemical production

For both source categories, “By-product emissions” and “Fugitive emissions”, the IPCC Tier 2 method is applied, based on plant-level data. Communication is supplied annually by the only national producer, and includes productions, emissions, import and export data for each gas (Solvay, several years; Syensqo, 2024). CF₄ emissions represent additional by product emissions together with HFC23 emissions. The operator supplied all the relevant information for a better understanding of the activities taking place at the site of Spinetta Marengo and to help the inventory team to allocate CF₄ emissions from HCFC22 production properly. The industrial site of Spinetta Marengo plant is one of the most important of the international chemical group Syensqo (a spin-off of Solvay). Over 35 product families and more than 1,500 formulations give life to a wide range of special polymers that include fluoropolymers, fluor elastomers, fluorinated fluids, polymers with high barrier properties and cross-linked composites. The industrial site is in the scope of EPER/PRTR, IPPC permitting procedure and Seveso European Legislation. At the facility the monitoring system has 27 devices to perform gas chromatography analysis and about 540 monitoring points at the site. The resulting monitoring data flow, which regards other pollutants, is sent via web to the regional agency for environmental protection (ARPA Piemonte).

In particular, the operator explained that HCFC22 production has been carried out in Spinetta Marengo since '50s and up to 1990 part of HCFC22 was probably also sold as a marketable product. Since 1990, all the HCFC22 produced has been the input for the TFM (tetrafluoroethylene monomer) production process (by pyrolysis of HCFC22 at 600 °C), the TFM has been then used to produce TFE (tetrafluoroethylene, C₂F₄) and PTFE (polytetrafluoroethylene), HFP (hexafluoropropylene) and other different fluoropolymers and fluoroelastomers. All the fluorinated flue gases from the different production lines are collected and treated in a centralized abatement unit (thermal oxidation system), specifically designed for the Spinetta Marengo plant, working at a temperature of 1400 °C with a residence time of the gases minor of 2 seconds. The abatement unit is run continuously and allows reducing F-gas emissions not depending on the operating level of the main production process. In the treated flue gases CF₄ is still present (65% of CF₄ released to air pass through the abatement system untreated for thermodynamic reasons; 35% of CF₄ released to air is formed during the reactions occurring in the abatement unit). Estimations of CF₄ emissions released to air have been reported to the national PRTR since 2007. The operator has provided the time series for the activity data from 2002 to 2010 (HCFC22 and TFM), since the activity data for the years before 2002 are not retrievable; to complete the activity data timeseries for the period 1990-2001 a linear increasing production level was assumed from 1990 to 2002. The ratio relating TFM production to HCFC22 production in 2002 has been taken also over the years 2001 back to 1990 to estimate the TFM productions. CF₄ emission factor for 2007 was set constant to estimate the CF₄ time series over the years from 1990 to 2006. CF₄ emissions time series have been then included in the estimates under the category 2.B.9.a.1 (By-product emissions from production of HCFC22).

To provide detailed information on the methodology applied for this category, CF₄ emissions estimation from HCFC22 can be summarized as follows:

- For the years 2007-2010 by-product CF₄ emissions from HCFC22 production has been supplied by the operator (through the national PRTR). Based on data reported to the national PRTR since 2007 and the activity data concerning HCFC production, the TFM/HCFC22 ratio along the time series, the EF for by-product CF₄ emission has been calculated.
- CF₄ EF (by-product emissions from HCFC22 production) for 2007 has been set as default value for the period 1990-2006 in order to estimate by-product CF₄ emissions consistently along the whole time series.
- Activity data for the facilities are available for the years 2002-2010, so the missing activity data were estimated based on the HCFC22 production capacity of the facility in 1990 and 2002 HCFC22 production figure assuming a linear increasing production level within the years. The TFM/HCFC22 ratio for 2002 was assumed as a default ratio to estimate TFM production consistently from 1990 and 2002.
- By product CF₄ emissions were estimated by applying the EF derived in point 2) to the TFM production levels along the years 1990-2002.

HFC23 is a by-product of the HCFC22 production process, the HFC23/HCFC22 rate is about 3%. The abatement system, as previously mentioned, allows for treating all the fluorinated flue gases, vented gases originated in the processes at the facility before being released into air. Since 1989 the abatement system has allowed to reduce HFC23 released to air, up to 1996 HFC23 emissions had been about 30 t/y. In 1996 the abatement system was improved with a second operating unit, since 1996 the abatement rate has been 99.99% thus reducing drastically HFC23 emissions close to zero. The operator communicated that for a HCFC22 production of 30,000 tons, HFC23 theoretical residual emissions are less than 100 kg; a monitoring analysis has measured about 10 kg of HFC-23 in one year (Spinetta Marengo, 2011).

C₂F₆ and HFC143a emissions are released from the production of C₃F₆ (and CFC115) and HFC134a, respectively. Fluorochemical were produced in one plant (Porto Marghera) and progressively stopped in the last years. More in detail C₃F₆ (and CFC115) production stopped in 1998 while HFC134a production

stopped in 2007. Data production and emission figures have been provided by the company (Solvay Fluor, several years).

Production of HFC-125, HFC-134a, HFC-227ea and SF₆ lead to fugitive emissions of the same gases. In particular, the production of HFC-227ea only occurred in 1999. Emissions figures have been communicated by the operator (Solvay Fluor, several years).

4.3.3 Uncertainty and time-series consistency

The uncertainty in N₂O emissions from adipic and nitric acid and caprolactame production and in CO₂ emissions from ammonia and for other chemical production is estimated by 10.4%, for each activity, as combination of uncertainties related to activity data (3%) and emission factors (10%). Uncertainty level for activity data is an expert judgement, considering the basic source of information, while the uncertainty level for emission factors is equal to the level reported in the IPCC Good Practice Guidance (IPCC, 2000) for the adipic and nitric acid N₂O emissions and for CO₂ emissions from other industrial processes. The uncertainty in F-gas emissions from fluorocarbons production is estimated to be 50.2% in annual emissions, 5% and 50% concerning respectively activity data and emission factors.

In Tables 4.15 and 4.16, the production of chemical industry, including non-key sources, and emission trends are reported. An overview of the emissions per compound from fluorochemical production is given for the 1990-2024 period.

In general, total emission trends for all the chemical productions have been affected by fluctuations in productions along the time series (and by reductions in productions over the years 2007-2009, except for adipic acid and titanium dioxide activity data), whenever abatement technologies (e.g. nitric acid since 2008) or closures of plants cannot be regarded as the specific causes for the decreasing emissions.

Table 4.15 Production of chemical industry, 1990 –2024 (kt)

Activity data	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt										
2B.1 - Ammonia	1,455	592	414	607	505	396	598	532	194	313	360
2B.2 - Nitric acid	1,037	588	556	572	417	390	447	402	342	324	326
2B.3 - Adipic acid	49	64	71	75	85	82	73	73	56	47	31
2B.4 - Caprolactame	120	120	111	-	-	-	-	-	-	-	-
2B.5 - Calcium carbide production&use	12	7	7	7	6	4	3	4	3	2	2
2B.6 - Titanium dioxide	58	69	72	60	70	60	51	62	43	10	-
2B.7 - Soda ash production and use	610	1,070	1,000	915	620	880	851	907	874	637	597
2B.8b - Ethylene	1,466	1,807	1,771	1,721	1,551	1,187	1,046	1039	833	664	608
2B.8d - Ethylene oxide	61	54	13	-	-	-	-	-	-	-	-
2B.8f - Carbon black	184	208	221	214	205	205	188	220	237	230	247
2B.8g - Styrene	365	484	613	520	524	547	501	472	413	338.9	310
2B.8g.i - Propylene	774	693	690	1,037	880	630	531	542	464	385.3	358
2B.9 - HCFC 22 production	20	23	26	27	21	26	18	22	21	17	14

Table 4.16 CO₂, CH₄ and N₂O emissions from chemical industry, 1990 – 2024 (kt) and HFCs, PFCs per compound 1990 - 2024 (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
CO₂ (kt)										
Ammonia	1,891.50	769.60	537.91	802.29	639.77	495.54	658.36	246.79	385.69	390.35
Calcium carbide	26.28	14.24	7.7	8.01	6.63	4.59	3.80	3.47	2.30	2.46
Carbon black	422.05	477.48	508.83	548.22	510.38	462.39	426.33	581.14	529.38	536.27
Titanium dioxide	-	-	-	-	-	-	-	-	-	-
Adipic acid	1.33	1.72	1.93	1.50	1.76	1.82	1.62	1.92	2.82	1.58
Soda ash production and use	183	321	300	275	203.33	255.35	268.37	260.54	229.21	214.55
CH₄ (kt)										
Carbon black	1.84	2.08	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
Ethylene	0.12	0.15	0.15	0.15	0.13	0.10	0.09	0.07	0.06	0.05
Propylene	0.07	0.06	0.06	0.09	0.07	0.05	0.05	0.04	0.03	0.03
Styrene	0.01	-	-	-	-	-	-	-	-	-
Ethylene oxide	0.42	0.37	0.09	-	-	-	-	-	-	-
N₂O (kt)										
Nitric acid	6.73	4.22	4.09	5.44	0.51	0.12	0.13	0.08	0.09	0.08
Adipic acid	14.77	19.09	21.42	19.59	1.58	0.37	0.27	0.06	0.08	0.02
Caprolactame	0.04	0.04	0.03	-	-	-	-	-	-	-
kt CO₂ eq.										
HFC 23	372.00	372.00	1.05	1.09	0.85	1.05	0.76	0.85	0.69	0.56
HFC 143a	-	28.80	4.80	5.28	-	-	-	-	-	-
CF ₄	792.12	890.54	889.50	1,388.28	1,166.88	1,392.30	374.60	300.34	173.04	177.02
PFC C ₂ ÷C ₃ (C ₂ F ₆)	44.40	44.40	-	-	-	-	-	-	-	-
<i>Total F-gas by product emissions</i>	1,208.52	1,335.74	895.35	1,394.65	1,167.73	1,393.35	375.35	301.19	173.74	177.58
HFC 125	-	31.70	3.17	3.80	-	-	-	-	-	-
HFC 134a	-	39.00	15.60	12.61	-	-	-	-	-	-
HFC 227ea	-	-	-	-	-	-	-	-	-	-
SF ₆	117.50	117.50	-	-	-	-	-	-	-	-
<i>Total F-gas fugitive emissions</i>	117.50	188.20	18.77	16.41	-	-	-	-	-	-
Total F-gas emissions from fluorochemical production	1,326.02	1,523.94	914.12	1,411.06	1,167.73	1,393.35	375.35	301.19	173.74	177.58

HFC23 emissions from HCFC22 had been drastically reduced since 1996 due to the installation of a second thermal oxidation system in the facility located in Spinetta Marengo (the only facility currently producing HCFC22 in Italy). Productions and emissions from 1990 to 1995 are constant as supplied by industry; from 1996, untreated leaks have been collected and sent to the thermal oxidation system, thus allowing reduction of emissions under 100 kg (E.F. 3.3 g of HFC23/t of HCFC22). CF₄ by-product emissions in HCFC22 production process have been fully investigated, information supplied by the operator has allowed estimating emissions for the whole time series. This information about production and emissions is updated yearly by the producer, and it is also reported in the framework of the national PRTR register, confirming that the technology is fully operating. Since 2020, a drastic reduction of CF₄ emission has occurred: as part

of Solvay's commitment to reducing greenhouse gas emissions, a new project for the abatement of CF₄ by thermo-oxidation has been developed.

PFC (C₂F₆) by-product emissions and SF₆ fugitive emissions were constant from 1990 to 1995 (4 t/y for C₂F₆ emissions; 5 t/y for SF₆ emissions) and from 1996 to 1998 (1 t/y for C₂F₆ emissions; 2 t/y for SF₆ emissions) and have eventually reduced to zero since 1999 due to the stop of the CFC115 production in one facility and the upgrade of the thermal oxidation system mentioned above in the other facility. Besides, SF₆ production stopped since the 1st of January 2005.

Regarding fugitive emissions, emissions of HFC125 and HFC134a have been cut in 1999 thanks to a rationalisation in the new production facility located in Porto Marghera, whereas HFC143 released as by-products from the production of HFC134a has been recovered and commercialized. The relevant productions in Italy which originate these fugitive emissions stopped in the first quarter of 2008.

4.3.4 Source-specific QA/QC and verification

Emissions from adipic acid, nitric acid, ammonia and other chemical industry production have been checked with the relevant process operators and with data reported to the national EPER/E-PRTR registry. Emissions and activity data for adipic acid, nitric acid and ammonia productions have also been checked against the relevant information reported by operator to the national competent authority for the ETS, the resulting consistency of both emissions and activity data for those sectors is the outcome of this control. Emissions from fluorochemical production have been checked with data reported to the national EPER/E-PRTR registry.

4.3.5 Source-specific recalculations

Recalculations occurred for CO₂ emissions from Calcium carbide production and use in 2023 (1.95%) due to the update of the activity data.

Table 4.17 Recalculation of CO₂ emissions from Chemical Industry (%)

Gas/subcategory	2023
2.B.5 Chemical Industry	+1.95

4.3.6 Source-specific planned improvements

A detailed balance of natural gas reported in the energy balance, as no energy fuel consumption, and the fuel used for the production processes in the petrochemical sector is planned.

4.4 Metal production (2C)

4.4.1 Source category description

The sub-sector metal production comprises five sources: iron and steel production, ferroalloys production, aluminum production, magnesium foundries and zinc/lead production; CO₂ emissions from iron and steel production are key sources at trend assessment with Approach 1 with and without LULUCF; PFC emissions from aluminum production are key sources at trend assessment both with the Tier1 and Tier2 approaches with and without LULUCF. In 1990, PFC emissions were key sources at level assessment with and without LULUCF but without LULUCF only considering uncertainty, CO₂ emissions from iron and steel production were key sources at level assessment with Tier1 and Tier2 approaches with and without LULUCF.

In 2024, the share of CO₂ emissions from metal production accounted for 0.46% of the national total CO₂ emissions, and 11.31% of the total CO₂ from industrial processes. In 2024, the share of CH₄ emissions is equal to 0.07% of the national total CH₄ emissions while N₂O emissions do not occur. The share of F-gas emissions from metal production out of the national total F-gas levels was 52.2% in the base-year and has decreased to 0.05% in the year 2024.

Iron and steel

The main processes involved in iron and steel production are those related to sinter and blast furnace plants, to basic oxygen and electric furnaces.

The sintering process is a pre-treatment step in the production of iron where fine particles of metal ores are agglomerated. Agglomeration of the fine particles is necessary to increase the passageway for the gases during the blast furnace process and to improve physical features of the blast furnace burden. Coke and a mixture of sinter, lump ore and fluxes are introduced into the blast furnace. In the furnace the iron ore is increasingly reduced and liquid iron and slag are collected at the bottom of the furnace, from where they are tapped. The combustion of coke provides both the carbon monoxide (CO) needed for the reduction of iron oxide into iron and the additional heat needed to melt the iron and impurities. The resulting material, pig iron (and also scrap), is transformed into steel in subsequent furnaces which may be a basic oxygen furnace (BOF) or electric arc furnace (EAF). Oxygen steelmaking allows the oxidation of undesirable impurities contained in the metallic feedstock by blowing pure oxygen. The main elements thus converted into oxides are carbon, silicon, manganese, phosphorus and sulfur.

In an electric arc furnace steel is produced from polluted scrap. Scrap is mainly produced by cars shredding and does not have a constant quality, but the recent stringent legislation and the adoption of BAT (Best Available Techniques) in scrap management allow an input with better product characteristics.

The iron and steel cycle is closed by rolling mills with production of long products, flat products and pipes.

In 1990, there were six integrated iron and steel plants in Italy. In 2014, there were only three of the above-mentioned plants, one of which lacking sintering facilities and another one not equipped with a BOF. Since 2015 there have been only two plants because the plant without sinter production has been closed and in 2021 only the largest integrated plant is still producing. In 2024, oxygen steel production represents about 10% of the total production and the arc furnace steel the remaining 90% (FEDERACCIAI, several years). Currently, long products represent about 50.9% of steel production in Italy, flat products about 37.5% and pipes the remaining 11.6%. In 2024 long production has been equal to 11.7 Tg with a decrease of -0.2% over the previous year and still below -29.9% compared to 2008; flat production has been equal to 8.6 Tg, -9.8% compared to the previous year and with a decrease of 38.4% compared to 2008 level. Most of the flat production derives from the only integrated iron and steel plant, while in steel plants equipped with electric ovens, almost all located in the northern regions, long products are produced predominantly (e.g. carbon steel, stainless steels) and seamless pipes (only one plant) (FEDERACCIAI, several years).

CO₂ emissions from steel production refer to carbonates used in basic oxygen furnaces and crude iron, carbonates, *coals* and electrodes in electric arc furnaces. CO₂ emissions from pig iron production refer to carbonates used in sinter and pig iron production. CO₂ emissions from iron and steel production due to the fuel consumption in combustion processes are estimated and reported in the energy sector (1A2a) to avoid double counting. CH₄ emissions from steel production refer to blast furnace charging, basic oxygen furnace, electric furnaces and rolling mills. CH₄ emissions from coke production are fugitive emissions during solid fuel transformation and have been reported under 1B1b category while CH₄ emissions from the combustion of fuels are allocated in the energy sector.

Ferroalloys

Ferroalloy is the term used to describe concentrated alloys of iron and one or more metals such as silicon, manganese, chromium, molybdenum, vanadium and tungsten. Usually, alloy formation occurs in electric

arc furnaces (EAF) and CO₂ emissions occur during oxidation of carbon still present in coke and because of consumption of the graphite electrodes. In early nineties there were 13 plants producing various kinds of ferroalloys: FeCr, FeMn, FeSi, SiMn, Si-metal and other particular alloys, but since 2001 production has been carried on only in one plant (ISPESL, 2005). The last remaining plant in Italy produces mainly ferro-manganese and silicon-manganese alloys but since 2015 the facility has not been working.

Aluminum

From primary aluminum production CO₂ and PFCs (CF₄ and C₂F₆) are emitted. PFCs are formed during a phenomenon known as the 'anode effect', when alumina levels are low.

In 1990 primary aluminum production in Italy was carried out in 5 sites where different technologies were implemented:

- Fusina: Point Fed Prebake and Side Work Prebake (up to 1995);
- Portovesme: Point Fed Prebake and Side Work Prebake (up to 1990);
- Bolzano: Vertical Stud Soderberg;
- Fusina 2 and Porto Marghera: Side Work Prebake.

Since then, the implemented technology has been upgraded from Side Work Prebake to Point Fed Prebake; while three old plants stopped the operations in 1991 (Bolzano) and in 1992 (Fusina 2 and Porto Marghera). Since 2000 Alcoa has replaced ENIRISORSE in operating the plants. Up to 2010, two primary aluminum production plants, which use prebake technology with point feeding, characterised by low emissions, have operated. Only one plant, located in Portovesme, was operating until 2012 (99.5 kt of primary aluminum). In 1990, primary aluminum production was 232 kt. In 2021 the plant did not produce primary aluminum. The plant has stopped production but is not dismantled: in 2018 the new Company Sider Alloys took over Portovesme plant from Alcoa, that is currently under renovation.

Magnesium foundries

In the magnesium foundries, SF₆ is used as a cover gas to prevent oxidation of molten magnesium. In Italy there is only one plant, located in the north, which started its activity in September 1995. Since the end of 2007, SF₆ has been replaced by HFC125, due to the enforcement of fluorinated gases regulations (EC, 2006; EU, 2014) which, however, allow for the use of SF₆ in annual amounts less than 1 Mg. HFC125 emissions also occurred and, in 2010, they were equal to 605 kg. Since 2011 HFC125 has been replaced by HFC134a (3,000 kg of emissions in 2024).

Zinc production

Since 1998, in Italy there is just an integrated plant for the zinc and lead production which cover the entire production of zinc and of primary lead. In 2013, this plant began to submit data in the framework of ETS reporting data subdivided in combustion and process emissions; consequently, a survey has been started to investigate time series for process emissions resulting in CO₂ emissions from 1990 up to now. CO₂ emissions refer both to zinc and lead production.

4.4.2 Methodological issues

CO₂ and CH₄ emissions from the sector have been estimated on the basis of activity data published in the national statistical yearbooks (ISTAT, several years [a]), data reported in the framework of the national EPER/E-PRTR registry and the European Emissions Trading Scheme, and supplied by industry (FEDERACCIAI, several years; ALCOA, several years). Emission factors reported in the EMEP/EEA Guidebook

(EMEP/EEA, 2009), in sectoral studies (APAT, 2003; CTN/ACE, 2000) or supplied directly by industry (FEDERACCIAI, 2004; ALCOA, 2004; Italghisa, 2011) have been used.

Iron and steel

CO₂ emissions from iron and steel production refer to the carbonates used in sinter plants, in blast furnaces and in steel making plants to remove impurities; they are also related to the steel and pig iron scraps, carbonates, *coals* and graphite electrodes consumed in electric arc furnaces.

Basic information for this sector derives from different sources in the period 1990-2024. Activity data are supplied by official statistics published in the national statistics yearbook (ISTAT, several years [a]) and by the sectoral industrial association (FEDERACCIAI, several years).

For the integrated plants, emission and production data have been communicated by the two largest plants for the years 1990-1995, distinguished by sinter, blast furnace and BOF, and by combustion and processes emissions. From 2000, CO₂ emissions and production data have been supplied by all the plants in the framework of the ETS scheme, for the years 2000-2004 disaggregated for sinter, blast furnace and BOF plants, from 2005 specifying carbonates and fuels consumption and related CO₂ emissions. For 2002-2022 data have also been supplied by all the integrated iron and steel plants in the framework of the European EPER/E-PRTR registry not distinguished for combustion and processes. Qualitative information and documentation available on the plants allowed reconstructing their history including closures or modifications of part of the plants; additional qualitative information regarding the plants collected and checked for other environmental issues or directly asked to the plant permitted to individuate the main driving of the emission trends for pig iron and steel productions. Finally, since 2017, national experts have also been involved in the process of elaboration of the "monitoring and control plan" for the largest integrated plant in Italy in the framework of IPPC permit, allowing other terms of comparison and verification.

Time series of carbonates used in basic oxygen furnaces have been reconstructed based on the above-mentioned information resulting in no emissions in the last years. In fact, carbonates have been substituted by self-produced lime avoiding CO₂ emissions. Indeed, as regards the largest Italian producer of pig iron and steel, lime production has increased significantly from 2000 to 2008 by about 250,000 over 410,000 tonnes and the amount introduced in basic oxygen furnaces was, in 2004, about 490,000 tonnes (ILVA, 2006). In 2009 lime production, for the same plant, is equal to 216,000 tonnes but also steel production has sharply decreased because of the economic recession; in the following years lime production increased again up to 390,000 but in the last years it decreased because the plant went into receivership. Emissions from lime production in steel making industries are reported in "1.A.2 Manufacturing Industries and Construction" category and in "2.A Mineral production" respectively for the combustion and processes emissions.

Concerning the electric arc furnaces, additional information on the consumption of scraps, pig iron, graphite and electrodes and their average carbon content has been supplied together with the steel production by industry for a typical plant in 2004 (FEDERACCIAI, 2004) and checked with other sectoral study (APAT, 2003). Based on these figures, an average emission factor has been calculated and applied for the period 1990 - 2003. Since 2004, the same scheme as the previous period has been followed but using data becoming from ETS and related to the amounts of pig iron, metallurgical coke, graphite, anthracite, dolomite, limestone and electrodes for 34 plants in 2024. The availability of data for each plant has allowed also a first attempt application of the Tier 3 methodology (IPCC, 2006) that demonstrated the soundness of estimates.

On account of the amount of carbonates estimated in sinter plants, average emission factor was equal in 1990 to 0.15 t CO₂/t pig iron production, while in 2024 it reduced to 0.10 t CO₂/t pig iron production. The reduction is driven by the increase in the use of lime instead of carbonates in sinter and blast furnaces in

the Italian plants. Emissions are reported under pig iron because they are emitted as CO₂ in the blast furnaces producing pig iron.

CO₂ average emission factor in basic oxygen furnaces results in 1990 equal to 0.079 t CO₂/t steel production, while from 2003 is null.

CO₂ average emission factor in electric arc furnaces has been calculated based on Tier 2 of the 2006 IPCC Guidelines (IPCC, 2006) considering the pig iron and graphite electrodes used in the furnace and the amount of carbon stored in the final product. The same emission factor has been used for the period 1990 - 2003. Since 2004 ETS data have been used, in this way it has been possible to evaluate the contribution of anthracite and metallurgical coke producing an emission factor equal to 0.057 t CO₂/t of steel in 2024. The amount of carbon stored in steel produced with EAF has been considered and subtracted from the carbon balance (see Annex 3). Implied emission factors for steel production reduced from 0.053 to 0.050 t CO₂/t steel production, from 1990 to 2024, due to the reduction in the basic oxygen furnaces.

CO₂ emissions due to the consumption of coke, coal or other reducing agents used in the iron and steel industry have been accounted for as fuel consumption and reported in the energy sector, including fuel consumption of derived gases; in Annex 3, the energy and carbon balance in the iron and steel sector, with detailed explanation, is reported.

During the last in country review, Italy reported on the results of a survey which found that there is no accurate information by which to disaggregate the emissions between energy and process. Coke is the only irreplaceable material in the blast furnace as it has several roles:

- the combustion of coke produces carbon monoxide which is responsible for the reduction of iron ores;
- the combustion of coke generates the heat needed to melt the iron ore;
- coke mechanically supports the charge allowing the crossing of the reducing gas;
- coke allows the process of carburization of liquid iron by lowering its melting point.

These are intrinsic properties of the coke and cannot be separated one from the other, all the coke when burning simultaneously produces energy in the form of heat and CO as a reducing agent.

As any arbitrary disaggregation would not reflect the real situation, the ERT agreed that leaving the total emissions from the use of coke in the iron and steel industry in the energy sector is appropriate. Ultimately, carbon plays the dual role of fuel and reductant and it is very important not to double-count the carbon from the consumption of coke or other reducing agents if this is already accounted for as fuel consumption in the energy sector. For this reason, a balance is made between the coal used for coke production and the quantities of derived fuels used in various sectors. The iron and steel sector gets the resulting quantities of energy and carbon after subtraction of what is used for electricity generation, non energy purposes and other industrial sectors (see Annex 3).

The amount of carbon stored in steel produced in integrated plants has been considered and subtracted from the carbon balance (see Annex 3). The amount of carbon contained in steel has been estimated on the basis of EN standard and, from 2005, with emission trading data. Carbon stored is equal to 48,511 tonnes of CO₂ in 1990 and equal to 6,197 Mg in 2024.

CH₄ emissions from steel production have been estimated on the basis of emission factors derived from the specific IPPC BREF Report (IPPC, 2001), sectoral study (APAT, 2003) and the EMEP/CORINAIR Guidebook (EMEP/CORINAIR, 2007) and refer to blast furnace, basic oxygen furnace, electric furnaces and rolling mills.

Ferroalloys

CO₂ emissions from ferroalloys have been estimated based on activity data published in the national statistical yearbooks (ISTAT, several years [a]) until 2001. Time series of ferroalloys activity data have been reconstructed from 2002 based on statistical information (ISTAT, several years [b]), personal communication (Italghisa, 2011) and on the basis of production data communicated to E-PRTR register and

to ETS from the only plant of ferroalloys in Italy. The comparison between E-PRTR and ETS data revealed some differences: further investigation led to direct contact with the plant and to rectifying the incorrect activity data.

The average emission factor has been calculated according to the IPCC Guidelines (IPCC, 2006) taking into consideration the different types of ferroalloys produced. The splitting up of national production in different types of ferroalloys was obtained from U.S. Geological Survey until 2001 (USGS, several years). Since 2002 only one plant of ferroalloys is in Italy and different types of production are reconstructed based on information listed above. This information is reported in Table 4.18.

Table 4.18 Splitting up of ferroalloys national production and IPCC 2006 emission factors

	1990	1995	2000	2005	2010	2011	2012	2013	2014	2015-2024	IPCC 2006 EF
	<i>Ferroalloy (%)</i>										kg/t
FeCr	0.30	0.26	-	-	-	-	-	-	-	-	1,300
FeMn	0.24	0.10	0.28	0.50	0.40	0.60	0.36	0.29	0.61	-	1,500
FeSi	0.02	-	-	-	-	-	-	-	-	-	4,800
SiMn	0.32	0.53	0.62	0.50	0.60	0.40	0.64	0.71	0.39	-	1,400
Si-Metal	0.06	0.05	0.03	-	-	-	-	-	-	-	5,000
Other	0.07	0.06	0.07	-	-	-	-	-	-	-	5,000

Implied emission factor for ferroalloys has been reduced from 1.90 to 1.46 t CO₂/t ferroalloys production, from 1990 to 2014 as a consequence of the sharp reduction in ferroalloys production, which is characterized by high emission factors (ferro-silicon and silicon-metal alloys). The simultaneous reduction of total production (from about 200 kt to 16 kt) has resulted in CO₂ emissions decreasing from 395 Kt in 1990 to 24 Kt in 2014. Since 2015 the plant has not been working.

Primary aluminum production

PFC emissions from aluminum production have been estimated using both IPCC tier 1 and tier 2 methodologies. The tier 1 has been used to calculate PFC emissions from 1990 to 1999, while tier 2 has been used since 2000; the use of different methods throughout the period is due to the lack of detailed data for the years before 2000.

Despite repeated efforts by the inventory team to obtain historical operating data for 1990–1999, the information remains unavailable. Alcoa cannot supply this data because the plants were managed by a different company that no longer exists. Therefore, the use of both tiers has been adopted, as supported by previous review processes, which confirmed the transparency, accuracy, and conservativeness of this approach.

PFC emissions, specifically CF₄ and C₂F₆, have been calculated on the basis of information provided by national statistics (ENIRISORSE, several years; ASSOMET, several years) and the national primary aluminum producer (ALCOA, several years), with reference to the documents drawn up by the International Aluminium Institute (IAI, 2003; IAI 2006) and the IPCC Guidelines (IPCC, 2006).

Tier 1 method has been used to calculate PFC emissions related to the entire period 1990-1999. The emission factors for CF₄ and C₂F₆ were provided by the main national producer (ALCOA, 2004) based on the IAI document (IAI, 2003).

The tier 1 method used by ALCOA is based on the IAI methodology, which collected anode effect data from 1990 up to 2000, accounting also for reductions in specific emissions for all technology categories (specific factors for Point Fed Prebake cells have been considered to estimate emissions).

In 1990 at the five production sites the following technologies were implemented:

- Fusina: Point Fed Prebake (16% of the cells) and Side Work Prebake (84% of the cells);
- Portovesme: Point Fed Prebake (84% of the cells) and Side Work Prebake (16% of the cells);
- Bolzano: Vertical Stud Soderberg (100% of the cells)
- Fusina 2 and Porto Marghera: Side Work Prebake (100% of the cells).

The EFs for PFCs were then calculated by ALCOA as weighted arithmetic mean values of EFs for the different technologies (IAI, 2003), the weights representing the implemented technologies.

In the following tables (Tables 4.19, 4.20) the emission factors and the default parameters used are reported; site specific values are confidential, but they have been supplied to the inventory team and considered in the estimation process.

Table 4.19 Historical default Tetrafluoromethane (CF₄) emission values by reduction technology type (IAI, 2003)

	Technology specific emissions (kg CF ₄ / t Al)		
	1990 - 1993	1994 - 1997	1998 - 1999
Point Fed Prebake	0.3	0.1	0.08
Side Work Prebake	1.4	1.4	1.4
Vertical Stud Soderberg	0.6	0.5	0.4

Table 4.20 Multiplier factor for calculation of Hexafluoroethane (C₂F₆) by technology type (IAI, 2003)

Technology multiplier factor	
Center Work Prebake	0.17
Point Fed Prebake	0.17
Side Work Prebake	0.24
Vertical Stud Soderberg	0.06

PFC emissions from the year 2000 are estimated by the IPCC Tier 2 method, based on default technology specific slope factors and facility specific anode effect minutes. Site-specific values (CF₄ and C₂F₆ emissions) and default coefficients (slope coefficients for CF₄ and C₂F₆) were provided by the main national producer (ALCOA, several years). Moreover, from 2005 certificated emission values and parameters, including anode effects, have been communicated under EU-ETS (ALCOA, 2010). In Table 4.21 slope coefficients used for CF₄ and C₂F₆ are reported. ALCOA uses these values suggested by International Aluminium Institute (IAI, 2006), in accordance with the coefficients reported in the IPCC 2006 Guidelines (IPCC, 2006).

Table 4.21 CF₄ and C₂F₆ Slope Coefficients (IAI, 2006)

Type of Cell	CF ₄	C ₂ F ₆
	Slope Factor (kg PFC/tAl/AE-minutes/cell day)	
Center Work Prebake	0.143	0.0173

Anode Effects (minutes/cell day)

	2000	2005	2006	2007	2008	2009	2010	2011	2012
Primary Aluminum Plant	0.96	0.87	0.74	1.00	0.55	0.81	0.60	0.53	0.31

CO₂ emissions from aluminum production have been also estimated based on activity data provided by industrial association (ENIRISORSE, several years; ASSOMET, several years) and default emission factor reported by industry (ALCOA, 2004) and by the IPCC Guidelines (IPCC, 1997) which refer to the prebaked anode process.

Emission factor has been assumed equal to 1.55 t CO₂/t primary aluminum production for the years 1990-2001, based on data provided by the producer for 2002; this value is also consistent with the emission factors contained in the IPCC Guidelines and in the Aluminium Sector Greenhouse Gas Protocol. Since 2002

the emission factor has been calculated on account of information from the relevant plant supplied to the national EPER/EPTR registry (emissions and productions). Therefore, thanks to the availability of this additional information, CO₂ emission estimations have been carried out by the operator since 2002 according to the criteria defined by the International Aluminium Institute (IAI) and are given by the following three components:

- Electrolysis Emissions from Prebake Anode
- Pitch Volatile Matter Oxidation from Pitch Coking
- Bake Furnace Packing Material

This detailed information is not available for the period 1990–2001, despite repeated efforts by the inventory team. As a result, the tier 2 approach cannot be applied to those years, and tier 1 must be used instead. The combined tier 1 + tier 2 approach therefore ensures both the quality of the estimates and the consistency of the CO₂ emissions time series, given the available data.

In the following tables (Tables 4.22, 4.23), the emission factors and the default parameters used are reported; site specific values are confidential, but they have been supplied to the inventory team.

Table 4.22 Coefficients used for estimation of CO₂ from aluminium production process with the Tier 2 methodology by plant

	Sulphur Weight %	Baked Anode Properties Ash Weight %	Impurities Weight %
Portovesme	ssv*	Ssv	DV** = 0.4
Fusina	DV = 1.6	Ssv	DV = 0.4

* site specific value

** default value

Table 4.23 Coefficients used for estimation of CO₂ from aluminium production process with the Tier 2 methodology by plant

	Pitch content in green anodes Weight %	Hydrogen content in pitch Weight %	Recovered tar kg/t BAP	Packing coke consumption t Pcc/ t BAP	Sulphur content of packing coke Weight %	Ash content of packing coke Weight %
Portovesme	ssv*	ssv	DV** = 0	DV = 0.05	DV = 3	DV = 5
Fusina	ssv	DV = 4.45	DV = 0	DV = 0.05	DV = 3	DV = 5

* site specific value

** default value

Magnesium Production

For SF₆ used in magnesium foundries, according to the IPCC Guidelines (IPCC, 2006), emissions are estimated from consumption data made available by the company (Magnesium Components Verrès, several years), assuming that all SF₆ used is emitted. In 2007, SF₆ has been used partially, replaced in November by HFC125, due to the enforcement of fluorinated gases regulation (EC, 2006). This regulation allows for the use of SF₆ in annual amounts less than 850 kg starting from 1 January 2008; for this reason, SF₆ was still reported together with HFC 125 emissions for the years 2008 and 2009 while for 2010 only HFC125 was reported. Since 2011 HFC134a has replaced HFC125.

Zinc production

Until the 2016 submission, emissions from lead and zinc production have been reported only in 1.A.2 because of the lack of information about process emissions. Since 2013, ETS data contain info about the sole integrated plant in Italy but, as it is an integrated plant, it is not possible to distinguish zinc from lead emissions, so in CRT tables IE is reported for category 2.C.5 Lead production and CO₂ emissions are reported in 2.C.6 Zinc production. Starting from ETS activity and CO₂ emissions data for the period 2013 –

2017, it has been possible to reconstruct the time series on the basis of different sources as this plant already submitted its data to INES/E-PRTR register since 2002 (but without the distinction between combustion and process) and on the basis of activity data and info on the technological evolution provided by industrial association (ENIRISORSE, several years; ASSOMET, several years). In the period 1990 – 2024 activity data and CO₂ emissions show a decreasing trend, in particular emissions decrease from 500 Mg in 1990 to 152 Mg in 2024 and the IEF change from 1.562 to 2.455 kgCO₂/Mg of Pb and Zn, with abnormal growth in the last year due to a sudden drop in production.

4.4.3 Uncertainty and time-series consistency

The combined uncertainty in PFC emissions from primary aluminum production is estimated to be about 20% in annual emissions, 3% and 20% concerning respectively activity data and emission factors; the uncertainty for HFC emissions from magnesium foundries is estimated to be about 20%, 3% for activity data and 20% for emission factors. The uncertainty in emissions from iron and steel, ferroalloys and zinc production is estimated to be 10.4%.

In Table 4.24 emission trends of CO₂, CH₄ and F-gases from metal production are reported. The decreasing CO₂ emissions from iron and steel category is driven by the use of lime instead of limestone and dolomite to remove impurities in pig iron and steel and by the production level while CO₂ emissions from aluminum, zinc and ferroalloys are driven mainly by the production levels.

In Table 4.25 the emission trend of F-gases per compound from metal production is given. PFC emissions from aluminum production decreased because of the closure of three old plants in 1991 and 1992 and the update of technology for the two plants still operating. The decreasing of SF₆ consumption in the magnesium foundry from 2003 is due to the abandonment of recycling plant and the optimization of mixing parameters.

Table 4.24 CO₂, CH₄ and F-gas emissions from metal production, 1990 – 2024 (kt)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂ (kt)											
Iron and steel	3,124	2,897	1,280	1,656	1,343	1,327	1,215	1,506	1,392	1,324	1,232
Aluminium production	359	276	295	299	250	-	-	-	-	-	-
Ferroalloys	395	230	229	89	77	-	-	-	-	-	-
Zinc production	500	500	501	375	164	236	214	232	197	161	152
CH₄ (kt)											
Pig iron	2.13	2.10	2.02	2.06	1.54	0.91	0.61	0.74	0.61	0.54	0.36
Steel	0.58	0.60	0.60	0.67	0.63	0.62	0.61	0.73	0.65	0.64	0.64
PFC (kt CO₂ eq.)											
Aluminium production	1,778.47	314.96	207.58	190.74	89.19	-	-	-	-	-	-
SF₆ (kt)											
Magnesium foundries	-	-	0.0072	0.0035	0.0007	-	-	-	-	-	-
HFC125 - (kt)											
Magnesium foundries	-	-	-	-	0.0006	-	-	-	-	-	-
HFC134a - (kt)											
Magnesium foundries	-	-	-	-	-	0.0071	0.0038	0.0034	0.0027	0.0031	0.0030

Table 4.25 F-gas emissions per compound from metal production in kt CO₂ equivalent, 1990 – 2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	kt CO ₂ eq.										
CF ₄ (PFC-14)	1,315.02	240.52	172.61	158.65	74.18	-	-	-	-	-	-
C ₂ F ₆ (PFC-16)	463.45	74.45	34.96	32.10	15.01	-	-	-	-	-	-
<i>Total PFC emissions from aluminium production</i>	<i>1,778.47</i>	<i>314.96</i>	<i>207.58</i>	<i>190.74</i>	<i>89.19</i>	-	-	-	-	-	-
SF ₆ emissions from magnesium foundries	-	-	169.20	83.28	17.18	-	-	-	-	-	-
HFC-125 emissions from magnesium foundries	-	-	-	-	1.92	-	-	-	-	-	-
HFC-134a emissions from magnesium foundries	-	-	-	-	-	9.25	4.88	4.37	3.47	4.06	3.90
Total F-gas emissions from metal production	1,778.47	314.96	376.78	274.03	108.28	9.25	4.88	4.37	3.47	4.06	3.90

A more robust tier 1 comparison has been evaluated to strengthen the conservativeness of combined tier 1 and tier 2 approaches (detailed information are reported in previous submissions).

4.4.4 Source-specific QA/QC and verification

Emissions from the sector are checked with the relevant process operators. In this framework, primary aluminum production supplied by national statistics (ENIRISORSE, several years; ASSOMET, several years) and the only national producer ALCOA (ALCOA, several years), in addition to data reported in a site-specific study (Sotacarbo, 2004), have been checked. Moreover, emissions from magnesium foundries are annually compared with those reported in the national EPER/E-PRTR registry while for the iron and steel sector emissions reported in the national EPER/E-PRTR registry and for the Emissions Trading Scheme are compared and checked. Emissions from primary aluminum production have been also checked with data reported under EU-ETS.

4.4.5 Source-specific recalculations

No recalculations occur.

4.4.6 Source-specific planned improvements

The analysis of data reported in the IPPC permits of the integrated plant for zinc and lead production should allow a better allocation between zinc and lead emissions.

4.5 Non-energy products from fuels and solvent use (2D)

4.5.1 Source category description

The sub-sector comprises the following sources: lubricant use, paraffin wax, and other categories which include the use of urea, asphalt roofing and paving with asphalt and solvent use. Following different UNFCCC review recommendations, Italy reports CO₂ emissions from the oxidation of NMVOCs from solvent use not in the relevant categories but, separately and all together, as indirect CO₂ emissions. The description on the methodology to estimate indirect CO₂ emissions is included in this chapter under the section 'Solvent use and indirect CO₂ emissions'.

Lubricant use

Lubricants are mostly used in industrial and transportation applications. Lubricants are produced either at refineries through separation from crude oil or at petrochemical facilities. Under this category, emissions originated by lubricant use in industry and white lubricants and lubricants used for insulating purposes have been considered, CO₂ and NMVOC emissions have been estimated for the whole time series. Emissions from lubricant use in vehicles have been accounted for in the Energy Sector.

Paraffin wax

Paraffin waxes are separated from crude oil during the production of light (distillate) lubricating oils. Paraffin waxes are categorised by oil content and the amount of refinement. About 60-70% of the total amount of paraffin waxes produced in the EU area is used to manufacture candles. Nowadays about 95% of candles are paraffin wax candles; 3% are stearic candles and the remaining 2% is made of beeswax. Slack oils could enter the manufacturing process thus potentially resulting in emissions of SO_x and PAH.

Use of urea

Urea can be used in Selective Catalyst Reduction (SCR) systems to reduce NO_x emissions from combustion. SCR systems are generally applied to engines (vehicles) and to industrial combustion (e.g. Power Plants). CO₂ emissions originating from the use of urea in SCR systems have been estimated and reported in this sub-sector.

Asphalt roofing and road paving with asphalt

In 2024 in Italy 17 facilities manufactured bitumen, binders and bituminous emulsions, 11 facilities have been producing bitumen roofing membranes and about 80 facilities operate in the production and laying of asphalt mix products for road paving. SITEB, the Italian asphalt and road association is the relevant source of information for these two source categories. NMVOC emissions have been estimated for these two source categories throughout the whole time series.

Solvent use and indirect CO₂ emissions

Following different UNFCCC review recommendations, Italy reports CO₂ emissions from the oxidation of NMVOCs from solvent use not in the relevant categories but, separately and all together, as indirect CO₂ emissions. Indirect CO₂ emissions have been identified as a key source at level assessment with Approach 2 without and with LULUCF; in 1990 it was a key category at level assessment.

The use of solvents manufactured using fossil fuels as feedstocks can lead to evaporative emissions of various NMVOC and CO₂ emissions, after oxidation of NMVOC in the atmosphere.

Methodologies for estimating NMVOC emissions can be found in the EMEP/EEA air pollutant emission inventory guidebook (EMEP/EEA, 2023). Also, some indications on the subcategories to include in the 'solvent use' category are reported in the 2006 IPCC guidelines (IPCC, 2006), which are the following: solvent use in paint application, degreasing and dry cleaning, manufacture and processing of chemical products, other solvent use, such as printing industry, glues application, use of domestic products.

4.5.2 Methodological issues

Lubricant use

The use of lubricants in industrial engines is primarily for their lubricating properties and associated emissions are therefore considered as non-combustion emissions to be reported in the IPPU Sector. NMVOC and CO₂ emissions are reported for this category. CO₂ emissions for the whole time series are calculated based on a Tier 1 approach considering the average Lower Heating Value (LHV) of lubricants, the average ODU factor and the average carbon content of lubricants (Equation 5.2 IPCC Guidelines 2006):

$$CO_2 \text{ Emissions} = LC \cdot CC_{Lubricant} \cdot ODU_{Lubricant} \cdot 44 / 12$$

where

LC= lubricant consumption

CC_{lubricant}= carbon content

ODU_{lubricant}= oxidation factor

44/12= mass ratio CO₂/C

Statistics related to the total amount of lubricants consumed in Italy are officially provided by MASE every year in the Oil Bulletin (MASE, several years) but no details concerning different kind of lubricants are available thus allowing us only for a Tier 1 approach; LHV, Carbon Content and ODU factors used are the default values included in the IPCC 2006 Guidelines are taken. The activity data for this subcategory is the total consumption of lubricants minus the amount of lubricants used in 2-stroke engines (which is derived from reversing COPERT equation to estimate CO₂ emissions in 2-stroke engines). Emissions from the use of lubricants in 2-stroke engines have been accounted for in the Energy Sector.

NM VOC emissions for the whole time series have been estimated, based on the total lubricants' consumption and a NM VOC EF equals to 28 kg NM VOC/tons of lubricant (EMEP/EEA, 2013). The whole time series for NM VOC emissions has been revised in the present submission as a consequence of the review of the activity data time series.

Paraffin wax

In Italy paraffin waxes are mostly used in the manufacture of candles, although a number of different applications (e.g. food production and many others) could have paraffin waxes as an input. Emissions from the use of waxes derive primarily when the waxes or derivatives of paraffins are combusted during use (e.g., candles). No other use of paraffin wax in products implying wax combustion during the product use is known in Italy. In order to estimate CO₂ emissions for the whole time series it has been assumed that 65% of total amount of paraffin wax is destined to the manufacture of candles on account of information provided by the industrial association (Assocandele, 2015). Total paraffin wax consumption is included in the Oil Bulletin provided by the MASE and publicly available on <https://sisen.mase.gov.it/dgsaie/bollettino-petroliifero>.

Default values for carbon content of paraffin wax as well as ODU factor and LHV have been assumed (2006 IPCC Guidelines) and applied to the activity data according to a Tier 1 approach as in Equation 5.4 of the 2006 IPCC Guidelines:

$$CO_2 \text{ Emissions} = PW \cdot CC_{Wax} \cdot ODU_{Wax} \cdot 44 / 12$$

where:

CO₂ Emissions = CO₂ emissions from waxes, tonne CO₂

PW = total wax consumption, TJ

CC_{Wax} = carbon content of paraffin wax (default), tonne C/TJ (= kg C/GJ)

ODU_{Wax} = ODU factor for paraffin wax, fraction

44/12 = mass ratio of CO₂/C

Use of urea

Emissions of CO₂ originated by the use of urea in SCR systems in engines and Power plants have been estimated and reported in this sub-sector.

Concerning vehicles, SCR systems were introduced in Italy in 2006 so CO₂ emissions related to SCR systems can be traced back in the time series up to 2006. The amount of urea and CO₂ emitted using urea can be estimated by COPERT, which is the model used by Italy to estimate emissions for road transport. For further details, see paragraph 3.5.2 in the energy chapter.

Concerning power plants, the amount of urea used in SCR systems has been reported by operators under the Italian ETS together with CO₂ emissions.

Asphalt roofing and road paving

NMVOC emissions from the manufacturing of asphalt roofing materials have been estimated based on the total surface of bitumen roofing membranes (Federchimica, several years; Siteb, several years) and default emission factors (EMEP/EEA, 2009).

NMVOC emissions from road paving operations have been estimated based on the amount of asphalt mix produced for each year (ISTAT, several years; Siteb, several years) and the emission factors are set constant along the whole time series and taken from the EMEP/EEA Guidebook.

Solvent use and indirect CO₂ emissions

Emissions of NMVOC from solvent use have been estimated according to the methodology reported in the EMEP/EEA guidebook, applying both national and international emission factors (EMEP/EEA, 2023). Country specific emission factors provided by several accredited sources have been used extensively, together with data from the national EPER/EPRT Registry; in particular, for paint applications (Offredi P., several years; solvent use in dry cleaning (ENEA/USLRMA, 1995), solvent use in textile finishing and in the tanning industries (UNIC, several years). Basic information from industry on percentage reduction of solvent content in paints and other products has been applied to EMEP/EEA emission factors to evaluate the reduction in emissions during the period considered.

Emissions from domestic solvent use have been calculated using a detailed methodology, based on VOC content per type of consumer product.

As regards household and car care products, information on VOC content and activity data has been supplied by the Sectoral Association of the Italian Federation of the Chemical Industry (Assocasa, several years) and by the Italian Association of Aerosol Producers (AIA, several years [a] and [b]). As regards cosmetics and toiletries, basic data have been supplied by the Italian Association of Aerosol Producers too (AIA, several years [a] and [b]) and by the national Institute of Statistics and industrial associations (ISTAT, several years; UNIPRO, several years); emission factors time series have been reconstructed on the basis of the information provided by the European Commission (EC, 2002).

The conversion of NMVOC emissions into CO₂ emissions has been carried out considering a fossil carbon content equal to 65% as indicated in the 2006 IPCC Guidelines (chapter 5.5.4).

4.5.3 Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from non-energy products from fuels and solvent use is estimated equal to 58.3% due to an uncertainty of 30% and 50% in activity data and emission factors, respectively. In 2024, CO₂ emissions derive mainly from the subcategory 'Lubricants use' for almost 64% of the sectoral emissions. Table 4.26 shows CO₂ emission trends.

Table 4.26 Trend in CO₂ emissions from the non-energy products from fuels and solvent use category (kt)

Gas/subcategory	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
2D. non-energy products from fuels. Other	370	323	332	303.4	270.3	275.4	269.1	304.6	287.2	306.9	312.9
2D1. Lubricant use	351	303	308.5	287.2	217	211	187.3	208.2	182.4	203.1	200.9
2D2. Paraffin wax use	19	20	21.1	13.8	13	14.5	7.2	9.7	7.2	3.4	1.2
2D3. Other	-	-	2.4	2.3	40.2	49.4	74.6	86.7	97.5	100.5	110.8
2D3a. Urea (emissions abatement in engines)	-	-	-	-	28.5	42	64	78.4	87.7	90.4	100.4
D3b. Urea (emissions abatement in power plants)	-	-	2.4	2.3	11.7	7.3	10.6	8.3	9.8	10.1	10.4
D3c. Road paving	-	-	-	-	-	-	-	-	-	-	-
2D3d. Asphalt roofing	-	-	-	-	-	-	-	-	-	-	-
Indirect CO₂ emissions- Solvent	1,391	1,296	1,173	1,155	976	815	876	858	790	843	871

Indirect CO₂ emissions decreased by 37.4% from 1990 to 2024. This category is a key category when applying Approach 2 at level assessment (with and without LULUCF). The uncertainty of the category is equal to 58.3%. The decrease observed in emission levels of indirect CO₂ emissions from solvent use from 1990 to 2024, is to be attributed to the reduction in emissions from solvent use, mainly for the reduction in paint application, in other use of solvent and in degreasing and dry cleaning activities; specifically, the reduction of emissions from paint application for domestic use, which drop by about 54.4% from 1990, is due to the implementation of Italian Legislative Decree 161/2006. Other European directives applies to the solvent use category, which represents the main source of NMVOC emissions at national level (46.9% of the total NMVOC in 2024); for instance, the European Directives (EC, 1999; EC, 2004) regarding NMVOC emission reduction in paint application entered into force, in Italy, in January 2004 and in March 2006, establishing a reduction of the solvent content in products.

4.5.4 Source-specific QA/QC and verification

Emissions from the category are checked with the relevant data providers and industrial associations. Data production and consumption time series for some activities (paint application in constructions and buildings, polyester processing, polyurethane processing, pharmaceutical products, paints manufacturing, glues manufacturing, textile finishing, leather tanning, fat edible and non-edible oil extraction, application of glues and adhesives) are checked with data acquired by the National Statistics Institute (ISTAT, several years), the Sectoral Association of the Italian Federation of the Chemical Industry (AVISA, several years) and the Food and Agriculture Organization of the United Nations (FAO, several years). For specific categories, emission factors and emissions are also shared with the relevant industrial associations; this is particularly the case of paint application for wood, some chemical processes and anaesthesia and aerosol cans. For paint application, data communicated from the industries in the framework of the EU Directive 2004/42, implemented by the Italian Legislative Decree 161/2006, on the limitation of emissions of volatile organic compounds due to the use of organic solvents in certain paints and varnishes and vehicle refinishing products have been used as a verification of emission estimates. These data refer to the composition of the total amount of paints and varnishes (water and solvent contents) in different subcategories for interior and exterior use and the total amount of products used for vehicle refinishing and they are available from the year 2007.

4.5.5 Source-specific recalculations

Recalculation occurred for CO₂ emissions from Lubricant use (2.D.1) due to the use of updated activity data time series and also in 2.D.3. As for CO₂ emissions from lubricants use (2.D.1) and from the use of urea in the engines (2.D.3.a), recalculations occurred from 2005 and 2006, respectively, due to the update of the data resulting from COPERT model; recalculations occurred also for Indirect CO₂ along the whole timeseries because of the update of the activity data, mainly in the domestic solvent use category. Recalculations are shown in Table 4.27.

Table 4.27 Recalculation of CO₂ emissions from 2.D.1 lubricants use; from the use of urea in SCR systems (2.D.3.a) (%) and recalculation of indirect CO₂ emissions (%)

Year	2D.1 Lubricants- CO ₂	2D.3.a UREA in SCR systems (vehicles) - CO ₂	2.D.3.e Solvent application (domestic solvent use) -indirect CO ₂
1990	-	-	0.0003
1991	-	-	-0.0003
1992	-	-	0.00002
1993	-	-	-0.0003
1994	-	-	-0.0002
1995	-	-	0.0002
1996	-	-	-0.0002
1997	-	-	-0.0002
1998	-	-	-0.0001
1999	-	-	0.00003
2000	-	-	1.15
2001	-	-	1.13
2002	-	-	1.1
2003	-	-	1.07
2004	-	-	1.04
2005	0.0001	-	1.01
2006	-0.0001	-	0.96
2007	-0.0001	-	0.95
2008	-0.0003	-	1.26
2009	0.00003	-	1.83
2010	0.0002	-	1.92
2011	-0.0002	-	1.59
2012	-0.0001	-	1.68
2013	-0.0002	-	1.82
2014	-0.0004	-	1.79
2015	-0.18	-4.36	1.77
2016	-0.0002	-	2.03
2017	-0.0004	-	3.1
2018	-0.0002	-	1.74
2019	0.09	1.63	1.19
2020	0.0002	-	1.51
2021	0.09	-0.0007	2.04
2022	-0.33	-5.65	2.11
2023	-0.63	-6.44	1.35

4.5.6 Source-specific planned improvements

No further improvements are planned.

4.6 Electronics Industry (2E)

4.6.1 Source category description

Fluorocarbons emissions from this sub-sector are from semiconductor manufacturing industry (2.E.1). Actually, in Italy, there are three national plants of semiconductor manufacturing, owned by two company, ST Microelectronics (in the past purchased for a couple of years by Numonyx) and LFoundry (ex Micron Technology): in particular, ST Microelectronic is active from 1995, while LFoundry from 1998. The semiconductor manufacturing companies supply yearly consumption and emission data for each plant (ST Microelectronics, several years; Micron, several years; Numonyx, several years; LFoundry, several years).

F-gas emissions from semiconductor manufacturing are estimated using the Tier 2a methodology of the new 2006 IPCC Guidelines (IPCC, 2006).

Fluorinated compounds emissions from heat transfer fluids are also estimated. Since 2017 the industry has started to communicate the consumption of the substances used in service equipment and consequently emissions have been estimated equal to consumptions (ST Microelectronic, several years; LFoundry, several years). For the previous years, industry has communicated that no data is available and explained that consumptions of these substances are of course linked to production but not dependent on it (i.e. if production of semiconductors occurs, the use of this service equipment occurs, but the refrigerant consumption is random). Because of previous considerations, emissions have been estimated constant for the whole time series.

As concerns photovoltaic (PV) manufacturing, currently in Italy there is no production of PV cells, but only assembly. Before 2011, PV cells production occurred but no fluorinated compounds have been used for the process (Lux, 2015; Solsonica, 2015). Finally, no thin-film-transistor flat panel display (TFT-FPD) production occurs in Italy (Linde Gas, 2015). The share of F-gas emissions from the electronics industry in the national total of F-gases accounts for 3.2% in 2024.

4.6.2 Methodological issues

F-gas emissions from semiconductor manufacturing are estimated using the Tier 2a methodology of the 2006 IPCC Guidelines (IPCC, 2006). As reported in the Guidelines, total emissions are equal to the sum of emissions from the gas FC_i used in the production process plus the emissions of by-product calculated with equation 6.3/6.4/6.5/6.6.

Companies involved in the semiconductor manufacturing provide yearly data on consumption and emissions (ST Microelectronics, several years; Micron, several years; Numonyx, several years; LFoundry, several years), calculated based on the following equation, accepted by the World Semiconductor Council (WSC). The formula gathers the IPCC Guidelines equations (combining equations 6.2/6.3/6.4/6.5/6.6 of the Guidelines) and includes both direct and by-product emissions):

$$\text{Emissions for PFC}_i = \text{PFC}_i \cdot (1-h) [(1-C_i)(1-A_i) \cdot \text{GWP}_i + B_i \cdot \text{GWP}_{(\text{byproduct})} \cdot (1-A_{(\text{byproduct})})]$$

where:

h = fraction of gas_i remaining in container (heel)

PFC_i = purchases of gas_i = kg_{Si}

kg_{Si} = mass of gas_i purchased

GWP_i = 100 yr global warming potential of gas_i
 C_i = average utilization factor of gas_i (average for all etch and CVD processes) = $1 - EF_i$
 EF_i = average emission factor of gas_i (average for all etch and CVD processes)
 B_i = mass of CF₄ created per unit mass of PFC_i transformed
 A_i = fraction of PFC_i destroyed by abatement = $a_{ij} * V_a$

By product formation

A_{CF4} = fraction of PFC_i converted to CF₄ and destroyed by abatement = $a_{CF4} * V_a$
 a_{ij} = average destruction efficiency of abatement tool_j for gas_i
 a_{CF4} = average destruction efficiency of abatement tool_j for CF₄
 V_a = fraction of gas_i that is fed into the abatement tools
 A_{CF4} = fraction of PFC_i converted to CF₄ and destroyed by abatement = $a_{CF4} * V_a$
 a_{ij} = average destruction efficiency of abatement tool_j for gas_i
 a_{CF4} = average destruction efficiency of abatement tool_j for CF₄
 A_{C2F6} = fraction of PFC_i that is converted to C₂F₆ and destroyed by abatement = $a_{C2F6} * V_a$
 a_{C2F6} = average destruction efficiency of abatement tool_j for C₂F₆
 A_{C3F8} = fraction of PFC_i that is converted to C₃F₈ and destroyed by abatement = $a_{C3F8} * V_a$
 a_{C3F8} = average destruction efficiency of abatement tool_j for C₃F₈
 V_a = fraction of gas_i that is fed into the abatement tools

Emissions are calculated for the following fluorinated gases: HFC 23, HFC 32, HFC 134a, C₂F₆, CF₄, C₃F₈, C₄F₈, SF₆ and NF₃. From 2012, according to the World Semiconductor Council (WSC), data on CH₂F₂, C₄F₆, C₅F₈ are gathered. Since 2000, emissions are calculated considering the contribution of abatement systems.

ST Microelectronics provided emissions for each gas (CF₄, C₂F₆, HFC 23, C₂F₆, C₃F₈, C₄F₈, SF₆ and NF₃) for the year 1995 and from 2001 onwards. For the years 1996-2000 the company was not able to provide detailed data but only aggregated total emissions confirming that they occurred for all the gases and emissions of each gas have been estimated proportionally considering their distribution in 1995 and 2001. Moreover, based on the 2001 emission factors (emission gas_i/consumption gas_i), consumption data have been extrapolated for the missing years. This year, ST Microelectronics also provided emissions for N₂O relating to 2023 and 2024. Nitrous oxide, in fact, can be used as an input gas during TFD processes and for other N₂O-using manufacturing processes such as diffusion and dry removal of photoresist.

For what concern Heat Transfer Fluids, during the manufacture of semiconductor devices, HTFs serve as coolants in chillers, removing excess heat during many manufacturing processes. During semiconductor device testing, containers of HTFs are cooled or heated to a desired temperature into which the devices are immersed to test their integrity. In addition, when testing the function of devices, HTFs are used to remove the heat the devices generate while being tested. HTFs are also used to attach semiconductor devices to circuit boards via solder, which may be melted by the vapor of an HTF heated to its boiling point. HTFs may also serve to cool semiconductor devices and other devices or systems that generate high heat during operation (EPA, 2006). The semiconductor industry started to collect data and communicated from the year 2017 the annual recharge of these coolants. Emissions have been estimated in terms of tonnes of CO₂ equivalent of unspecified mix of HFCs and PFCs (ST Microelectronic, several years; LFoundry, several years).

4.6.3 Uncertainty and time-series consistency

The combined uncertainty in F-gas emissions for PFC, HFC, SF₆, NF₃ and N₂O emissions from semiconductor manufacturing, including Heat Transfer Fluids, is estimated to be about 20.6% in annual emissions, 5% and

20% concerning respectively activity data and emission factors. In Table 4.28 emissions from semiconductor manufacturing are reported

Table 4.28 Fluorocarbon and N₂O emissions from semiconductor industry (kt CO₂ eq.), 1990–2024

GAS	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 23	NO	6.07	8.65	7.19	10.73	9.36	7.71	7.69	8.65	6.89	5.34
HFC 32	NO	NO	NO	NO	NO	0.11	0.06	0.07	0.07	0.13	0.1
HFC 134a	NO	NO	0.05	NO	NO	NO	NO	NO	NO	NO	NO
HFC 41	NO	NO	NO	NO	NO	NO	NO	NO	NO	0.000	0.000
CF ₄	NO	65.27	131.86	84.89	66.52	94.97	91.99	93.13	95.77	67.21	62.74
C ₂ F ₆	NO	17.08	121.08	81.22	27.48	21.44	22.23	23.87	23.13	19.56	12.68
C ₃ F ₈	NO	8.62	11.75	4.29	0.03	0.21	0.03	0.07	0.15	0.06	0.08
C ₄ F ₈	NO	10.01	1.51	10.02	26.54	19.81	9.82	17.04	23.78	18.21	12.97
C ₅ F ₈	NO	NO	NO	NO	NO	NO	NO	NO	0.01	0.00	0.00
SF ₆	NO	14.9	61.9	57.16	30.58	47.31	36.91	40.77	54.51	48.02	81.15
NF ₃	NO	76.57	13.26	33.38	20.17	28.42	16.24	15.23	19.50	19.74	25.71
N ₂ O	NO	NO	NO	NO	NO	NO	NO	NO	NO	0.86	2.57
Unspecified mix of HFCs and PFCs from Heat Transfer Fluids	NO	24.43	24.43	24.43	24.43	24.43	22.37	25.33	22.13	28.65	32.68
F-gas emissions (kt CO₂ eq.)	NO	222.95	374.50	302.58	206.47	246.06	207.35	223.19	247.70	208.47	233.46
N₂O emissions (kt CO₂ eq.)	NO	NO	NO	NO	NO	NO	NO	NO	NO	0.86	2.57

4.6.4 Source-specific QA/QC and verification

This source category is covered by the general QA/QC procedures. Where information is available, emissions from production and consumption of fluorinated gases have been checked with data reported to the national EPER/E-PRTR registry.

4.6.5 Source-specific recalculations

Minor recalculation occurred due to an update of data communicated.

4.6.6 Source-specific planned improvements

No further improvements are planned.

4.7 Fluorinated substitutes for ozone depleting substances (2F)

4.7.1 Source category description

The sub-sector “Emissions of fluorinated substitutes for ozone depleting substances” consists of the following sub-applications 2.F.1 – Emissions from Refrigeration and Air Conditioning; 2.F.2 – Emissions from Foam Blowing agents; 2.F.3 – Emissions from Fire Protection; 2.F.4 – Emissions from Aerosols.

For category 2.F.5 Solvents, there is no evidence that these emissions occur in Italy. Data collected, in the context of Article 19 of Regulation (EU) 517/2014, has been analyzed. Only one company has declared a small quantity of HFC preparation placed on Community market for the years 2008, 2009, 2010, 2011 and 2013 for solvents applications: since the substances declared, HFC-134a, R-507A and R-410A, are not usually used as solvents, the Company was contacted and replied that these data referred to RAC systems in Chemistry industry. Moreover, Assogastecnici, the Association of companies involved in the production and distribution of technical, special and medicinal gases also confirmed that they have no evidence of F-gases used as Solvents.

HFC emissions from Refrigeration and Air Conditioning and are key categories at level and trend assessment, both using Tier 1 and Tier 2, with and without LULUCF, in 2024. HFC emissions from Fire extinguishers are a key category at level and trend assessment using Tier 2 without LULUCF and at trend assessment using Tier 2 with LULUCF. HFC emissions from Foam blowing agents are a key category at trend assessment using Tier 2 with and without LULUCF.

The share of F-gas emissions of fluorinated substitutes for ozone depleting substances in the national total of F-gases (including the contribution of the unspecified mix of HFC and PFC) is 91.0% in 2024.

4.7.2 Methodological issues

The methods used to calculate F-gas emissions of fluorinated substitutes for ozone depleting substances are presented in Table 4.29.

Table 4.29 Sub-sources of F-gas emissions and calculation methods

Source category	Sub-application	Calculation method
Fluorinated Substitutes for ODS (2F)	Refrigeration and air conditioning equipment (2F1)	IPCC Tier 2a
	Foam blowing (2F2)	IPCC Tier 2a
	Fire extinguishers (2F3)	IPCC Tier 2a
	Aerosols/metered dose inhalers (2F4)	IPCC Tier 2a

Total emissions have been calculated as the sum of Manufacturing emissions, Use (Operation) emissions and Disposal emissions, as indicated by the IPCC equation 7.4 (2006 IPCC Guidelines, vol. 3, chapter 7). Moreover, for Refrigeration and Air Conditioning, the IPCC equation 7.10 (2006 IPCC Guidelines, vol. 3, chapter 7) has been applied, also considering emissions from containers, which comprise all emissions related to the refrigerant transfers from bulk containers down to small capacities, ready to be sold to the manufacturers or users. "Recovery" has been calculated as the "Amount remaining in products at decommissioning" minus "Disposal emissions".

The Legislative Decree n. 151/05 has implemented in Italy the EU Directive on Waste from Electric and Electronic Equipment (WEEE): according to this Decree when equipment is disposed of it is by law required to recover the remaining F-gas and either reuse or destroy it. At present, although the number of authorized centers for the treatment of WEEE is known, bulk data, not only F-gases, are not available and there are many small, authorized centers which do not have to report about their activities and also the major centers are not able to communicate data on single gas recovered. ISPRA is in contact with Erion, the largest Italian system of extended producer responsible for the management of waste associated with electronic products, regarding a study on stationary conditioning appliances end-of-life that is finalizing.

IPCC Tier 2a implies the availability of either number of applications/equipment using the individual gas, or the amounts of the gas used in the different sectors.

Based on the amount of individual gas produced in Italy until 2012 and the sectoral uses of the gas, emissions are estimated according to IPCC Tier 2a. The estimates are based on single gas consumptions data supplied, until 2013, by the only national refrigerants producer (Solvay, 1998; Solvay, 2006) and from

2014 by Assogastecnici who supplies data on F-gases consumption for different applications (Assogastecnici, several years). In the context of a survey, at a national level HFCs alternative substances with low GWP, natural refrigerants and alternative technologies led by ISPRA (ISPRA, 2018), collaboration with air conditioning and refrigeration national associations, major import/export F-gas companies, and the major experts of the sector, as well as companies, has been put in place. This collaboration with Assogastecnici led to an important achievement for F-gases consumption data on RACHP. Data are also supplied for Mobile Air Conditioning and medical Aerosols. For Domestic refrigeration and Stationary Air Conditioning sub-sector, emissions have been calculated based on appliances produced and placed on the market supplied by APPLiA (Association of Manufacturers of Domestic and Professional Appliances) and Assoclimate (Association of Manufacturers of Air Conditioning Systems). The applied methodology, although it is not a balance of chemical sales, uses specific emission factors for each consumption type. Since the methodology is based on the consumption of the F-gases in the different categories, the estimated consumption, where relevant, also includes the amount of fluid contained in the imported products, which contribute only to the estimates of lifetime emissions and not to manufacturing emissions (i.e. MAC, Stationary Air Conditioning).

In Table 4.30 a summary of refrigerants and chemicals used in Italy in each sub-application is reported. The ozone layer-depleting substances used in the early nineties were also reported, as well as the alternative substances to HFCs that entered the market following the European Directive 517/2014, now replaced by the new Regulation (EU) 2024/573. Compared to the previous submission, in 2024 a new gas, R-454B, entered the market and has been included in the communication for Stationary Air Conditioning.

Table 4.30 Refrigerants and other chemicals and propellants used in Italy over the period 1990 – 2024

Sub-application	1990-1995	1995-1998	1998-2010	2010-2014	2014-2024
Commercial Refrigeration (2.F.1.a)	R-11, R-12, R-22	R-11, R-12, R-22, R-404A, R-507A	R-22, R-404A, R-507A, R-134a	R-404A, R-507A, R-134a	R-404A, R-507A, R-134a, R-407F, R-407H, R-448A, R-449A, R-600a, R-290, R-744, R-422D, R-417A, R-438A, R-454C, R-455A,
Domestic Refrigeration (2.F.1.b)	R-12	R-12, R-134a	R-134a	R-134a	R-600a
Industrial Refrigeration (2.F.1.c)	R-12, R-22, R-717	R-717, R-23, R-404A, R-507A	R-717, R-23, R-404A, R-507A, R-134a	R-717, R-23, R-404A, R-507A, R-134a	R-717, R-23, R-508B, R-404A, R-507A, R-134a, R-407F, R-407H, R-448A, R-449A, R-422D, R-417A, R-438A, R-454C, R-455A, HCs; R-744
Transport Refrigeration (2.F.1.d)	R-11, R-12, R-22, R-502	R-11, R-12, R-22, R-502, R-404A, R-507A	R-22, R-404A, R-507A, R-134a	R-404A, R-507A, R-134a	R-404A, R-507A, R-134a, R-452A R-422D, R-417A, R-438A, R-454C, R-455A, R-744
Mobile Air Conditioning (2.F.1.e)	R-12, R-134a	R-134a	R-134a	R-134a	R-134a, R-1234yf

Sub-application	1990-1995	1995-1998	1998-2010	2010-2014	2014-2024
Stationary Air Conditioning (2.F.1.f)	R-12, R-22	R-12, R-22, R-410A, R-407C, R-134a	R-22, R-410A, R-407C, R-134a	R-410A, R-407C, R-134a	R-410A, R-407C, R-134a, R-32, R-513A, R-454C, R-515B, R-454B, R-290, R-1234ze-
Foams (2.F.2)	R-22, R-141b, R-142b	R-22, R-141b, R-142b	R-22, R-141b, R-142b, R-134a, R-245fa	R-134a, R-245fa	R-134a, R-245fa, HC, HFO
Fire Extinguishers (2.F.3)	Halon, HCFC mixture, NAF S-III, R-23, R-125, R-227ea	R-23, R-125, R-227ea	R-23, R-125, R-227ea	R-23, R-125, R-227ea	R-23, R-125, R-227ea, FK-5-1-12, NOVEC 1230
Aerosols (MDI) (2.F.4)	R-11, R-12, R-114	R-11, R-12, R-114	R-134a	R-134a	R-134a

Assogastecnici provided the percentage distribution of refrigerants consumptions by sector of use, from 2014 to 2024 (Assogastecnici, several years), as reported in Tables 4.31 and 4.32.

Table 4.31 Market distribution of HFCs and HFO (%), 2014 - 2021

Refrigerant HFC/HFO	Commercial and Industrial refrigeration	Stationary Air Conditioning	Mobile Air Conditioning	Transport refrigeration
R134a	20%	15%	60%	5%
R407C/F/H	20%	80%		
R410A		100%		
R32		100%		
R448A/R449A/R452A	85%			15%
YF/ZE		20%	80%	
R404A/R507	90%			10%
R422D/R417A/R-438A/R-454C/R-455A	100%			

Table 4.32 Market distribution of HFCs and HFO (%), 2022 - 2024

Refrigerant HFC/HFO	Commercial and Industrial refrigeration		Stationary Air Conditioning		Mobile Air Conditioning		Transport refrigeration	
	2022-2023	2024	2022-2023	2024	2022-2023	2024	2022-2023	2024
R134a	20%	25%	20%	25%	55%	50%	5%	
R407C/F/H	60%	20%	40%	80%				
R410A			100%	100%				
R32			100%	100%				
R448A/R449A/R452A	90%	80%		10%			10%	10%
ZE		10%	100%	90%				
YF					100%	100%		
R404A/R507	85%	90%					15%	10%

Refrigerant HFC/HFO	Commercial and Industrial refrigeration		Stationary Air Conditioning		Mobile Air Conditioning		Transport refrigeration	
	2022-2023	2024	2022-2023	2024	2022-2023	2024	2022-2023	2024
R-454C/R-515B/R454B			100%	100%				
R422D/R417A/R-438A/R-454C/ R-455A	100%	100%						

Assogastecnici also provides data splitted between *First Charge* consumption and *Service* consumption. Consumption data were subjected to a review process with the involvement of the Refrigeration and Air Conditioning national association, import/export F-gas companies, and experts of the RACHP sector that validated them, as well as continuous comparison with data from F-gases database. At present, these data represent the best available information of this source category, together with data provided directly from the automotive industry for the Mobile Air Conditioning sub-category, from Assoclima for Stationary Air Conditioning sub-category and from the pharmaceutical industry for Aerosols sub-category.

Finally, in Table 4.33, the sources of activity data and emissions factors for each sub-sector are summarized.

Table 4.33 Summary of activity data and emission factors sources

CRT Category	Category	Substance	Activity Data References	Emission Factors References
2.F.1.a	Commercial Refrigeration	HFC-134a R-404A R-507A R-407F R-407H R-448A R-449A	Solvay, Assogastecnici	Expert Judgement/IPCC
2.F.1.b	Domestic Refrigeration	HFC 134a	APPLiA	Expert Judgement/IPCC
2.F.1.c	Industrial Refrigeration	HFC-23 HFC-134a R-404A R-507A R-407F R-407H R-448A R-449A	Solvay, Assogastecnici	Expert Judgement/IPCC
2.F.1.d	Transport Refrigeration	HFC-134a R-404A R-507A R-452A	Solvay, Assogastecnici	Expert Judgement/IPCC
2.F.1.e	Mobile Air Conditioning	HFC-134a	Solvay, Assogastecnici FIAT, IVECO, UNRAE, CNH, ACI	Expert Judgement/IPCC
2.F.1.f	Stationary Air Conditioning	HFC-134a R-410A R-407C R-32 R-513A	Assoclima Solvay, Assogastecnici	Expert judgement
2.F.2.a	Foam Blowing	HFC-245fa HFC-134a	Solvay, Assogastecnici	IPCC
2.F.3	Fire Extinguishers	HFC-227ea	Clean Gas, Gastec Vesta, Expert Judgment Solvay, Assogastecnici	ASSURE

CRT Category	Category	Substance	Activity Data References	Emission Factors References
2.F.4	Metered Dose Inhalers	HFC-134a	Menarini, Chiesi, Sanofi Aventis, GSK, Lusofarmaco, Istituto De Angeli, BoehringerSolvay, Assogastecnici	Chiesi

4.7.3 Commercial refrigeration (2.F.1.a)

Commercial refrigeration includes emissions from those refrigeration systems and small appliances used in the food retail industry as well as professional refrigeration such as blast chiller estimations because no detailed information is available to split into a specific sub-category.

IPCC Tier 2a methodology has been applied, using activity data and resulting bank calculations derived and emission factors that reflect the unique emission characteristics related to various processes, products and equipment.

Refrigerants market: activity data and HFC used in Commercial refrigeration

The Tier 2a methodology of the 2006 IPCC Guidelines takes into account the phase out or the phase down of CFCs and HCFCs depending on the Montreal Protocol schedule and possible national or regional regulations, in order to establish the refrigerant choice for all applications. This has been done by Solvay (Solvay, 1998; Solvay, 2006) who produced fluorinated gases in Porto Marghera plant until 2012. The Company communicated production, import and export data of the substances, as well as the emissions of HFC, PFC and SF₆ from 2B9 category; moreover, in order to calibrate its productions based on market demand, Solvay, who was the only producer in Italy, supplied an annual estimates of total national refrigerants consumption, including also all other substances not included in their production but placed in the market.

The year in which HFCs entered the market to replace ozone layer-depleting substances is 1995. Consumption data of those specific refrigerants used in the refrigeration sector from 1995 to 2013 are derived from Solvay communications, whereas data from 2014 to 2024 have been supplied by Assogastecnici (Assogastecnici, several years).

In Table 4.34, annual consumption of refrigerants used overall in large systems and small appliances is reported.

Table 4.34 Gas consumption for Commercial refrigeration (t), 1990 – 2024

2.F.1.a consumptions	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	t										
HFC-134a	NO	NO	693.26	892.00	561.80	256.00	144.00	152.27	134.94	128.25	100.00
R-404A	NO	4.50	317.91	756.00	987.00	1,134.00	189.00	194.04	95.62	99.37	107.10
R-507A	NO	3.60	105.97	144.00	188.00	216.00	36.00	36.96	12.25	13.94	17.85
R-407F	NO	NO	NO	NO	NO	67.50	27.50	31.42	12.39	13.52	2.33
R-407H	NO	NO	NO	NO	NO	67.50	27.50	31.42	12.39	13.52	2.33
R-448A	NO	NO	NO	NO	NO	24.00	592.88	632.40	367.93	495.87	372.60
R-449A	NO	NO	NO	NO	NO	18.00	197.63	210.80	182.03	316.32	202.80
R-422D	NO	NO	NO	NO	NO	130.70	10.00	9.33	2.63	1.27	0.90
R-417A	NO	NO	NO	NO	NO	46.70	5.00	NO	NO	NO	0.17
R-438A	NO	NO	NO	NO	NO	46.70	16.00	14.00	5.25	2.53	0.22

2.F.1.a consumptions	1990	1995	2000	2005	2010	2015 t	2020	2021	2022	2023	2024
R-454C	NO	NO	NO	NO	NO	NO	1.00	1.17	1.31	1.27	1.40
R-455A	NO	NO	NO	NO	NO	NO	2.00	3.50	3.94	3.80	2.13
Total Consumption	NO	8.10	1,117.13	1,792.00	1,736.80	2,007.10	1,248.50	1,317.30	830.69	1,089.65	809.84

R-422D, R-417A R-438A R-454C R-455A have been included in Commercial refrigeration sub-category, from the 2025 submission. As a consequence of HFC bans and phase down, and of the market dynamic of the last years, with the increasing of the cost of HFC with higher GWP and a reduction of their availability, such as for R-404A, R-507A, R-422D, R-417A and R-438A, new HFC and alternative substances with lower or null GWP have been entering the market. The refrigerants market is moving towards a model characterized by the presence of many different gases, each one with a specific different application, both in large refrigeration systems and in small applications.

Assogastecnici communicated the share of consumption of refrigerant used for the first charge and the share of refrigerant used for service. This allowed the *First Charge* consumption to be used to calculate Manufacturing emissions, as well as *Service* consumption to calculate Operation emissions. The shares were communicated for the year 2022, but the experts supported the inventory team to reconstruct back the time series: the share for 2023 and 2024 has been defined on the basis of the phase-down and phase-out of gases of the F-Gas Regulation. The share of consumption used for the first charge of the appliance or used for service is reported in the Technical Document *Emission of fluorinated substances from ODS* (ISPRA, 2026).

Emission factors for Commercial refrigeration

Appropriate emission factors have been applied considering the equipment where refrigerants are generally used, as suggested by a pool of experts during a specific meeting held at the Ministry of the Environment (ISPRA-MATTM, 2013), to assess F-gas emissions from refrigeration and air conditioning. For the years 1990-1999 emission factors were supplied by the industrial associations of manufacturers as the best available country specific information. For the years from 2000 they have been revised to take into consideration the changes in technology which have been occurring in the manufacturing of the equipment: the year 2000 has been taken as a turning point in terms of changes of technologies and good practice in the refrigerants handling, because of the transition from the use of CFCs and HCFCs towards the use of HFCs.

The Regulation (EC) 2037/2000 of the European Parliament and of the Council of 29 June 2000 on substances that deplete the ozone layer (EC, 2000) entered into force in 2000, introducing the phase out of CFC and the phase down of HCFC and restriction in handling these substances. Because of the legislation, together with the increase of refrigerant prices, the relevant operational procedures in manufacturing, during installation and in exercise changed resulting in a turning point of leakage rates, as well as 2015.

For operational emission factors for large commercial refrigeration, a 10% emission factor has been adopted since 2015, to account for the entry into force of the F-Gas Regulation (EU) 517/2014, which has resulted in an increased focus on refrigerant gas management.

The average lifetimes for each type of refrigeration systems are from expert judgement and from IPCC Guidelines (IPCC, 2006; ISPRA-MATTM, 2013; WG1, 2013). In the following Table 4.35 the emission factors, average lifetime, recovery efficiency and the initial charge remaining are reported.

Table 4.35 Manufacturing and operating emission factors and parameters for the end-of-life emissions estimation for Commercial refrigeration equipment

	1995 - 1999	2000 - 2014	2015 - 2024
Stand-alone Commercial Applications			

	1995 - 1999	2000 - 2014	2015 - 2024
Manufacturing emission factor	0.5%	0.5%	0.5%
Operating emission factor	5%	5%	5%
Average lifetime	12	12	12
Initial Charge Remaining	40%	40%	40%
Recovery Efficiency	50%	50%	50%
Medium & Large Commercial refrigeration			
Manufacturing emission factor	3.0%	0.5%	0.5%
Operating emission factor	15%	12%	10%
Average lifetime	12	12	12
Initial Charge Remaining	75%	75%	75%
Recovery Efficiency	50%	50%	50%

Finally, the emissions related to the complete refrigerant management of containers, provided by sectoral experts, are estimated between 5 and 0.5 percent of the refrigerant market. The emission factor from containers is equal for all sub-categories, because refrigerants are stored in the same containers, regardless of the market sector where they will be sold. This emission factor decreased over the time due to the implementation of the F-gas Regulation and the good practices adopted by the operators, as reported in Table 4.36.

Table 4.36 Refrigerants containers management emission factor

1994-1999	2000-2004	2005-2014	from 2015
5.0%	2.0%	1.0%	0.5%

HFC emissions estimation from Commercial refrigeration

As reported above, in a Tier 2a calculation, refrigerant emissions at a year t result from the sum of containers emissions, manufacturing emissions, operational emissions and disposal emissions. All these quantities have to be calculated for each type of HFC used in the applications.

HFC market supplied by Solvay and Assogastecnici is already net of losses from containers, thus, to calculate the amount of HFC contained in the containers, F-gas consumption was increased by the amount that it would then have lost. It should be noted that for sectors for which containers emissions have been estimated, they have been reported in the "CRT reporting table" included in the voice "Emissions from stocks", together with the lifetime emissions.

The first charge consumption was used to calculate manufacturing emissions directly by multiplying the annual tons used for new equipment placed on the market by the relevant emission factor, as reported in equation 7.12 of the 2006 IPCC Guidelines. The amount charged as *First Charge* includes all systems which are charged in Italy, including those which are produced for export. Unlike Stationary Air Conditioning, in the Commercial refrigeration imported pre-charged equipment seems to be very rare.

Annual leakage from the refrigerant banks represents operational emissions. Besides component failures, such as compressor burn-out, equipment is serviced mainly when the refrigerating capacity is too low due to loss of refrigerant from fugitive emissions. Depending on different conditions, servicing could be done every year, every certain time interval, or sometimes not at all during the entire lifetime. Formula 7.13 of the 2006 IPCC Guidelines is applied to calculate operational emissions.

Based on the HFC consumption data, the average annual stock for Commercial refrigeration is calculated. The stock is given by the sum of the amount of refrigerant in the machines placed on the market in the considered year, plus the amount of the refrigerant still in the machines from the previous year and less

the quantity of refrigerant in the machines that left the market in that year because at the end of their life, plus the amount of refrigerant used for service. For each refrigerant the average annual stocks are calculated according to the 2006 IPCC Guidelines.

In the following Table 4.37 the HFC average annual stocks for each refrigerant used in commercial refrigeration are reported. Data are reported by single F-gas, considering the composition of each blend.

Table 4.37 Amount of HFC banked in existing systems (t) for Commercial refrigeration, 1990 - 2024

2.F.1.a Commercial refrigeration (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 134a	NO	0.18	1,610.98	4,323.75	5,163.56	3,886.13	2,613.63	2,456.26	2,200.88	2,111.52	1,901.18
HFC 143a	NO	4.12	391.61	1,684.77	2,618.48	2,793.52	1,605.32	1,440.98	1,217.99	1,069.44	936.34
HFC 125	NO	3.76	345.14	1,479.53	2,288.55	2,707.65	2,002.99	1,900.35	1,641.09	1,584.02	1,415.53
HFC 32	NO	NO	NO	NO	NO	58.35	332.31	382.21	328.79	413.43	371.22
Total HFC bank (t)	NO	8.06	2,347.73	7,488.05	10,070.59	9,445.65	6,554.25	6,179.80	5,388.75	5,178.42	4,624.28

In the following Table 4.38, total emissions are reported, distinguished in Containers, Manufacturing, Operational and Disposal, both for stand-alone and large commercial refrigeration systems by single F-gas, considering the composition of each blend. The largest contribution to emissions is due to the operational phase of the equipment throughout the entire timeseries.

Table 4.38 HFC Total emissions from Commercial refrigeration (t), 1990 – 2024

2.F.1.a Commercial refrigeration (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers Emissions (t)											
HFC 134a	NO	0.01	14.41	9.32	6.07	2.31	1.83	1.94	1.39	1.67	1.19
HFC 143a	NO	0.22	4.46	4.70	6.13	3.51	0.58	0.60	0.28	0.29	0.32
HFC 125	NO	0.20	3.94	4.09	5.34	3.90	1.67	1.74	1.00	1.34	1.03
HFC 32	NO	NO	NO	NO	NO	0.24	0.87	0.93	0.53	0.70	0.50
Manufacturing Emissions (t)											
HFC 134a	NO	0.004	2.99	3.32	1.76	0.93	0.47	0.46	0.34	0.34	0.22
HFC 143a	NO	0.10	0.80	1.32	1.21	0.81	0.04	0.02	NO	NO	NO
HFC 125	NO	0.09	0.71	1.15	1.06	1.10	0.28	0.27	0.15	0.19	0.11
HFC 32	NO	NO	NO	NO	NO	0.02	0.21	0.22	0.14	0.18	0.11
Lifetime Emissions (t)											
HFC 134a	NO	0.03	188.01	504.57	603.53	382.52	257.94	242.02	216.90	207.66	187.02
HFC 143a	NO	0.58	44.25	190.38	295.89	265.38	152.51	136.89	115.71	101.60	88.95
HFC 125	NO	0.53	39.00	167.19	258.61	257.23	190.28	180.53	155.90	150.48	134.48
HFC 32	NO	NO	NO	NO	NO	4.82	31.18	36.08	30.63	38.35	33.82
Disposal Emissions (t)											
HFC 134a	NO	NO	NO	NO	106.37	143.51	94.20	82.24	70.57	59.40	48.89
HFC 143a	NO	NO	NO	NO	9.65	62.53	51.37	50.16	48.58	46.62	44.27
HFC 125	NO	NO	NO	NO	8.50	55.24	44.69	43.64	42.26	40.55	38.52
HFC 32	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total Emissions (t)											

2.F.1.a Commercial refrigeration (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 134a	NO	0.04	205.41	517.21	717.73	529.26	354.44	326.65	289.20	269.07	237.32
HFC 143a	NO	0.90	49.51	196.39	312.88	332.23	204.50	187.68	164.57	148.51	133.55
HFC 125	NO	0.82	43.64	172.42	273.49	317.47	236.93	226.19	199.32	192.56	174.13
HFC 32	NO	NO	NO	NO	NO	5.09	32.25	37.24	31.30	39.23	34.43

As reported above, professional refrigeration such as blast chiller estimations is included in Commercial refrigeration because no detailed information is available to split consumptions and emissions. A brief focus on professional refrigeration is reported in the technical document (ISPRA, 2026). Because the new Regulation (EU) 2024/573 establishes further limitations for this sector, further investigation is planned for the next submissions.

4.7.4 Domestic refrigeration (2.F.1.b)

Domestic refrigeration includes appliances used for the storage of chilled and frozen food and drink products in households' spaces. The sector includes refrigerators, freezers and fridge-freezers. Prior to 1990 most refrigeration appliances used CFC-12. In developed countries there was a shift to HFC-134a from around 1993 (in Italy in 1994). Many countries have subsequently moved to systems using hydrocarbon HC-600a which is now the predominant refrigerant for new domestic refrigeration appliances. In Italy, from 2015, new appliances placed on the market are equipped with isobutane.

Refrigerants market: activity data and HFC used in Domestic refrigeration

Domestic refrigeration estimations are based on data of manufactured and sold fridges and freezers provided by APPLiA Italia who represents the manufacturers of the Domestic and Professional Appliance sector. Domestic refrigeration appliances started to use HFC-134a from 1994 (RAEE, 2017), as a consequence of the ban of CFC forced by Law n. 549/1993, reporting the measures to protect the stratospheric ozone and the environment (Law 28th of December 1993). APPLiA Italia supplied production data of fridges and freezers from 1987 (APPLiA Italia, several years). Data for the other years (1992, 1994, 1995, 1996, 1998, 2000) have been interpolated. Production data has been used to estimate emissions from manufacturing.

Emissions from stocks have been estimated starting from the number of appliances placed on the market each year. Data has been supplied by APPLiA Italia for the year 1993 and from 2001 (APPLiA Italia, several years), even if for the year 1993 the appliances placed on the market still used CFCs. Data for the other years have been interpolated (1994-2000). Data is reported in Table 4.39. APPLiA Italia also supplied data on HFCs coverage on the total of sales, the average charge of appliances and the lifetime (APPLiA Italia, several years). The percentage of appliances containing HFC-134a decreased over the time passing from 35% in 1994 to 0% in 2015, due to the bans of the F-gas Regulation 517/2015. For the emissions estimation an average lifetime of 14 years was assumed for equipment together with an average charge equals 137.5g from 1994 to 2000, 117.5g in 2001 and 2002 and 110g from 2003 (a specific table is reported in the technical document (ISPRA, 2026)).

Table 4.39 Number of manufactured and sold equipment for Domestic refrigeration, 1994-2024

	1994	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Manufactured equipment (units*1000)											
Fridges	5,461	5,746	7,169	5,496	2,400	1,804	1,438	1,714	NA	NA	NA
Freezers	1,693	1,782	2,229	1,890	1,200	521.91	583	670	NA	NA	NA

	1994	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Sold equipment (units*1000)											
Fridges	1,701	1,783	2,190	2,232	2,294	1,832	1,846	2,056	NA	NA	NA
Freezers	420	455	630	593	647	425	671	733	NA	NA	NA

The quantities of HFC contained in the manufactured and sold equipment are reported in the following Table 4.40. As all the domestic equipment is factory charged and are hermetically sealed units (and no gas refilling is necessary during their lifetime), the quantities of refrigerants used to fill new manufactured products coincide with the annual HFC Domestic refrigeration consumption.

Table 4.40 Quantities of HFC contained in the manufactured and sold Domestic refrigeration equipment, 1994-2024 (t)

2.F.1.b Domestic refrigeration	1994	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC in manufactured equipment (t)											
HFC-134a	344.26	724.53	775.33	162.51	27.72	NO	NO	NO	NO	NO	NO
HFC in sold equipment (t)											
HFC-134a	102.09	215.39	232.67	62.15	22.64	NO	NO	NO	NO	NO	NO

Emission factors and HFC emissions estimation from Domestic refrigeration

As for Commercial refrigeration, IPCC Tier 2a methodology has been applied, using activity data and resulting bank calculations derived and emission factors. Total emissions are the sum of containers, manufacturing, operational and disposal emissions. For each term equations 7.11, 7.12, 7.13 and 7.14 of the 2006 IPCC Guidelines have been applied. In table 4.41 the manufacturing and operating emissions factors, the initial charge remaining and recovery at decommissioning for Domestic refrigeration are reported. The emission factors from containers are reported in Table 4.36.

Table 4.41 Manufacturing and operating emission factors, initial charge remaining and recovery at decommissioning for domestic refrigeration equipment

2.F.1.b Domestic refrigeration	%
Manufacturing emission factor	3%
Operating emission factor	0.7%
Initial Charge Remaining	90.2%
Recovery at decommissioning	85%

On the basis of the HFC consumption data, the average annual stock for Domestic sub-sectors was calculated (Table 4.42).

Table 4.42 HFC average annual stocks from Domestic refrigeration (t), 1994-2024

2.F.1.b Domestic refrigeration (t)	1994	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Average annual stock (t)											
HFC-134a	101.38	314.55	1,580.21	2,152.09	1,762.92	620.8	152.49	105.74	71.48	44.21	23.48

Table 4.43 shows the emissions separated into container emissions, manufacturing emissions, lifetimes emissions and disposal emissions: the emissions, after a peak in 1995, decrease over the years and in 2024 are equal to 3.23 t.

Table 4.43 HFC total emissions from Domestic refrigeration (t), 1994-2024

2.F.1.b Domestic refrigeration	1994	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers emissions (t)											
HFC-134a	18.12	38.13	15.82	1.64	0.28	NO	NO	NO	NO	NO	NO
Manufacturing emissions (t)											
HFC-134a	10.33	21.74	23.26	4.88	0.83	NO	NO	NO	NO	NO	NO
Lifetime emission (t)											
HFC-134a	0.71	2.20	11.06	15.06	12.34	4.35	1.07	0.74	0.50	0.31	0.16
Disposal emission (t)											
HFC-134a	NO	NO	NO	NO	32.85	25.68	7.07	6.85	5.03	4.01	3.06
Total HFC-134a emissions (t)	29.16	62.07	50.14	21.58	46.30	30.02	8.14	7.59	5.53	4.32	3.23

4.7.5 Industrial refrigeration (2.F.1.c)

Industrial Refrigeration includes refrigeration systems used in manufacturing and process industries. Most of the industrial refrigeration is used in the processing and storage of food and beverages and the manufacturing of petrochemicals, chemicals and pharmaceuticals. Several other industrial operations use refrigeration, such as the manufacture of plastic products and semi-conductors.

The industrial sector was the only refrigeration market using a significant amount of non-fluorocarbon refrigerants prior to 1990. R-717 (ammonia) was in widespread use and is increasing following the phase-out of the F-gases with high GWP. Most small and medium sized systems used fluorocarbons such as R-12, R-22 prior to 1990. From 1995 various HFCs were introduced in Italy, such R-23, R-404A, R507A and from 1998 HFC-134a. In recent years, new blends R-508B (like HFC-23 but with higher performance), R-407F, R 407H, R-448A, R-449A, R-422D, R-417A, R-438A, R-454C, R-455A are used in the industrial refrigeration.

Refrigerants market: activity data and HFC used in Industrial refrigeration

As for Commercial, also for Industrial Refrigeration estimates are based on single gas consumptions data supplied by Solvay and Assogastecnici (Solvay, 1998; Solvay, 2006; Assogastecnici, several years). Assogastecnici also provided HFC consumption data by use (*First Charge and Service*). This information is reported in the technical document (ISPRA, 2026). In 2024, 100% of R-23, R-404A and R-507A are used for service, the amount of R-134a used for maintenance is 77% whilst the amount of R-407F and R-407H are 76%, R-448A and R-449A are 85% and finally the amount of R-508B, 422D, R-417A, R-438A, R-454C, R-455A used for service is 41%. For the years before the percentage allocation of gas between first charge and service is based on expert judgment. The following table (Table 4.44) shows the HFC total consumptions of the industrial refrigeration subsector.

Table 4.44 HFC consumption from Industrial refrigeration (t), 1990-2024

2.F.1.c Industrial refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC-23	NO	15.00	16.56	21.11	11.11	11.15	10.00	9.50	10.50	11.50	NO
HFC-134a	NO	NO	1,039.88	1,337.99	842.69	384.00	216.00	228.40	202.41	192.38	150.00

2.F.1.c Industrial refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
R-404A	NO	4.50	317.91	756.00	987.00	1,134.00	189.00	194.04	95.62	99.37	107.10
R-507A	NO	3.60	105.97	144.00	188.00	216.00	36.00	36.96	12.25	13.94	17.85
R-407F	NO	NO	NO	NO	NO	67.50	27.50	31.42	12.39	13.52	2.33
R-407H	NO	NO	NO	NO	NO	67.50	27.50	31.42	12.39	13.52	2.33
R-448A	NO	NO	NO	NO	NO	16.00	395.25	421.60	245.29	330.58	248.40
R-449A	NO	NO	NO	NO	NO	12.00	131.75	140.53	121.35	210.88	135.20
R-508B	NO	NO	NO	NO	NO	7.00	6.00	7.00	7.88	7.60	0.14
R-422D	NO	NO	NO	NO	NO	130.67	10.00	9.33	2.63	1.27	0.90
R-417A	NO	NO	NO	NO	NO	46.67	5.00	0.00	0.00	0.00	0.17
R-438A	NO	NO	NO	NO	NO	46.67	16.00	14.00	5.25	2.53	0.22
R-454C	NO	NO	NO	NO	NO	NO	1.00	1.17	1.31	1.27	1.40
R-455A	NO	NO	NO	NO	NO	NO	2.00	3.50	3.94	3.80	2.13
Total Consumption (t)	NO	23.10	1,480.32	2,259.11	2,028.81	2,139.15	1,073.00	1,128.87	733.21	902.15	668.18

Emission factors from Industrial refrigeration

As for the other refrigeration subsectors, appropriate emission factors have been applied taking into account the equipment where refrigerants are generally used, as suggested by a pool of experts during a specific meeting held at the Ministry of the Environment (ISPRA-MATTM, 2013). Emission factors have been checked recently with Assogastecnici and with those reported in the 2006 IPCC Guidelines.

The average lifetimes for each type of refrigeration systems are from expert judgement and from IPCC Guidelines (IPCC, 2006; ISPRA-MATTM, 2013; WG1, 2013). In the following Table 4.45 the emission factors, average lifetime, recovery efficiency and the initial charge remaining are reported.

Table 4.45 Emission factors, average lifetime, initial charge remaining and recovery at decommissioning for Industrial refrigeration

2.F.1.c Industrial refrigeration	1995 – 1999	2000 - 2014	2015 - 2024
Manufacturing emission factor	1.8%	1.8%	1.8%
Operating emission factor	15%	15%	11%
Average lifetime	20	20	20
Initial charge remaining	75%	75%	75%
Recovery efficiency	50%	50%	50%

HFC emissions estimation from Industrial refrigeration

As reported above, in a Tier 2a calculation, refrigerant emissions result from the sum of emissions from containers, manufacturing emissions, operational emissions and disposal emissions, using equations 7.11, 7.12, 7.13 and 7.14 of the 2006 IPCC Guidelines (vol. 3, chapter 7). All these quantities have to be calculated for each type of HFC used in the applications. Emissions from containers have been estimated using appropriate losses rates provided by sector's experts (see Table 4.36).

To estimate the amount of HFC stored in containers, before being used for different operations (installation, topping up, etc.), it is necessary to increase the stock by the quantity that will be lost when switching between containers larger to smaller ones.

In Table 4.46 the HFC average annual stocks for each refrigerant used in Industrial refrigeration are reported. Data is reported by single F-gas, considering the composition of each blend.

Table 4.46 Average annual stock for Industrial refrigeration (t) 1990-2024

2.F.1.c Industrial refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
C2F6	NO	NO	NO	NO	NO	6.46	12.25	13.44	14.82	15.80	12.79
HFC 23	NO	14.76	56.29	73.78	61.5	49.06	40.06	39.05	41.21	44.10	20.05
HFC 134a	NO	0.18	2,292.94	5,047.40	4,882.31	3,489.77	791.93	545.12	455.27	476.78	404.65
HFC 143a	NO	4.07	355.87	1,330.67	1,787.78	1,891.40	728.73	501.46	213.34	58.64	64.62
HFC 125	NO	3.72	313.82	1,167.35	1,559.62	1,906.89	1,044.04	855.20	541.56	444.40	401.76
HFC 32	NO	NO	NO	NO	NO	51.36	215.25	244.25	199.85	250.16	215.41
Total HFC average annual stock (t)	NO	22.73	3,018.92	7,619.20	8,291.21	7,394.95	2,832.27	2,198.51	1,466.06	1,289.89	1,119.30

In Table 4.47, total emissions are reported, distinguished in containers, manufacturing, lifetime and disposal, by single F-gas considering the composition of each blend.

Table 4.47 HFC total emissions from Industrial refrigeration (t), 1990-2024

2.F.1.c Industrial refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers emissions (t)											
C2F6	NO	NO	NO	NO	NO	0.02	0.02	0.02	0.02	0.02	0.0004
HFC 23	NO	0.79	0.34	0.21	0.11	0.07	0.06	0.06	0.07	0.08	0.0003
HFC 134a	NO	0.01	21.48	13.82	8.91	2.93	1.90	2.01	1.53	1.68	1.23
HFC 143a	NO	0.22	4.46	4.70	6.13	3.51	0.58	0.60	0.28	0.29	0.32
HFC 125	NO	0.20	3.94	4.09	5.34	3.88	1.33	1.38	0.76	0.99	0.78
HFC 32	NO	NO	NO	NO	NO	0.25	0.77	0.83	0.51	0.74	0.50
Manufacturing emissions (t)											
C2F6	NO	NO	NO	NO	NO	0.04	0.03	0.04	0.05	0.04	0.0008
HFC 23	NO	0.24	0.22	0.22	0.08	0.08	0.04	0.04	0.04	0.04	0.0007
HFC 134a	NO	0.003	16.08	17.77	9.39	4.48	1.95	1.91	1.44	1.33	0.87
HFC 143a	NO	0.07	2.88	4.74	4.37	2.93	0.14	0.07	NO	NO	NO
HFC 125	NO	0.06	2.55	4.13	3.80	3.98	0.79	0.73	0.39	0.46	0.27
HFC 32	NO	NO	NO	NO	NO	0.06	0.51	0.55	0.35	0.44	0.27
Lifetime emissions (t)											
C2F6	NO	NO	NO	NO	NO	0.94	1.47	1.55	1.63	1.66	1.28
HFC 23	NO	2.21	8.44	11.07	9.22	7.25	5.03	4.72	4.78	4.88	2.19
HFC 134a	NO	0.03	343.94	757.11	732.35	506.02	95.03	62.69	50.08	50.06	40.47
HFC 143a	NO	0.61	53.38	199.60	268.17	274.25	87.45	57.67	23.47	6.16	6.46
HFC 125	NO	0.56	47.07	175.10	233.94	276.50	125.28	98.35	59.57	46.66	40.18
HFC 32	NO	NO	NO	NO	NO	7.45	25.83	28.09	21.98	26.27	21.54
Disposal emissions (t)											
C2F6	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 23	NO	NO	NO	NO	NO	5.06	4.55	4.43	4.31	4.17	4.03
HFC 134a	NO	NO	NO	NO	NO	0.06	334.96	359.56	371.16	400.19	406.45
HFC 143a	NO	NO	NO	NO	NO	0.63	15.15	21.04	25.78	29.59	21.57

2.F.1.c Industrial refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 125	NO	NO	NO	NO	NO	1.28	53.04	73.65	90.22	103.58	93.75
HFC 32	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total emissions (t)											
C2F6	NO	NO	NO	NO	NO	1.00	1.52	1.61	1.70	1.72	1.28
HFC 23	NO	3.25	9.00	11.50	9.42	12.47	9.69	9.26	9.19	9.16	6.23
HFC 134a	NO	0.04	381.5	788.70	750.64	513.49	433.85	426.17	424.20	453.26	449.01
HFC 143a	NO	0.90	60.72	209.04	278.67	281.32	103.32	79.38	49.53	36.05	28.36
HFC 125	NO	0.82	53.55	183.32	243.08	285.64	180.45	174.11	150.94	151.69	134.98
HFC 32	NO	NO	NO	NO	NO	7.76	27.10	29.46	22.85	27.45	22.31

4.7.6 Transport refrigeration (2.F.1.d)

This market sector includes refrigeration systems used in various modes of transport. Most transport refrigeration systems are used for the carriage of frozen or chilled food and beverage products.

Prior to 1990 most of road transport systems and containers used R-502, R-12 and R-22. From 1995, R-404A and R-507A have been introduced, followed by HFC-134a in 1998 and the new R-422D, R-417A, R-438A, R-454C, R-455A and R-452A in 2014 and 2015, the new blend targeted at the transport sector as an alternative with low discharge temperature at high ambient.

Refrigerants market: activity data and HFC used in Transport refrigeration

For what concern activity data, Assogastecnici provides both refrigerants consumption for Transport refrigeration as well as the percentage distribution between *First Charge* and *Service*. In 2024, 100% of R-404A and R-507A are used for service, the amount of R-134a and R-452A used for maintenance are 84% and 92% respectively, whereas the amount of R-422D, R-417A, R-438A, R-454C, R-455A use for service is estimated to be 41%.

For the years from 1990 to 2013 HFC consumption data were communicated by Solvay (Solvay, 1998; Solvay, 2006).

In Table 4.48, the total consumptions of R-404A, R-507A, HFC-134a, R-452A, R-422D, R-417A, R-438A, R-454C and R-455A are shown. The consumption by use (*First Charge* and *Service*) is reported in the technical document (ISPRA, 2026). The consumption of R-404A and R-507A in Transport refrigeration began in 1995 and increased steadily until 2014, when it peaked with 260.4 t of R-404A and 49.6 t of R-507A used. The consumption of R-404A has always been predominant over R-507A. In 2024 the consumption of R-404A was equal to 37.80 t and the ones for R-507A was 6.30 t. HFC-134a entered the market in 1998 (367.33 t used); the amount used increased until 2004 then began to decline and in 2024 consumption equal to zero was registered. Refrigerants R-422D, R-417A, R-438A have been used as replacement of R-22 and its consumption has decreased a lot due to their high GWP. Across 2014 and 2015, the use of R-452A began, as the main replacement for R-404A gradually banned from the market by the F-gas Regulation. In particular, in 2015, a consumption of 10 t of R-452A was registered, it increased to 491.00 t in 2023, while in 2024 it decreased to 128.30 t. In addition, R-454C and R-455A entered the market in 2019, again as substitutes for R-404A. In 2024, the consumption of these gases was 1.40 t and 2.13 t respectively.

Table 4.48 HFC Consumption from Transport refrigeration (t), 1990-2024

2.F.1.d- Transport refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 134a	NO	NO	433.28	557.50	351.12	160.00	90.00	95.17	84.34	80.16	NO
R 404A	NO	1.00	70.65	168.00	219.33	252.00	42.00	43.12	33.75	35.07	37.80
R 507A	NO	0.80	23.55	32.00	41.78	48.00	8.00	8.21	4.32	4.92	6.30
R-452A	NO	NO	NO	NO	NO	10.00	232.50	248.00	347.77	491.00	128.30
R-422D	NO	NO	NO	NO	NO	130.66	10.00	9.33	2.63	1.27	0.90
R-417A	NO	NO	NO	NO	NO	46.67	5.00	NO	NO	NO	0.17
R-438A	NO	NO	NO	NO	NO	46.67	16.00	14.00	5.25	2.53	0.22
R-454C	NO	NO	NO	NO	NO	NO	1.00	1.17	1.31	1.27	1.40
R-455A	NO	NO	NO	NO	NO	NO	2.00	3.50	3.94	3.80	2.13
Total Consumption (t)	NO	1.80	527.48	757.50	612.23	694.00	406.50	422.50	483.31	620.01	177.22

Emission factors for Transport refrigeration

Country specific emission factors for this sector are under investigation, and at the moment Italy uses those reported in the 2006 IPCC Guidelines. In Table 4.49 the emission factors, average lifetime, recovery efficiency are reported.

Table 4.49 Manufacturing and operating emission factors, average lifetime and recovery at decommissioning for Transport refrigeration

2.F.1.b Transport refrigeration	
Manufacturing emission factor	0.5%
Operating emission factor	20%
Initial charge remaining	35%
Recovery at decommissioning	50%
Average lifetime	9 years

HFC emissions estimation from Transport refrigeration

IPCC Tier 2a methodology has been applied for the estimations of the sub-sector. Emissions from containers have been estimated using appropriate emission factors provided by experts of the sector (see Table 4.36). In Table 4.50, the average annual stock for the single compound is reported. The presence of R-32 since 2015 is due to the market entry of R-452A, of which R-32 is a component. The HFC-134a increased over the years reaching the maximum value in 2006 (1,690.81 t) then progressively decreased.

Table 4.50 Average annual stock for Transport refrigeration (t), 1990-2024

2.F.1.d Transport refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 134a	NO	0.04	864.40	1,689.44	1,102.84	436.79	177.58	166.48	141.88	101.01	12.45
HFC 143a	NO	0.92	76.82	268.04	307.20	266.36	38.86	25.64	19.71	20.70	22.81
HFC 125	NO	0.84	67.75	235.03	267.41	454.02	347.78	328.25	361.59	396.73	162.96
HFC 32	NO	NO	NO	NO	NO	1.10	31.08	34.51	47.00	64.77	26.86
Total HFC average annual stock (t)	NO	1.80	1,008.97	2,192.51	1,677.45	1,158.27	595.30	554.88	570.18	583.21	225.07

In Table 4.51 the emissions from Transport refrigeration subsector are reported, distinguished by containers, manufacturing, lifetime and disposal emissions. The largest contribution to total emissions is lifetime emissions along the entire timeseries.

Table 4.51 HFC total emissions from Transport refrigeration (t), 1990-2024

2.F.1.d Transport refrigeration	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers emissions (t)											
HFC 134a	NO	0.00	8.90	5.70	3.64	1.29	0.52	0.53	0.45	0.42	0.01
HFC 143a	NO	0.05	0.99	1.04	1.36	0.78	0.13	0.13	0.10	0.10	0.11
HFC 125	NO	0.04	0.87	0.91	1.19	1.35	0.88	0.91	1.14	1.56	0.48
HFC 32	NO	NO	NO	NO	NO	0.01	0.13	0.14	0.20	0.28	0.07
Manufacturing emissions (t)											
HFC 134a	NO	NO	1.64	1.76	0.90	0.57	0.15	0.13	0.09	0.08	0.00
HFC 143a	NO	NO	0.18	0.29	0.27	0.18	0.01	NO	NO	NO	NO
HFC 125	NO	NO	0.16	0.25	0.23	0.54	0.12	0.11	0.11	0.13	0.03
HFC 32	NO	NO	NO	NO	NO	0.00	0.01	0.02	0.02	0.03	0.01
Lifetime emissions (t)											
HFC 134a	NO	0.01	172.88	337.89	220.57	87.36	35.52	33.30	28.38	20.20	2.49
HFC 143a	NO	0.18	15.36	53.61	61.44	53.27	7.77	5.13	3.94	4.14	4.56
HFC 125	NO	0.17	13.55	47.01	53.48	90.80	69.56	65.65	72.32	79.35	32.59
HFC 32	NO	NO	NO	NO	NO	0.22	6.22	6.90	9.40	12.95	5.37
Disposal emissions (t)											
HFC 134a	NO	NO	NO	0.05	61.11	55.40	26.06	21.15	16.56	25.01	19.92
HFC 143a	NO	NO	NO	0.71	8.65	10.24	9.06	8.61	8.08	7.48	6.33
HFC 125	NO	NO	NO	0.61	7.64	8.91	7.89	7.49	7.03	26.16	19.02
HFC 32	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	0.02
Total emissions (t)											
HFC 134a	NO	0.01	183.42	345.40	286.21	144.61	62.25	55.11	45.48	45.71	22.42
HFC 143a	NO	0.24	16.53	55.65	71.72	64.47	16.97	13.88	12.12	11.72	11.01
HFC 125	NO	0.22	14.58	48.78	62.54	101.60	78.45	74.17	80.60	107.20	52.12
HFC 32	NO	NO	NO	NO	0.00	0.23	6.36	7.06	9.62	13.26	5.47

4.7.7 Mobile air conditioning (2.F.1.e)

This sector includes Mobile Air-Conditioning (MAC) systems used to cool the driver and passengers in land transport including cars, vans, lorries, buses, etc.

Prior to 1990, all MACs for cars and small vans used CFC-12. Italy started to use HFC-134a in new cars and for retrofit in 1992. HFC-134a is the global standard refrigerant for small MAC systems, replaced by R-1234yf from 2013, due to entering into force the European Directive 40/2006, relating to emissions from air conditioning systems in motor vehicles (EU, 2006).

Refrigerants market: activity data and HFC used in MAC

As reported above, HFC market, including HFC-134a, has been supplied by Solvay and Assogastecnici (Solvay, 1998; Solvay, 2006; Assogastecnici, several years).

The information collected, such as the distribution of consumption of HFC-134a between the different sub-sectors of use and the distribution of total consumption between *First Charge* and *Service*, made it possible to obtain the consumption of HFC-134a used in mobile air conditioning.

Moreover, since 1992 the national motor company and the agent's union of foreign motor-cars vehicles have provided HFC-134a yearly consumptions of HFC-134a used in new vehicles (FIAT, several years [a]; IVECO, several years; UNRAE, several years).

Combining these sources, at present, consumption data reported in Table 4.52 represent the best available information of this sub-category: it was decided to use data from car manufacturers regarding the quantities of HFC-134a contained in the MAC systems of new vehicles produced and placed on the market, while as regards *Service*, data from Solvay and Assogastecnici were used.

Regarding HFC 134a used in new trucks, data supplied by the industry has been missing for some years and an interpolation has been made. Data from national statistics on vehicles from the Automobile Club of Italy (ACI, several years) have been used together with the assumption of a nominal refrigerant charge of 1.2 kg and a lifetime of 12 years, according to IPCC Guidelines (IPCC, 2006).

Data from off-road vehicles have been supplied too by Case New Holland (CNH, several years).

Worthy remark is that vehicles that are imported pre-charged are not considered in *First Charge* consumption but contribute to the calculation for operational emissions (UNRAE, several years). Similarly, vehicles produced in Italy but exported are accounted for the calculation of manufacturing emissions but not for that of operational emissions.

Table 4.52 HFC consumption from Mobile Air Conditioning (t), 1992-2024

2.F.1.e MAC (t)	1992	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
First Charge											
HFC-134	83.33	278.65	631.07	548.53	492.87	346.27	221.81	230.88	194.89	166.58	127.23
Service											
HFC-134a	300.00	800.00	1,000.00	1,800.00	1,704.18	1,575.47	859.30	1,066.99	882.69	836.74	455.00
Total Consumptions	383.33	1,078.65	1,631.10	2,348.53	2,197.05	1,921.73	1,081.11	1,297.87	1,077.59	1,003.32	582.23

Emission factors for MAC

Country specific emission factors for this sector are under investigation, and at the moment Italy uses those reported in the 2006 IPCC Guidelines (Table 7.9), revised with experts of Assogastecnici for what concerns the trend over the years. For the emission factor from containers management, in line with the other RAC sectors and according to national experts, its value varies from 5% in 1992 to 0.5% in 2024.

In the following Table 4.53 the emission factors, average lifetime, recovery efficiency and the initial charge remaining are reported.

Table 4.53 Emission factors, average lifetime, initial charge remaining and recovery at decommissioning for Mobile Air Conditioning

2.F.1.e MAC	1992 – 1999	2000 - 2014	2015 - 2024
Manufacturing emission factor	4%-3%	2%-0.5%	0.5%
Operating emission factor	20%	20%	20%-16%
Average lifetime	12	12	20
Initial charge remaining	40%	40%	40%
Recovery Efficiency	0%-6%	6%-10%	10%

HFC emissions estimation from MAC

IPCC Tier 2a methodology has been applied for the estimations of the sub-sector, using, as for the other subsectors, equations 7.11, 7.12, 7.13 and 7.14 of the 2006 IPCC Guidelines.

The HFC-134a stock in MAC systems is given by the sum of the amount of refrigerant in the new vehicles placed on the market in the considered year, plus the amount of the refrigerant still in the vehicles from

the previous year and less the quantity of refrigerant in the vehicles that left the market in that year because at the end of their life, plus the amount of refrigerant used for service.

The disposal emissions have been calculated as the difference between the remaining HFC-134a in MAC at decommissioning and the quantity of HFC-134a recovered, equal to zero until 1996 because vehicles are still dismantled in junkyard cars. From 1997, due to enforcement of Legislative Decree no. 22 of 5 February 1997 regarding hazardous waste which establishes authorized centers for demolition, recovery efficiency has started to increase slightly (10% in 2024) although the sector of car demolition is still poorly controlled.

In the following Table 4.54, the HFC-134a average annual stock in MAC systems is reported.

Table 4.54 Average annual stock for Mobile Air Conditioning (t), 1990-2024

2.F.1.e Mobile Air Conditioning	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Average annual stock (t)											
HFC-134a	NO	1,550.34	4,530.50	6,676.88	6,133.60	4,720.50	2,689.16	2,330.70	1,655.83	1,203.97	503.61

The total emissions, distinguished in containers, manufacturing, lifetime and disposal emissions from MAC subsector are reported in Table 4.55.

Table 4.55 HFC total emissions from Mobile Air Conditioning (t), 1990-2024

2.F.1.e Mobile Air Conditioning	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers emissions (t)											
HFC-134a	NO	40.00	20.00	18.00	17.04	7.88	4.30	5.33	4.41	4.18	2.28
Manufacturing emissions (t)											
HFC-134a	NO	11.15	12.62	2.74	2.46	1.73	1.11	1.15	0.97	0.83	0.64
Lifetime emissions (t)											
HFC-134a	NO	310.07	906.10	1,335.38	1,226.72	920.50	457.16	384.57	264.93	186.62	75.54
Disposal emissions (t)											
HFC-134a	NO	NO	NO	52.81	347.93	400.77	400.90	384.09	377.28	372.11	340.75
Total HFC-134a emissions	NO	361.21	938.72	1,408.93	1,594.15	1,330.87	863.46	775.14	647.60	563.74	419.20

4.7.8 Stationary Air Conditioning (2.F.1.f)

The term "Stationary Air Conditioning" covers several applications used for the climatization of residential and commercial buildings, including moveable systems, split systems, multi-split systems, rooftop systems, displacement chillers, heat pumps and centrifugal chillers.

Prior to 1990 most air conditioning systems used R-12 and R-22. From 1995, R-410A, R-407C and R-134a have been introduced, followed by R-32 in 2016, R-513A in 2022, R-454C and R-515B in 2023 and R454B in 2024; these are new blends targeted at the air conditioning sector as an alternative with low GWP.

The estimates of emissions from the Stationary Air Conditioning sector are based on data on air conditioning equipment production and sales, provided by Assoclimate, the Italian Association of Air Conditioning Systems Manufacturers, who collects an annual statistical survey of the Italian companies in the sector, considering the production and sales data by type of equipment and capacity. The Association supplied data on production and sales from 1995 to 2024 (Assoclimate, several years [a]) together with data on the average refrigerant charge of each type of appliance (Assoclimate, several years [b]). Data interpolation

has been done in those cases where data was not available for confidential reasons (this affected some cases for which the companies that declare their production and/or sales were less than 3). Data on production include the appliances manufactured and sold in Italy plus the appliances manufactured in Italy and sold in the foreign market (EU and external EU); data on sales include appliances manufactured and sold in Italy plus appliances imported from abroad and sold in Italy. As Assoclimate represents most of the industry but, for some kinds of appliances, not 100%, multiplicative factors have been provided by the Association to cover the total of the air conditioning companies, including those that are not associated. Multiplicative factors have been used for each type of equipment and are constant for all the years of the time series (Assoclimate, several years[b]).

Production data has been used to estimate emissions from manufacturing while sales data has been used for estimating lifetime emissions.

Hybrid machines are included in the estimates. These machines are like chillers with capacities up to 50 kW, so the parameters used for chillers were assigned to hybrid machines with the same capacity. This approach was shared with the experts of the sector. Domestic hot water production machines were also introduced in 2022. For these machines, Assoclimate provided the information and parameters needed to estimate emissions (average charge, gases used and emission factors).

The equipment type, capacity, average charge and the multiplication factor used for estimation are given in the technical document (ISPRA, 2026). The average charge depends on the equipment and on its capacity: i.e. for air-cooled chillers it ranges from 2.2 to 154.3 kg, while for water-cooled chillers the charge is between 0.9 kg and 200 kg. For split the average charge goes from 1.1 to 3.9 kg. The charge of equipment using R-32 is reduced by 20% compared to the same equipment using R-410A; in fact, as this refrigerant has higher capacity in terms of cooling and heating compared to R-410A, R-32 equipment uses up to 20% less refrigerant than R-410A for the same performance.

Regarding the general trend of products and components for air conditioning systems, 2015 has been the year in which the sector restarts to grow after a period of economic crisis. The time series of the equipment production data shows a steady and significant decrease from 2000 to 2014 due to an increment to the import sector, with a very weak recovery in subsequent years (but in 2024 production shows about 84% decline compared to 1996). A different trend is registered for sales data. Overall, total sales of air conditioning equipment increased from 477,068 units in 1996 to 2,350,599 in 2024, with a fluctuating trend over the period.

Referring to Assoclimate's latest survey (Assoclimate, several years[a]), 2024 shows a slight decrease in production compared to the previous year and a 9% increase in sales.

Regarding the portable air conditioners with remote condenser, production stopped in 2013, because they don't respect the minimum efficiency limits required by the Energy-Related Products Directive ErPD, 2009/125/EC (Assoclimate, several years [b]). For further details, see the technical document (ISPRA, 2026).

In Table 4.56, data on manufactured and sold equipment in the Stationary Air Conditioning sector are reported. Small corrections were made to the number of estimated units, resulting in a slight recalculation.

Table 4.56 Number of manufactured and sold equipment in Stationary Air Conditioning, 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
Production (number of units)										
Room air conditioner	309,318	244,769	165,152	34,938	10,566	17,614	44,702	46,524	46,524	46,524
Monosplit	229,900	575,242	65,286	25,141	35	-	-	-	-	-
Multisplit	22,718	46,680	18,576	4,464	-	-	-	-	-	-
VRF	-	-	-	51	-	-	-	-	-	-
Packaged, roof top	7,090	2,384	3,376	1,990	1,891	1,507	1,386	1,585	1,938	2,130
Precision air conditioning	9,927	24,635	13,619	2,237	5,387	4,087	4,224	4,825	5,296	-
Air cooled chiller	28,847	46,276	55,851	67,085	36,253	34,562	42,537	70,627	58,396	43,560
Water cooled chiller	2,736	4,898	5,724	5,762	5,689	4,266	4,352	3,653	3,847	4,004
Hybrid machines	-	-	-	-	-	-	-	-	7,551	8,558
Hot water-only machines	-	-	-	-	-	-	-	-	-	-
Sales (number of units)										
Room air conditioner	112,212	101,860	111,540	143,632	72,552	157,093	143,966	124,295	132,521	123,633
Monosplit	358,756	875,558	1,082,572	910,491	741,229	1,271,003	1,622,428	1,683,972	1,563,096	1,794,811
Multisplit	22,879	129,860	326,525	281,118	222,176	375,282	458,520	488,584	482,211	543,545
VRF	-	-	8,292	18,116	15,131	22,436	29,058	32,546	33,288	35,634
Packaged, roof top	2,429	3,907	4,141	1,744	1,199	1,258	1,297	1,315	1,627	1,877
Precision air conditioning	4,233	11,458	3,515	791	1,247	309	515	357	583	-
Air cooled chiller	21,706	31,529	34,262	27,707	33,105	52,482	109,934	192,813	131,674	96,975
Water cooled chiller	1,628	2,988	2,654	2,155	1,921	1,486	1,586	975.46	1,047	1,238
Hybrid machines	-	-	-	-	3,767	15,706	70,915	148,662	36,125	12,239
Hot water-only machines	-	-	-	-	2,300	8,256	17,305	34,125	27,656	25,720

Refrigerants market: activity data and HFC used in the Stationary air conditioning sector

Air conditioning appliances started to use HFC, as substitutes of HCFC, in the second half of the 1990s (Assoclima, several years [b]), and the replacement process was completed by 2005, with the elimination of HCFCs in new equipment.

R-410A, R-134a and R-407C have long been the main refrigerants used in the air conditioning sector. R-410A was the dominant HFC for many years, followed by R-134a. R-410A has always been used mainly for small air conditioning systems even if in the last years it was replaced by R-32, R-134a is a good replacement for larger equipment; for intermediate power machines both R-410A and R-134a can be used. R-407C was used for different years in the past as a substitute for R-22, instead of R-410A because this

refrigerant allows the use of the same components of a R-22 system but, due to thermodynamic problems, it has been progressively substituted by R-410A. For this reason, the use of R-407C started to decrease from 2010.

In the last years, with the introduction of new refrigerants (natural refrigerants, HFOs) in substitution of the HFC, due to the F-gas Regulation and market dynamics, the percentage of sales and production of HFC equipment has changed. For portable air conditioners, the replacement of HFCs with HCs started earlier than the other machines thanks to the low charge involved that allow the use of flammable refrigerants. According to expert judgment, propane has started to be used after 2005, and in 2010 the 50% of the portable room air conditioner are with R-290; this percentage grew to 90% in 2017 (Assoclima, several years [b]) and became equal to 100% in 2020 because, according to the F-gas Regulation, as of January 2020, portable room air conditioners that contain a refrigerant with a GWP of 150 or more are banned from the market. In 2021, propane-powered air-cooled chillers with a capacity of up to 50 kW (1%) were introduced on the Italian market. In 2022, air-cooled and water-cooled chillers using R-1234ze were also placed on the market. For water-cooled chillers, only machines with higher capacity (≥ 351 kW) began to use this new refrigerant, while it is used in all air-cooled chillers, both small and large capacity. As a result, with the increase in the number of chillers that use alternative refrigerants with low or zero GWP, the percentage of HFC machines has decreased. In 2024, this percentage ranges from 95% of air-cooled chillers with a capacity of up to 50 kW to 100% of water-cooled chillers with a capacity of up to 350 kW.

The percentage share of HFC equipment on the total of sales and production per year (1996-2024) is reported in the technical document (ISPRA, 2026).

The percentage of HFC conditioning equipment, by type of refrigerant, supplied by Assoclima (Assoclima, several years [b]), shows a deep change in the mix of refrigerants used over the years. Portable air conditioners initially used R-134a but later moved largely to R-410A. Chillers with rotary compressors first adopted R-407C, while screw and centrifugal units transitioned directly to R-134a. Over time, R-407C declined and disappeared from new equipment registrations by 2023. High-capacity chillers still mainly use R-134a, though their market share is decreasing.

As the sectoral experts communicated (Assoclima, several years [b]), R-32 has been used primarily in residential split systems. It began replacing R-410A in mono e multisplit units in 2016 (about 20% share), reaching 100% by 2024.

R-32 units also entered the VRF, rooftop, and packaged segments in 2022. However, adoption remains limited in VRFs (2024: ~2% for ≥ 16 kW and 8% for < 16 kW). In contrast, R-32 accounts for about 25% of packaged units and 70% of rooftop units, with the remainder still using R-410A and, to a lesser extent, R-407C.

In 2020 R-32 air cooled chiller with a capacity up to 50 kW appeared in the Italian market with a percentage penetration equal to 19% increasing up to 90% (capacity up to 17 kW) and 75% (18- 50 kW) in 2024. In 2022, R-32 air-cooled chillers with capacities between 51 kW and 350 kW also entered the market whilst in 2023 R-32 chillers with capacity between 351 kW and 700 kW.

In 2022 R-513A air- and water-cooled chillers with capacity ≥ 201 kW entered the market, with a percentage between 5% and 10%. In 2023 air cooled chillers equipped with R-513A (< 50 kW) entered the market, covering a small quota (1%), together with water cooled chillers with capacity between 51 and 200 kW (10%). These percentages remained stable in 2024. Domestic hot water machines are also equipped with a 12% quota of R-513A in 2024.

In 2023 a quota of 5% of air-cooled chillers with capacity between 201 kW and 500 kW equipped with the new refrigerant R-454C entered the market, whilst R-515B appeared in water cooled chillers with a capacity greater than 101 kW (in percentage between 5%-10% depending on capacity). In 2024, R-454B entered the market (5% of rooftop machines). The percentage of HFC conditioning equipment sold and produced by type of refrigerant is reported in the technical document (ISPRA, 2026).

Based on the number of equipment manufactured and sold in the Italian market, of the average refrigerant charge and of the percentage of equipment by type of HFC, the quantities of HFC contained in the equipment manufactured and sold have been calculated (Table 4.57).

As already mentioned, compared to the previous Submission, some corrections were made to the estimate of the number of equipment produced and sold and to the percentages of equipment by refrigerant type. These changes affected some years of the time series.

Table 4.57 Quantities of HFCs contained in the air conditioning equipment manufactured and sold in the Italian market (t), 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC in manufactured equipment (t)										
HFC-134a	19.80	80.45	364.14	353.29	274.66	240.21	239.33	207.86	231.96	221.24
R-410A	3.39	8.60	238.39	626.90	541.52	458.63	477.84	376.82	364.90	283.15
R-407C	3.17	64.16	519.38	16.02	4.52	3.55	3.34	1.64	NO	NO
R-32	NO	NO	NO	NO	NO	11.23	31.35	153.04	217.16	221.79
R-513A	NO	NO	NO	NO	NO	NO	NO	25.68	32.98	30.69
R-454C	NO	NO	NO	NO	NO	NO	NO	NO	10.10	10.02
R-515B	NO	NO	NO	NO	NO	NO	NO	NO	6.15	6.14
R-5454B	NO	NO	NO	NO	NO	NO	NO	NO	NO	2.20
HFC in sold equipment (t)										
HFC-134a	7.36	34.59	165.19	102.99	89.34	73.48	83.38	78.28	92.41	86.33
R-410A	4.26	8.54	1,189.29	1,955.93	1,646.17	588.93	793.32	698.82	485.00	416.26
R-407C	2.33	71.56	984.16	10.44	2.60	2.68	2.77	1.36	NO	NO
R-32	NO	NO	NO	NO	NO	1,611.40	2,238.39	2,785.77	2,449.45	2,657.07
R-513A	NO	NO	NO	NO	NO	NO	NO	7.08	18.39	12.34
R-454C	NO	NO	NO	NO	NO	NO	NO	NO	5.31	4.32
R-515B	NO	NO	NO	NO	NO	NO	NO	NO	1.62	1.58
R-5454B	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO

Emission factors for the Stationary air conditioning subsector

Appropriate losses rates have been applied for each gas used in the stationary air conditioning sector, considering the equipment where refrigerants are generally used, as suggested by a pool of experts during a specific meeting held at the Ministry of the Environment (ISPRA-MATTM, 2013). These experts represent the National Association of Manufacturers of aerodynamic equipment and systems (ASSOCLIMA-ANIMA) and the Italian Association of Air Conditioning, Heating and Refrigeration (AICARR).

For more information about this, please see the paragraph relative to Commercial refrigeration. The manufacturing and operating emission factors of the Stationary air conditioning sector have not changed compared to last year's estimates.

Regarding the operating emission factors, for all the types of equipment, except split and VRF, two different periods have been considered: from 1996 to 2006 and from 2007 onward. For split and VRF, as communicated by the expert, three periods have been identified: from 1996 to 2006, from 2007 to 2014, from 2015. The emission factors for the period 1996-2006 have been assumed to be higher than those of

the following period, because with the entry into force of Regulation 842/2006 on certain fluorinated greenhouse gases, improvements in the prevention of leaks from equipment containing F-gases were introduced.

Consequently, starting from that year, more attention has been paid by the technicians to install, service and maintain, repair or decommission of AC systems and the year 2007 has been taken as another turning point in terms of changes in good practice in the refrigerants handling. According to the sectoral experts, the emission factors for the period 1996-2006 are 50% higher than those from 2007 onwards (Assoclima, several years [b]).

Similarly, also the emission factors for the period from 2007 to 2014 have been estimated by expert judgment and the values of losses presented are an average of the risk relating to the entire fleet, by including machines that work correctly and those that may have problems.

For split system, the leakages are directly proportional to the number of connections according to the following equation:

$$Leakage\ rate_{split/multisplit} = 3\% * \frac{N^{\circ}\ of\ connection}{4}$$

For monosplit, the number of connections is equal to 4; for multisplit, it has been considered a weighted average of the connections equals to 10, that means a loss rate of 7.5%. Chillers and rooftops (being packaged systems) are factory sealed products, therefore leak rate is estimated equals to 1%, while VRF system, being similar to multisplit, have leak rate depending on the number of connections. The emission factor value for this equipment is 12%. More information on the assumptions is reported also in the document *"Comments on Appendix A&B of the "Preparatory study for the Review of Regulation 842/2006 /Working group 1"* (WG1, 2013). For the period from 2015 onward the operating emission factors have been reduced to consider the good practices adopted in refrigerants management as the result of the F-gas Regulation implementation. Based on the expert judgment, the emission factor for monosplit has been assumed equal to 2%, the emission factor for multisplit has been assumed equals to 4% and that for VRF equal to 6%. The appropriate manufacturing and operating emission factors for the stationary air conditioning sector are reported in the following Tables 4.58 and 4.59.

As some procedures used in manufacturing or during the installation of the RAC systems changed in 2000, also F-gases market price has influenced losses control. In fact, since the F-gases are also expensive material in the manufacturing process it was a matter of concern for the manufacturers to succeed in limiting losses in that stage and that was achieved by setting higher levels in the acceptance testing procedures.

Table 4.58 Manufacturing and operating emission factors for room air conditioner, packaged and roof top, precision air conditioning, chiller, hybrid and domestic hot water machines

Manufacturing and operating emission factors in the Stationary Air Conditioning sector				
Type of equipment	Manufacturing (%)		Operating (%)	
	1996-1999	from 2000	1996-2006	from 2007
ROOM AIR CONDITIONER				
(Monoblock without outdoor unit (ductable duct)	3.0%	0.5%	1.5%	1.0%
Portable air conditioner up to 3 kW (single duct)				
Portable air conditioner with remote condenser up to 4 kW (split type)				
PACKAGED, ROOF TOP				
(ductable or not)	3.0%	0.5%	1.5%	1.0%
PRECISION AIR CONDITIONING	3.0%	0.5%	1.5%	1.0%
CHILLER				
(Air/water cooled chiller, only cooling or heat pump)	3.0%	0.5%	1.5%	1.0%
HYBRID MACHINES				
(Heath pump + boiler)	3.0%	0.5%	1.5%	1.0%
DOMESTIC HOT WATER MACHINES				
(Heath pump)	NO	0.5%	NO	1.0%

Table 4.59 Manufacturing and operating emission factors for split and VRF

Manufacturing and operating emission factors in the Stationary Air Conditioning sector					
Type of equipment	Manufacturing (%)		Operating (%)		
	1996-1999	from 2000	1996-2006	2007-2014	from 2015
MONOSPLIT					
Outdoor condensing units connected to an indoor unit (wall floor installation, cassette, ducted false ceiling)	3.00%	0.50%	4.50%	3.00%	2.00%
MULTISPLIT					
Outdoor condensing units connected to indoor units (wall floor installation, cassette, ducted false ceiling)	3.00%	0.50%	11.30%	7.50%	4.00%
VRF					
(Only external condensing units)	3.00%	0.50%	18%	12.00%	6.00%

Emissions related to refrigerant container management are also estimated. The emission factors from containers are reported in Table 4.36.

The average lifetime for each type of air conditioning systems is from expert judgement and from IPCC Guidelines (IPCC, 2006; Assoclima, several years [b]; ISPRA-MATTM, 2013; WG1, 2013). Regarding the average lifetime, a distinction must be made between air-conditioning units used for human comfort and those used with other purposes (in example to ensure an appropriate temperature level for flower foodstuffs shops or process plants). The former are more susceptible to fashion and are often replaced before the end of their natural life cycle, also because these units are usually not subjected to constant maintenance that is often required by industrial machines. The machines aimed at human comfort are mainly with heat pump configuration while for the other uses only cooling machines are used. For this reason, only cooling chillers have a lifetime higher than heat pump chillers.

Regarding the HFC recovery at the end of life of equipment, the national experts communicated that almost all the gases of larger size machines are currently recovered, while in the smaller equipment the recovery quotas can be lower. For this smaller equipment, the gas recovery percentage has been assumed equal to 50% for the period from 1996 to 2015, while from 2015 it was set to 70% to consider the effect of F-gas Regulation (Assogastecnici, several years). For chillers a 90% recovery has been adopted. Future improvements could come from the National Register of fluorinated greenhouse gases and equipment containing fluorinated gases (DPR 146/2018).

Some issues emerged from the analysis of the database carried out by ISPRA and although some gaps were overcome thanks to the cooperation with the Responsible of the Registry, there are still criticalities on data. For this reason, we have decided not to use the information contained in the registry yet. In recent months, a new collaboration with Assofrigoristi (the national association of installers and refrigeration technicians) has been started to improve the Data Bank collection system and obtain more precise information on emission factors, gas recovery percentage, frequency of topping up but no new data or information is currently available (for more details, please see paragraph 4.7.13). Data on average lifetimes and recovery at decommissioning are reported in the technical document (ISPRA, 2026).

Service of appliances during lifetime is also considered. Unlike the refrigeration sector, where consumption data are supplied split by use (*First Charge* and *Service*), for this sector a different approach is used. For each type of equipment and thus according to the specific emission factor of this equipment, a periodic gas refilling frequency is adopted. In detail, for equipment with a higher emission factor a higher frequency is assumed. Therefore, the total amount of refrigerant placed on the market every year is equal to the

amount contained in the new equipment sold in that year plus the amount used for the maintenance in the same year.

In the following Table 4.60, the amounts of HFC placed on the market equal to the amount sold equipment plus amount used for topping up, by type of refrigerant are reported. As a result of some corrections in sales data and in the estimation process the time series of the amount of HFCs put on the market has changed compared the previous submission.

Table 4.60 Amounts of HFC placed on the market of Stationary air conditioning (t), 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
Amounts of HFC placed on the market (t)										
HFC-134a	7.36	34.59	165.19	107.66	107.51	84.51	95.70	92.34	107.66	106.27
R-410A	4.26	8.79	1,205.51	2,349.04	2,230.16	1,115.37	1,273.29	1,259.10	950.06	850.20
R-407C	2.33	71.70	1,014.87	293.87	211.57	40.54	19.36	8.74	9.69	14.03
R-32	NO	NO	NO	NO	NO	1,630.30	2,269.77	2,869.47	2,572.23	2,838.16
R-513A	NO	NO	NO	NO	NO	NO	NO	7.08	15.13	11.98
R-454C	NO	NO	NO	NO	NO	NO	NO	NO	5.31	4.32
R-515B	NO	NO	NO	NO	NO	NO	NO	NO	1.62	1.58
R-5454B	NO	NO	NO	NO	NO	NO	NO	NO	NO	1.94

HFC emissions estimation from Stationary air conditioning subsector

HFC emissions from Stationary Air Conditioning have been estimated according to 2006 IPCC Guidelines (Tier 2a methodology). Based on the amounts of refrigerant placed on the market, the HFC average annual stock for each year and refrigerant is calculated.

In Table 4.61 the HFC average annual stocks are reported. As mentioned earlier, some corrections in sales data and other parameters have resulted in an update of the HFC average annual stock.

Table 4.61 HFC average annual stock for Stationary air conditioning (t), 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
Average annual stock (t)										
HFC-134a	7.36	100.66	750.43	1,350.78	1,585.75	1,850.51	1,918.17	1,978.43	2,048.89	2,112.74
R-410A	4.26	35.45	3,018.58	11,201.24	18,800.02	22,545.03	22,029.44	21,069.52	19,987.54	19,084.61
R-407C	2.33	127.43	3,823.56	5,781.39	5,731.32	2,896.63	2,282.31	1,706.78	1,346.30	1,162.81
R-32	NO	NO	NO	NO	NO	4,614.47	6,766.05	9,465.08	11,806.77	14,359.33
R-513A	NO	NO	NO	NO	NO	NO	NO	7.08	22.14	33.90
R-454C	NO	NO	NO	NO	NO	NO	NO	NO	5.31	9.57
R-515B	NO	NO	NO	NO	NO	NO	NO	NO	1.62	3.19
R-5454B	NO	NO	NO	NO	NO	NO	NO	NO	NO	1.94

Amount of refrigerants stocked in the containers is also estimated and reported under “Emissions from stocks”, together with the lifetime emissions. The amount of HFC stocked in the containers is reported in Table 4.62.

Table 4.62 HFC stocked in containers for the Stationary air conditioning sector (t), 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC stocked in containers (t)										
HFC-134a	20.84	82.09	367.82	361.57	294.3	252.50	252.92	223.03	248.45	223.42
R-410A	3.57	9.03	257.18	1,030.31	1,131.16	990.02	962.62	941.80	834.14	285.64
R-407C	3.33	65.61	555.65	302.48	214.56	41.62	20.02	9.06	9.74	1.07
R-32	NO	NO	NO	NO	NO	30.28	63.05	237.93	341.64	223.97
R-513A	NO	NO	NO	NO	NO	NO	NO	25.81	33.15	31.91
R-454C	NO	NO	NO	NO	NO	NO	NO	NO	10.15	11.16
R-515B	NO	NO	NO	NO	NO	NO	NO	NO	6.18	7.26
R-5454B	NO	NO	NO	NO	NO	NO	NO	NO	NO	3.30

The disposal emissions have been calculated as the difference between the remaining HFC in products at decommissioning and the quantity of HFC recovered. Based on the product life leakage rate and the average lifetimes, the charge remaining at decommissioning is calculated as:

$$(1 - \text{product life leakage rate}) * \text{average lifetimes.}$$

In Table 4.63 the containers, manufacturing, lifetime and disposal emissions are reported.

Table 4.63 HFC emissions from Stationary air conditioning (t), 1996-2024

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
Containers emissions (t)										
HFC 134a	1.13	2.32	6.57	5.19	2.03	1.37	1.32	1.20	1.34	1.19
HFC-125	0.13	0.42	2.68	5.91	3.10	2.53	2.43	2.37	2.10	0.72
HFC-32	0.13	0.39	2.56	5.85	3.07	2.67	2.74	3.55	3.82	1.86
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Manufacturing emissions (t)										
HFC 134a	0.64	0.57	3.17	1.81	1.39	1.21	1.21	1.10	1.23	1.17
HFC-125	0.07	0.10	1.25	1.59	1.36	1.15	1.20	0.94	0.91	0.71
HFC-32	0.07	0.10	1.19	1.59	1.36	1.21	1.36	1.71	2.01	1.84
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	0.003	0.003
Lifetime emissions (t)										
HFC 134a	0.14	4.45	108.38	113.11	78.58	46.15	39.33	32.82	29.56	28.46
HFC-125	0.12	2.27	138.4	285.15	270.46	305.29	294.13	278.00	263.27	252.41
HFC-32	0.11	2.15	134.67	281.32	268.05	422.42	463.79	508.03	548.53	613.18
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	0.001	0.003
Disposal emissions (t)										
HFC-134a	NO	NO	NO	8.05	36.88	176.02	141.30	130.14	72.04	30.19
HFC-125	NO	NO	NO	0.16	11.07	240.65	247.06	307.59	253.84	194.31
HFC-32	NO	NO	NO	0.15	10.4	233.99	241.70	302.68	251.14	193.24
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total emissions (t)										
HFC-134a	1.92	7.34	118.12	128.16	118.87	224.76	183.15	165.26	104.17	61.02

2.F.1.f Stationary Air Conditioning	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC-125	0.32	2.79	142.33	292.81	285.99	549.62	544.82	588.90	520.13	448.15
HFC-32	0.32	2.64	138.43	288.9	282.88	660.29	709.58	815.97	805.49	810.12
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	0.004	0.006

Total HFC emissions from the stationary air conditioning equipment increased from 1996, driven by the increase of their consumptions. In years when the operating emission factor decreased (2006 and 2015) to account for the effects of F-gas regulations, emissions decreased but the trend has been always increasing throughout the period from 1996 to 2019. The years 2020 and 2021 have shown a contraction in gas consumption due to effect of the Sars-Covid 19 pandemic, followed by an increase in 2022 and 2023 and a significant drop in 2024, due to the introduction of alternatives.

4.7.9 Foam blowing (2.F.2)

Refrigerants market: activity data and HFC used in Foam blowing

The estimates of emissions from Foam blowing subsector are based on single gas consumption data supplied by Solvay, the only national refrigerants producer, and by Assogastecnici, the Association of companies involved in the production and distribution of technical, special and medicinal gases (Solvay, 1998; Solvay, 2006; Assogastecnici, several years).

HFC-245fa and HFC-134a only are used in the subsector and no information is available on the type of foam, if open or closed cells, on which a different emission factor depends. To gather this information and data, the inventory team contacted the main national associations of foam blowing and the experts of the sector who reported that closed cells are more widespread than open cell foams and that other information at present is not available. For this reason, HFC consumptions have been entirely attributed to closed cells.

In Table 4.64, gas consumption is reported.

Table 4.64 Consumption of HFC contained in the Foam blowing (t), 1994-2024

2.F.2.a Foam blowing	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Consumptions (t)											
HFC 134a	NO	NO	338.00	980.00	718.39	408.34	224.29	187.48	160.00	NO	NO
HFC 245fa	NO	NO	NO	800.00	973.32	1,010.66	370.71	242.72	200.00	NO	NO
Total HFC Consumptions (t)	NO	NO	338.00	1,780.00	1,691.72	1,419.00	595.00	430.20	360.00	NO	NO

HFC emissions estimation from Foam blowing sub-sector

The methods used to calculate F-gas emissions from the Foam blowing subsector is the 2006 IPCC Guidelines Tier2a. Total emissions have been calculated as the sum of manufacturing emissions, lifetime emissions and disposal emissions. The "Recovery" was calculated as the "Amount remaining in products at decommissioning" minus "Disposal emissions".

Emission factors for the closed cells reported in the 2006 IPCC Guidelines were used (Table 4.65), constant for the whole time series.

The average lifetimes and the percentage of recovered gas at decommissioning have been applied are also based on default values from 2006 IPCC Guidelines and expert judgment. However, since an average life of 50 years has been assumed, the foam decommissioning will start only in 2048.

Table 4.65 Manufacturing and operating emission factors, average lifetime and recovery at decommissioning for Foam blowing

Subsector	Emission factors (%)		Average Lifetimes (years)	Recovery at decommissioning (%)
	Manufacturing	Operating		
Foam blowing (closed cells)	10%	4.5%	50	0

Based on gas consumption, emission factors and the average lifetime, the average annual stock for each gas and year was calculated (Table 4.66).

Table 4.66 HFC average annual stock for the Foam blowing (t), 1996-2024

2.F.2.a Foam blowing	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Average annual stock (t)											
HFC 134a	NO	NO	345.92	1,823.77	3,155.01	3,566.28	3,438.58	3,368.21	3,288.64	3,140.65	2,999.32
HFC 245fa	NO	NO	NO	1,528.61	3,074.34	4,627.11	4,940.10	4,827.02	4,699.81	4,488.31	4,286.34
Total HFC average annual stock (t)	NO	NO	345.92	3,352.38	6,229.35	8,193.40	8,378.68	8,195.23	7,988.44	7,628.96	7,285.66

In Table 4.67, an overview of the total emissions (manufacturing, lifetime and disposal) from the Foam blowing sub-sectors is given for the 1990-2024 period, per compound. No recalculation occurred for this sector.

Table 4.67 HFC emissions from Foam blowing (t), 1990-2024

2.F.2.a Foam blowing	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Manufacturing emissions (t)											
HFC 134a	NO	NO	33.80	98.00	71.84	40.83	22.43	18.75	16.00	NO	NO
HFC 245fa	NO	NO	NO	80.00	97.33	101.07	37.07	24.27	20.00	NO	NO
Lifetime emissions (t)											
HFC 134a	NO	NO	15.57	82.07	141.98	160.48	154.74	151.57	147.99	141.33	134.97
HFC 245fa	NO	NO	NO	68.79	138.35	208.22	222.30	217.22	211.49	201.97	192.89
Disposal emissions (t)											
HFC 134a	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 245fa	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total HFC emissions (t)											
HFC 134a	NO	NO	49.37	180.07	213.81	201.32	177.17	170.32	163.99	141.33	134.97
HFC 245fa	NO	NO	NO	148.79	235.68	309.29	259.38	241.49	231.49	201.97	192.89

4.7.10 Fire protection (2.F.3)

The estimate of emissions from the Fire protection sector has been changed compared to Submission 2025, as a technical correction has been made following the Inventory EU review process. Specifically, as part of the EU Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/84, expert review team (ERT) pointed at that Italy

reported high per capita emissions compared to other Member States and requested clarification from the Italian inventory team. As a result, the breakdown between service refills and initial refills was revised by changing the method for estimating refills. In addition, another change concerned the estimate of the initial charge for R-23. This charge was set at zero from 2016 onwards to consider the F-gas Regulation, which prohibits the use of this gas in new equipment from January 1, 2016.

The changes described above have led to a reduction in emissions in the sector compared to 2025 submission. For details, please refer to paragraph 4.7.14.

Refrigerants market: activity data and HFC used in Fire protection

The estimates of emissions from Fire extinguishers are based on single gas consumption data. The European Association for Responsible Use of HFCs in Fire Fighting was contacted (ASSURE, 2005), as well as the Consortium of fire protection systems (Clean Gas, 2001). More in details HFC-227ea partial consumptions for fire extinguishers along the whole time series has been provided by Clean Gas Consortium. Because other Consortia of fire protection systems are present in the country, consumption data provided by Clean Gas have been multiplied for a factor equal to five according to expert judgment and a comparison with the stock of gas estimated in 2005 (Gastec Vesta, 2017). HFC-227ea consumption levels have been supplied for the years 1990-2000 together with projections of consumptions for the years 2005 and 2010, for which Clean Gas estimated the same value (130 t). Data from 2000 to 2004 have been extrapolated, data from 2005 to 2010 has been assumed constant (130 t) and data from 2011 onwards have been estimated based on the following assumptions. From 2010, according to information supplied by industry (Gastec Vesta, 2017) the amount of HFC-227ea started to decrease, replaced by the new chemical Novec concurrently with the entering in force of the Regulation n. 517/2014 (EU, 2014): in 2016 the consumption of HFC-227ea can be assumed the 80% of the 2010 consumption. According to the expert judgment and ASSURE, because of HFC-227ea covers the 90% of the fire extinguishers market, consumption data of HFC-125 and HFC-23 have been estimated, considering that HFC-125 is 2/3 of the remaining quota. In addition to the Novec, among the best alternative solutions to HFCs on the market are inert gases but at the moment no information about the quotas placed in the market is available. From 2021 the value has been estimated on the basis of HFC 227ea, HFC 23 and HFC 125 consumptions provided by Assogastecnici (Assogastecnici, several years): data are coherent with those estimated with the previous approach. ANIMA, the Federation of National Associations of Mechanical and Engineering similar which includes fire protection industry, has been contacted to verify the presence of Consortia of fire protection systems. At present also the Federation does not provide updated information. Investigation to collect information on the HFC recovery, recycling, regeneration or disposal activities used in fire extinguishers sector was carried out from ISPRA, contacting one of the major fire protection Company, Gielle, that collects, throughout the national territory, exhausted refrigerant gases, CFCs, HCFCs and HFCs, to be sent for recovery, recycling, regeneration or disposal. According to Gielle, at the end of life no emissions occur when the equipment is delivered to an authorized and expert company.

In the following Table 4.68, the HFC consumptions are summarized.

Table 4.68 HFC consumptions for Fire protection (t), 1990-2024

2.F.3 Fire protection	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 227ea	NO	38.75	210.00	780.00	780.00	650.00	433.49	410.67	350.00	350.00	205.14
HFC 23	NO	1.44	7.78	28.89	28.89	15.00	10.83	10.00	9.17	8.33	7.50
HFC 125	NO	2.87	15.56	57.78	57.78	48.15	32.11	30.42	25.93	25.93	15.20
Total HFC Consumptions (t)	NO	43.06	233.33	866.67	866.67	713.15	476.43	451.09	385.09	384.26	227.84

HFC emissions estimation from Fire protection

Emissions from Fire Protection are calculated based on 2006 IPCC Guidelines Tier2a methodology. ASSURE provided us with information concerning losses rates in manufacturing firefighting systems (0%) and during the average lifetime of the fire extinguishers (less than 5%) (ASSURE, 2005). About the lifetime emission, national fire protection industries explained that an alarm safety system installed in the fire protection equipment starts when losses are over 5%. The whole gas is considered emitted and not recovered as required by the latest European and National legislation. In Table 4.69 the emission factors, the average lifetime and recovery at decommissioning used for the emissions estimation are reported.

Table 4.69 Manufacturing and operating emission factors, average lifetime and recovery at decommissioning for Fire extinguishers

Subsector	Emission factors (%)		Average lifetime (years)	Recovery at decommissioning (%)
	Manufacturing	Operating		
Fire protection	0%	5%	15	0%

The average annual stock for each gas used in the Fire protection sector is shown in the following table 4.70. Data are from 1990 to 2024.

Table 4.70 HFC average annual stock for Fire protection (t), 1990-2024

2.F.3 Fire protection	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 227ea	NO	77.58	804.21	3,172.59	5,909.42	7,062.53	6,190.55	5,794.13	5,380.00	5,007.49	4,528.89
HFC 23	NO	2.87	29.79	117.50	218.87	252.50	164.78	141.77	119.91	99.12	79.36
HFC 125	NO	5.75	59.57	235.01	437.73	523.15	458.56	429.19	398.52	370.93	335.47
Total HFC average annual stock (t)	NO	86.20	893.57	3,525.10	6,566.02	7,838.19	6,813.89	6,365.09	5,898.43	5,477.55	4,943.73

In Table 4.71, an overview of the total emissions (manufacturing, lifetime and disposal) from the Fire protection sector is given for the 1990-2024 period, per compound. Emissions from manufacturing are not occurring because the emission factor is equal to zero.

Table 4.71 HFC emissions from Fire protection (t) 1990-2024

2.F.3 Fire protection	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Manufacturing emissions (t)											
HFC 227ea	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 23	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 125	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Lifetime emissions (t)											
HFC 227ea	NO	3.88	40.21	158.63	295.47	211.88	185.72	173.82	161.40	150.22	135.87
HFC 23	NO	0.14	1.49	5.88	10.94	7.58	4.94	4.25	3.60	2.97	2.38
HFC 125	NO	0.29	2.98	11.75	21.89	15.69	13.76	12.88	11.96	11.13	10.06
Disposal emissions (t)											
HFC 227ea	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 23	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
HFC 125	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total emissions (t)											
HFC 227ea	NO	3.88	40.21	158.63	295.47	211.88	185.72	173.82	161.40	150.22	135.87
HFC 23	NO	0.14	1.49	5.88	10.94	7.58	4.94	4.25	3.60	2.97	2.38

2.F.3 Fire protection	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 125	NO	0.29	2.98	11.75	21.89	15.69	13.76	12.88	11.96	11.13	10.06

4.7.11 Aerosol (2.F.4)

Refrigerants market: activity data and HFC used for Aerosol

The estimates of emissions are based on single gas consumption data. Pharmaceutical industry has provided aerosols/metered dose inhaler data (Sanofi Aventis, several years; Boehringer Ingelheim, several years; Chiesi Farmaceutici, several years; GSK, several years; Lusofarmaco, several years; Menarini, several years; Istituto De Angeli, several years). Due to the methodology used to estimate emissions, based on the consumption of the F-gases, the estimated consumption also includes the amount of fluid contained in the imported products. As for aerosols (i.e. MDI), every year the relevant operators provide us with the consumption of F-gases used in the national production process. Some of the reporting operators manufacture the MDI at Italian facilities as well as export the products, while some others just market in Italy imported MDI. In the following Table 4.72 the HFC-134a consumptions are reported.

Table 4.72 Consumption of HFC contained in the MDI (t), 1990 -2024

2.F.2.a Aerosol	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC 134a	NO	NO	8.8	97.25	208.39	221.78	332.78	336.76	411.65	427.47	459.82

HFC emissions estimation from Aerosol

Emissions from MDI are estimated based on HFC consumptions and losses rates provided by the relevant operators in Italy, using the Equation 7.6 of the 2006 IPCC Guidelines. Specifically, the loss rate during manufacturing is set at 1.95% while it is assumed that 50% of the chemical charge escapes within the first year and the remaining charge escapes during the second year, according to 2006 IPCC Guidelines. The average lifetimes and the percentage of recovered gas at decommissioning applied are based on default values from 2006 IPCC Guidelines and expert judgment. In the following table 4.73 the main parameters used for the emissions estimations are reported.

Table 4.73 Manufacturing and operating emission factors, average lifetime and recovery at decommissioning for MDI.

Subsector	Emission factors (%)		Average lifetimes (years)	Recovery at decommissioning (%)
	Manufacturing	Operating		
Metered Dose Inhalers	1.95	50%	2	0

The total emissions from the Aerosol subsector for each year are reported in Table 4.74.

Table 4.74 HFC emissions from MDI (t), 1990-2024

2.F.2.a Aerosol	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Manufacturing emissions (t)											
HFC 134a	NO	NO	0.17	1.90	4.06	4.32	6.49	6.57	8.03	8.34	8.97
Lifetime emissions (t)											
HFC 134a	NO	NO	81.37	223.42	196.63	125.05	152.00	114.96	109.09	125.57	136.19
Disposal emissions (t)											
HFC 134a	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Total HFC emissions	NO	NO	81.54	225.32	200.69	129.37	158.49	121.52	117.12	133.90	145.15

4.7.12 Uncertainty and time-series consistency

The combined uncertainty in F-gas emissions for HFC and PFC emissions from HFC and PFC used as substitutes for ODS is estimated to be about 58% in annual emissions, 30% and 50%, concerning activity data and emission factors, respectively.

HFC emissions (expressed in ktCO₂eq) from refrigeration sector increased from 1994 to 2014, driven by the increase of their consumptions. The maximum value of emissions was registered in 2014 with 8,017.75 ktCO₂eq then emission started to decrease and in 2024 they are equal to 3,034.24 ktCO₂eq (Table 4.75). The largest contribution to emissions comes from the commercial refrigeration subsector for all years except for the period from 1995 to 2010, when the industrial refrigeration subsector registered the highest emissions. The lowest emissions are from domestic refrigeration (Figure 4.3).

HFC total consumption started to decrease from 2003 due to the reduction of the quantity of hydrofluorocarbons placed on the market. Over the entire series, the maximum value of gases consumptions was registered in 2003 with 5,316 t. From 2003 consumptions of refrigerants with high GWP constantly decreased until; in 2014 new refrigerants with a lower GWP entered in the market as alternatives due to the F-gas Regulation 517/2014, resulting in an increase of the total consumption equal to 5,276.38t. From 2014 a strong reduction in consumption is registered and in 2024 HFC total consumption is 1,695.24t (2,985.16 ktCO₂ eq.): in the face of a reduction of the refrigerant consumptions expressed in tons of approximately 68% (2014 – 2024), there has been a decrease of approximately 82% in the same consumption expressed in CO₂ eq. (Figure 4.4).

Table 4.75 Total HFC emissions from Refrigeration sector (ktCO₂eq), 1990-2024

Emissions Refrigeration Sector (ktCO₂eq)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
C2F6	NO	NO	NO	NO	NO	11.06	16.89	17.82	18.85	19.13	14.21
HFC 23	NO	40.25	111.60	142.54	116.77	154.62	120.10	114.80	113.99	113.62	77.24
HFC 134a	NO	80.81	1,066.61	2,174.75	2,341.16	1,582.61	1,116.28	1,060.18	993.73	1,004.08	925.56
HFC 143a	NO	9.74	608.43	2,213.23	3,183.72	3,254.51	1,559.03	1,348.49	1,085.83	942.11	829.98
HFC 125	NO	5.87	354.35	1,282.31	1,835.81	2,233.92	1,571.76	1,504.05	1,365.81	1,431.08	1,145.12
HFC 32	NO	NO	NO	NO	NO	8.85	44.49	49.93	43.17	54.12	42.12
Total emissions (ktCO₂eq)	NO	136.67	2,140.98	5,812.83	7,477.46	7,245.57	4,428.55	4,095.28	3,621.39	3,564.14	3,034.24

Figure 4.3 Total HFC emissions by sub-sector of refrigeration sector (ktCO₂eq), 1990-2024





Figure 4.4 Total HFC consumptions from refrigeration sector (kt CO₂eq), 1990-2024



HFC consumptions from MAC sub-sector increased until 2006 when they reached the value of 2,455.9t (equal to 3,192.65 ktCO₂eq). In 2020 a strong decline in consumptions compared to the previous year was registered, probably due to the SARS_COVID19 pandemic, with a new increase in the following year. Specifically, in 2024 a consumption of 582.23 t (756.89 ktCO₂eq) was recorded. HFC total emissions from MAC continued to increase until 2009 when they reached the maximum value of 2,074.68 ktCO₂eq. A major decrease started from 2018. In 2024 the emissions were equal to 544.96 ktCO₂eq. The emissions reduction trend is postponed compared the consumption trend because of the methodology adopted. In Table 4.76 the total emissions of HFC from MAC subsector are reported.

Table 4.76 Total HFC emissions from MAC sector (ktCO₂eq), 1990-2024

Emissions (kt CO ₂ eq)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC-134a	NO	469.58	1,220.34	1,831.61	2,072.40	1,730.14	1,122.50	1,007.68	841.88	732.86	544.96

HFC emissions from the Stationary air conditioning equipment increased from 1996 driven by the increase of their consumptions. The overall consumptions trend was increasing until 2016 and then it started to decline. In 2020 there was a consumptions reduction, due to the Sars Covid-19 pandemic, with a recovery in the following years. For emissions, the maximum value was registered in 2019 with 2,780.04 ktCO₂eq. while in 2024 emissions were 2,048.41 ktCO₂eq. (Table 4.77). Because of the methodological approach adopted, emission reduction is postponed compared to consumption reduction. The HFC substitution process with the alternatives with a lower or null GWP, some of which flammable, started in delay in respect the other sectors because of highly restrictive Italian regulation about the use of flammable refrigerants in public buildings. In this context, the use of HC, which is highly inflammable, as alternative of the traditional gases initially concerned the portable conditioning systems due to their small charge. R-32 gas entered in the Italian market in 2016 in the residential split with an increasing use over the years and in 2022 VRFs, roof tops and air-cooled chillers using R32 have also entered the market. Also in 2022, the first R-513A chillers appeared, albeit in small percentages and in 2023 chillers equipped with R-454C and R-515B also entered the market; in 2024 rooftop started to use R454B. Among the new refrigerants, not belonging to the F-gas family, hydrocarbons and hydrofluoroolefins should be mentioned. Small percentages of chillers use these gases today and are expected to increase in the coming years.

Table 4.77 Total HFC emissions from Stationary Air Conditioning sector (kt CO₂eq), 1996 – 2024

Emissions (KtCO ₂ eq)	1996	2000	2005	2010	2015	2020	2021	2022	2023	2024
HFC-134a	2.50	9.54	153.56	166.61	154.53	292.19	238.10	214.84	135.42	79.32
HFC-125	1.01	8.84	451.19	928.21	906.56	1,742.30	1,727.08	1,866.81	1,648.80	1,420.62
HFC-32	0.22	1.79	93.72	195.59	191.51	447.02	480.39	552.41	545.32	548.45
HFC-227ea	NO	NO	NO	NO	NO	NO	NO	NO	0.01	0.02
Total HFC emissions (ktCO₂eq)	3.73	20.17	698.46	1,290.40	1,252.60	2,481.50	2,445.56	2,634.06	2,329.56	2,048.41

HFC emissions from Foam blowing, Fire extinguishers and Aerosols sub-sectors increased from 1994, driven by the increase of their consumptions. HFC consumption from Foam blowing increased until 2004 when the maximum value of 1,865.36t (equal to 2,027.17 ktCO₂eq.) was registered. A much more pronounced reduction in consumption has begun since 2014, due to the reduction of the quantity of hydrofluorocarbons placed on the market as well as the restrictions for some products and equipment derived from the entering in force of the European F-gases Regulation (EU, 2014). The foam emissions started to decrease since 2014 when they reached the maximum value of 531.45 ktCO₂eq. In 2024, emissions were equal to 340.96 ktCO₂eq.

For Fire extinguishers sub-sector, F-gas consumptions increased until 2005 and after a few years of stability, in 2011 they started to decrease. In fact, as with the foam sector, the availability of low- or zero-GWP alternatives has enabled a more rapid phase out of HFCs. The HFC total emissions for Fire extinguishers increased until 2014 when they reached the value of 1,402.92 ktCO₂eq. In 2024, with 516.60t, there was a slightly decrease compared the previous year. Due to the methodological approach followed, the reduction in emissions is postponed in time compared to the reduction in consumption.

For Aerosol sub-sector, emissions increased from 1990 to 2006 when they registered the maximum value of 303.61 ktCO₂eq t. Then they decreased until 2016 with the minimum value of 149.24 ktCO₂eq. A new

increase was registered from 2016 to 2019 and then they came back to decline. In 2024 HFC emissions were equal to 188.70 ktCO₂eq. Emissions from MAC, foam blowing, fire extinguishers and Aerosols sector are reported in Table 4.78.

Table 4.78 HFC emissions from MAC, Foam blowing, Fire protection and Aerosols sectors (kt CO₂eq), 1990-2024

Emissions (ktCO ₂ eq)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
2.F.2.a - Foam blowing (closed cell)											
HFC 134a	NO	NO	64.18	234.09	277.96	261.71	230.31	221.41	213.19	183.73	175.46
HFC 245fa	NO	NO	0.00	127.66	202.21	265.37	222.54	207.20	198.62	173.29	165.50
<i>Total emissions (ktCO₂eq)</i>	<i>NO</i>	<i>NO</i>	<i>64.18</i>	<i>361.75</i>	<i>480.17</i>	<i>527.08</i>	<i>452.86</i>	<i>428.61</i>	<i>411.80</i>	<i>357.02</i>	<i>340.96</i>
2.F.3 - Fire protection											
HFC 227ea	NO	12.99	134.71	531.41	989.83	709.78	622.15	582.31	540.69	503.25	455.15
HFC 23	NO	1.78	18.47	72.85	135.70	93.93	61.30	52.74	44.61	36.87	29.52
HFC 125	NO	0.91	9.44	37.25	69.38	49.75	43.61	40.82	37.90	35.28	31.90
<i>Total emissions (ktCO₂eq)</i>	<i>NO</i>	<i>15.69</i>	<i>162.61</i>	<i>641.51</i>	<i>1,194.91</i>	<i>853.47</i>	<i>727.06</i>	<i>675.86</i>	<i>623.19</i>	<i>575.40</i>	<i>516.58</i>
2.F.4 – Aerosol											
HFC-134a (ktCO ₂ eq)	NO	NO	106.00	292.91	260.9	168.19	206.03	157.98	152.25	174.07	188.70
<i>Total emissions (ktCO₂eq)</i>	<i>NO</i>	<i>NO</i>	<i>106.00</i>	<i>292.91</i>	<i>260.90</i>	<i>168.19</i>	<i>206.03</i>	<i>157.98</i>	<i>152.25</i>	<i>174.07</i>	<i>188.70</i>

4.7.13 Source-specific QA/QC and verification

This source category is covered by the general QA/QC procedures.

Air conditioning category, as well as refrigeration, foam blowing, fire extinguishers and aerosols has been analyzed with experts of the national associations, in the framework of the study planned by the agreements with the Ministry of Environment for a survey, about HFCs alternative substances with low GWP, natural refrigerants and alternative technologies. Besides, a continuous sharing of information between the experts of the national association and the Inventory team is ongoing by enabling both the collection of new data and the verification and updating of those used to date.

In January 2019, the new National Telematic Registry of fluorinated greenhouse gases and equipment containing fluorinated gases instituted by DPR 146/2018, entered into force. Compared to the previous National F-gas Data Bank (established by Presidential Decree 43/2012), which includes refrigeration, air conditioning and fire protection systems, the new Registry also contains data on electrical switches and cold rooms in refrigerated trucks or trailers. ISPRA is not involved in data collection but has access to the database.

As already reported in the previous Submission, we have already started to check data of the Registry but it emerged that the information contained is not always in the form and at the level of detail useful for estimating the Inventory. We worked with the Responsible of the Registry to try to overcome some of the issues that have emerged after the check of the database. Although some gaps were overcome, there are still critical data. For this reason, we have decided not to use the information contained in the registry yet. In 2024 a new collaboration with Assofrigoristi has been initiated to improve the Data Bank collection system and obtain more precise information on emission factors, gas recovery percentage and frequency of equipment topping up. In detail, Assofrigoristi launched an initial survey among the Association by requesting data and information. The data collected at the moment does not yet have statistical value and

therefore cannot be used. Through this collaboration, we expect to be able to verify and update the data we use.

4.7.14 Source-specific recalculation

As already mentioned in the previous paragraphs, a technical correction has been applied in the framework of EU Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999, resulting in a remarkable revision of emissions from 2F3 Fire protection subcategory. The revision resulted in a reduction in emissions from firefighting compared to submission 2025; for 2023 the updated emissions in ktCO₂eq are approximately 65% lower than the emissions estimated in the previous 2025 submission.

A minor recalculation occurred in sector 2F1 refrigeration and air conditioning (except for Domestic refrigeration), while no recalculation was made for the aerosol and foam sub-sectors.

In Table 4.79 the difference between 2026 and 2025 submissions for total 2F sector is reported from 2014, by single gas emitted, a focus on the recalculation for the Fire protection sector is also reported.

Table 4.79 Differences between 2026 and 2025 submission for RACHP sector (%)

Difference in emissions for the 2F sector for gases (%)	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
C2F6	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
HFC 23	-4.85%	-24.22%	-26.19%	-28.28%	-30.85%	-33.81%	-37.25%	-40.49%	-42.96%	-45.20%
HFC 32	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	-1.22%	-0.09%
HFC 125	-0.18%	-1.29%	-1.31%	-1.36%	-1.38%	-1.37%	-1.58%	-1.70%	-2.49%	-0.82%
HFC 134a	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	-0.86%	0.33%
HFC 143a	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
HFC 245fa	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
HFC 227ea	-7.74%	-45.63%	-46.26%	-47.60%	-49.60%	-52.18%	-55.31%	-58.15%	-60.83%	-63.27%
<i>Difference in emissions for the Fire extinguishers sub-sector only (%)</i>	-7.74%	-45.65%	-46.46%	-47.96%	-50.12%	-52.86%	-56.17%	-59.18%	-62.03%	-64.64%

4.7.15 Source-specific planned improvements

Recovery of gas at equipment end-of-life is expected to improve through the National Telematic Registry of fluorinated greenhouse gases, established by DPR 146/2018, in force since January 2019. Compared to the previous F-gas Data Bank (DPR 43/2012), which covered refrigeration, air conditioning, and fire protection systems, the Registry also includes data on electrical switches and refrigerated truck or trailer cold rooms, enabling analysis of these systems as well. Initial reviews of Registry data show that, despite some improvements, the information is not consistently detailed or structured enough for Inventory estimation, and critical data gaps remain. Therefore, the Registry data are not yet being used. A collaboration with Assofrigoristi, launched at the end of 2023, aims to improve data collection (see paragraph 4.7.4).

To improve estimates across all subcategories, a constant engagement with national experts and associations is maintained, to gather newly available data, accounting for market changes such as new refrigerants, technological advancements in equipment, and improved gas management practices that influence emission factors. Further improvement could come from the collaboration with the Department of Pure and Applied Sciences of the University of Urbino Carlo Bò within the PARIS Project (Process Attribution of Regional Emissions). The Horizon Europe research project aims to significantly increase

knowledge on the emissions of climate "forces" from eight European countries (including F-gas and Italy), focusing on the interface between bottom-up and top-down approaches and aiming to strengthen collaboration between scientists and teams that deal with the preparation of national inventories in order to calibrate the results deriving from atmospheric models (Inverse model) that use measurement data recorded by 4 existing stations in Europe (one of which is present in Italy on Monte Cimone) and 5 of future installation and those deriving from the estimates of the inventories.

4.8 Other product manufacture and use (2G)

4.8.1 Source category description

The sub-sector "Other product manufacture and use" consists of the following sub-applications:

2.G.1 – SF₆ Emissions from electrical equipment

2.G.2 – SF₆ used in equipment in university and research particle accelerators

2.G.3 – N₂O from product uses

The share of SF₆ emissions from the sector in the national total of SF₆ was 72.1% in the base-year 1990, and 75.3% in 2024, whereas in the national total of F-gases, the share of SF₆ emissions from the sector was 8.9% in 1990 and 3.37% in 2024. N₂O accounts for only 3.4% of the national total N₂O emissions in 2024.

4.8.2 Methodological issues

Electrical Equipment (SF₆)

As regards SF₆ emissions from electrical equipment, these have been estimated according to the IPCC Tier 2 approach. Concerning manufacturing and installation emissions, since 1995 the methodology used is largely in accordance with the IPCC Tier 3 methodology. In 1997, the ANIE Federation began a statistical survey within their associated companies, in accordance with ISPRA, to monitor yearly SF₆ used in electrical equipment > 1kV, and thus SF₆ manufacturing emissions (ANIE, 2001). ANIE Federation is the Confindustria member representing the electrotechnical and electronic companies operating in Italy. ANIE has developed data sheets for their associated companies in accordance with the methodology drawn up by CAPIEL, the Coordinating Committee for the Associations of Manufacturers of Switchgear and Controlgear equipment in the European Union: the CAPIEL inventory methodology covers all sorts of use of SF₆ in the electrical sector, from the SF₆ purchase till the end of life of the equipment and covers all aspects of the required data (CAPIEL, 2002). It is based on a Mass Balance Methodology, as given by IPCC Tier 3b, comparing the input and output on a yearly basis. In Table 4.80 the summary sheet used for manufacturing inventory is reported (ANIE, several years).

Table 4.80 SF₆ balance at manufacturing level (year 2024)

INVENTORY'S CATEGORIES					Year 2024 (kg)
1. Purchased amount	1.1 In Italy		Weight of SF ₆ contained in the tanks		4,354
	1.2 Abroad		Weight of SF ₆ contained in the tanks		62,818
				TOTAL 1.	67,172
2. Amount contained in the equipment at the terms of sale	2.1 In Italy	2.1.1 ENEL	Weight of SF ₆ contained in the equipment and in the tanks		18,075

INVENTORY'S CATEGORIES					Year 2024 (kg)
		2.1.2 Energy industry and railways	Weight of SF ₆ contained in the equipment and in the tanks		17,861
		2.1.3 Others (Industry, Tertiary, Private, etc.)	Weight of SF ₆ contained in the equipment and in the tanks		3,846
	2.2 Abroad		Weight of SF ₆ contained in the equipment and in the tanks		13,990
				TOTAL 2.	53,772
3. Amount contained in the equipment returned to the manufacturer			Weight of SF ₆ contained in the equipment and in the tanks	TOTAL 3.	0
4. a) Destroyed amount			Weight of SF ₆ in the equipment sent to authorized disposal treatment		0
4. b) Amount returned to the manufacturer			Weight of SF ₆ returned to manufacturer for authorized recycling		4,203
				TOTAL 4.	4,203
5. Annual stock changes				TOTAL 5.	8164
SF₆ emissions from manufacturing		Balance input-output (1+3-5)-(2+4)			1,033

From 1990 to 1994 emissions have been estimated based on leakage rate during manufacturing and installation and the amount of SF₆ contained in the equipment sold to the end users, because, for this period, only data referred to point 1 and point 2 of the Table 4.80, are available from ANIE. The leakage rates during manufacturing and installation of the equipment, used to estimate the SF₆ emissions, are reported in Table 4.81. Leakage rates have been derived from ANIE Federation expert judgement.

Table 4.81 Leakage rates used to estimate SF₆ emissions from manufacturing and installation from 1990 to 1994

	1990	1991	1992	1993	1994
Manufacturing	0.060	0.060	0.060	0.060	0.060
Installation	0.060	0.055	0.050	0.045	0.040

In Table 4.82, SF₆ emissions from manufacturing (which include installation), operating and disposal are reported. Emissions from manufacturing were about 14t in 1995, whereas in 2024 are only 1.03t, due to the great increase of the SF₆ recycled. The emissions trend from manufacturing is strongly decreasing thanks to the diligence of the companies involved, which have taken voluntary actions to reduce emissions as much as technically possible. Probable fluctuations within the time series in manufacturing emissions are basically due to yearly variation of the stocked quantity of SF₆.

Table 4.82 SF₆ emissions from manufacturing, operating and disposal from 1990 to 2024

SF ₆ EMISSIONS (Mg)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Manufacturing	8.47	14.66	5.64	3.56	3.19	1.26	0.49	0.25	2.52	2.96	1.03
Operating	0.46	4.89	6.47	9.59	10.30	11.57	8.21	9.18	9.82	7.76	8.56
Disposal	NO	0.62	0.46	0.20	0.06	0.04	0.00	0.00	NO	NO	NO
Total	8.93	20.17	12.57	13.35	13.55	12.87	8.70	9.43	12.34	10.73	9.59

SF₆ operating emissions are those from Closed Pressure Systems, including high voltage equipment that requires refilling with gas during its lifetime. Equipment operating emissions are estimated by multiplying the quantity of SF₆ yearly accumulated by an operating emission factor. The quantity of SF₆ accumulated is estimated using SF₆ annual sales activity data (ANIE, several years), multiplied for the factor 0.8, which

considers the percentage of the total sales referred to Closed Pressure Systems. Moreover, equipment use emissions are the sum of three components:

- emissions from ENEL (the former electricity monopoly);
- emissions from electricity utilities and the national railways company;
- emissions from industries and other private operators.


Since 1994, refilling data of SF₆ used in high voltage gas-insulated transmission lines have been supplied by the main energy distribution companies (in the past included in ENEL) checked with data reported under the national PRTR register (EDIPOWER, several years; EDISON, several years; ENDESA, 2004; ENDESA, several years [a] and [b]; ENEL, several years; TERNA, several years). The emission factor used to estimate the SF₆ operating emissions is assumed equal to 0.01 from 1990 to 2009 and 0.005 from 2010, based on national expert judgment (AIET, 2007). Finally, SF₆ disposal emissions from electrical equipment are estimated by multiplying the quantity of SF₆ contained in retired equipment by the fraction of SF₆ left in the equipment at the end of its life, assumed to be constant and equal to 0.15 from 1990 to 1995, and linearly decreasing until to 2010 value 0.03, as reported in Table 4.83. Since 1995, activity data (point 3 of Table 4.80) are directly supplied by ANIE (ANIE, several years), whereas from 1990 to 1994 the total amount of SF₆ accumulated in the equipment is multiplied by a disposal rate which is equal to zero in that period. Disposal rate and disposal emission factors derived from personal communication.

Table 4.83 Disposal rate and disposal emission factor, 1990-2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Disposal rate	0	0	-	-	-	-	-	-	-	-	-
Disposal emission factor	0.15	0.15	0.11	0.07	0.03	0.03	0.03	0.03	0.03	0.03	0.03

To illustrate emission fluctuations over time, Figure 4.5 is provided. For the period 1995–2000, total SF₆ emissions are calculated as the sum of emissions from manufacturing, operation, and retirement. All three components peak in 1997, although manufacturing and operation are the main contributors to total emissions. Data between 1995 and 2000 is consistent and based on an SF₆ mass balance. Figure 4.5 also shows time series of SF₆ purchases and the three emission sources from electrical equipment. The trend in manufacturing emissions closely follows the trend in purchased SF₆.

Figure 4.5 Time series for SF₆ purchased amounts and emissions from electrical equipment



SF₆ used in equipment in university and research particle accelerators

SF₆ emissions from research particle accelerators have been estimated since 1990 through surveys of national institutes, including INFN (National Institute for Nuclear Physics) and INAF (National Institute of Astrophysics). INFN provided SF₆ refilling data for four accelerators located in Catania, Legnaro, and Florence, covering 1990–2024. These accelerators have used SF₆ since 1976, 1981, 1984, and 2004. INAF reported no use of SF₆ in its research activities.

SF₆ emissions from industrial and medical accelerators have also been estimated since 1990. A dedicated survey was conducted for medical applications. In Italy, such accelerators are supplied by three companies, Siemens Healthcare, Varian Medical Systems, and Elekta, which provided data on the number of units and SF₆ charge over the full time series (Siemens, several years; Varian, several years).

N₂O from product use

N₂O emissions from the use of N₂O for anesthesia, aerosol cans and explosives are estimated, based on information available by industrial associations. Specifically, the manufacturers and distributors association of N₂O products has supplied data on the use of N₂O for anesthesia from 1994 (Assogastecnici, several years). For previous years, data have been estimated by the number of surgical beds published by national statistics (ISTAT, several years [a]). It is assumed that all N₂O used will eventually be released into the atmosphere, therefore the emission factor for anesthesia is equal to 1 Mg N₂O/Mg product use.

Moreover, the Italian Association of Aerosol Producers (AIA, several years [a] and [b]) has provided data on the annual production of aerosol cans used for whipped cream which contain N₂O as propellant. The emission factor used is 0.025 Mg N₂O/Mg product use, because the N₂O content is assumed to be 2.5% on average (Co.Da.P., 2005). The association also provides the number of aerosol cans for other uses (cosmetics, household and cleaning products, pharmaceutical products) and the propellants (LPG and HFC-134a for pharmaceutical products); relevant emissions are estimated in domestic solvent use category as NMVOC and in HFC-134a emissions from aerosols/metered dose inhalers category.

For the estimation of N₂O emissions from explosives, data on the annual consumption of explosives have been obtained by a specific study on the sector (Folchi and Zordan, 2004); as stated in the document, this figure is believed to be constant for all the time series with a variation within a range of 30%. As for the emission factor, the estimated N₂O emissions represent the theoretically maximum emittable amount; in fact, no figures are available on the amount of N₂O emissions actually emitted upon detonations and the value of 3,400 Mg N₂O/Mg explosive use is provided by a German reference (Benndford, 1999) which corresponds to the assumption of 68 g N₂O per kg ammonium nitrate.

N₂O emissions have been calculated multiplying activity data, total quantity of N₂O used for anesthesia, total aerosol cans and explosives, by the related emission factors.

4.8.3 Uncertainty and time series consistency

The uncertainty in SF₆ emissions from electrical equipment and particle accelerators is estimated to be 20.6% in annual emissions, 5% and 20% concerning respectively activity data and emission factors. In Table 4.84 an overview of SF₆ emissions from electrical equipment and particle accelerators is given for the 1990–2024 period. SF₆ emissions from electrical equipment increased from 1990 to 1997 and decreased in the following years; from 2004 emissions are stable enough, in 2020 and 2021 a significant decrease was registered especially due to a drop in operating emissions.

Table 4.84 SF₆ emissions from other product manufacture and use (t), 1990-2024

COMPOUND (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
2.G.1											
SF ₆ emissions from electrical equipment	8.93	20.17	12.57	13.35	13.55	12.87	8.70	9.43	12.34	10.73	9.59
2.G.2.b											
SF ₆ emissions from research particle accelerators	3.98	3.99	4.02	4.72	1.65	5.69	0.44	0.85	2.55	2.84	0.92
Total SF₆ emissions from 2G sector	12.91	24.16	16.59	18.07	15.20	18.56	9.14	10.28	14.90	13.56	10.50

The combined uncertainty in N₂O emissions is estimated equal to 11.2% due to an uncertainty in activity data of 5% and 10% in the emission factor. N₂O emissions remain almost at the same level from 1990 onwards although, from 2000, a reduction is detected, due to a decrease in the anesthetic use of N₂O that has been replaced by halogen gas. Table 4.85 shows the N₂O emission trend from 1990 to 2024.

Table 4.85 Trend in N₂O emissions from product uses, 1990 – 2024 (kt)

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
2.G.3 Other product manufacture and use: N₂O (kt)											
N ₂ O from product uses (use of N ₂ O for anesthesia, aerosol cans and explosives)	2.62	2.49	3.31	2.66	2.02	1.57	1.71	1.68	1.67	1.78	1.76

4.8.4 Source-specific QA/QC and verification

This source category is covered by the general QA/QC procedures. Where information is available SF₆ data for refilling has been checked with data reported to the national EPER/E-PRTR registry. For N₂O emissions from anesthesia and aerosol cans, emission factors and emissions are also shared with the relevant industrial associations.

Other relevant uses of SF₆, as listed in the IPCC Guidelines, have been investigated to study the occurrence at national level. Some of these applications could be excluded, such as car tyres, soundproof windows and shoes soles also due to manufacturing additional costs.

Regarding the other potential sources of emissions, such as SF₆ emissions from AWACs, in 2014 the Italian Air Force has been contacted to investigate the presence of such aircraft. The Italian Air Force answered that such kind of aircraft is a NATO aircraft and according to the Decision 3/CP.3 of the Kyoto Protocol, emissions resulting from multilateral operations pursuant to the Charter of the United Nations shall not be included in national total.

4.8.5 Source-specific recalculation

No recalculations occurred in this submission.

4.8.6 Source-specific Planned improvements

For SF₆ emissions from electrical equipment, improvements should be also obtained by consulting the new National Telematic Registry of fluorinated greenhouse gases and equipment containing fluorinated gases that has been instituted by DPR 146/2018, entered into force in January 2019. In fact, compared to the

previous National F-gas Data Bank (established by Presidential Decree 43/2012), which includes refrigeration, air conditioning and fire protection systems, the new Registry contains data also on electrical switches. As already mentioned in the previous paragraphs, the data in the database are not yet being used for estimates due to various critical issues that have been identified. However, work is underway to try to overcome the critical issues in the database with a view to its future use.

4.9 Other production (2H)

4.9.1 Source category description

Only indirect gases and SO₂ emissions occur from these sources. In this sector, non-energy emissions from pulp and paper as well as food and drink production, especially wine and bread, are reported. CO₂ from food and drink production (e.g., CO₂ added to water or beverages) can be of biogenic or non-biogenic origin but only information on CO₂ emissions of non-biogenic origin should be reported in the CRT.

According to the information provided by industrial associations, CO₂ emissions do not occur, but only NMVOC emissions originate from these activities. CO₂ emissions from food and beverages do not occur since they originated from sources of carbon that are part of a closed cycle. As regards the pulp and paper production, NO_x and NMVOC emissions as well as SO₂ are estimated. NO_x and SO₂ emissions have been referred to the paper and pulp production from acid sulphite and neutral sulphite semichemical processes up to 2009, activity data and emissions were provided by the two Italian production plants: in 2008 the bleached sulphite pulp production has stopped while in 2009 the neutral sulphite semi-chemical pulp process has closed (reconversion of the plant is currently under negotiation). NMVOC emissions are related to chipboard production and have been estimated and reported.

5 AGRICULTURE

5.1 Sector overview

In this chapter information on the estimation of greenhouse gas (GHG) emissions from Agriculture sector is given. Emissions from enteric fermentation (3A), manure management (3B), rice cultivation (3C), agriculture soils (3D), field burning of agriculture residues (3F), liming (3G), urea application (3H) and other carbon-containing fertilizers (3I) are included in this sector. Methane (CH₄), nitrous oxide (N₂O) and carbon dioxide (CO₂) emissions are estimated and reported. Savanna areas (3E) are not present in Italy. Emissions from other sources (3J) do not occur.

To provide information on the characteristics of the agriculture sector in Italy, figures from the latest available Agricultural Census (2020), released by ISTAT, are reported. According to these data, in Italy there are 1.1 million of farms with a total Utilized Agricultural Area (UAA) of 12.4 million hectares. Comparing the data from the censuses (see Table 5.1), it can be noted as the number of farms and the agricultural area have decreased; in particular, between 2010 and 2020 more than about 480 thousand farms have been closed and between 2000 and 2010, the reduction of farms is equal to 33% (about 780 farms). At national level, the average size of farms varied from 5.5 hectares in 2000 to 11.1 hectares in 2020. This trend is in line with the average size of farms increment from 7.4 hectares (in 2005) to 7.6 hectares (in 2007) observed by the Farm structure survey (FSS). According to 2010 data, more than 50% of farms have an area of less than 2 hectares of UAA. The distribution of farms by type confirms a typical family conduction system, which characterized the Italian agriculture system. About one million farms (93.5 percent of total farms) are sole proprietorships or family farms. These farms hold about 9 million hectares of UAA (73.0% of total)⁶ (EUROSTAT, 2007[a], [b], 2012; ISTAT, 2008[a]). CREA⁷ annually updates figures of the agriculture sector such as added value, employment, productivity (CREA, 2025).

Table 5.1 Farms characteristics from Agricultural Censuses

Farms characteristics	1982	1990	2000	2010	2020
Number of farms	3,133,118	2,848,136	2,393,161	1,615,590	1,133,006
Utilized agricultural area - hectares	15,833,000	15,026,000	13,181,859	12,856,048	12,431,808
Total area of farms - hectares	22,398,000	21,628,000	18,767,000	17,081,000	16,085,987
Average size of farms - hectares	5.1	5.3	5.5	8.0	11.0

5.1.1 Emission trends

Emission trends per gas

In 2024, 7.7% of the Italian GHG emissions, excluding emissions and removals from LULUCF, (6.9% in 1990) are originated from the agriculture sector. Therefore, it is the second source of emissions, after the energy and followed by IPPU sector which accounts for 81.0% and 5.5%, respectively. For the agriculture sector, the trend of GHGs from 1990 to 2024 shows a decrease of 22.3% due to the reduction of the activity data, such as the number of animals, the cultivated surface/crop production, the amount of synthetic nitrogen fertilisers applied, and the changes in manure management systems (see Figure 5.1). In 2024, CH₄, N₂O and CO₂ emissions accounted for 69.2%, 29.2% and 1.6%, respectively. In the period 1990-2024, CH₄, N₂O and CO₂ emissions decreased by 21.2%, 25.2% and 14.1%, respectively (see Table 5.2). The large reduction in 2022 of N₂O and CO₂ emissions is due to the reduction in the synthetic fertilizer figure compiled by ISTAT. The data refer to the quantities sold in the country, which are assumed to be distributed on agricultural

⁶ Agricultural Census data are available at the link <https://esploradati.istat.it/databrowser/#/it/censimentoagricoltura>


⁷ Council for agricultural research and analysis of the agrarian economy <https://www.crea.gov.it/en/about-crea>

soils. According to *Assofertilizzanti– Federchimica*⁸, the 2022 data are lower than annual average (for nitrogen, phosphorus pentoxide, and potassium oxide) because they follow a two-year period in which quantities purchased increased and refer to a year in which high market prices prompted operators to delay purchases in anticipation of falling prices, an event, which occurred during 2023. In 2024, the agriculture sector has been the first source for CH₄ sharing 45.1% of national CH₄ levels and for N₂O accounting for 59.3% of national N₂O emissions. As for CO₂, the agriculture sector represents 0.1% of national CO₂ emissions.

Table 5.2 GHG emissions and trend from 1990 to 2024 for the agriculture sector (kt CO₂ eq.)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CH₄	24,599	24,096	23,518	21,764	21,332	21,006	21,071	20,841	20,547	20,355	19,389
N₂O	10,936	11,440	11,191	10,712	9,040	8,705	9,307	8,922	7,562	8,485	8,182
CO₂	510	567	571	564	381	458	503	463	236	442	438
Total	36,045	36,103	35,280	33,039	30,753	30,169	30,881	30,226	28,346	29,283	28,009

Figure 5.1 Trend of GHG emissions for the agriculture sector from 1990 to 2024 (kt CO₂ eq.)



Emission trends per sector

Total GHG emissions and trends by subcategory from 1990 to 2024 are shown in Table 5.3 (expressed in kt CO₂ eq.). CH₄ emissions from enteric fermentation (3A) and N₂O emissions from agricultural soils (3D) are the most relevant categories. In 2024, their individual share in national GHG emissions excluding LULUCF was 3.7% and 1.7%, respectively.

Table 5.3 Total GHG emissions from 1990 to 2024 for the agriculture sector (kt CO₂ eq.)

Year	GHG emissions (kt CO ₂ eq.) by category						TOTAL
	3A	3B	3C	3D	3F	3G-H-I	
1990	17,174	8,384	2,102	7,856	19	510	36,045.3
1995	16,796	8,016	2,228	8,477	18	567	36,103.1
2000	16,631	7,914	1,855	8,291	18	571	35,280.4
2005	14,521	7,832	2,078	8,022	22	564	33,039.1

⁸ Federchimica is the National Association of the Chemical Industry and Assofertilizzanti represents the production companies of the fertilizer industry.

Year	GHG emissions (kt CO ₂ eq.) by category						TOTAL
	3A	3B	3C	3D	3F	3G-H-I	
2010	14,125	7,475	2,255	6,501	16	381	30,753.3
2015	14,310	6,943	1,943	6,499	16	458	30,169.3
2020	14,815	6,627	1,696	7,225	14	503	30,881.0
2021	14,695	6,474	1,677	6,902	15	463	30,225.6
2022	14,518	6,453	1,547	5,578	14	236	28,345.6
2023	14,314	6,521	1,510	6,481	15	442	29,282.5
2024	13,488	5,960	1,793	6,316	13	438	28,009.0

5.1.2 Key categories

In 2024, CH₄ emissions from enteric fermentation and manure management, direct and indirect N₂O emissions from manure management and managed soils were ranked among the level key sources with Approach 2, including the uncertainty (L2). CH₄ emissions from enteric fermentation and direct N₂O emissions from managed soils were ranked among the trend key sources with Approach 1 and 2, including uncertainty (T). Including LULUCF sector in the analysis, CH₄ emissions from enteric fermentation and direct N₂O emissions from managed soils are key sources at trend assessment with Approach 1 and 2 (T). In Table 5.4, key and non-key categories from the agriculture sector are shown, with a level and/or trend assessment (*IPCC Approach 1 and Approach 2*), excluding and including the LULUCF sector in the analysis.

Table 5.4 Key-sources identification in the agriculture sector with the IPCC Approach 1 and Approach 2 for 2024

GHG source categories			excluding LULUCF	including LULUCF
3A	CH ₄	Emissions from enteric fermentation	Key (L, T)	Key (L, T)
3B	CH ₄	Emissions from manure management	Key (L)	Key (L, T1)
3Ba	N ₂ O	Direct emissions from manure management	Key (L)	Key (L1)
3Bb	N ₂ O	Indirect emissions from manure management	Key (L2)	Non-key
3C	CH ₄	Rice cultivation	Key (L1)	Key (L1)
3Da	N ₂ O	Direct emissions from managed soils	Key (L, T)	Key (L, T)
3Db	N ₂ O	Indirect emissions from managed soils	Key (L, T2)	Key (L, T2)
3F	CH ₄	Emissions from field burning of agriculture residues	Non-key	Non-key
3F	N ₂ O	Emissions from field burning of agriculture residues	Non-key	Non-key
3G	CO ₂	Liming	Non-key	Non-key
3H	CO ₂	Urea application	Non-key	Non-key
3I	CO ₂	Other carbon-containing fertilizers	Non-key	Non-key

5.1.3 Activities

Emission factors used for the preparation of the national inventory reflect the characteristics of the Italian agriculture sector. Information from national research studies is considered. Activity data are mainly collected from the National Institute of Statistics (ISTAT, *Istituto Nazionale di Statistica*). Every year, national and international references, and personal communications used for the preparation of the agriculture inventory are archived in the *National References Database*.

Improvements for the Agriculture sector are described in the Italian Quality Assurance/Quality Control plan (ISPRA, several years [a]). Moreover, an internal report describes the procedure for preparing the agriculture UNFCCC/CLRTAP national emission inventory and projections (Di Cristofaro, several years).

The national agriculture UNFCCC/CLRTAP emission inventory is used every 4 years (from 2021; previously it was every 5 years), to prepare a more disaggregated inventory by region and province as requested by CLRTAP. A database with the time series for all sectors and pollutants is available (ISPRA, 2021; ISPRA, several years [b]). The methods and emission factors applied for GHG inventory are also used for emission scenarios and projections (MASE, 2022).

5.1.4 Agricultural statistics

Every year, the Italian National Statistical System (SISTAN⁹) revises the National Statistical Plan that covers three years and includes, among others, the system of agricultural statistics. In this framework, the Agriculture, Forestry and Fishing Quality Panel has been established under the coordination of the agriculture service of ISTAT where the producers and key users of agricultural statistics (mainly public institutions) meet each other every year to monitor and improve national statistics. ISTAT plays the major role in the agricultural sector collecting comprehensive data through different surveys (Greco and Martino, 2001):

- Structural surveys (FSS, survey on economic results of the farm, survey on the production inputs);
- Conjunctural surveys¹⁰ (survey on the cultivation area and relative production, livestock number, milk production, slaughter, fertilizers, etc.);
- General Agricultural Census¹¹, carried out every 10 years (1990, 2000, 2010, 2020).

Detailed information on the agriculture sector is found every two/three years in the FSS¹² (ISTAT, 2018; ISTAT, 2015; ISTAT, 2008[a]; ISTAT, 2007[a]; ISTAT, 2006[a]). ISTAT has provided quality reports for the FSS 2005 and FSS 2007 (ISTAT, 2008[b]; ISTAT, 2007[d]) and a report on the assessment of the quality of the agricultural census data (ISTAT, 2013). The main agricultural statistics used for the agriculture emission inventory are available online. Detailed information is provided in Table 5.5.

Table 5.5 Main activity data sources used for the agriculture emission inventory

Agricultural statistics	Time series	Web site
Livestock number	Table 5.8; 5.9; 5.13; 5.16	https://esploradati.istat.it/databrowser/#/it/dw/categories/IT1.Z1000AGR.1.0/AGR_CRP/DCSP_CONSISTENZE
Milk production	Table 5.8	https://esploradati.istat.it/databrowser/#/it/dw/categories/IT1.Z1000AGR.1.0/AGR_CRP/DCSP
Fertilizers	Table 5.43; 5.50; 5.58; 5.59	https://esploradati.istat.it/databrowser/#/it/dw/categories/IT1.Z1000AGR.1.0/AGR_MEANS/D_CSP_FERTILIZZANTI
Crops production/surface	Table 5.54; 5.55	https://esploradati.istat.it/databrowser/#/it/dw/categories/IT1.Z1000AGR.1.0/AGR_CRP/DCSP_COLTIVAZIONI

Differences in some animal populations data are found comparing national statistics and FAOSTAT¹³ data. FAO publishes figures for the $x-1$ year on 1st January of the x year. Each year ISPRA verifies the official statistics directly contacting the experts responsible for each agricultural survey (number of animals, agricultural surface/production, fertilizers, etc). Agricultural statistics reported by ISTAT are also published in the European statistics database¹⁴ (EUROSTAT).

Whenever outliers are identified, these are shown to ISTAT and category associations. Differences in the livestock number are found comparing conjunctural surveys (used for emissions estimation) and the Agricultural census for the year 2020: +5% non-dairy cattle (the number of dairy cows is almost the same),

⁹ SISTAN, Sistema Statistico Nazionale (<http://www.sistan.it/>)

¹⁰ <http://agri.istat.it/>

¹¹ <http://dati-censimentoagricoltura.istat.it/>; <https://esploradati.istat.it/databrowser/#/it/censimentoagricoltura>

¹² Indagine sulla struttura e produzione delle aziende agricole (SPA), survey carried out every two/three years in agricultural farms.

¹³ FAOSTAT <http://www.fao.org/faostat/en/#home>

¹⁴ <http://ec.europa.eu/eurostat/data/database>

+3% poultry, -2% buffalo and swine, +12% goats, while equines are almost three times as large. The verification of statistics is part of the implemented QA/QC procedures.

In general, for estimating emissions from livestock, the number of livestock measured by the annual surveys of the National Institute of Statistics (ISTAT), which surveys the number of livestock on farms as of December 1 each year, is used. The surveyed values are considered statistically an average value of the livestock raised during the year (of all animal subcategories), which can be equated with the number of places present on livestock farms, which is the activity data needed to estimate emissions. Livestock surveys surveyed as of December 1 are carried out by ISTAT in accordance with EU Regulation 1165/2008, which establishes the rules for carrying out EU livestock statistics and sets December 1 as the data collection date for representing the number of livestock raised annually. The data on the number of animals are compared each year with those from the National Livestock Registry Database (BDN, several years). From 2022, data on equines come from this database.

As for poultry, since no annual statistics on the number of animals are available, the following methodology was followed. For 1990 the ISTAT data from the Agricultural Census have been used; for the years 1991-1999, the number of heads was estimated on the basis of the annual decreases/increases in the production of heads and meat supplied by UNA (National Union of Poultry, which later became UNAITALIA); since 2000, different methodologies have been adopted for the three poultry categories: laying hens, broilers, and other poultry. Since 2000, for the category "other poultry," the number of animals has been estimated based on the annual decreases/increases in the production of meat supplied by UNAITALIA.

For the laying hen category, the following methodology was used:

- for 2000, ISTAT census data was used;
- for subsequent years up to 2015, the number of heads was calculated each year as the average between two values. The first value is the annual number of animals provided by UNAITALIA; the second value consists of ISTAT data from censuses and FSS for the years 2005, 2007, 2010, 2013, 2016, and 2020, and for the intermediate years, the data are estimated using interpolations;
- for the years after 2015, the number of animals is calculated each year as the average of three values: the first two values have just been described; the third value is the number of animals from the National Livestock Registry Database (BDN, several years).

For the broiler category, the following methodology was used:

- for 2000, the number of heads was estimated based on the annual decreases/increases in the production of heads supplied by UNAITALIA;
- for subsequent years, the number of heads is calculated each year as the average between two values. The first value is estimated on the basis of the annual decreases/increases in the production of heads supplied by UNAITALIA, applied to the number of heads recorded by ISTAT in the censuses and FSS for the years 2005, 2007, 2010, 2013, 2016, and 2020; the second value consists of ISTAT data from the censuses and FSS for the years 2000, 2005, 2007, 2010, 2013, 2016, and 2020, and for the intermediate years, the data are estimated using interpolations.

The data on turkeys are estimated based on ISTAT census data and FSS data for the years 1990, 2000, 2005, 2007, 2010, 2013, 2016, and 2020. Intermediate years have been estimated by interpolating the data. From 2021 onwards, the data are estimated based on the annual number of turkeys produced, as provided by UNAITALIA.

5.2 Enteric fermentation (3A)

5.2.1 Source category description

Methane is produced as a by-product of enteric fermentation, which is a digestive process where carbohydrates are degraded by microorganisms into simple molecules.

Methane emissions from enteric fermentation are a key category, in terms of level and trend assessment, for Approach 1 and Approach 2. All livestock categories have been estimated except camels and llamas. Methane emissions from poultry and fur animals are not applicable. Emissions from rabbits, mules and asses, goats, buffalo, ostriches and horses are estimated and included in “Other livestock” as shown in the CRT tables. In 2024, CH₄ emissions from this category were 481.71 kt which represents 69.6% of CH₄ emissions for the agriculture sector (69.8% in 1990) and 31.4% for national CH₄ emissions excluding LULUCF (31.2% in 1990). Methane emissions from this source consist mainly of cattle emissions: dairy cattle (220.60 kt) and non-dairy cattle (159.38 kt). These two subcategories represented 45.8% (47.9% in 1990) and 33.1% (36.0% in 1990) of total enteric fermentation emissions, respectively.

5.2.2 Methodological issues

Methane emissions from enteric fermentation are estimated by defining an emission factor for each livestock category, which is multiplied by the population of the same category. Data for each livestock category are collected from ISTAT (several years [a], [b], [c], [f], [g]; ISTAT, 1991; 2007[a], [b]) and the National Livestock Registry Database (BDN, several years). Livestock categories, provided by ISTAT, are classified according to the type of production, slaughter or breeding, and the age of animals. In Table 5.6, livestock categories and sources of information are provided. Parameters for the livestock categories are shown in Table 5.36. To have a consistent time series, it was necessary to estimate the number of animals for some categories. The estimation is based on information available from other official sources such as FAO and UNAITALIA (FAO, several years; UNAITALIA, several years).

Table 5.6 Activity data for the different livestock categories

Livestock category	Source
Cattle	ISTAT
Buffalo	ISTAT
Sheep	ISTAT
Goats	ISTAT
Horses	ISTAT/FAO(a)/BDN
Mules and asses	ISTAT/FAO(a)/BDN
Swine	ISTAT
Poultry	ISTAT/UNAITALIA(b)
Rabbits	ISTAT(c)

(a) Reconstruction of a consistent time series; (b) For 1990 data from the census and reconstruction for broilers, hens and other poultry based on meat production (UNAITALIA, several years); (c) For 1990 data from the census and reconstruction based on a production index (ISTAT, 2007[b]; ISTAT, several years [k]).

Dairy cattle

Methane emissions from enteric fermentation for dairy cattle are estimated to use a Tier 2 approach, following the 2019 IPCC Guidelines (IPCC, 2019). Feeding characteristics are described in a national publication (CRPA, 2004[a]) and have been discussed in a specific working group in the framework of the MeditAIRaneo project (CRPA, 2006[a]; CRPA, 2005). Parameters used for the calculation of the emission factor are shown in Table 5.7.

Nem and Nea for dairy cattle from IPCC default (IPCC, 2019). According to the 2019 IPCC Refinement, DE e Ym parameters for dairy cattle have been estimated considering average annual milk production per cow

and per production level and information on animal diets. Data to calculate the emission factor from dairy cattle are national (ISTAT, Centro Ricerche Produzioni Animali, Reggio Emilia - CRPA and others).

Table 5.7 Parameters for calculating the 2024 dairy cattle emission factors from enteric fermentation

Parameter	Value	Reference	IPCC 2019(*)
Average weight (kg)	602.7	CRPA, 2006[a]	600
Coefficient NE _m (lactating cows)	0.386	NRC, 2001; IPCC, 2019	0.386
Pasture 1990-2024 (%)	5-6.8	CRPA, 2006[a]; ISTAT, 2003	0(**)
Weight gain (kg day ⁻¹)	0.051	CRPA, 2006[a]; CRPA, 2004[b]	0
Milk fat content 1990-2024 (%)	3.59-3.95	ISTAT, several years[a], [b], [d], [e], [h]	4.2
Hours of work per day	0	CRPA, 2006[a]	0
Portion of cows giving birth 1990-2024	0.97-0.92	AIA, several years[a]	0.9
Milk production 1990-2024 (kg head ⁻¹ day ⁻¹)	11.5-26.6	CRPA, 2006[a]; OSSLATTE/ISMEA, 2003; ISTAT, several years[a], [b], [c], [d], [e], [f], [h]; OSSLATTE, 2001	20.3
Digestibility of feed (%)	68.95	CRPA, 2006[a]; CRPA, 2005; IPCC, 2006	71
Methane conversion factor (%)	5.97	CRPA, 2006[a]; IPCC, 2006	6.3
Energy content of methane (MJ/kg methane)	55.65	IPCC, 2006	55.65

(*) Data for estimating tier 1 and tier 1A enteric fermentation CH₄ emission factors for dairy cows (Western Europe); (**) Stall fed (feeding situation).

The national statistics on milk production were analyzed. Milk used for dairy production and milk used for calf feeding contributes to total milk production. The latter was estimated on national and ISTAT publications (ISTAT, several years[h]). For the calculation of milk production (kg head⁻¹ d⁻¹), total production is divided by the number of animals and by 365 days, as suggested by the IPCC (IPCC, 2019). Therefore, lactating and non-lactating periods are included in the estimation of the CH₄ dairy cattle EF (CRPA, 2006[a]).

The percentages of dairy cattle on pasture are based on the percentage of cows grazing calculated by CRPA (MeditAIRaneo project - CRPA, 2006[a]) for the period 1990-2006 and on data from the 2020 Agriculture Census for the period 2007-2024. From 2007 onward, a linear change was calculated until 2020, when the figure from the Census Agriculture 2020 was considered.

In Table 5.8, the time series of the dairy cattle population, fat content in milk, portion of cows giving birth and milk production are shown. Further information on parameters used for dairy cattle estimations is reported in Annex 7.1.

According to the 2019 IPCC Refinement (IPCC, 2019), DE e Y_m parameters for dairy cows have been estimated considering average annual milk production per cow and per production level (low "<5000 kg/head/year", medium "5000-8500 kg/head/year" and high ">8500 kg/head/year") and information on animal diets. Based on data from the Italian Livestock Breeders' Association (AIA) on average annual milk production and the number of dairy cows in production, by region and breed, the distribution of animals was calculated according to the three productivity levels identified by the 2019 IPCC Refinement, for the years 2004-2019. The AIA carries out milk productivity checks on behalf of the Ministry of Agriculture and each year the sample of animals checked is about 50% of the number of animals raised. The difference in cow numbers between the AIA total and the ISTAT total (used for emission estimates) was attributed to the low production level. The DE values assigned to the three production levels (low, medium, high) are 62%, 65% and 70.11% of gross energy intake respectively and were identified in collaboration with the CRPA (Research Centre on Animal Production) dairy cow feeding experts. The value 62 is the minimum value of the range indicated in Table 10.12 for low producing cows of the 2019 IPCC Refinement (Chapter 10 of the Volume 4). The value 65 is lower than the average value of the range indicated in Table 10.12 for medium producing cows. The value 70.11 for high-producing cows is a weighted average of two values: the first is 65 (corresponding to diets with DE₇₀ and NDF₃₅) and was attributed to 27% of the high-producing cows fed without silage fodder; the second is 72 (corresponding to diets with DE₇₀ and NDF₃₅) and was attributed to 73% (=100-27%) of the high-producing cows fed with silage fodder. With reference to the 27% of cows, this value includes cows whose milk is intended for the production of Parmigiano Reggiano (17% of total cows), and cows fed with good quality dry and green fodder (e.g. for the production

of Trentingrana PDO (Protected Designation of Origin), Latte Fieno STG (Traditional Speciality Guaranteed) and other mountain cheeses) which correspond to the other 10% of total cows. In support of the choices made for high productivity values, mention is made of a study published in 2020 (Gislon et al, 2020) carried out on eight Italian Friesian cows in multiparous lactation, with high productivity, using a 4 × 4 replicated Latin square pattern. The experimental design of the square involves all cows receiving all diets (with adaptation periods between each), so 2 groups of 4 cows that rotated 4 times on 4 diets have been considered. The number of observations for each diet is 32. According to CRPA experts, the cow effect is nullified because all of them received all diets and, therefore, the results obtained are irrefutable and highly representative. Four diets, based on the following forages (expressed in % of dry matter of forages, DM, and in the neutral detergent fiber content, NDF, expressed as % of dry matter intake), were tested: corn silage (CS, 49.3; 32.8 NDF), alfalfa silage (AS, 26.8; 27.1 NDF), wheat silage (WS, 20.0; 33.7 NDF), and a typical hay-based Parmigiano Reggiano cheese production diet (PR, 25.3 of both alfalfa and Italian ryegrass hay; 36.7 NDF). The lowest DM digestibility was observed for the PR diet (64.5%) and the highest for the CS diet (73.3%); AS and WS diets showed intermediate values (71.4 and 70.3% respectively). PR diet is associated with diets with $DE \geq 70$ and $NDF \geq 35$ in Table 10.12 of the 2019 IPCC Refinement (Chapter 10 of the Volume 4) and the other three diets are associated with diets with $DE \geq 70$ and $NDF \leq 35$ in the same table. For the year 2024, the percentages of dairy cows according to the three productivity levels (low, medium e high milk production) are 7.8%, 10.3% and 81.8%, respectively. The digestibility values associated with these productivity levels are, as previously mentioned, 62%, 65% and 70.11%, respectively. With this data, the average digestibility value of the diets consumed by dairy cows was estimated at 68.95%. The weighted average value of Ym for the year 2024 is 5.97% of gross energy intake. This value was estimated from the percentage distribution of dairy cows according to the three productivity levels and using the default factors given in Table 10.12 of the 2019 IPCC Refinement (Chapter 10 of Volume 4). These values are: for lactating phase, 6.5 for low producing cows, 6.3 for medium producing cows, 6.0 and 5.7 for high producing cows; for dry phase, 7 for low producing cows, 6.3 for medium and high producing cows. From the two values for high producing cows in lactating phase, a weighted average value of 5.78 was estimated, with the distribution of cows according to diet type, shown above: 27% of high-productivity cows are associated with diets with $DE \geq 70$ and $NDF \geq 35$ (Ym 6.0); 73% of high-productivity cows are associated with diets with $DE \geq 70$ and $NDF \leq 35$ (Ym 5.7).

By analyzing data from the AIA bulletin on production data in herds participating in functional controls for the years 2004-2024, information can be gathered on the productivity of the most numerous dairy cattle breeds. Dairy cattle with lactations over 200 days were considered, representing more than 50% of the dairy cattle surveyed by ISTAT in 2024. The most representative breeds are Frisone (87% in 2024; 82% in 2004), Bruna (4% in 2024; 10% in 2004) and Pezzata Rossa Italiana (5% in 2024; 4% in 2004), which produce on average, in 2024, 10536 kg of milk/head/year (+22% over 2004, 8634 kg/head/year), 7665 kg/head/year (+18% over 2004, 6509 kg/head/year,) and 7278 kg/head/year (+18% over 2004, 6185 kg/head/year,), respectively. There are other breeds that produce an average of more than 5000 kg of milk/head/year, which are Angler, Grigio Alpina, Jersey, Pinzgauer, Reggiana, and Rendena, which account for less than 2% of the dairy cattle in 2024.

In Table 5.15, the dairy cattle emission factors (EF) are reported. In 2024, the CH₄ dairy cattle EF was 145.1 kg CH₄ head⁻¹ year⁻¹ with an average milk production of 9,699 kg head⁻¹ year⁻¹ (26.6 kg head⁻¹ day⁻¹). The IPCC default EF is 126 kg CH₄ head⁻¹ year⁻¹ with a milk production of 7,410 kg head⁻¹ year⁻¹ (IPCC, 2019).

Table 5.8 Parameters used for the estimation of the CH₄ emission factor for dairy cattle

Year	Dairy cattle (head)	Fat content in milk (%)	Portion of cows giving birth	Milk production yield (kg head ⁻¹ d ⁻¹)
1990	2,641,755	3.59	0.97	11.5
1995	2,079,783	3.64	0.95	14.8
2000	2,065,000	3.65	0.93	15.1
2005	1,842,004	3.71	0.91	17.2
2010	1,746,140	3.72	0.90	18.8

Year	Dairy cattle (head)	Fat content in milk (%)	Portion of cows giving birth	Milk production yield (kg head ⁻¹ d ⁻¹)
2015	1,826,484	3.76	0.89	19.1
2020	1,638,382	3.88	0.91	23.7
2021	1,609,948	3.82	0.92	25.0
2022	1,631,128	3.95	0.92	24.6
2023	1,574,406	3.95	0.92	25.3
2024	1,520,686	3.95	0.92	26.6

Non-dairy cattle

For non-dairy cattle, CH₄ emissions from enteric fermentation are estimated with a Tier 2 approach of the 2019 IPCC Guidelines. The estimation of the EF uses country-specific data, disaggregated by livestock categories (see Table 5.9), and it is based on dry matter intake (kg head⁻¹ day⁻¹) calculated as percentage of live weight as estimated by CRPA and described in Annex 7. Dry matter intake is converted into gross energy (MJ head⁻¹ day⁻¹) using 18.45 MJ/kg dry matter conversion factor (IPCC, 2019). Emission factors for each category are calculated with equation 10.21 from 2019 IPCC Guidelines (Chapter 10 of Volume 4).

In Table 5.10, parameters used for the estimation of non-dairy cattle EF are shown. Average weights have been assessed with information from the Nitrogen Balance Inter-regional Project (CRPA, 2006[a]; Regione Emilia Romagna, 2004). For reporting purposes, some animal categories are aggregated, such as the non-dairy cattle and the swine categories. The non-dairy cattle category includes different subcategories as shown in Table 5.9; consequently, the gross energy intake, CH₄ conversion factor and EFs for this category are calculated as a weighted average.

Table 5.9 Non-dairy cattle population (heads) classified by type of production and age

Year	<1 year		1-2 years males		1-2 years females		>2 years males	>2 years females			Total
	for slaughter	others	breeding	for slaughter	breeding	for slaughter	all	breeding	for slaughter	others	
1990	300,000	2,127,959	72,461	708,329	749,111	186,060	128,958	467,216	57,654	312,649	5,110,397
1995	458,936	1,796,034	27,871	783,300	684,881	154,548	155,116	430,564	40,198	657,856	5,189,304
2000	408,000	1,783,000	27,521	641,479	736,000	160,000	93,000	500,000	51,000	588,000	4,988,000
2005	500,049	1,418,545	26,424	615,921	588,660	181,971	102,081	466,566	37,971	471,733	4,409,921
2010	507,452	1,228,696	23,913	557,386	597,733	212,983	70,284	445,370	70,411	372,089	4,086,317
2015	492,126	1,141,545	19,966	465,391	638,566	205,966	82,304	524,745	64,570	319,685	3,954,864
2020	463,597	1,253,974	22,574	526,175	726,873	260,935	101,006	536,547	101,810	361,142	4,354,633
2021	450,312	1,214,907	22,025	513,390	706,874	260,270	99,930	552,414	101,821	338,983	4,260,926
2022	419,500	1,084,594	22,616	527,155	656,355	253,922	88,891	399,022	77,476	472,077	4,001,608
2023	421,028	1,097,934	22,007	512,957	662,663	258,917	88,883	396,445	77,583	469,280	4,007,697
2024	489,531	1,243,973	12,347	287,785	583,165	230,833	57,624	382,006	74,810	445,172	3,807,246

Table 5.10 Main parameters used for non-dairy cattle CH₄ emission factor estimations

Parameters	<1 year	1-2 years males		1-2 years females		>2 years males	>2 years females		
	others (*)	breeding	for slaughter	breeding	for slaughter	all	breeding	for slaughter	others
Average weight (kg)	236	557	557	405	444	700	540	540	557
Percentage weight ingested	2.1	2.0	1.7	3.0	2.0	2.0	2.5	1.7	2.0
Dry matter intake (kg head ⁻¹ day ⁻¹)	4.8	11.1	9.5	12.2	8.9	14.0	13.5	9.2	11.1

Parameters	<1 year	1-2 years males		1-2 years females		>2 years males	>2 years females		
	others (*)	breeding	for slaughter	breeding	for slaughter	all	breeding	for slaughter	others
Gross Energy (MJ head ⁻¹ day ⁻¹)	89.4	205.5	174.7	224.2	163.8	258.3	249.1	169.4	205.5
CH ₄ conversion (%)	4.16	4.72	4.62	4.63	4.68	4.32	4.54	4.65	4.48

(*) It has been considered that calves for slaughter of <1 year do not emit CH₄ emissions, as they are milk fed. Therefore, the average weight for the category "others" of <1 year considers fattening male cattle, fattening heifer and heifer for replacement.

EFs reflect the national characteristics of Italian breeding as well as the age classification of animals and dry matter intake. Detailed information on the CH₄ conversion factors for non-dairy cattle category is reported in Annex 7.

In Table 5.15, Implied Emission Factors (IEF) for non-dairy cattle are shown. In 2024, the non-dairy cattle EF was 41.9 kg CH₄ head⁻¹ year⁻¹, while the 2019 IPCC Guidelines default EF is 52 kg CH₄ head⁻¹ year⁻¹ (Chapter 10 of Volume 4). Following the indications given in the 2006 and 2019 IPCC guidelines, the subcategory calves (included in 'less than 1 year for the slaughter' subcategory) has not been considered when estimating methane emissions as calves are milk fed. In the case of meat animals, the production in Italy is based on imported calves and that number of animals produced in Italy for fattening is few. The relevant parameters for estimating N₂O emissions from manure management, for this category, are the following:

- Average body weight: 157 kg;
- Nitrogen excretion: 14.6 kg N/head/year;
- Average milk period: 4-6 months;
- Average weight at slaughter: less than 300 kg.

As regards the share of grazing animals, the same value used for dairy cattle was assumed for the other females in the category non-dairy cattle and no grazing is assumed for the males (see paragraph *Dairy cattle*).

Buffalo

The 2019 IPCC Tier 2 approach was applied for the buffalo category. Two different country specific CH₄ EFs, for cow buffalo and other buffaloes, were estimated. In 2024, the CH₄ EFs were 82.4 and 61.8 kg CH₄ head⁻¹ year⁻¹ for cow buffaloes and other buffaloes respectively. The CRT IEF is an average value for the two categories (73.3 kg CH₄ head⁻¹ year⁻¹). Parameters used for the Tier 2 approach are shown in Table 5.11 and 5.12. For buffalo cows the average value of DE provided by Table 10.2 of Volume 4 of 2019 Refinement for cattle and other ruminants (pasture/mixed diet fed) equal to 67.5% was introduced to calculate the EF, in place of 65% used before.

Table 5.11 Parameters to estimate emission factors from enteric fermentation of cow buffalo

Parameters	Value	Reference
Average body weight (kg)	630	Infascelli, 2003; Consorzio per la tutela del formaggio mozzarella di bufala campana, 2002
Coefficient NEm (lactating cows)	0.386	IPCC, 2019
Pasture (%)	2.90	ISTAT, 2003; Zicarelli, 2001; De Rosa and Di Francia, 2006
Weight gain (kg day ⁻¹)	0.055	Infascelli, 2003; Consorzio per la tutela del formaggio mozzarella di bufala campana, 2002
Milk fat content 1990-2024 (%)	7.73-6.97	ISTAT, several years [a], [b], [d], [e], [h]
Hours of work per day	0	De Rosa and Di Francia, 2006
Proportion of calving cows 1990-2024	0.89-0.84	Barile, 2005; De Rosa and Tralbalzi, 2004
Milk production 1990-2024 (kg head ⁻¹ day ⁻¹)	1.91-3.18	OSSLATTE/ISMEA, 2003; OSSLATTE, 2001; ISTAT, several years [a], [b], [c] [d], [e], [f], [h]
Digestibility of feed (%)	67.5	Infascelli, 2003; Masucci et al., 1997, 1999; IPCC, 2019

Parameters	Value	Reference
Methane conversion factor (%)	6.5	CRPA, 2006[a]; IPCC, 2019
Energy content of methane (MJ/kg methane)	55.65	IPCC, 2019

The buffalo grazing is very infrequent, equal to 5%, in the provinces of Caserta and Frosinone, where according to the University of Naples experts (MeditAIRaneo project (CRPA, 2006[a]), 58% of national livestock are raised.

Table 5.12 Parameters to estimate emission factors from enteric fermentation of other buffaloes

Parameter	Calves (3 months-1 year)	Sub-adult buffaloes (1-3 years)
Average body weight (kg)	150	405
Dry matter intake (% of body weight head ⁻¹ day ⁻¹)	3.0	2.5
Dry matter intake (kg head ⁻¹ day ⁻¹)	4.5	10.1
Gross Energy (MJ head ⁻¹ day ⁻¹)	82.75	186.58
CH ₄ conversion (%)	6.5	6.5
CH ₄ emission factor (kg head ⁻¹ year ⁻¹)	26.46 (*)	79.54

(*) original CH₄ emission factor was 35.28 kg CH₄ head⁻¹ year⁻¹; a correction factor of 9/12 has been applied to consider the time between 3 months and 1 year, therefore the final emission factor was 26.46 kg CH₄ head⁻¹ year⁻¹.

The coefficient for calculating net energy for maintenance (NE_m) and the methane conversion factor (Y_m) for buffalo are the default values of the 2019 IPCC Guidelines.

Sheep

Methane emissions from enteric fermentation for sheep are estimated to use a Tier 2 approach, following the 2019 Refinement of IPCC Guidelines (IPCC, 2019). Gross energy intake was estimated separately for three subcategories: mature ewes, growing lambs, other mature sheep. Data of mature ewes and other sheep (which includes growing lambs and other mature sheep) are provided by ISTAT (as reported in the 5.1.4 *Agricultural statistics*). Growing lambs and other mature sheep were estimated by applying the percentages of 85% and 15% respectively to the total number of other sheep (CRPA, 2006[a]). In Table 5.13, time series of sheep population are shown.

Table 5.13 Sheep population (heads) classified by subcategories

Year	Mature ewes (head)	Growing lambs (head)	Other mature sheep (head)
1990	7,492,089	1,060,089	187,075
1995	8,518,496	1,827,054	322,421
2000	8,334,000	2,341,750	413,250
2005	7,007,217	804,908	142,043
2010	7,089,123	689,259	121,634
2015	6,196,466	809,258	142,810
2020	6,110,114	785,443	138,608
2021	5,867,151	732,020	129,180
2022	5,939,610	533,746	94,190
2023	5,869,207	533,627	94,169
2024	4,930,496	390,872	68,977

The sharp decline between 2000 and 2005 is mainly due to the spreading of Bluetongue infectious disease in 2001. This epidemic led to a decline in livestock numbers in subsequent years as well. In addition, the sheep number reduction along the whole time-series has been caused by the gradual erosion of profit margins in the production system of Sardinia, the Italian administrative region which holds the largest

number of farms rearing sheep. Parameters used for the calculation of the emission factor are shown in Table 5.14.

Table 5.14 Parameters for the calculation of sheep emission factors from enteric fermentation

Parameter	Mature ewes	Growing lambs	Other mature sheep	Reference
Average weight (kg)	51	14	59	CRPA, 2006[a]
Coefficient NE _m	0.217	0.236	0.217-0.250 (1)	IPCC, 2019
Pasture (%) (2)	29	31	33	Estimated data
Weight gain (kg day ⁻¹) (3)		0.019 (4)		ARA, 2017; Agraria, 2009; AIA, several years[b]
Milk production 1990-2024 (kg head ⁻¹ day ⁻¹)	0.30-0.47			ISTAT, several years[h], [l], [b]; ISTAT, 2006[a]
Wool production 1990-2024 (kg head ⁻¹ y ⁻¹)	1.88-1.31			ISTAT, several years[l]
Portion of ewes giving birth	0.93			AIA, several years[c]
Single birth fraction 1990-2024 (%)	70.8-74.8			AIA, several years[b]
Double birth fraction 1990-2024 (%)	29.2-25.2			AIA, several years[b]
Digestibility of feed (%)	67.5	67.5	67.5	IPCC, 2019 (5)
Methane conversion factor (%)	6.5	7	6.5	IPCC, 2019 (6)

(1) The value increased by 15% for intact males; (2) Values estimated assuming an average of 11 month on pasture for 8 hours per day; (3) Assumptions made: sex ratio 40% males and 60% females; weight at weaning (30 days) 10 kg; weight at slaughter (90 days) 18 kg for males and 17 kg for females; (4) the value of 0.019 kg head yr⁻¹ was calculated only for the table in NID 5.13. The value corresponds to 6.7 kg head day between 30 and 90 days, which are the average time to weaning and slaughter, respectively; (5) see Table 10.2 of the 2019 IPCC Guidelines; (6) see the instructions above Table 10.13 of the 2019 IPCC Guidelines.

In the CRT tables, the weighted average values of parameters reported in Table 5.14 were considered for sheep category.

Considering DE parameter, Italy has introduced in this submission the average value of DE provided by Table 10.2 of Volume 4 of 2019 Refinement for cattle and other ruminants (pasture/mixed diet fed) equal to 67.5%. The data used have been confirmed by experts in the sheep sector of AGRIS Sardegna, the agency of the Region of Sardinia for scientific research, experimentation and technological innovation in the agricultural, agro-industrial and forestry sectors. A literature review on dairy sheep feeding (Molle et al., 2008) and an available database on fresh forages and supplement composition commonly used for feeding sheep (Molle and Cannas, 2015) show that sheep diet digestibility (on dry matter basis) averages 70% in adult ewes during lactation (6-4 months) when they are usually fed at pasture and receive concentrate and hay as supplements. In contrast, diet digestibility as low as 60% (FU¹⁵ 0.5-0.7/ kg dry matter) is common in mature ewes fed standing-hay or hay with a low amount of concentrate during dry period (8-6 months). These data support the use of the median level of diet digestibility (67.5%) shown in Table 10.2 of the 2019 IPCC Guidelines.

Moreover, the updated values of Y_m, based on text provided before the Table 10.13 of volume 4 of 2019 Refinement, has been applied: 7.0 percent, more appropriate where average dry matter intake is <0.6 kg day⁻¹, has been attributed to growing lambs, while 6.5 percent, more appropriate where average dry matter intakes are >0.8 kg day⁻¹, has been attributed to ewes and other mature sheep.

For housed ewes the updated value of Ca 0.0096 MJ day⁻¹ kg⁻¹ from Table 10.5 of 2019 Refinement have been used to calculate the net energy for activity (NE_a).

With reference to the 2025 Comprehensive Review of National Greenhouse Gas Inventory Data (EEA, 2025) Table 4 recommendation IT-3-2025-0003, the following information is provided.

¹⁵ Feed unit is the net energy contained in one kg of barley = 1760 kcal

Methane emissions from enteric fermentation for goats are estimated using the default emission factor (kg CH₄/head) from the 2019 IPCC Guidelines, so there is no need to calculate gross energy intake (GE).

Methane emissions from sheep and goat manure management are estimated using the default emission factors (kg CH₄/head) by temperature from the 2006 IPCC Guidelines. In both cases, a weighted average emission factor was calculated using average temperatures and the number of animals raised at the provincial level. Therefore, again, it was not necessary to calculate the amount of volatile solids contained in the stored livestock manure.

GE of the sheep category was calculated for the three subcategories ewes, growing lambs and other mature sheep. GE of replacement ewes is included in the subcategory of ewes because the number of ewes in ISTAT's annual statistics includes ewes that have been mounted for the first time. GE of lambs is included in the subcategory other sheep.

NET energy for growth was calculated for the growing lambs category only, as reported in the 2019 IPCC Guidelines. The rationale followed in the IPCC Guidelines is presumably to equate the estimated maintenance and production energy requirements of an adult sheep (which will be higher than that of a primiparous - replacement ewes, since the latter weighs less) with the total energy requirements of a primiparous, which will be given by a maintenance and production energy requirement, lower than that of the adult sheep, plus the energy requirement for growth.

The December 1 ISTAT statistics on average represent the entire stock of sheep raised. It should be noted that on average most lambs are slaughtered over the Christmas period. Therefore, this category of animals is well represented in the December 1 annual statistics.

Rabbits

Methane emissions from rabbits have been estimated using a country-specific EF suggested by the CRPA. Daily dry matter intakes for brood-rabbits and other rabbits are 0.13 kg day⁻¹ and 0.11 kg day⁻¹, respectively. Besides, a value of 0.6% has been assumed as CH₄ conversion rate (CRPA, 2004[c]).

Other livestock categories

A Tier 1 approach is used to estimate CH₄ emissions from swine, goats, horses, mules and asses, ostriches, with default EFs from Table 10.10 of Volume 4 of 2019 Refinement (IPCC, 2019). For goats and swine the updated values of this table were applied, which distinguish among high and low productivity systems: data from the National Livestock Registry Database (BDN, several years) about low productivity breeding systems by family-run farms, available starting from the year 2011, were used to calculate a weighted average EF starting from the values provided by Table 10.10; before 2011, EF of high productivity system were used.

For the first time emissions from enteric fermentation of ostriches were estimated in this submission, as EF were made available by Table 10.10 of Volume 4 of 2019 Refinement.

Table 5.15 presents the emission factors (EFs) for all livestock categories, including dairy cattle, non-dairy cattle, buffalo, swine, sheep, goats, horses, mules and asses, rabbits, and ostriches. Table 5.16 shows the time series of the number of animals for these categories.

Table 5.15 Average CH₄ emission factors for enteric fermentation (kg CH₄ head⁻¹ year⁻¹)

Year	Dairy cattle	Non-dairy cattle	Buffalo	Sheep	Goats	Horses	Mules and asses	Sows	Other swine	Rabbits	Ostriches
average CH ₄ EF (kg CH ₄ head ⁻¹ year ⁻¹)											
1990	111.1	43.2	71.7	7.0	9.0	18.0	10.0	1.5	1.5	0.08	5.0
1995	123.6	43.7	73.0	6.9	9.0	18.0	10.0	1.5	1.5	0.08	5.0
2000	124.6	43.9	75.4	6.4	9.0	18.0	10.0	1.5	1.5	0.08	5.0
2005	122.5	43.1	81.3	7.1	9.0	18.0	10.0	1.5	1.5	0.08	5.0
2010	122.6	43.0	73.8	7.1	9.0	18.0	10.0	1.5	1.5	0.08	5.0
2015	124.9	44.0	74.4	7.1	9.0	18.0	10.0	1.5	1.5	0.08	5.0
2020	135.8	44.8	73.9	7.3	8.8	18.0	10.0	1.5	1.5	0.08	5.0
2021	138.7	45.0	74.0	7.3	8.8	18.0	10.0	1.5	1.5	0.08	5.0
2022	139.9	45.1	73.8	7.4	8.8	18.0	10.0	1.5	1.5	0.08	5.0
2023	140.9	45.0	73.8	7.5	8.8	18.0	10.0	1.5	1.5	0.08	5.0
2024	145.1	41.9	73.3	7.8	8.8	18.0	10.0	1.5	1.5	0.08	5.0

Table 5.16 Time series of number of animals from 1990 to 2024 (heads)

Year	Buffalo	Sheep	Goats	Horses	Mules and asses	Sows	Other swine	Rabbits	Ostriches	Poultry
heads										
1990	94,500	8,739,253	1,258,962	287,847	83,853	650,919	7,755,602	14,893,771	200	173,341,562
1995	148,404	10,667,971	1,372,937	314,778	37,844	689,846	7,370,830	17,110,587	5,000	184,202,416
2000	192,000	11,089,000	1,375,000	280,000	33,000	708,000	7,599,000	17,873,993	38,387	176,725,551
2005	205,093	7,954,167	945,895	278,471	30,254	721,843	8,478,427	20,504,282	28,245	178,206,175
2010	365,086	7,900,016	982,918	373,324	46,475	717,366	8,603,753	17,957,421	5,246	185,074,894
2015	374,458	7,148,534	961,676	384,767	70,872	582,447	8,092,346	15,760,502	3,962	175,554,568
2020	407,027	7,034,164	1,065,712	367,561	72,455	568,550	7,974,479	11,010,203	2,272	176,802,026
2021	409,408	6,728,351	1,060,748	367,561	72,455	550,991	7,856,977	10,945,940	2,272	174,744,759
2022	416,053	6,567,546	1,010,143	365,414	75,978	692,714	8,046,670	12,674,189	2,272	162,721,734
2023	416,479	6,497,003	979,913	314,303	80,939	649,429	8,521,731	14,247,336	2,272	172,409,888
2024	437,256	5,390,345	910,545	321,649	88,799	596,994	7,223,496	14,654,745	2,272	174,003,075

5.2.3 Uncertainty and time-series consistency

Uncertainty related to CH₄ emissions from enteric fermentation was 20.2% for annual emissions, resulting from the combination of 3% of uncertainty for activity data and 20% for emission factors.

In 2024, CH₄ emissions from enteric fermentation were 481.71 kt, i.e., 21.5% lower than in 1990 (613.37 kt). Between 1990 and 2024 cattle livestock decreased by 31.3% (from 7,752,152 to 5,327,932 heads). Dairy cattle and non-dairy cattle have decreased by 42.4% (from 2,641,755 to 1,520,686) and 25.5% (from 5,110,397 to 3,807,246), respectively. The reduction in the number of cattle is the main driver for the reduction in CH₄ emissions, particularly as emissions per head from cattle are more than 10 times greater than those of sheep or goats. In 2024, cattle contributed 78.9% to total CH₄ emissions from enteric fermentation.

In Table 5.17, emission trends from the enteric fermentation category are shown. Emissions from swine (11.72 kt) are disaggregated in 'other swine' and 'sow'.

Table 5.17 Trend of CH₄ emissions from enteric fermentation (kt)

Year	Dairy cattle	Non-dairy cattle	Buffalo	Sheep	Goats	Horses	Mules and asses	Sows	Other swine	Rabbits	Ostriches	Total
1990	293.57	220.88	6.77	61.04	11.33	5.18	0.84	0.98	11.63	1.16	0.001	613.37
1995	256.99	226.59	10.84	73.62	12.36	5.67	0.38	1.03	11.06	1.33	0.025	599.87
2000	257.36	218.97	14.48	71.39	12.38	5.04	0.33	1.06	11.40	1.39	0.192	593.98
2005	225.58	190.23	16.67	56.76	8.51	5.01	0.30	1.08	12.72	1.59	0.141	518.60
2010	214.10	175.66	26.94	56.34	8.85	6.72	0.46	1.08	12.91	1.39	0.026	504.47
2015	228.11	173.88	27.85	50.72	8.66	6.93	0.71	0.87	12.10	1.22	0.020	511.07
2020	222.55	195.06	30.09	51.01	9.38	6.62	0.72	0.85	11.94	0.86	0.011	529.09
2021	223.35	191.82	30.30	49.23	9.31	6.62	0.72	0.83	11.77	0.85	0.011	524.80
2022	228.13	180.44	30.72	48.92	8.86	6.58	0.76	1.04	12.05	0.98	0.011	518.49
2023	221.90	180.27	30.72	48.42	8.59	5.66	0.81	0.97	12.77	1.11	0.011	511.22
2024	220.60	159.38	32.05	42.16	7.98	5.79	0.89	0.89	10.82	1.14	0.011	481.71

5.2.4 Source-specific QA/QC and verification

Information related to the Agricultural census has been analysed and verified, as mentioned in paragraph 5.1.4. Information and administrative data related to number of heads, average weight by livestock category, milk production data are collected by the Ministry of Agriculture as part of the 2016 December the 9th Decree of Ministry for the Environment, Land and Sea entitled "*Attuazione della legge 3 maggio n. 79 in materia di ratifica ed esecuzione dell'Emendamento di Doha al Protocollo di Kyoto*" (GU, 2016[b]) and comparisons and verifications were made with the data used to estimate emissions.

5.2.5 Source-specific recalculations

The 2019 IPCC guidelines for enteric emissions from buffaloes, swine, sheep and goats have been implemented.

For buffalo cows the average value of DE provided by Table 10.2 of Volume 4 of 2019 refinement for cattle and other ruminants (pasture/mixed diet fed) equal to 67.5% was used to calculate the EF, in place of 65% used before, leading to reduced estimated CH₄ emissions.

For goats and swine the updated values of Tier 1 EF from Table 10.10 of Volume 4 of 2019 Refinement were applied, which distinguish among high and low productivity systems: data from the National Livestock Registry Database (BDN, several years) about low productivity breeding systems by family-run farms, available starting from the year 2011, were used to calculate a weighted average EF starting from the values provided by Table 10.10; before 2011, EF of high productivity system were used, which for swine is equal to the EF of IPCC 2006 guidelines, previously applied, so in this case there is no recalculation.

The same updated value of DE was used for sheep leading to a recalculation of the EF, together with an updated value of Y_m, based on text above Table 10.13 of volume 4 of 2019 refinement: the value of 7.0 percent being more appropriate where average dry matter intake is <0.6 kg day⁻¹ has been attributed to growing lambs, and the value of 6.5 percent being more appropriate where average dry matter intakes are >0.8 kg day⁻¹ has been attributed to ewes and other mature sheep.

For dairy cattle two errors have been corrected about the number of heads used to calculate milk production for the years 2017 and 2023; for the year 2017 the correction caused a recalculation of 0.003% (0.01 kt CH₄). Moreover, the values of DE and Y_m have been corrected for the year 2021, as the reference table from the Italian Livestock Breeders' Association (AIA) was modified.

For housed ewes a minor recalculation concerned the use of the updated value of Ca 0.0096 MJ day⁻¹ kg⁻¹ from Table 10.5 of 2019 Refinement, in place of the IPCC 2006 value 0.0090, to calculate the net energy for activity (NEa).

For horses, mules and asses the EF was not updated in 2019 Refinement; only the number of heads for the year 2023 was updated, causing a recalculation for that single year.

The national population of rabbits has been updated for the year 2023, based on an update of the source activity data.

For the first time emissions from enteric fermentation of ostriches were estimated in this submission, resulting in a 100% recalculation along the entire historical series.

The impacts of the described recalculations on estimated CH₄ emissions are summarized in Table 5.18, expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. The resulting overall CH₄ recalculation from enteric fermentation were in the range of $\pm 1\%$ along the time series.

Table 5.18 Recalculation of reported CH₄ emissions from enteric fermentation

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Dairy cattle									
Recalculation [kt CH ₄]	-	-	-	-	-	-	- 1.56	-	- 3.96
% recalculation	-	-	-	-	-	-	-1%	-	-2%
Buffalo cows									
Recalculation [kt CH ₄]	-0.26	-0.54	-0.69	-1.05	-1.07	-1.08	-1.07	-1.07	-0.26
% recalculation	-4%	-4%	-4%	-4%	-3%	-3%	-3%	-3%	-4%
Sheep									
Recalculation [kt CH ₄]	-1.85	-0.79	-1.93	-1.62	-1.67	-1.64	-1.87	-1.84	-1.85
% recalculation	-3%	-1%	-3%	-3%	-3%	-3%	-4%	-4%	-3%
Goats									
Recalculation [kt CH ₄]	5.04	5.50	3.78	3.93	3.85	4.05	4.00	3.80	3.69
% recalculation	80%	80%	80%	80%	80%	76%	76%	75%	75%
Horses									
Recalculation [kt CH ₄]	-	-	-	-	-	-	-	-	- 0.92
% recalculation	-	-	-	-	-	-	-	-	-14%
Mules and Asses									
Recalculation [kt CH ₄]	-	-	-	-	-	-	-	-	0.05
% recalculation	-	-	-	-	-	-	-	-	7%
Swine									
Recalculation [kt CH ₄]	-	-	-	-	- 0.04	- 0.02	- 0.02	- 0.02	- 0.02
% recalculation	-	-	-	-	-0.3%	-0.2%	-0.2%	-0.1%	-0.1%
Rabbits									
Recalculation [kt CH ₄]	-	-	-	-	-	-	-	-	0.04
% recalculation	-	-	-	-	-	-	-	-	4.0%
Ostriches									
Recalculation [kt CH ₄]	0.00	0.19	0.14	0.03	0.02	0.01	0.01	0.01	0.01
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	100%
Total									
Recalculation [kt CH ₄]	2.92	4.36	1.30	0.83	1.17	1.31	- 0.28	0.86	- 3.72
% recalculation	0.48%	0.74%	0.25%	0.16%	0.23%	0.25%	-0.05%	0.17%	-0.72%

5.2.6 Source-specific planned improvements

In 2026, a project will be launched with the CRPA, which will last about a year and will include various activities related to livestock farming. Based on numerous studies and data collected, and through an analysis of existing literature and the most recent experimental contributions carried out in Italy on beef cattle, data relating to rations used, estimates of GE, DE and Ym parameters for cattle by subcategory, ration protein and corresponding nitrogen excretion will be verified and updated. The data estimated in the inventory will be verified at the same time and updated if necessary.

It will be verified with AGRIS Sardegna the data on the number of sheep giving birth and the estimated number of lambs based on ISTAT data.

5.3 Manure management (3B)

5.3.1 Source category description

In 2024, CH₄ emissions from manure management were 146.35 kt, which represents 21.1% of CH₄ emissions for the agriculture sector (21.6% in 1990) and 9.5% of national CH₄ emissions (9.6% in 1990). CH₄ emissions from cattle were 66.92 kt and from swine were 63.89 kt. These two subcategories represented 45.7% and 43.7% of total CH₄ manure management emissions, respectively. CH₄ emissions from manure management also include emissions from ostriches and emissions from pasture of cattle and buffalo categories, as recommended during 2019 UNFCCC review.

N₂O direct and indirect emissions, produced during the storage and treatment of manure before it is applied to soils, are reported separately. In 2024, N₂O emissions from manure management were 7.03 kt (of which 5.19 kt are direct emissions and 1.84 kt are indirect emissions), which represents 22.8% of total N₂O emissions for the agriculture sector (28.1% in 1990) and 13.5% of national N₂O emissions (13.6% in 1990). In 2024, direct N₂O emissions from manure management consist of the solid storage system (3.21 kt), which also includes the chicken-dung drying process system, liquid system (1.90 kt) and anaerobic digesters (0.09 kt).

In the framework of the Nitrogen Balance Inter-regional Project, parameters related to the estimation of CH₄ and N₂O emissions, such as average weight, production of slurry and solid manure and the nitrogen excretion rates, have been set.

CH₄ emissions from manure management are key sources at level, following Approach 1 and 2, including and excluding LULUCF sector. Direct N₂O emissions from manure management are key sources at level, following Approach 1 and 2, including LULUCF sector. Indirect N₂O emissions from manure management are not key sources.

5.3.2 Methodological issues

The IPCC Tier 2 approach is used for estimating methane EFs for manure management of cattle, buffalo and swine. For estimating slurry and solid manure EFs and the specific conversion factors, a detailed methodology (*Method 1*) was applied at a regional level for cattle and buffalo categories. Then, a simplified methodology, for estimating EF time series, was followed (*Method 2*). Livestock population activity data is collected from ISTAT (see Table 5.8; Table 5.9; Table 5.16).

Methane emissions (cattle and buffalo)

Method 1: Regional basis

Methane emission estimations for manure management are drawn up on a regional basis and depend on specific manure management practices and environmental conditions (Safley *et al.*, 1992; Steed and Hashimoto, 1995; Husted, 1993; Husted, 1994). The following factors are used: average monthly temperatures (ISPRA, 2020), amount of slurry and solid manure produced per livestock category (CRPA, 2018; CRPA, 2006[a]; Regione Emilia Romagna, 2004), storage temperatures and timescale for emptying manure storages for the application of slurry and solid manure to soils for agricultural purposes in Italy (CRPA, 1993).

For cattle and buffalo, the estimation of the EF starts with the calculation of the *methane emission rate* ($\text{g CH}_4 \text{ m}^{-3} \text{ day}^{-1}$), which is obtained from equations 5.1 and 5.2 reported below for slurry and solid manure respectively.

For the quantification of emissions from storage of cattle manure, the methodology adopted is based on the studies conducted by Husted. The Husted methodology allows estimating methane based on the parameters defining the manure storage in Italy. These parameters, which are mentioned in the introduction of this section, are average monthly temperatures, amount of slurry and solid manure produced per livestock category, storage temperatures and timescale for emptying manure storages. This method was adopted as it is based on experimental surveys carried out in the field, in environmental and breeding conditions that are transferable to the Italian reality with appropriate adaptations. This methodology allows to modulate the mass of methane emitted in relation to changes in temperature on a monthly basis. The average annual temperature represents an approximate datum for the elaboration of the methane emission estimates, since the same average annual value can correspond to more or less wide temperature excursions between the months (Steed and Hashimoto, 1995). This is followed by different methane emissions from manure storage depending on the number of months for which the 10°C threshold is exceeded, below which emissions are considered negligible. According to the methodology adopted, the mass of methane is calculated based on two parameters, one of which is measured experimentally in field conditions (emission per unit volume of manure in relation to temperature) and the other estimated (the amount of slurry and solid manure produced and stored).

Average monthly temperature data were updated based on SCIA¹⁶ data. SCIA made available the climatic normal temperature values for the 30-year climatological periods 1971-2000, 1981-2010 and 1991-2020 in raster format. Using GIS software, the raster data were converted into points and intersected with the shape of the municipal boundaries to which altitude and LU data (i.e., data on the number of animals reared at municipal level, expressed in livestock unit, where 1 LU=one adult dairy cow) were also associated. Average data of 1971-2000 climatological period were considered to estimate the emissions in the first decade of the time series (1990-2000), while average data of 1981-2010 climatological period were considered to estimate the emissions for the period 2001-2010 and average data of 1991-2020 climatological period were considered to estimate the emissions from 2011 onward. Temperature data above 1000 m were not considered. National average monthly temperature data (obtained by weighing provincial average monthly temperature data with LUs) were used to update methane emissions from storage, according to the country-specific methodology. This update resulted in a revision of the CH₄ estimate from manure management for cattle and buffalo categories. Temperature data, aggregated per province by weighting with LUs, were used to recalculate MCF.

Equations are presented below (CRPA, 2006[a]; Husted, 1994).

For slurry:

¹⁶ SCIA is the national system for the collection, elaboration and dissemination of climatological data, by ISPRA, in the framework of the national environmental information system, in collaboration with the relevant institutions: http://www.scia.isprambiente.it/wwwrootscia/Home_new_eng.html

$$\text{CH}_4 \text{ (g m}^{-3} \text{ day}^{-1}) = e^{(0.68+0.12) * t \text{ (}^\circ\text{C) (average monthly temperature)}} \quad \text{Eq. 5.1}$$

For solid manure:

$$\text{CH}_4 \text{ (g m}^{-3} \text{ day}^{-1}) = e^{(-2.3+0.1) * t \text{ (}^\circ\text{C) (average monthly storage temperature)}} \quad \text{Eq. 5.2}$$

The monthly storage temperature from the solid manure is estimated with the following equation (Husted, 1994):

$$T \text{ solid manure storage} = 6,7086e^{0.1014t \text{ (}^\circ\text{C) (average monthly temperature)}}$$

For temperatures below 10°C emissions are considered negligible.

The volume of slurry and solid manure produced per livestock category ($\text{m}^3 \text{ head}^{-1}$) was obtained by multiplying the average production of slurry and solid manure per livestock category per day ($\text{m}^3 \text{ head}^{-1} \text{ day}^{-1}$) by the days of storage of slurry and solid manure. The volume of slurry and solid stored manure is based on regional regulations concerning the spreading of manure on agricultural land. Information about days of storage considers the retention time in storage facilities and temporal dynamics of storage and application on soils of slurry and manure (CRPA, 1997[a]). The production of solid manure and slurry were estimated assuming a distribution of housing systems in Italy. The distribution of housing for dairy cattle has been assessed on the basis of a 1998 CRPA survey carried out in Lombardy, Emilia Romagna and center of Italy, and on the basis of ISTAT statistics of 2003 (CRPA, 2006[a]; Bonazzi *et al.*, 2005; APAT, 2004[a]; APAT, 2004[b]) for the period 1990-2005; from 2010 onward, the housing systems distribution has been deduced by the results of the 2010 Agricultural Census. Between 2005 and 2010 a gradual transition to the updated distribution of housing systems has been assumed for the intermediate years, taking into account the gradual penetration of systems to ensure animal welfare. For non-dairy cattle and buffalo categories data on distribution of housing systems derive from national studies and expert judgment (CRPA, 2006[a]). Starting from 2020, the distribution of housing based on 2020 Agriculture Census was used for cattle category.

By multiplying the *methane emission rates* (obtained from equations 5.1 and 5.2) with the volume of slurry and solid stored manure, the methane emissions were calculated.

The next step is to estimate the volatile solid (VS) production, calculated by multiplying the average production of slurry and solid manure (previously converted from volume to weight: slurry and solid manure values expressed in volume were multiplied by 1 t/m^3 and 0.75 t/m^3 , respectively, to obtain the values in mass unit) by the factors proposed by Husted: 47.5 g VS/kg (slurry) and 142.7 g VS/kg (solid manure) (Husted, 1994; CRPA, 2006[a]). These values are very close to those obtained from a survey carried out by the CRPA on the characteristics of zootechnical manure in different types of breeding, equal to 48.21 g VS/kg (slurry) and 128.31 g VS/kg (solid manure). This survey allowed a collection of national data relating to solid and liquid manure of dairy cows for different types of housing. This collection of samples made it possible to quantify the production of manure, the total solids and the volatile solids (APAT, 2004[a]).

Finally, the *specific conversion factors* for slurry and solid manure are calculated as the ratio between methane emissions and VS production. These *specific conversion factors* are used for simplified methodology (*Method 2*). The *specific conversion factor* values for slurry are 17.25, 18.12 and 18.87 g $\text{CH}_4/\text{kg VS}$ for the period 1990-2000, 2001-2010 and from 2011 onward, respectively; and for solid manure are 8.11, 9.28 and 10.68 g $\text{CH}_4/\text{kg VS}$ for 1990-2000, 2001-2010 and from 2011 onward, respectively.

Method 2: National basis

A simplified methodology (*Method 2*) for estimating methane EFs from manure management was used for the whole time series. Slurry and solid manure EFs ($\text{kg CH}_4 \text{ head}^{-1} \text{ year}^{-1}$) were calculated with Equations 5.3 and 5.4, respectively. These equations include the *specific conversion factors* and the production of VS ($\text{kg head}^{-1} \text{ day}^{-1}$), estimated with the slurry and solid manure production and the Husted factors (Husted, 1994; CRPA, 2006[a]): 47.5 g VS/kg (slurry) and 142.7 g VS/kg (solid manure).

The daily VS excreted, estimated for slurry and solid manure, are summed and used for calculating the methane producing potential (Bo).

In Table 5.19, EF estimations are shown.

EF slurry (for the period 1990-2000) = $17.25 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production slurry (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.3(a)

EF slurry (for the period 2001-2010) = $18.12 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production slurry (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.3(b)

EF slurry (for the period since 2011) = $18.87 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production slurry (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.3(c)

EF solid manure (for the period 1990-2000) = $8.11 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production solid manure (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.4(a)

EF solid manure (for the period 2001-2010) = $9.28 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production solid manure (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.4(b)

EF solid manure (for the period since 2011) = $10.68 \text{ g CH}_4/\text{kg VS} \bullet \text{VS production solid manure (kg VS head}^{-1} \text{ day}^{-1}) \bullet 365 \text{ days}$
Eq. 5.4(c)

Table 5.19 Methane manure management EFs for cattle and buffalo in 2024 (kg CH₄ head⁻¹ yr⁻¹)

Livestock category	Slurry (kg CH ₄ head ⁻¹ yr ⁻¹)	Solid manure (kg CH ₄ head ⁻¹ yr ⁻¹)	CH ₄ manure management EF (kg CH ₄ head ⁻¹ yr ⁻¹)
Calf	7.74	0.00	7.74
Male cattle	4.03	8.19	12.22
Female cattle	3.19	6.94	10.14
Other non-dairy cattle (*)	4.88	10.87	15.74
Dairy cattle	11.44	11.93	23.37
Cow buffalo	6.16	13.99	20.15
Other buffaloes	3.35	6.36	9.71

(*) Suckling cows and cows in late career (average weight 557 kg).

The subcategory 'Other non-dairy cattle' includes suckling cows (cows farmed for feeding of calves, whose milk is not normally intended for human consumption) and cows in late career defined as cows after the last lactation, no longer productive that will be slaughtered. Dairy cows in late career but still productive are included in dairy cattle category.

The average production of slurry and solid manure per livestock category per day (m³ head⁻¹ day⁻¹) has been set with results from the Nitrogen Balance Inter-regional Project (Regione Emilia Romagna, 2004). The updating on manure production for cattle and buffalo, based on Ministerial Decree of 25 February 2016 on criteria and general technical standards for the regional regulation of the agronomic use of farmed effluents and wastewater, as well as for the production and agronomic use of digestate (GU, 2016[a]), has been done. Based on the type and housing systems distribution for the different animal categories, and on the average weight of animals, a time series of slurry and solid manure production was obtained. The manure production data (liquid/slurry and solid) from the 2016 Ministerial Decree were used for the cattle and buffalo categories from 2016 onward and a gradual change from 2006 to 2016 production factors were calculated over the period from 2007 to 2015.

In Table 5.20 the disaggregated manure management EFs for cattle and buffalo are shown. In Table 5.26 the average EFs of main categories (dairy, non-dairy, buffalo and swine) are reported.

Table 5.20 Methane manure management EFs for cattle and buffalo (kg CH₄ head⁻¹ yr⁻¹)

Year	Calf	Male cattle	Female cattle	Other non dairy cattle (*)	Dairy cattle	Cow buffalo	Other buffaloes
(kg CH ₄ head ⁻¹ yr ⁻¹)							
1990	7.07	11.08	9.81	15.85	22.38	23.61	9.32
1995	7.07	11.70	9.82	15.85	22.38	23.45	9.26
2000	7.07	11.29	9.95	15.85	22.38	23.29	9.19
2005	7.43	12.92	11.31	17.71	25.01	25.94	10.11
2010	7.43	12.48	10.51	16.15	25.09	22.80	9.56
2015	7.74	12.81	10.65	15.92	24.50	21.06	9.86
2020	7.74	13.52	10.59	15.74	23.37	20.15	9.71
2021	7.74	13.54	10.67	15.74	23.37	20.15	9.71
2022	7.74	13.73	10.47	15.74	23.37	20.15	9.71
2023	7.74	13.67	10.45	15.74	23.37	20.15	9.71
2024	7.74	12.22	10.14	15.74	23.37	20.15	9.71

(*) Suckling cows and cows in late career (average weight 557 kg).

In Table A.7.12-14 in Annex 7, reported in the NIR submitted in 2024 (National Inventory Report - Italian Greenhouse Gas Inventory 1990-2022), available at the link <https://emissioni.sina.isprambiente.it/inventario-nazionale/>, all data, parameters and equations used to estimate CH₄ emission from manure management for cattle and buffalo are reported. These data are: the average monthly temperature; storage temperatures and timescale for emptying manure storages; the amount of manure generated by each subcategory of cattle and buffalo (m³/head day⁻¹); the *methane emission rates* (g CH₄/m³ day⁻¹) calculated on the basis of the equations 5.1 and 5.2; the specific conversion factors (g CH₄/kg VS); the content of VS in manure (g VS/head day⁻¹) produced by different subcategories of cattle (dairy and non-dairy cattle) and buffalo (cow buffaloes and other buffaloes); the slurry and solid manure EFs (kg CH₄/head year⁻¹) calculated with Equations 5.3 and 5.4 respectively; the total (slurry and solid manure) amount of VS handled in slurry/liquid and solid manure management systems for the entire reporting period; the total (slurry and solid manure) CH₄ emission factors.

In this submission the methane emission rates have been applied only to the amount of manure generated by housed livestock over the entire time series, to avoid double counting of emissions from pasture which are calculated separately. CH₄ emissions from manure management category (3B) also include emissions from the biogas production. A national census on biogas production/technology/installed power/organic matrix used is available in CRPA and CRPA/AIEL (CRPA, 2013; CRPA, 2011; ENAMA, 2011; CRPA, 2008[a]; CRPA/AIEL 2008). Biogas production data are collected annually by the National Electric Network (TERNA, several years) and the National Energy Balance. Emissions of methane, from biogas produced by anaerobic digesters fed with animal manure, to be deducted to the total amount of methane from manure management, were calculated using the information and data provided by TERNA and CRPA and GSE (Energy services provider). For further information on the country-specific methodology used see Annex 7.2. Based on the study for the evaluation of the effects on emissions of livestock management practices carried out by CRPA (CRPA, 2018), the percentages of the different substrates feeding the anaerobic digesters and data on the average content of volatile solids by type of substrates have been changed resulting in a decrease of the estimated amount of manure feeding anaerobic digesters. For the year 2024 this amount is equal to about 17 million tons and that is 46% of the total amount of feed treated in anaerobic digesters. Emissions from plant biogas losses, fueled by manure, energy crops and agro-industrial by-products, are greater than avoided emissions due to biogas recovery (for cattle until 2012). This is due to the estimated amount of manure that feeds the digesters, which is low compared to other substrates. Therefore, increases in CH₄ emissions related to biogas recovery are assumed for cattle until 2012 according to the methodology described in Annex 7.2 (see paragraph *CH₄ emissions to be subtracted*).

In 2024, the CRT IEFs, for dairy cattle and non-dairy cattle, were 21.69 kg CH₄ head⁻¹ year⁻¹ and 8.91 kg CH₄ head⁻¹ year⁻¹, respectively. IPCC default EFs of cool temperate are 29 kg CH₄ head⁻¹ year⁻¹ and 8 kg CH₄ head⁻¹ year⁻¹ for dairy cattle and non-dairy cattle, respectively (IPCC, 2006). The IPCC default EFs of cool temperate are considered as the estimate of the national average temperature is 14.8 °C calculated from SCIA data of 1991-2020 climatological period. The IEF for non-dairy cattle and buffalo represents a weighted average. The non-dairy cattle IEF includes calves, male cattle, female cattle and other non-dairy cattle. The buffalo category includes cow buffalo and other buffaloes' categories. In Table 5.21, EFs and IEFs are shown. Differences, as mentioned before, are related to the amount of CH₄ reductions from biogas recovery and IEFs include also CH₄ emissions from pasture. In Table 5.21, the default EFs of the IPCC 2006 Guidelines are also reported.

Table 5.21 CH₄ EFs, IEF and default EF for cattle and buffalo (kg CH₄ head⁻¹ yr⁻¹)

Livestock category	EF (*) (kg CH ₄ head ⁻¹ yr ⁻¹)	IEF (**) (kg CH ₄ head ⁻¹ yr ⁻¹)	IPCC 2006 default EF (kg CH ₄ head ⁻¹ yr ⁻¹)
Dairy cattle	23.37	21.69	29
Non-dairy cattle	10.90	8.91	8
Buffalo	15.52	15.13	5

(*) Data do not include EFs for pasture; (**) IEF as reported in the CRT submission 2026.

Emissions from the biogas combustion for energy production are estimated and reported in the energy sector in the 1.A.4.c category, agriculture, forestry and fisheries, biomass fuel.

Detailed information on the estimate of weighted average values of CH₄ producing potential (Bo) and methane conversion factor (MCF) is provided below.

The methodology used, based on Husted studies, does not require the estimate of Bo. Therefore, the factor is estimated with 2006 IPCC Guidelines Equation 10.23 (Chapter 10 of Volume 4) and using country specific EFs and VS by livestock category described above and the average value of MCF by livestock category.

The 2006 IPCC MCF values by temperature for manure management systems (solid storage, pasture, liquid/slurry system) are used. For liquid/slurry system, at first, the values of MCF at the provincial level were calculated based on the 2006 IPCC MCFs, by temperature, based on the average provincial temperatures (i.e., the average temperature at provincial level was calculated by weighing the temperature at municipal level data with the percentage of animals at provincial level). Subsequently, the MCF national average values by livestock category for climate zone (considering cool (<15°C) and temperate (≥ 15°C) climate zone) were calculated as the average of the provincial MCF values weighed with the animals distributed by province for climatic zone. In relation to the climatic zones of the country and the average temperatures, see also the paragraph *Other livestock categories* below. The number of animals at provincial level come from the Agriculture Census from 1990, 2000, 2010 and 2020, and from the FSS for 2005 (ISTAT, 2007[a]), 2007 (ISTAT, 2008[a]), 2013 and 2016¹⁷.

Information on the estimation process of the weighted average values of MCF for animal manure digested in anaerobic digesters are reported in Annex 7.2. Average MCFs were not used for estimating manure management EF, but they are useful to verify the EF accuracy.

In Table 5.22, estimated country-specific VS and Bo parameters, and IPCC default values are shown (IPCC, 2006). Differences are mainly attributed to country-specific characteristics.

Table 5.22 VS and Bo parameters for cattle, buffalo and swine

Livestock category	VS country-specific (*) (kg dm head ⁻¹ day ⁻¹)	VS IPCC default (kg dm head ⁻¹ day ⁻¹)	Bo country-specific (*) (CH ₄ m ³ /kg VS)	Bo IPCC default (CH ₄ m ³ /kg VS)
Dairy cattle	4.72	5.10	0.22	0.24
Non-dairy cattle	2.33	2.60	0.30	0.18

¹⁷ <http://dati.istat.it/?lang=en&SubSessionId=cead0f83-139d-4121-9178-e7de3f81675f>

Livestock category	VS country-specific (*) (kg dm head ⁻¹ day ⁻¹)	VS IPCC default (kg dm head ⁻¹ day ⁻¹)	B ₀ country-specific (*) (CH ₄ m ³ /kg VS)	B ₀ IPCC default (CH ₄ m ³ /kg VS)
Buffalo	3.43	3.90	0.18	0.10
Swine	0.33	0.31(**)	0.40	0.45

(*) as reported in the CRT submission 2026; (**) weighted average with the number of heads of sows and other swine categories.

As recommended during 2019 UNFCCC review, the VS for cattle and buffalo are calculated also using equation 10.24 of the 2006 IPCC Guidelines (Chapter 10 of Volume 4). The results are: for dairy cattle 5.07 kg dm/head/day in 1990 and 6.48 kg dm/head/day in 2024; for non-dairy cattle 2.86 kg dm/head/day in 1990 and 2.76 kg dm/head/day in 2024; for buffalo 3.10 kg dm/head/day in 1990 and 3.19 kg dm/head/day in 2024.

For dairy cows, VS from manure is affected by the variation over the years of the housing systems, which affect the production of manure; the equation 10.24 of the 2006 IPCC Guidelines does not allow for this important parameter to be considered when estimating methane emissions from storage. For non-dairy cattle category, the enteric VS was calculated assuming DE equal to 65%, but this value should be higher given the Y_m values estimated using Ellis' formula, as described in Section 5.2.2 Methodological issues (Non-dairy cattle).

As regards the contribution of straw, the methodology used, based on Husted studies, does not require a control on the straw used. As reported in the MeditAIRaneo project, the VS produced in slurry/liquid and solid animal manure were elaborated using Husted data, i.e., 47.5 gVS/kg of slurry and 142.7 gVS/kg of solid manure (Husted, 1994; CRPA, 2006[a]). As reported in Husted (Husted, 1994), cattle slurry does not contain bedding material and cattle solid manure consisted mainly of faeces and a minor fraction of bedding material. Finally, as reported in the 2006 IPCC Guidelines, since the bedding materials typically are associated with solid storage systems, their contribution would not add significantly to overall methane production. However, the amount of straw used as bedding was estimated and the cross-check of amounts of bedding material contained in the manure used to estimate CH₄ emissions and N₂O emissions from animal manure applied to agricultural soils has been done, as recommended by the 2019 UNFCCC review. The amount of straw used as bedding that ends up on agricultural land during the spreading of manure was estimated considering the amount of straw per day (per tonnes of live weight, per type of housing, for cattle and buffalo), contained in the Ministerial Decree of 25 February 2016 on the use of zootechnical effluents, combined with the manure production coefficients used in the estimation of CH₄ emissions from storage. The nitrogen content was considered and added to the nitrogen input from manure applied to soils for N₂O emissions estimate. Data for cattle were updated, while data for buffaloes, previously missing, were included. Data have been updated since 1990. Further information and data can be found in paragraph 5.5.2 (Direct N₂O emissions from F_{AM}) and in Annex 7.3.

In the calculation of CH₄ EFs, for cattle and buffalo categories, the MCF value for both cool and temperate climate conditions was considered in the estimate in line with equation 10.23 of the 2006 IPCC Guidelines (Chapter 10 of Volume 4). In Table 5.23 the disaggregated manure management EFs from pasture of cattle and buffalo are shown.

Table 5.23 CH₄ EFs from pasture for cattle and buffalo (kg CH₄ head⁻¹ yr⁻¹)

Year	Calf	Male cattle	Female cattle	Other non-dairy cattle (*) (kg CH ₄ head ⁻¹ yr ⁻¹)	Dairy cattle	Cow buffalo	Other buffaloes
1990	0.019	0.029	0.026	0.042	0.164	0.128	0.050
1995	0.020	0.033	0.028	0.045	0.164	0.123	0.048
2000	0.023	0.036	0.032	0.050	0.164	0.118	0.047
2005	0.022	0.038	0.034	0.053	0.182	0.128	0.050
2010	0.068	0.114	0.096	0.148	0.161	0.106	0.045
2015	0.151	0.251	0.208	0.311	0.181	0.085	0.040
2020	0.256	0.447	0.350	0.521	0.188	0.081	0.039

Year	Calf	Male cattle	Female cattle	Other non-dairy cattle (*)	Dairy cattle	Cow buffalo	Other buffaloes
(kg CH ₄ head ⁻¹ yr ⁻¹)							
2021	0.256	0.448	0.353	0.521	0.188	0.081	0.039
2022	0.256	0.454	0.346	0.521	0.188	0.081	0.039
2023	0.256	0.452	0.346	0.521	0.188	0.081	0.039
2024	0.256	0.404	0.335	0.521	0.188	0.081	0.039

(*) Suckling cows and cows in late career (average weight 557 kg).

Methane emissions (swine)

For the estimation of CH₄ emissions for swine, a country-specific *methane emission rate* was experimentally determined by the Research Centre on Animal Production (CRPA, 1996). The estimation of the EF considers: the storage systems for slurry (tank and lagoons), type of breeding and production of biogas.

Different parameters were considered, such as the livestock population, average weight for fattening swine and sows, and *methane emission rate*. Methane emission rates used are 41 normal liters CH₄/100 kg live weight/day for fattening swine, and 47 normal liters CH₄/100 kg live weight/day for sows including piglets (CRPA, 2006[a]). These data were based on experimental measurements on covered storage systems.

The shares of covered/uncovered storage systems are equal to 3% and 97% (CRPA, 2006[b]), respectively; the CH₄ emission rates used for uncovered storage systems were: 37.6 normal liter CH₄/100 kg live weight/day for fattening swine and 43.1 normal liter CH₄/100 kg live weight/day for sows, including piglets. These figures have been estimated based on data provided by CRPA on methane emission rates from covered and total storage (CRPA, 1997 [a]; CRPA, 2006[a]; CRPA, 2006[b]).

The uncovered systems are emitting less than the covered ones since the temperatures are lower. According to the information on the storage systems collected by the 2010 Agriculture Census, the shares of covered/uncovered storage systems are equal to 11% and 89%, respectively; the shares of covered/uncovered storage systems are equal to 25% and 75%, respectively, considering the outcomes of the 2013 FSS ISTAT survey. Based on 2020 Agriculture Census, the shares of covered/uncovered storage systems for other swine are equal to 27% and 73%, for sows are 35% and 65%, respectively.

Characteristics of swine breeding and EFs are shown in Table 5.24; the emission factors reflect the share of covered/uncovered storage systems. The slurry production considered the different swine categories (classified by weight and housing characteristics); the average weight of sows, the production of slurry (t year⁻¹ per t live weight) and the volatile solid content in the slurry (g SV/kg slurry w.b.) have been set based on 598 measurements carried out by CRPA (CRPA, 1996; CRPA, 2006[a]).

In 2024, the EF from sow was 23.85 kg CH₄ head⁻¹year⁻¹, and for the other swine category was 9.52 kg CH₄ head⁻¹ year⁻¹ (average swine EF is 8.33 kg CH₄ head⁻¹year⁻¹). In Table 5.26 the time series of EFs for the swine category (sow and other swine) are shown. The CRT IEF reported is 8.17 kg CH₄ head⁻¹ year⁻¹. IPCC 2006 Guidelines default EF is 8 kg CH₄ head⁻¹year⁻¹ for market swine and 12 kg CH₄ head⁻¹year⁻¹ for breeding swine respectively, for cool temperature and 14°C as average annual temperature (IPCC, 2006). The difference between the EF and the IEF is due to the reduction in CH₄ because of biogas recovery (see Annex 7.2).

For reporting purposes, the VS daily excretion and Bo are estimated and is useful to verify EF accuracy. The VS daily excretion was estimated for each subcategory with the following parameters: animal number, production of slurry (t/y/t live weight) and the volatile solids content in the slurry (g VS/kg slurry). Methane producing potential (Bo) used 2006 IPCC Guidelines Equation 10.23 (Chapter 10 of Volume 4). See paragraph *Methane emissions (cattle and buffalo)* for more details on the estimation process.

Table 5.24 Methane manure management parameters and emission factors for swine in 2024

Livestock category	Average weight (kg)	Breed live weight (t)	Methane emission rate production (Nl CH ₄ /100 kg live weight)	Emission factor (kg CH ₄ head ⁻¹ yr ⁻¹)
Other swine	94	501,553	14,067	9.52
20-50 kg	35	42,766	14,067	3.55
50-80 kg	65	58,626	14,067	6.60
80-110 kg	95	84,914	14,067	9.64
110 kg and more	135	311,648	14,067	13.70
Boar	200	3,599	14,067	20.30
Sows	172	121,536	16,238	23.85
Piglets	10	18,793	16,238	1.17
Sows	172	102,743	16,238	20.16
Total				8.33

The fundamental characteristic of Italian swine production is the high live weight of the animals slaughtered as related to age; the optimum weight for slaughtering to obtain meat suitable for producing the typical cured meats is between 155 and 170 kg of live weight. Such a high live weight must be reached in no less than nine months of age. Other characteristics are the feeding situation, to obtain high quality meat, and the concentration of Italian pig production, limited to a small area (*Lombardia, Emilia-Romagna, Piemonte and Veneto*), representing 75% of national swine resources (Mordenti *et al.*, 1997). These peculiarities of swine production influence the methane EF for manure management as well as nitrogen excretion factors used for the estimation of N₂O emissions.

Other livestock categories

Methane EFs used for calculating the other livestock categories are included in the 2006 IPCC Guidelines. CH₄ emissions from pasture of other livestock categories (i.e., sheep, goats, horses, mules and asses) were not calculated as the manure management emissions for these animal categories were calculated using Tier1 emission factors, which include all management systems, including grazing.

Based on the number of heads at provincial level (NUTS2) and the average temperature of each province, CH₄ emissions were calculated using the 2006 IPCC default emission factors by average annual temperature (considering cool (<15°C) and temperate (≥ 15°C) climate zone) at the provincial level. For the national estimate an IEF was calculated based on the sum of the provincial emissions.

In Table 5.25 the distribution of animals of 2020 is distributed between temperate and cool zones based on provincial the 2020 Agriculture Census data and provincial average temperatures for the 30-year period 1991-2020.

Table 5.25 Number of animals of 2020 in temperate and cool zones

Livestock categories in 2020 based on data from the 2020 Agriculture Census	Heads	Animals in temperate zone (≥ 15°C)		Animals in cool zone (< 15°C)	
		N animals	% animals	N animals	% animals
Non-dairy cattle	4,354,633	1,115,619	25.62	3,239,014	74.38
Dairy cattle	1,638,382	279,135	17.04	1,359,247	82.96
Buffalo	407,027	368,705	90.58	38,322	9.42
Other swine	7,974,479	480,398	6.02	7,494,081	93.98
Sows	568,550	81,775	14.38	486,775	85.62
Sheep	7,034,164	5,488,060	78.02	1,546,104	21.98
Goats	1,065,712	732,807	68.76	332,905	31.24
Horses	367,561	142,577	38.79	224,984	61.21
Mules and asses	72,455	25,220	34.81	47,235	65.19

Livestock categories in 2020 based on data from the 2020 Agriculture Census	Heads	Animals in temperate zone ($\geq 15^{\circ}\text{C}$)		Animals in cool zone ($< 15^{\circ}\text{C}$)	
		N animals	% animals	N animals	% animals
Broilers	101,920,917	9,903,695	9.72	92,017,221	90.28
Layer hens	43,086,376	6,073,293	14.10	37,013,083	85.90
Other poultry	34,321,536	1,548,802	4.51	32,772,734	95.49
Rabbits	11,010,203	833,789	7.57	10,176,415	92.43

In Table 5.26, the average methane EFs for cattle, buffalo and swine categories are shown for the whole time series. For the other categories, the EFs are as follows:

- rabbits, 0.080 kg CH₄ head⁻¹ year⁻¹
- sheep, 0.261 kg CH₄ head⁻¹ year⁻¹
- goats, 0.178 kg CH₄ head⁻¹ year⁻¹
- horses, 1.865 kg CH₄ head⁻¹ year⁻¹
- mules and asses, 0.874 kg CH₄ head⁻¹ year⁻¹
- laying hens, 0.030 kg CH₄ head⁻¹ year⁻¹
- broilers, 0.020 kg CH₄ head⁻¹ year⁻¹
- other poultry, 0.090 kg CH₄ head⁻¹ year⁻¹
- fur animals, 0.680 kg CH₄ head⁻¹ year⁻¹
- ostriches, 5.67 kg CH₄ head⁻¹ year⁻¹

The difference between the EF and the IEF for poultry is due to the reduction in CH₄ because of biogas recovery (see Annex 7.2).

Table 5.26 Average methane EFs for manure management (*) (kg CH₄ head⁻¹ year⁻¹)

Year	Dairy cattle	Non-dairy cattle	Buffalo	Sows	Other swine
			(kg CH ₄ head ⁻¹ year ⁻¹)		
1990	22.38	10.52	18.66	22.14	8.54
1995	22.38	11.00	18.20	21.96	8.52
2000	22.38	10.83	17.71	21.97	8.43
2005	25.01	12.05	20.70	22.30	8.35
2010	25.09	11.18	18.43	22.50	8.42
2015	24.50	11.23	16.75	22.80	8.94
2020	23.37	11.42	15.68	23.10	8.94
2021	23.37	11.45	15.69	23.10	8.87
2022	23.37	11.61	15.57	23.01	8.94
2023	23.37	11.57	15.56	23.19	8.80
2024	23.37	10.90	15.52	23.85	9.52

(*) These are the EFs used for estimating CH₄ emissions from manure management. CH₄ reductions and CH₄ emissions from pasture for cattle and buffalo are not included.

Nitrous oxide emissions from manure management

Direct and indirect N₂O emissions, produced during the storage and treatment of manure before it is applied to soils, are reported separately, as indicated in the 2019 IPCC Guidelines.

Direct N₂O emissions from manure management

Direct N₂O emissions from manure management were estimated with Tier 2 approach, following equation 10.25 of 2006 IPCC Guidelines (IPCC, 2006). Different parameters were used for the estimation: number of livestock species, country-specific nitrogen excretion rates per livestock category, fraction of total annual

nitrogen excretion for each livestock category managed in each manure management systems and EFs for manure management systems.

The updated EF₃ from Table 10.21 of Chapter 10, Volume 4 of 2019 Refinement of IPCC Guidelines have been applied for all manure management systems and animal categories on the whole time series.

Liquid system and solid storage are considered according to their significance and major distribution in Italy. Solid storage includes the chicken-dung drying process system. This system has been considered since 1995, since it has become increasingly common (CRPA, 2000; CRPA, 1997[b]). As regards the anaerobic digesters, another management system used in the country, the nitrogen quantities in livestock manure sent to anaerobic digestion were calculated. Based on CRPA data (CRPA, 2018; CRPA, 2006[a]) on manure production and the amount of N excreted by animal category and type of housing, the coefficients expressed in g N/kg manure were calculated. These coefficients were then multiplied by the quantities of manure sent for anaerobic digestion. N₂O emissions of anaerobic digesters are reported as 0.0006 kg N₂O-N (kg nitrogen excreted)⁻¹ in line with the 2019 refinement of IPCC Guidelines (IPCC, 2019).

When estimating emissions from manure management, the amount related to manure excreted while grazing is subtracted and reported in 'Agricultural soils' under soil emissions - urine and dung deposited by grazing animals (see Table 5.27). As recommended during the 2021 UNFCCC review, N₂O direct and indirect emissions for ostriches are estimated and reported in the IPCC 'Agricultural soils' category because the only manure management system for this category is pasture, range and paddock. The estimate of nitrogen excretion per manure management system is reported in CRT Table 3.B(b) (consistently with CRT Table 3.B(a)s2), in pasture range and paddock in other livestock. Further details on the estimate are given in 5.5.2 *Methodological issues* paragraph, in Direct N₂O emissions from managed soils, in *Urine and dung from grazing animals* (FPRP). Different parameters such as the nitrogen excretion rates (CRPA, 2006[a]; GU, 2006; Xiccato *et al.*, 2005), the slurry and solid manure production, and the average weight (CRPA, 2006[a]; GU, 2006; Regione Emilia Romagna, 2004) were updated.

In Table 5.27, nitrogen excretion rates used for the estimation of N₂O are shown. In 2024, the nitrogen excretion rate for swine is 15.76 kg head⁻¹ yr⁻¹. This last parameter is a weighted average of sows (28.51 kg head⁻¹ yr⁻¹) and other swine (14.33 kg head⁻¹ yr⁻¹). The value for sows also includes the excreted nitrogen from piglets. The average nitrogen excretion rate for swine reported in the CRT is equal to 11.97 kg head⁻¹ yr⁻¹. The figure is lower than the average rate for swine reported here since the value reported in the CRT is calculated by comparing the excreted nitrogen to the total pigs, including piglets.

Table 5.27 Average weight and nitrogen excretion rates in 2024

Livestock category	Average weight (kg)	N excreted housing (kg N head ⁻¹ yr ⁻¹)	N excreted grazing (kg N head ⁻¹ yr ⁻¹)	Total nitrogen excreted (kg N head ⁻¹ yr ⁻¹)
Non-dairy cattle	366.6	38.98	9.32	48.30
Dairy cattle	602.7	106.93	7.82	114.75
Buffalo	492.4	57.07	1.70	58.77
Other swine	93.9	14.33		14.33
Sows	172.1	28.51		28.51
Sheep	48.5	1.62	14.58	16.20
Goats	48.3	1.62	14.58	16.20
Horses	550.0	20.00	30.00	50.00
Mules and asses	300.0	20.00	30.00	50.00
Poultry	1.6	0.46		0.46
Rabbits	1.6	1.02		1.02
Fur animals	1.0	4.10		4.10

Country-specific annual nitrogen excretion rates have been set, based on the Nitrogen Balance Inter-regional Project results (nitrogen balance in animal farms); this project involved *Emilia Romagna*,

Lombardia, Piemonte and Veneto regions, where animal breeding is concentrated. The N-balance methodology has been applied in real case farms, monitoring their normal feeding practice, without specific diet adaptation. In the project, the most relevant dairy cattle production systems in Italy have been considered. Contrary to what is normally found in European milk production systems, poor correlation between the N excretion and milk production has been found. The two possible reasons are: a) an extreme heterogeneity in the protein content of the forage and in the use of the feed; b) the non-optimization of the protein diet of less productive cattle (De Roest and Speroni, 2005; CRPA, 2010). The N-balance methodology was followed, as suggested by the IPCC. As a result, estimations of nitrogen excretion rates¹⁸ and net nitrogen arriving to the field¹⁹ were obtained. To get reliable information on feed consumption and characteristics, and composition of the feed ratio, the project considered territorial and dimensional representativeness of Italian breeding. The final annual nitrogen excretion rates used for the UNFCCC/CLRTAP agriculture national inventory are included in a CRPA report (CRPA, 2006[a]).

In Table 5.28, nitrogen excretion rates for the main livestock categories are shown for the whole time series. For the other livestock categories, nitrogen excretion is the same for the whole time series, as shown in Table 5.27. For the dairy cattle category, the annual average values of nitrogen excretion rates are estimated using equations 10.31-33 of the 2006 IPCC Guidelines and therefore are calculated with the data used to estimate the enteric fermentation emissions. Following the update of the gross energy intake (GE), based on the estimation of the parameters digestibility (DE) of diet and methane conversion factor (Ym), the excreted nitrogen value of dairy cows was updated from the year 2004 onward. Excreted nitrogen is in fact calculated from GE using equations 10.31-10.33 of the 2006 IPCC Guidelines. The percentage for protein in diet is used with GE in the estimation of excreted nitrogen. As regards the percentage for protein in diet, the crude protein of the ration was updated based on data from around 500 samples of rations (unifed) of lactating and dry dairy cows, analyzed by the CRPA's zootechnical feed service for the three-year period 2017-2019, from all over Italy. The data were obtained by weighing the values expressed as % of the dry matter of the ration with the average annual lactation period (equal to 305 days) and the dry period (equal to 60 days). The value obtained is 14.22% and it was used for the time series from 2010 onwards, as indicated by the CRPA experts. For the previous years, the previous figure of 15.32% (Bittante *et al.*, 2004) was left until 2000, and an average value of 14.5% was used for the intermediate years between 2000 and 2010. This change results in a change in the nitrogen excreted by dairy cows (which is down from the previous submission).

For non-dairy cattle, buffalo and swine categories, the average values of nitrogen excretion rates are calculated based on the weight of the annual number of animal subcategories and fluctuate over the years. For the 'Less than 1 year' subcategory of the non-dairy cattle category, an average value of nitrogen excreted was calculated based on the weight of the number of animals of the subcategories calf, fattening male cattle, fattening heifer and heifer for replacement subcategories. For the sows' category, an average weighted nitrogen excretion rate is calculated taking in account the nitrogen excretion from piglets (swine less than 20 kg).

Table 5.28 Nitrogen excretion rates for main livestock categories (kg N head⁻¹ yr⁻¹)

Year	Dairy cattle	Non-dairy cattle (kg N head ⁻¹ yr ⁻¹)	Buffalo	Other swine	Sows
1990	104.85	49.89	94.32	13.13	28.10
1995	112.58	49.89	92.84	13.10	27.86
2000	105.65	50.07	91.20	12.96	27.87
2005	105.70	49.85	95.28	12.84	28.30
2010	102.07	50.07	81.99	12.85	28.36
2015	103.60	51.37	63.57	13.48	28.36
2020	109.24	52.01	59.21	13.45	28.50

¹⁸ Nitrogen excretion = N consumed – N retained

¹⁹ Net nitrogen to field = (N consumed – N retained) – N volatilized

Year	Dairy cattle	Non-dairy cattle (kg N head ⁻¹ yr ⁻¹)	Buffalo	Other swine	Sows
2021	110.42	52.33	59.22	13.35	28.51
2022	111.99	51.67	58.91	13.45	28.39
2023	112.46	51.53	58.87	13.24	28.62
2024	114.75	48.30	58.77	14.33	28.51

For verification purposes, a time series reported by ISTAT in the yearbooks (animal weight before slaughter) was collected (CRPA, 2006[a]). For the specific case of sheep and goats, a detailed analysis was applied with information coming from the National Association for Sheep Farming (ASSONAPA, 2006). To estimate the average weight for sheep and goats, breed distribution in Italy and consistency for each breed were considered (CRPA, 2006[a]; PROINCARNE, 2005).

Slurry and solid manure production parameters are set based on Italian breeding characteristics, considering the slurry and solid manure effluents, housing systems and the distribution for the different animal categories (CRPA, 2006[a]; Bonazzi *et al.*, 2005; APAT, 2004[a]; APAT, 2004[b]).

Fractions of total annual nitrogen excretion for cattle category managed in solid manure and liquid/slurry systems have been updated considering the distribution of housing systems resulting from the 2010 and 2020 Agricultural Censuses.

Indirect N₂O emissions from manure management

N₂O emissions result from volatile nitrogen losses occurring primarily in the forms of ammonia and NO_x and from nitrogen leaching and run-off. Updated values of EF₄, EF₅ and Fra_{CLEACH} from Table 11.3 of Chapter 11, Volume 4 of 2019 Refinement of IPCC Guidelines have been used.

N₂O emissions due to atmospheric deposition of NH₃ and NO_x have been estimated following the IPCC Tier 2 approach (Equations 10.26 of the 2006 IPCC Guidelines, Volume 4, Chapter 10). The following parameters are used: total N excreted by livestock (kg head⁻¹yr⁻¹), the fraction of total annual nitrogen excretion for each livestock category managed in each manure management systems, Fra_{CGasMS} emission factor, which is the percentage of managed manure nitrogen that volatilizes as NH₃ and NO_x in the manure management systems (see Table 5.29) and emission factor EF₄ (IPCC, 2019). The Fra_{CGasMS} emission factor is equal to the ratio between the amount of NH₃-N and NO_x-N emissions at housing and storage system and the total nitrogen excreted.

NH₃ and NO_x emissions are estimated based on the methodology indicated in the EMEP/EEA Guidebook for transboundary air pollutants. The estimation procedure for NH₃ and NO_x emissions of the manure management category consists in successive subtractions from the quantification of nitrogen excreted annually for each livestock category. This quantity can be divided into two different fluxes, depending on whether animals are inside (housing, storage and manure application) or outside the stable (grazing). More in detail, part of the nitrogen excreted in housing volatilizes during the settle of manure in the stable and it is calculated with the relevant emission factor in housing for the different livestock; this amount is therefore subtracted from the total nitrogen excreted to derive the amount of nitrogen for storage. During storage another fraction of nitrogen is lost (calculated with the relevant emission factor for storage), and, therefore, it is subtracted to obtain the amount of nitrogen available for the agronomic spreading. Losses occurring during the spreading are finally calculated with the related emission factor for spreading. For the nitrogen excreted in the pasture, losses due to volatilization, calculated with the relevant emission factor for grazing by livestock, only occur at this stage. Ammonia and NO_x emissions coming from housing and storage by each livestock category are then summed and divided by the total nitrogen excreted for each year (CRPA, 2006[a]). Ammonia emissions related to the housing and storage by cattle, swine and laying hens categories have been updated based on ISTAT statistics such as 2010 and 2020 Agricultural Census and 2013 Farm Structure Survey, on the distribution of housing and storage systems.

In relation to the ammonia emissions from storage, NH₃ emissions from digesters biogas facilities (in particular due to different phases of the process: during storage of feedstock on the premises of the biogas facility; during open storage of the digestate) have been estimated taking into account the amount of excreted nitrogen feeding anaerobic digesters and the Tier 1 emission factor derived by the EMEP/EEA Guidebook (EMEP/EEA, 2023). NH₃ emissions from digesters biogas facilities have been subtracted from manure management category (only for cattle, swine and poultry categories) and allocated in the anaerobic digestion at biogas facilities (5B2 of the waste sector in the NFR classification under UNECE/LRTAP Convention). The percentage of nitrogen lost through N-NH₃ emissions from anaerobic digesters was subtracted from the percentage of nitrogen left after emissions during housing and storage, reducing the amount of nitrogen used at the spreading. The amount of nitrogen used at spreading also includes digestate.

In order to implement a Tier 2 estimate of N₂O emissions, using disaggregated emission factor EF₄ provided by refinement 2019 of IPCC Guidelines, the cropland areas pertaining to wet and dry climate zones were calculated. Fertilized cropland areas were identified by selecting 10 CORINE Land Cover (CLC) classes 211, 212, 213, 221, 222, 223, 241, 242, 243, 244. The CLC was overlaid with the Climatic Zone layer based on the IPCC classification (ESDAC, 2010) in a GIS (Geographic Information System) environment and the percentages of wet and dry cropland area were calculated. The CLC 1990 was used to evaluate the wet and dry percentages of cropland from 1990 to 1999; the CLC 2000 for the same calculation in the years ranging from 2000 up to the creation of the subsequent CLC, namely 2005; the CLC 2006 for the years from 2006 to 2011; the CLC 2012 from 2012 to 2017; and the CLC 2018 from 2018 onwards.

For estimating N₂O emissions due to nitrogen leaching and run-off the IPCC Tier 2 approach was followed (Equation 10.27 of the 2006 IPCC Guidelines, Volume 4, Chapter 10). The following parameters are used: total N excreted by livestock (kg head⁻¹yr⁻¹), the fraction of total annual nitrogen excretion for each livestock category managed in each manure management systems, Frac_{leachMS} factor, which is the percent of managed manure nitrogen losses due to leaching and runoff during solid and liquid storage of manure (see Table 5.29) and the emission factor EF₅ from Table 11.3 (IPCC, 2019).

National legislation (as well as the regional ones) requires that the storage of liquid manure is in containers with waterproof bottom. The solid storage should have concrete or similar materials on the bottom and the leachate collection system. Nevertheless, manure heaps near the field are permitted for limited time after storage aimed at spreading (CRPA, 2016[b]). Frac_{leachMS} factor is assumed equal to an average of 1% (a weighted average of the values provided by 2019 IPCC Guidelines in the updated Table 10.22 for solid, liquid and digester manure management systems). Frac_{leachMS} is applied on the amount of N after the N volatilized from manure management is subtracted.

Table 5.29 Parameters used for the estimation of N₂O indirect emissions

Year	N excreted (t N)	Frac _{GasMS} (%)	N volatilised as NH ₃ and NO _x (t N)	N excreted housing minus N volatilised (t N)	Frac _{LeachMS} (%)	N leached from manure management (t N)
1990	929,130	24.16	224,508	527,916	1.0	5,401
1995	932,041	22.67	211,260	516,372	1.0	5,415
2000	914,840	22.23	203,387	502,422	1.1	5,461
2005	815,333	22.85	186,269	474,244	1.1	5,129
2010	797,357	23.19	184,943	444,781	1.0	4,486
2015	776,173	21.67	168,179	436,759	0.9	3,758
2020	779,150	20.62	160,648	430,614	0.8	3,420
2021	766,341	20.52	157,275	426,457	0.8	3,317
2022	751,577	20.54	154,367	420,432	0.8	3,205
2023	751,848	20.73	155,871	422,484	0.8	3,252
2024	695,215	20.78	144,449	398,473	0.8	3,078

5.3.3 Uncertainty and time-series consistency

Uncertainty of CH₄ and N₂O emissions from manure management has been estimated equal to 20.6%, as a combination of 5% and 20% for activity data and emission factors, respectively. Uncertainty of indirect N₂O emissions from manure management has been estimated equal to 50.2%, as a combination of 5% and 50% for activity data and emission factors, respectively.

In 2024, CH₄ emissions from manure management were 22.8% (146.35 kt CH₄) lower than in 1990 (189.57 kt CH₄). From 1990 to 2024, dairy and non-dairy cattle livestock population decreased by 42.4% and 25.5%, respectively, while swine decreased by 7.0% (in particular, sows and other swine decrease by 8.3% and by 6.9% respectively).

The reduction of manure management emissions has mainly driven down by the number of cattle. For cattle category until 2012, CH₄ emissions from biogas produced by anaerobic digesters fed with animal manure must be added to the emissions from manure management and not deducted because of the plant biogas losses are greater than avoided emissions due to biogas recovery. Cattle CH₄ emissions contribute 45.7% (in 1990 for 57.7%) to total CH₄ manure management emissions and swine for 43.7% (36.0% in 1990). For cattle, swine and poultry, the reduction of manure management emissions is also due to the reduction in CH₄ because of biogas recovery.

In Table 5.30, CH₄ emission trends from manure management (including emissions from pasture) are shown. These emissions considered the reduction of CH₄ because of biogas recovery.

Table 5.30 Trend in CH₄ emissions from manure management (kt)

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Dairy cattle	56.60	44.62	44.28	44.25	42.09	42.03	35.62	34.95	35.41	34.19	32.98
Non-dairy cattle	52.69	55.97	52.84	52.19	43.24	39.04	40.85	39.94	38.01	37.96	33.94
Buffalo	1.72	2.64	3.32	4.14	6.56	6.11	6.22	6.26	6.32	6.32	6.62
Sows	14.41	15.14	15.55	15.98	15.99	13.01	12.87	12.47	15.62	14.76	13.95
Other swine	53.78	50.53	51.56	56.09	57.41	58.66	57.44	56.34	55.77	59.06	49.94
Sheep	2.07	2.52	2.60	1.88	1.90	1.86	1.83	1.75	1.71	1.69	1.41
Goats	0.21	0.23	0.23	0.16	0.17	0.17	0.19	0.19	0.18	0.17	0.16
Horses	0.50	0.55	0.49	0.48	0.65	0.71	0.69	0.69	0.68	0.59	0.60
Mules and asses	0.08	0.03	0.03	0.03	0.04	0.06	0.06	0.06	0.07	0.07	0.08
Poultry	6.10	6.84	6.48	6.71	6.78	6.20	5.75	5.61	4.88	5.41	5.48
Rabbits	1.19	1.37	1.43	1.64	1.44	1.26	0.88	0.88	1.01	1.14	1.17
Fur animals	0.22	0.15	0.16	0.14	0.09	0.12	0.03	0.01	0.01	0.01	0.01
Ostriches	0.00	0.03	0.22	0.16	0.03	0.02	0.01	0.01	0.01	0.01	0.01
Total	189.57	180.61	179.18	183.84	176.38	169.28	162.45	159.17	159.69	161.40	146.35

In Table 5.31, N₂O emissions from liquid systems and solid storage sources are shown.

Table 5.31 Trend in N₂O emissions from manure management (kt)

Year	Direct emissions			Indirect emissions	Total
	Liquid system	Solid storage	Total		
	kt				
1990	2.89	5.85	8.73	2.88	11.61
1995	2.71	5.74	8.45	2.71	11.16
2000	2.53	5.80	8.32	2.61	10.93
2005	2.35	5.39	7.74	2.39	10.13
2010	2.40	4.80	7.20	2.36	9.56
2015	2.17	3.94	6.11	2.14	8.25

Year	Direct emissions			Indirect emissions	Total
	Liquid system	Solid storage	Total		
	kt				
2020	2.13	3.59	5.72	2.04	7.76
2021	2.05	3.47	5.52	2.00	7.52
2022	2.06	3.37	5.43	1.96	7.39
2023	2.08	3.41	5.49	1.98	7.47
2024	1.90	3.21	5.11	1.84	6.94

In 2024, N₂O emissions from manure management were 39.5% (7.03 kt N₂O) lower than in 1990 (11.6 kt N₂O). The major contribution of direct emissions is made by the 'solid system' with 61.7% (in 1990 with 66.9%). In 2024, indirect N₂O emissions from manure management accounted for 26.1% of total N₂O emissions from manure management and were 36.1% (1.84 kt N₂O) lower than in 1990 (2.88 kt N₂O).

In Table 5.32, N₂O direct emissions by animal category are shown.

Table 5.32 Trend in N₂O direct emissions from manure management by animal category (kt)

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Dairy cattle	3.30	2.79	2.60	2.31	1.89	1.65	1.48	1.42	1.45	1.42	1.36
Non-dairy cattle	2.91	2.95	2.86	2.49	2.21	1.76	1.79	1.70	1.56	1.57	1.37
Buffalo	0.12	0.18	0.22	0.25	0.37	0.29	0.29	0.29	0.29	0.29	0.31
Sows	0.14	0.15	0.15	0.16	0.16	0.13	0.12	0.12	0.15	0.14	0.13
Other swine	0.65	0.61	0.62	0.67	0.68	0.69	0.67	0.66	0.65	0.69	0.59
Sheep	0.22	0.27	0.28	0.20	0.20	0.18	0.18	0.17	0.17	0.17	0.14
Goats	0.03	0.03	0.04	0.02	0.03	0.02	0.03	0.03	0.03	0.02	0.02
Horses	0.09	0.10	0.09	0.09	0.12	0.12	0.12	0.12	0.11	0.10	0.10
Mules and asses	0.03	0.01	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03
Poultry	0.99	1.08	1.15	1.21	1.25	1.04	0.92	0.91	0.87	0.91	0.92
Rabbits	0.24	0.27	0.29	0.33	0.29	0.25	0.18	0.18	0.20	0.23	0.23
Fur animals	0.02	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00
Total	8.73	8.45	8.32	7.74	7.21	6.17	5.80	5.61	5.52	5.57	5.19

5.3.4 Source-specific QA/QC and verification

A study carried out by the CRPA in 2018 (CRPA, 2018) mentioned above also includes a survey on the digesters and the outcomes of the survey have been used to update the estimates as described in paragraph 5.3.2.

A check was carried out on the VS values. An average of the time series of VS values was calculated for cattle. Three weighted mean values were calculated. The first was obtained using Husted values of 142.7 g VS/kg for solid manure and 47.5 g VS/kg for slurry. The second was obtained from the VS kg/head/day values calculated using Equation 10.24 of the 2006 IPCC Guidelines, which uses the data to estimate enteric emissions. The third was calculated as an average of the VS values measured by CRPA. Specifically, a crude average of VS values for manure and slurry was calculated from approximately 400 samples analyzed in the period 2001-2019; from the average VS values for manure and slurry, a weighted average was calculated. The values obtained were 98.2, 93.5 and 117.4 g VS/kg manure, respectively. This verification supports the estimates made, based on the Husted factors, but further investigations will be carried out.

For verification purposes, the Frac_{GasMS} parameter has been also estimated as a fraction of nitrogen excreted in stables that is emitted as N-NH₃-NO_x-N₂O-N₂ in stables and storage systems. This value is equal to 0.329, for 1990, and to 0.296 in 2024.

As recommended by the 2019 UNFCCC review, starting from the data on the amount of solid and slurry manure produced, used in the estimate of CH₄ emissions from manure management, the amount of straw added to the manure during housing was calculated. The estimated amount of straw for cattle and buffalo bedding was compared with the annual amount of wheat and barley straw used for various purposes. It was found that cattle and buffalo bedding is equal to 83% of the amount of wheat and barley straw.

A verification of CH₄ estimates from manure management was conducted using provincial Census agriculture head count data from the years 2000, 2010 and 2020 and monthly average temperature data. Head count data were distinguished between animals raised in temperate and cool climate zones. Regarding temperature data, average monthly temperatures of temperate and cool climate zones were calculated separately. Average monthly temperatures for three 30-year periods (1971-2000, 1981-2010, 1991-2020) were calculated. With this data, the national methodology for estimating cattle and buffalo CH₄ emissions for the years 2000 and 2010 was replicated. For 2000, the emissions estimated with this verification were 11% lower than the methodology used. While for 2010, emissions were almost identical. The 2000 census head count (summing cattle and buffalo), used for the verification performed, is 14% lower than the annual stock figures used in the national methodology (and just under 4% for 2010). This helps in part to explain the differences obtained. Finally, based on the 2020 agriculture census, the emissions estimated with this verification were 4% higher than the methodology used. The 2020 census head count (summing cattle and buffalo), used for the verification performed, is 5% lower than the annual stock figures used in the national methodology.

5.3.5 Source-specific recalculations

Changes related to CH₄ manure management emissions are described below.

A major recalculation of CH₄ emissions concerned cattle and buffalo from 1990 onwards, as the EF was applied only to housed livestock to avoid double counting of emissions from pasture which are calculated separately.

The amount of N sent to digesters was updated for cattle based on GSE (Energy Services Manager) data about biomethane production from 2017 (the biggest changes will start in 2021).

Another recalculation of CH₄ emissions from non-dairy cattle manure management was implemented starting from 2020, due to a modified distribution of livestock housing based on 2020 Agriculture Census. A minor recalculation due to an error correction in the estimation file of CH₄ emissions from biodigesters also occurred for the category non-dairy cattle in the year 2023.

Starting from 2011 the EF for cattle and buffalo categories has been modified, because of correction of some errors (n. of days in different months) in the estimation table of the methane conversion factor for liquid slurry (g CH₄/kgVS).

The estimated number of heads for poultry was modified, determining a recalculation of CH₄ emissions from poultry manure management on the entire time series (1998-2023 for laying hens and 2001-2023 for broilers) and of CH₄ emissions from anaerobic digestion (avoided emissions) starting from 2012, when poultry manure was introduced as feed to biodigesters; this recalculation affected also CH₄ avoided emissions from cattle manure management in digesters.

The number of heads for sheep, goats, horses, mules and asses was modified starting from 2020 based on provincial data of the 2020 Agriculture Census, determining a slight variation of CH₄ EF for these animal categories.

For 2023 the number of heads for horses, mules and asses was updated further.

The percentage of covered and uncovered manure storage systems for swine was updated, influencing the EF of CH₄ from manure management for this animal category from 1990 onwards and determining a minor recalculation.

The national population of rabbits has been updated for the year 2023, based on an update of the source activity data.

The impacts of the described recalculations on estimated CH₄ emissions from manure management are summarized in Table 5.33, expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. Total CH₄ emissions from manure management were reduced by 2-7% along the time series due to the implemented recalculations.

Table 5.33 Recalculation of reported CH₄ emissions from manure management

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Dairy cattle									
Recalculation [kt CH ₄]	- 2.96	- 2.31	- 2.30	- 2.42	- 3.09	- 2.92	- 2.91	- 2.95	- 3.10
% recalculation	-5%	-5%	-5%	-5%	-7%	-8%	-8%	-8%	-8%
Non-Dairy cattle									
Recalculation [kt CH ₄]	- 1.20	- 1.41	- 1.33	- 3.31	- 6.21	- 8.59	- 8.55	- 8.14	- 8.42
% recalculation	-2%	-3%	-2%	-7%	-14%	-17%	-18%	-18%	-18%
Buffalo cows									
Recalculation [kt CH ₄]	- 0.05	- 0.10	- 0.12	- 0.2	- 0.22	- 0.22	- 0.23	- 0.23	- 0.23
% recalculation	-3%	-3%	-3%	-3%	-3%	-3%	-3%	-3%	-3%
Sheep									
Recalculation [kt CH ₄]	-	-	-	-	-	0.003	0.003	0.003	0.003
% recalculation	-	-	-	-	-	0.18%	0.18%	0.18%	0.18%
Goats									
Recalculation [kt CH ₄]	-	-	-	-	-	0.0001	0.0001	0.0001	0.0001
% recalculation	-	-	-	-	-	0.04%	0.04%	0.04%	0.04%
Horses									
Recalculation [kt CH ₄]	-	-	-	-	-	0.0009	0.0009	0.0009	- 0.0945
% recalculation	-	-	-	-	-	0.13%	0.13%	0.13%	-13.88%
Mules and Asses									
Recalculation [kt CH ₄]	-	-	-	-	-	- 0.0003	- 0.0003	- 0.0003	0.0040
% recalculation	-	-	-	-	-	-0.51%	-0.51%	-0.51%	5.99%
Swine									
Recalculation [kt CH ₄]	0.062	0.061	0.065	0.059	0.048	0.045	0.044	0.046	0.001
% recalculation	0.09%	0.09%	0.09%	0.08%	0.07%	0.06%	0.06%	0.06%	0.01%
Poultry									
Recalculation [kt CH ₄]	-	0.0001	0.098	0.239	- 0.039	- 0.0190	0.0041	- 0.0030	0.0246
% recalculation	0%	0.002%	1.48%	3.66%	-0.63%	-0.33%	0.07%	-0.06%	0.46%
Rabbits									
Recalculation [kt CH ₄]	-	-	-	-	-	-	-	-	0.0438
% recalculation	-	-	-	-	-	-	-	-	4.00%
Total									
Recalculation [kt CH ₄]	- 4.14	- 3.75	- 3.59	- 5.62	- 9.51	- 11.70	- 11.63	- 11.27	-11.76
% recalculation	-2%	-2%	-2%	-3%	-5%	-6.72%	-6.81%	-6.59%	-6.79%

Changes related to direct N₂O manure management emissions are described below.

The updated EF₃ from Table 10.21 of Chapter 10, Volume 4 of 2019 Refinement of IPCC guidelines have been applied for all manure management systems and animal categories on the whole time series. This modification determined a major recalculation for this emission sub-category.

The modification of the distribution of livestock housing for non-dairy cattle starting from 2020, based on 2020 Agriculture Census data, described above in the paragraph about CH₄ emissions from manure management, determined recalculations also for direct N₂O emissions.

The amount of N sent to digesters was updated for cattle based on GSE (Energy Services Manager) data about biomethane production from 2017 (the biggest changes will start in 2021).

The update of nitrogen excreted on pasture for dairy cattle based on the 2020 agricultural census modified from 2007 (interpolation with the 2006 CRPA value) led to a recalculation of the non-dairy cattle category,

as the same updated percentage of nitrogen excreted on pasture, which changed the percentage of nitrogen excreted in housing, was used for females in the non-dairy cattle category.

Two errors about the number of heads of dairy cattle in 2017 and 2023 have been corrected in the estimation files, determining a minor recalculation of direct N₂O emissions from manure management in those years.

The estimated number of heads for poultry was modified, determining a recalculation of direct N₂O emissions from poultry manure management in the entire time series (1998-2023 for laying hens and 2001-2023 for broilers) and of direct N₂O emissions from anaerobic digestion starting from 2012, when poultry manure was introduced as feed to biodigesters; this recalculation affected also direct N₂O emissions from cattle manure management in digesters. For 2023 the number of heads for horses, mules and asses was updated further. The national population of rabbits has been updated for the year 2023, based on an update of the source activity data.

The impacts of the described recalculations on estimated direct N₂O emissions from manure management are summarized in Table 5.34, expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. Total direct N₂O emissions from manure management were increased by 43-51% throughout the entire time series due to the implemented recalculations.

Table 5.34 Recalculation of reported direct N₂O emissions from manure management

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Non-Dairy cattle									
Recalculation [kt N ₂ O]	0.95	0.95	0.81	0.73	0.62	0.65	0.59	0.54	0.54
% recalculation	48%	50%	49%	50%	54%	57%	53%	52%	52%
Buffalo									
Recalculation [kt N ₂ O]	0.05	0.09	0.10	0.14	0.10	0.10	0.10	0.10	0.10
% recalculation	71%	67%	66%	63%	57%	56%	56%	56%	56%
Dairy cattle									
Recalculation [kt N ₂ O]	1.23	0.97	0.86	0.58	0.49	0.41	0.36	0.38	0.35
% recalculation	60%	60%	60%	44%	42%	39%	35%	35%	33%
Swine									
Recalculation [kt N ₂ O]	-	0.000	0.002	0.003	0.003	0.003	0.003	0.003	0.003
% recalculation	-	0.02%	0.18%	0.37%	0.37%	0.37%	0.37%	0.37%	0.37%
Sheep									
Recalculation [kt N ₂ O]	0.11	0.14	0.10	0.10	0.09	0.09	0.09	0.08	0.08
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	100%
Horses									
Recalculation [kt N ₂ O]	0.045	0.044	0.044	0.059	0.060	0.058	0.058	0.057	0.041
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	72%
Mules and Asses									
Recalculation [kt N ₂ O]	0.013	0.005	0.005	0.007	0.011	0.011	0.011	0.012	0.013
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	113%
Poultry									
Recalculation [kt N ₂ O]	0.28	0.41	0.49	0.57	0.43	0.40	0.40	0.39	0.41
% recalculation	39%	56%	69%	83%	72%	77%	79%	82%	82%
Rabbits									
Recalculation [kt N ₂ O]	0.12	0.14	0.16	0.14	0.13	0.09	0.09	0.10	0.12
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	108%
Fur animals									
Recalculation [kt N ₂ O]	0.010	0.007	0.006	0.004	0.006	0.002	0.001	0.001	0.001
% recalculation	100%	100%	100%	100%	100%	100%	100%	100%	100%
Total									
Recalculation [kt N ₂ O]	2.82	2.78	2.60	2.35	1.96	1.83	1.72	1.68	1.68
% recalculation	48%	50%	51%	48%	46%	46%	44%	44%	43%

Changes related to indirect N₂O emissions from manure management are described below.

A major recalculation is attributable to the replacement of EF₄, EF₅ and Fra_{CLEACH} with the updated values from Table 11.3 of Chapter 11, Volume 4 of 2019 Refinement of IPCC guidelines (see detailed description in methodological issues section).

The following recalculations interested the estimates of NH₃ and NO_x, thus affecting also indirect N₂O emission from deposition:

- the modification of the distribution of manure management system for non-dairy cattle starting from 2020, based on 2020 Agriculture Census data, described above in the paragraph about CH₄ emissions and direct N₂O emissions from manure management, determined recalculations of NH₃ emissions and NO_x emissions from manure management;
- for the year 2023, the update of number of heads for equines and rabbits determined a recalculation of NH₃ and NO_x emissions in all manure management phase;
- the update of number of heads for poultry (1998-2023 for laying hens and 2001-2023 for broilers) determined a recalculation of NH₃ and NO_x at housing and storage phase, and of NH₃ emissions from anaerobic digestion starting from 2012, when poultry manure was introduced as feed to digesters;
- the update of N-excreted at pasture for dairy cattle based on 2020 Agriculture Census has determined a recalculation of NH₃ and NO_x at housing, storage, manure sent to anaerobic digestion and spreading from 2007 (interpolation with 2006 CRPA value); the same updated percentage of N excreted at pasture was used for non-dairy cattle and buffalo determining same recalculations;
- the amount of N sent to digesters was updated based on GSE data about biomethane production from 2017 and this modification determined a recalculation of NH₃ and NO_x from manure management for cattle;
- the NH₃ EF for laying hens at housing was modified from 2020;
- two errors about the number of heads of dairy cattle in 2017 and 2023 have been corrected in the estimation files, determining a minor recalculation of NH₃ and NO_x emissions.

The impacts of the described recalculations on estimated indirect N₂O emissions from manure management are summarized in Table 5.35, expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. Total indirect N₂O emissions from manure management were reduced by 20-21% along the time series due to the implemented recalculations.

Table 5.35 Recalculation of reported indirect N₂O emissions from manure management

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Deposition									
Recalculation [kt N ₂ O]	- 0.75	- 0.68	- 0.62	- 0.61	- 0.58	- 0.55	- 0.55	- 0.54	- 0.54
% recalculation	-21%	-21%	-21%	-21%	-22%	-22%	-22%	-22%	-22%
Leaching/Run-off									
Recalculation [kt N ₂ O]	0.03	0.04	0.03	0.03	0.01	0.01	0.01	0.01	0.01
% recalculation	50%	59%	59%	49%	26%	17%	14%	12%	13%
Total									
Recalculation [kt N ₂ O]	- 0.71	- 0.65	- 0.59	- 0.58	- 0.57	- 0.54	- 0.54	- 0.53	- 0.53
% recalculation	-20%	-20%	-20%	-20%	-21%	-21%	-21%	-21%	-21%

5.3.6 Source-specific planned improvements

In 2026, a project will be launched with the CRPA, which will last about a year and will include various activities related to livestock farming. In particular, based on numerous studies and data collected, and

through an analysis of existing literature, data relating to rations and estimates of GE, DE, and Ym parameters for cattle by subcategory will be verified and updated, checking the estimated data in the inventory, also evaluating the protein in the ration and the corresponding nitrogen excreted, and assessing updates if necessary.

Moreover the following data will be verified and updated: types of housing, storage, and spreading techniques for cattle, pigs, poultry, and subcategories (number of animals and NH₃ emission factors); emission reduction measures for all stages of livestock management (feeding, housing, storage, spreading) for greenhouse gases (CH₄ and N₂O) and ammonia, providing assessments for each measure and constructing scenarios for reducing greenhouse gas and ammonia emissions; biogas/biomethane production.

As part of the CRPA 2026-2027 project, an assessment will be carried out of the quantities of organic matrices (other than livestock waste) that are fed into anaerobic digesters to produce biogas.

Parameters used for this submission are shown in Table 5.36.

Table 5.36 Parameters used for the different livestock categories (2024)

Livestock category		Average weight (kg)	N excretion (kg N head ⁻¹ yr ⁻¹)
DAIRY CATTLE		602.7	114.75
NON- DAIRY CATTLE		366.6 (**)	48.30 (**)
Less than 1 year (*)		204.8 (**)	25.29 (**)
From 1 year - less than 2 years			
Male	for reproduction	557.0	66.8
	for slaughter	557.0	66.8
Female	for breeding	405.0	67.6
	for slaughter	444.0	53.3
From 2 years and more			
Male	for reproduction	700.0	84.0
	for slaughter and work	700.0	84.0
Female	Breeding heifer	540.0	90.2
	Slaughter heifer	540.0	64.8
	Other non-dairy cattle (***)	557.0	54.1
BUFFALO		492.4 (**)	58.77 (**)
	Cow buffalo	630.0	71.31
	Other buffaloes	319.5	43.0
OTHER SWINE		93.9 (**)	14.33 (**)
Weight less than 20 kg		10.0	
From 20 kg weight and under 50 kg		35.0	5.3
From 50 kg and more			
	Boar	200.0	30.5
	For slaughter		
	from 50 to 80 kg	65.0	9.9
	from 80 to 110 kg	95.0	14.5
	from 110 kg and more	135.0	20.6
SOWS		172.1	28.51 (**)
SHEEP	Sheep	51.1	16.2
	Other sheep	20.8	16.2
GOATS	Goats	53.8	16.2
	Other goats	14.9	16.2

Livestock category		Average weight (kg)	N excretion (kg N head ⁻¹ yr ⁻¹)
EQUINE	Horses	550.0	50.0
	Mules and asses	300.0	50.0
POULTRY	Broilers	1.2	0.36
	Layer hens	1.8	0.66
	Other poultry	2.6	0.46
RABBITS	Female rabbits	4.0	2.5
	Other rabbits	1.3	0.8
FUR ANIMALS		1.0	4.1

(*) Categories included in less than 1 year are: calf, fattening male cattle, fattening heifer and heifer for replacement; (**) values are variable for the time series; (***) Suckling cows and cows in late career.

5.4 Rice cultivation (3C)

5.4.1 Source category description

For the rice cultivation category, only CH₄ emissions are estimated, other GHGs do not occur; N₂O from fertilization during cultivation was estimated and reported in “Agricultural soils” under direct soil emissions - synthetic fertilizers. Methane emissions from rice cultivation have been identified as a key source at level assessment with Approach 1 including and excluding LULUCF categories. In 2024, CH₄ emissions from rice cultivation were 64.04 kt, which represents 9.2% of CH₄ emissions for the agriculture sector (8.5% in 1990) and 4.2% for national CH₄ emissions (3.8% in 1990).

In Italy, CH₄ emissions from rice cultivation are estimated only for an irrigated regime, other categories suggested by IPCC (rainfed, deep water and “other”) are not present. Methane emissions, reported in the CRT tables, represent two water regimes: delay flooding (21.4 kt) and multiple aeration (42.7 kt). A detailed methodology was developed in 2005/2006, in consultation with an expert in CH₄ emissions and rice cultivation (Wassmann, 2005) and following outcomes of previous UNFCCC review processes. For this purpose, an expert group on rice cultivation together with the C.R.A. – Experimental Institute of Cereal Research – Rice Research Section of Vercelli was established. Different national experts from the rice cultivation sector were also contacted²⁰. In 2022/2023, national experts on rice cultivation were contacted to verify and review the historical series of emissions²¹.

5.4.2 Methodological issues

For the estimation of CH₄ emissions from rice cultivation a detailed methodology in 2005/2006 was implemented following the IPCC guidelines (IPCC, 2006, volume 4, chapter 5). Country-specific circumstances have been considered. Parameters such as an adjusted integrated emission factor (kg CH₄ m⁻²day⁻¹), cultivation period of rice (days) and annual harvested area (ha) cultivated under specific conditions are considered. Information on the cultivated surface is collected from rice farmers. Every year, timely data collection is ensured by the National Rice Institute (ENR, several years [b]). Activity data information is shown in Table 5.37.

20 Stefano Bocchi, Crop Science Department (University of Milan); Aldo Ferrero, Department of Agronomy, Forestry and Land Management (University of Turin); Antonino Spanu, Department of agronomic science and agriculture genetics (University of Sassari).

21 Marco Romani, Eleonora Francesca Miniotti and Elisa Cadei, Ente Nazionale Risi (Enterisi); Daniel Said-Pullicino and Lucia Crosetto, Department of Agricultural, Forestry and Food Sciences (University of Turin).

Table 5.37 Parameters used for the calculation of CH₄ emissions from rice cultivation

Parameters	Reference
Cultivated surface with "dry-seeded" technique (%)	ENR, several years [a]
Cultivated surface – national (ha)	ISTAT, several years [a],[b],[j]; ENR, several years [b]
Cultivated surface by rice varieties (ha)	ENR, several years [b]
Cultivation period of rice varieties (days)	ENR, 2011; ENR, 2014 [a],[b]; ENSE, 1999; ENSE, 2004; ENR, 2013
Methane emission factor (kg CH ₄ m ⁻² d ⁻¹)	Peyron et al., 2016; Bertora et al., 2018; Vitali et al., 2024; Leip et al., 2002; Schutz et al., 1989[a], [b]
Crop production (t yr ⁻¹)	ISTAT, several years [a],[b],[j]
Yield (t ha ⁻¹)	Estimations based on cultivated surface and crop production data
Straw incorporation (%)	Expert judgement (Miniotti E. F., Romani M., 2023; Tinarelli, 2005; Lupotto et al., 2005)
Agronomic practices	Miniotti E. F., Romani M., 2023; ISTAT, 2006[b]; Tinarelli, 2005; Lupotto et al., 2005; Zavattaro et. al, 2004; Baldoni & Giardini, 1989; Tinarelli, 1973; 1986
Scaling factors (SFw, SFp, SFo)	IPCC, 2006; Yan et al., 2005

Rice cultivation practice

In Italy, rice is sown from mid-April to the end of May and harvested from mid-September to the end of October; the only practised system is the controlled flooding system, with variations in water regimes (Miniotti E. F., Romani M., 2023; Regione Emilia Romagna, 2005; Mannini, 2004; Tossato and Regis, 2002). Water regime trends have been estimated in collaboration with expert judgement expertise (Tinarelli, 2005; Lupotto *et al.*, 2005; Miniotti E. F., Romani M., 2023) and available statistics (ENR, several years [b]). Normally, the aeration periods are very variable in number and time, depending on different circumstances, as for example, the type of herbicide, which is used (Baldoni and Giardini, 1989). Another water regime system, present in southern Italy, is the sprinkler irrigation, which exists only on experimental plots and could contribute to the diffusion of rice cultivation in areas where water availability is a limiting factor (Spanu et al., 2004; Spanu and Pruneddu, 1996). In Table 5.38, water regimes descriptions for the most common agronomic practices in Italy are presented (Miniotti E. F., Romani M., 2023).

Table 5.38 Water regimes in Italy and classification according to IPCC Guidelines

Type of seeding	April	May	June	July	August	September-October	Description
Wet-seeded "classic"	15 April-15 May		Herbicide and fertilizer treatment (1/3)	Fertilizer application (1/3). Panicle formation		Harvest	2 aeration periods during rice cultivation, as minimum, not including the final aeration. IPCC classification: Intermittently flooded – <u>multiple aeration</u>
	1/3 pre-sowing fertilizer	1° aeration-AR (dry rooting (<i>asciutta di radicamento</i>), which occurs 6-10 days after sowing and lasts several days (>3 days))	2° aeration-AA (dry for herbicide and fertilizer application at tillering (<i>accestimento</i>) (tends to occur in June, concurrent with herbicide treatment) (1/3))	3° aeration-AA (*) (Fertilizer application at panicle initiation (<i>iniziazione pannocchia</i>))	Final aeration		
Wet-seeded	15-30 April	First application of herbicides, the soil is	At the end of June, fertilization	Fertilizer application		Harvest	2 aeration periods during rice

Type of seeding	April	May	June	July	August	September-October	Description
"red rice control"	Flooding and <u>wet-seeded</u>	dry. Approximately, on 15 May flooding and after some days (more or less 7) seeding	and herbicide treatment	(1/3). Panicle formation			cultivation, as minimum, not including the final aeration. IPCC classification: Intermittently flooded – <u>multiple aeration</u>
	2/3 Fertilizer application. There are many strategies for this type of application, so defining an unambiguous time of application is difficult: in some cases, fertilization takes place before submergence, in other cases application is postponed to post-emergence, and in still other cases, if fertilizers with inhibitors are chosen, application may be made before false seeding	1° aeration – AC Approx. after 10 days after seeding: 2° aeration – AR	3° aeration -AA	4° aeration - AA (*)	Final aeration		
Dry-seeded with delay flooding	15 April-15 May <u>Dry-seeded</u>	Approximately, on 15 May- 10 June flooding		Fertilizer application (1/3). Panicle formation		Harvest	1 aeration period during rice cultivation, as minimum, not including the final aeration.
		Between sowing and submergence, there is fertilizer application/herbicide treatment (2/3) in pre-sowing at the beginning of tillering (<i>inizio accestimento</i>)		1° aeration-AA (*) Fertilizer application at panicle initiation (<i>iniziazione pannocchia</i>)	Final aeration		

(*) To improve its fertilizer application efficiency, fertilizer is given on dry soil and then the field is flooded no later than 48 hours to limit losses by volatilization. Since 2020 fertilizers application at panicle initiation occurs in flooded conditions. Water shortage doesn't allow water to drain from the paddy field and reflood after some days. Aeration periods last mostly between 5-15 days and are classified as follows: AC=aeration to control red rice; AR=drained, aeration to promote rice rooting; AA=drained, tillering aeration.

In general, rice seeds are mechanically broadcasted in flooded fields. However, in Italy for the last 15 years, the seeds are also drilled to dry soil in rows. The rice which has been planted in dry soil is generally managed as a dry crop until it reaches the 3-4 leaf stage. After this period, the rice is flooded and grows in continuous submersion, as in the conventional system (Ferrero and Nguyen, 2004; Russo, 1994). During the cultivation period, water is commonly kept at a depth of 4-8 cm and drained away 2-3 times during the season to improve crop rooting, to reduce algae growth and to allow application of fertilizers/herbicides. Rice fields

are drained at the end of August to allow harvesting, once in a year (Miniotti E. F., Romani M., 2023; Ferrero and Nguyen, 2004; Baldoni and Giardini, 1989; Tinarelli, 1973; Tinarelli, 1986).

Nitrogen is generally the most limiting plant nutrient in rice production and is subject to losses because of the reduction processes (denitrification) and leaching. Table 5.38 describes the periods and amounts of fertilizer application. Based on the guidance received from the 2022/2023 working group, the percentages of incorporated/burned straw have been changed since 2001. In addition, since 2012, the only rice-growing areas where stubble burning takes place are those in Ferrara, Rovigo, Venice, and Vicenza. On the remaining areas, residues are incorporated (Miniotti E. F., Romani M., 2023).

Methane emission factor

An analysis on recent and past literature for the CH₄ daily EF (kg CH₄ m⁻² d⁻¹) was done. In 2005/2006, different scientific publications related to the CH₄ daily EF measurements in Italian rice fields were revised (Marik *et al.*, 2002; Leip *et al.*, 2002; Dan *et al.*, 2001; Butterbach-Bahl *et al.*, 1997; Schutz *et al.*, 1989[a], [b]; Holzapfel-Pschorn & Seiler, 1986). Other publications indirectly related to CH₄ production were also considered (Kruger *et al.*, 2005; Weber *et al.*, 2001; Dannenberg & Conrad, 1999; Roy *et al.*, 1997). Butterbach-Bahl *et al.* have presented interesting results associated with the difference in EFs of two cultivation periods (1990 and 1991). Marik *et al.* have published detailed information on agronomic practices (fertilized fields) related to measurements of CH₄ emission factors for years 1998 and 1999; values are like those presented in previous publications (Schutz *et al.*, 1989[a], [b]; Holzapfel-Pschorn & Seiler, 1986). Leip *et al.* have published specific CH₄ EF for the dry-seeded with delay flooding, as shown in Table 5.39. The dry-seeded technique could bring interesting benefits in emission reduction, since lower emission rates compared with normal agronomic practices, were determined experimentally.

The estimation of CH₄ emissions for the rice cultivation category considers an irrigated regime, which includes intermittently flooded with delay flooding and multiple aeration regime. The CH₄ emission factor for the years 1990-2007 is adjusted with the following parameters: a daily integrated emission factor for continuously flooded fields without organic fertilizers, a scaling factor to account for the differences in water regime in the rice growing season (*SFw*), a scaling factor to account for the differences in water regime in the pre-season status (*SFp*) and a scaling factor which varies for both types and amount of amendment applied (*SFo*). Scaling factor parameters have been updated according to literature (Yan *et al.*, 2005) and the IPCC 2006 Guidelines (IPCC, 2006, volume 4, chapter 5).

Based on the results that emerged from the 2022/2023 working group, emission factors were updated from 2008. The scientific studies supporting the new factors refer to field measurements carried out in the Italian rice district (an area in the Po Valley, in Northern Italy) in the years 2012, 2013, 2014, 2021 and 2022 (Peyron *et al.*, 2016; Bertora *et al.*, 2018; Vitali *et al.*, 2024). Emission factors refer to conventional (water-seeded) and dry-seeded cultivation techniques. The former technique involves continuous submergence with two drainage periods for fertilizer application at tillering (*accestimento*) and panicle initiation (*iniziazione della pannocchia*) prior to final field drainage; no pre-season submergence for > 180 days prior to rice cultivation; tillage with incorporation of crop residues (>30 days prior to flooding), no cover crop. The second technique involves continuous submergence after 3rd-4th leaves/early tillering (*accestimento*) with one drainage period for fertilizer application at panicle initiation (*iniziazione della pannocchia*) before final field drainage; no pre-season submergence for > 180 days before rice cultivation; tillage with incorporation of crop residues (>30 days before flooding), no cover crops (Romani M., 2023). The rooting dry (*asciutta di radicamento*) is always expected in water seeding and is additional to the other two dry described in the conventional technique (i.e., at tillering and panicle differentiation). Thus, the EF already takes this into account, and it is important that it does so because methane emissions are still possible during this stage since the soil is not completely aerobic. In dry seeding, on the other hand, a single soil dry is generally expected near panicle differentiation in addition to the final drainage (Said-Pullicino D., 2023[a]). EFs for the two seeding types do not need SFs because they are already included (Said-Pullicino D., 2023[b]). The

cultivation techniques used since 2012 (the scientific studies supporting the new factors refer to field measurements taken in the years 2012, 2013, 2014, 2021, and 2022) are the same as those used in previous years, therefore, it is assumed that the new emission factors can be applied since 2008 (Romani M., Said-Pullicino D. 2023, personal communication).

Assumptions of agronomic practices and parameters used for CH₄ emission estimations are shown in Table 5.37 and Table 5.39, respectively. Total CH₄ emissions for rice cultivation in 2024 were 64.04 kt.

Table 5.39 Parameters used for estimating CH₄ emissions from rice cultivation in 2024

Rice cultivation water regimes: Intermittently flooded	Delay flooding	Multiple aeration	Multiple aeration
Type of seeding	Dry-seeded	Wet-seeded (<i>classic</i>)	Wet-seeded (<i>red rice control</i>)
Surface (ha)	115,683	49,701	60,745
Daily EF (kg CH ₄ ha ⁻¹ d ⁻¹)	1.31	2.45	2.45
Days of cultivation (days)	141	158	158
Seasonal EF (kg CH ₄ ha ⁻¹ yr ⁻¹)	184.9	386.2	386.2
Methane emissions (kt)	21.39	19.19	23.46

5.4.3 Uncertainty and time-series consistency

Uncertainty of emissions from rice cultivation has been estimated equal to 11.2% as a combination of 5% and 10% for activity data and emissions factors, respectively. Lack of experimental data and knowledge about the occurrence and duration of drainage periods in Italy is the major cause of uncertainty. Moreover, it is not easy to quantify the surface where the traditional or the different number of aerations is practiced, which depends on the degree and the type of infestation, and the positive or negative results of the herbicide treatment application (Spanu, 2006).

In 2024, CH₄ emissions from rice cultivation were 14.7% (64.04 kt CH₄) lower than in 1990 (75.06 kt CH₄). In Italy, the driving force of CH₄ emissions from rice cultivation is the harvest area and the percentage of single aerated surface (lower CH₄ emission factor). From 1990-2024, the harvest area has increased by 5.0%, from 215,442 ha year⁻¹ (1990) to 226,129 ha year⁻¹ (2024). The percentage of single aerated surface has increased from 1.0% (1990) to 51.2% (2024). The dry seeded sowing (single aeration) has been widespread since the beginning of the 1990s owing to the simplification of cultivation operations and water management. Moreover, dry seeded sowing allows better production performance than sowing in water in areas with very loose soils. Data on rice cultivation including harvest area with single aeration are provided by the National Rice Institute. In Table 5.40, CH₄ emissions from rice cultivation and harvested area are shown.

Table 5.40 Harvest area and CH₄ emissions from the rice cultivation sector

Year	Harvested area (10 ³ m ² yr ⁻¹)	CH ₄ emissions (kt)
1990	2.15	75.06
1995	2.39	79.56
2000	2.20	66.26
2005	2.24	74.23
2010	2.48	80.53
2015	2.27	69.41
2020	2.27	60.58
2021	2.27	59.91
2022	2.18	55.25
2023	2.10	53.93
2024	2.26	64.04

5.4.4 Source-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the sum of subcategories. Data entries have been checked several times during the compilation of the inventory. Several QA activities are carried out in different phases of the inventory process. The quality of the Italian rice emission inventory was verified with the Denitrification Decomposition model (DNDC). Initial results have found a high correspondence between the EFs used for the Italian inventory and those simulated with DNDC model (Leip and Bocchi, 2007).

In particular, the applied methodology has been presented and discussed during several national workshop and expert meetings, collecting findings and comments to be incorporated in the estimation process. All the agriculture categories have been embedded in the overall QA/QC-system of the Italian GHG inventory. In November 2014, the CH₄ emission factors used for the rice cultivation category in the Italian emissions inventory were presented at the 9th Expert Meeting on Data for the IPCC Emission Factor Database (EFDB) and the values were entered into the database.

5.4.5 Source-specific recalculations

The value of water seeded days was modified for the year 2023, together with the harvested yield for the same year, determining a recalculation of -0.32 kt CH₄ (-0.6% of 2025 submission)

5.4.6 Source-specific planned improvements

No specific improvements are planned.

5.5 Agriculture soils (3D)

5.5.1 Source category description

In 2024, N₂O emissions from managed soils were 23.8 kt, representing 77.2% of N₂O emissions for the agriculture sector (71.8% in 1990) and 45.8% for national N₂O emissions (34.8% in 1990). N₂O emissions from this source consist of direct emissions from managed soils (15.86 kt) and indirect emissions from managed soils (7.98 kt).

Direct N₂O emissions from managed soils are key sources at level and trend assessment, with Approach 1 and 2, excluding and including the LULUCF sector in the analysis. Indirect N₂O emissions from managed soils are also key sources at level assessment, with Approach 1 and 2, excluding and including the LULUCF sector.

For direct emissions from managed soils the following sources are estimated: inorganic nitrogen fertilizers; organic nitrogen fertilizers, which include animal manure applied to soils, sewage sludge applied to soils, other organic fertilizers applied to soils (as compost and other organic amendments used as fertiliser); urine and dung deposited by grazing animals; crop residues; cultivation of organic soils (i.e. histosols). Mineralised nitrogen resulting from loss of soil organic C stocks in mineral soils through management practices change (F_{SOM}) has been assumed not occurring in cropland remaining cropland. F_{SOM} and related N₂O emissions due to other land use changes are reported in LULUCF sector.

For indirect emissions from managed soils, atmospheric deposition and nitrogen leaching and run-off are estimated. Nitrous oxide emissions from grazing animals are calculated together with the manure

management category based on nitrogen excretion and reported in agricultural soils under “Urine and dung deposited by grazing animals” (see Table 5.41).

CH₄ emissions from managed soils have not been estimated as in the IPCC Guidelines the methodology is not available.

Table 5.41 N₂O emissions from managed soils (kt)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Direct N₂O emissions from managed soils	19.42	21.22	20.71	20.04	16.10	16.24	17.95	17.10	13.74	16.39	15.86
Inorganic N fertilizers	10.03	10.55	10.30	10.26	6.88	6.75	7.55	7.03	3.85	6.44	6.33
Organic N fertilizers	4.54	4.47	4.41	4.15	4.08	4.34	4.63	4.48	4.78	4.42	4.03
a. Animal manure applied to soils	4.36	4.25	4.13	3.89	3.65	3.58	3.54	3.51	3.46	3.47	3.27
b. Sewage sludge applied to soils	0.04	0.07	0.09	0.07	0.08	0.07	0.06	0.06	0.05	0.05	0.05
c. Other organic fertilizers applied to soils	0.14	0.15	0.19	0.19	0.34	0.70	1.03	0.92	1.27	0.90	0.71
Urine and dung deposited by grazing animals	0.88	1.01	1.04	0.78	0.86	0.92	1.04	1.01	0.98	0.96	0.85
Crop residues	3.47	4.70	4.46	4.35	3.78	3.74	4.25	4.09	3.64	4.08	4.16
Cultivation of organic soils	0.50	0.50	0.50	0.50	0.50	0.50	0.49	0.49	0.49	0.49	0.49
Indirect N₂O emissions from managed soils	10.22	10.77	10.57	10.24	8.44	8.28	9.31	8.94	7.31	8.06	7.98
Atmospheric deposition	2.47	2.43	2.34	2.17	1.76	1.81	1.86	1.76	1.36	1.71	1.62
Nitrogen leaching and run-off	7.76	8.34	8.24	8.06	6.67	6.48	7.45	7.18	5.95	6.36	6.35

ISPRA is in charge of collecting, elaborating and reporting the UNFCCC/CLRTAP agriculture national emission inventory, thus, consistency among methodologies and parameters is ensured. The nitrogen balance, from the CLRTAP emission inventory, feeds the UNFCCC inventory, specifically for the estimation of: F_{acGASMS} parameter, used for calculating managed manure nitrogen available for application to managed soils (Equation 10.34 of 2006 IPCC Guidelines, volume 4, chapter 10) and to assess F_{AM} ; F_{acGASM} and F_{acGASF} parameters, used for calculating indirect N₂O emissions from atmospheric deposition of nitrogen volatilised from managed soils (Equation 11.9 of 2006 IPCC Guidelines). Direct and indirect N₂O emissions from the use of sewage sludge in agricultural soils have been estimated and reported.

5.5.2 Methodological issues

Methodologies used for estimating N₂O emissions from “Agricultural soils” follow the IPCC approach (Tier2) and have been assessed by the Research Centre on Animal Production (CRPA, 2018; CRPA, 2006[a]; CRPA, 2000; CRPA, 1997[b]). IPCC emission factors (IPCC, 2019, volume 4, chapter 11) have been used. Activity data used for estimations are shown in Table 5.42.

Table 5.42 Data used for estimating agricultural soil emissions

Data	Reference
Fertilizer distributed (t/yr)	ISTAT, several years [a], [b], [i]
Nitrogen content (t)	ISTAT, several years [a], [b], [i]
N excretion rates (kg head ⁻¹ yr ⁻¹)	CRPA, 2006[a]; GU, 2006; Xiccato <i>et al.</i> , 2005
Livestock data	ISTAT, several years [a], [b], [g]
Cultivated surface (ha yr ⁻¹)	ISTAT, several years [a], [b], [j]
Annual crop production (t yr ⁻¹)	ISTAT, several years [a], [b], [j]
Residue/crop product ratio by crop type	CESTAAT, 1988; ENEA, 1994; Motola V. <i>et al.</i> , 2009

Data	Reference
Crop residue production (tons dry matter ha ⁻¹ yr ⁻¹)	CRPA/CNR, 1992; ENEA, 1994
Dry matter of the residue and product by crop type	CESTAAT, 1988; CRPA/CNR, 1992; EPIC, 2015; IPCC, 2006
Protein content in dry matter by crop type	CESTAAT, 1988

The estimation of direct N₂O emissions from managed soils has been carried out in line with the 2019 Refinement of IPCC Guidelines (IPCC, 2019), taking into account country-specific peculiarities; N₂O-N emissions are estimated from the amount of: inorganic nitrogen fertilizers (F_{SN}); organic nitrogen fertilizers (F_{ON}), which include animal manure applied to soils (F_{AM}), sewage sludge applied to soils (F_{SEW}), other organic fertilizers applied to soils (as compost and other organic amendments used as fertiliser, F_{COMP} and F_{OOA} respectively); urine and dung deposited by grazing animals (F_{PRP}); crop residues (F_{CR}); cultivation of histosols (F_{OS}). Then default IPCC emission factors (IPCC, 2019, volume 4, chapter 11) are applied. Afterwards, N₂O-N emissions are converted to N₂O emissions, multiplying by the ratio of molecular weights (44/28). Urine and dung deposited by grazing animals' emissions are estimated according to the methodology described in section 5.3.2 for manure management.

N₂O emissions from N inputs to managed soils include also emissions related to the application of fertilizers to the short rotation forest crops, according to the 2006 IPCC Guidelines (IPCC, 2006, par. 11.2.1.3, vol. 4, chapter 11) and consistently with the KP Supplement (IPCC, 2014, par. 2.4.4.2).

In order to implement a Tier 2 estimate of direct and indirect N₂O emissions from managed soils, using the disaggregated emission factors by wet and dry climate (EF₁, EF_{3PRP, CPP}, EF₄), provided by refinement 2019 of IPCC Guidelines (IPCC, 2019), the following procedure was applied: the grassland and cropland areas pertaining to wet and dry climate zones were calculated. Grazed grassland areas (receiving nitrogen from urine and dung deposited from grazing animals) were identified by selecting CORINE land cover (CLC) classes 231 and 321, and fertilized cropland areas (receiving all other nitrogen inputs) by selecting CLC classes 211, 212, 213, 221, 222, 223, 241, 242, 243, 244. The CLC was overlaid with the Climatic Zone layer based on the IPCC classification (ESDAC, 2010) in a GIS environment to calculate wet/dry area shares. Different CLC datasets were applied by period: 1990 (1990–1999), 2000 (2000–2005), 2006 (2006–2011), 2012 (2012–2017), and 2018 (2018 onward).

Direct N₂O emissions from managed soils

Applied synthetic fertilizers (F_{SN})

The total use of synthetic fertilizers (expressed in t N year⁻¹) is estimated for each type of fertilizer (see Table 5.43). Data on synthetic fertilizers is from ISTAT as reported in paragraph 5.1.3, 5.1.4 and 5.5.2. N-N₂O emissions from synthetic fertilizers are obtained multiplying F_{SN} by the updated emission factors EF₁ provided in Table 11.1 of Chapter 11, Volume 5 of 2019 Refinement, disaggregated for wet and dry climates, and equal to 0.016 and, 0.005 kg N-N₂O/kg N respectively (IPCC, 2019). A weighted average of the two values was used for the estimate of N₂O emissions, based on the percentages of cropland and grassland under dry and wet climates, calculated in a GIS environment with the procedure described above, in the introductory part of methodological issues. The applied weighted average of EF₁ for F_{SN} is comprised in the range of 0.00849 and 0.00853 kg N-N₂O/kg N throughout the time series. The subcategory "Other nitrogenous fertilizers" was introduced since 1998, because activity data is available from that year (ENEA, 2006). The amount of nitrogen from synthetic fertilizers applied to areas planted with rice was also estimated. The figure used for the estimate of 127 kg N/hectare (Zavattaro *et al.*, 2004) was confirmed by the experts of the National Rice Institute (ENR). This value was multiplied by the area cultivated with rice and the result was subtracted from the quantity of N reported by ISTAT. The emission factor EF_{1FR} of 0.004 kg N-N₂O/kg N (IPCC, 2019) was used to estimate N₂O due to rice fertilization. The time series of nitrogen content of fertilizers is shown in Table 5.50. In 2024, the total use of synthetic fertilizers was 486,401 t N (see Table 5.43).

Table 5.43 Total use of synthetic fertilizer in 2024 (t N yr⁻¹)

Type of fertilizers	Fertilizers distributed (t yr ⁻¹)	Nitrogen content (%)	Nitrogen content of synthetic fertilizers (t N yr ⁻¹)
Ammonium sulphate	157,239	20.7%	32,527
Calcium cyanamide	10	3.0%	0
Nitrates (*)	92,133	48.0%	20,089
CAN	136,413	27.0%	36,832
Urea	572,801	45.9%	263,052
Other nitric nitrogen	91,409 (**)	32.3% (**)	2,346
Other ammoniacal nitrogen			8,669
Other amidic nitrogen			18,481
Phosphate nitrogen	192,519	16.7%	32,185
Potassium nitrogen	45,134	17.5%	7,910
NPK nitrogen	282,025	15.4%	43,299
Organic mineral	176,662	11.9%	21,011
Total	1,746,345		486,401

(*) includes ammonium nitrate < 27% and ammonium nitrate > 27% and calcium nitrate; (**) this amount refers to the total of other nitrogenous fertilizers, which includes other nitric, ammoniacal and amidic N fertilizers distributed. Total amount of N in these fertilizers is 29,496 t N/year, which is the sum of values reported in the column Nitrogen content of synthetic fertilizers for these three fertilizers considered. The nitrogen content (%) is calculated by dividing the total amount of N contained to the total amount of other nitrogenous fertilisers distributed.

The information on amount of fertilizers distributed (tonnes/year) and nitrogen contained in the fertilizers (tonnes N/year) are collected by the ISTAT based on annual questionnaires sent to Italian companies that distribute fertilizers to wholesale and/or retail commercial structures, to farmers, cooperatives, etc. Data on nitrogen content (%) reported in Table 5.43 are calculated values based on two above-mentioned amounts and are not directly used in the estimations of N₂O emissions from inorganic fertilizers applied to soils. The methodology for estimating the amount of CAN used and the nitrogen content is given in section 5.9.2.

The time series of applied synthetic fertilisers is shown in Table 5.44. A strong decrease is observed in the years from 2009 to 2011 as shown in the official statistics provided by the National Institute of Statistics (ISTAT), due to the economic crisis for urea applied to soils. In 2012, a recovery from the sharp decline was recorded.

Table 5.44 Trend of annual amount of synthetic fertiliser N applied to soils (t N yr⁻¹)

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
F_{SN} (t N)	759,510	799,614	782,701	779,846	528,029	517,854	577,451	538,893	299,788	493,655	486,401

Applied organic N fertilisers (F_{ON})

The amount of organic N inputs applied to soils other than by grazing animals is calculated using Equation 11.3 of the 2006 IPCC Guidelines. This includes applied animal manure (F_{AM}), sewage sludge applied to soil (F_{SEW}) and other organic amendments (F_{OOA}), which also includes compost applied to soils (F_{COMP}) (Table 5.45).

Table 5.45 Trend of applied organic N fertilisers (t N yr⁻¹)

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
F_{AM} (t N)	521,395	508,781	494,174	465,271	436,674	428,049	424,213	419,826	414,020	415,807	391,357
F_{SEW} (t N)	5,071	8,137	10,954	8,874	10,040	8,303	7,078	6,745	6,375	5,639	6,112
F_{OOA} (t N)	16,518	18,116	22,571	22,308	41,125	83,535	122,688	110,087	152,016	107,133	84,728

Emissions are calculated with the updated emission factors EF₁ provided in Table 11.1 of Chapter 11, Volume 5 of 2019 Refinement, disaggregated for wet and dry climates, and equal to 0.006 and 0.005 kg N-

N₂O/kg N respectively (IPCC, 2019). A weighted average of the two values was used for the estimate of N₂O emissions, based on the percentages of cropland and grassland under dry and wet climates, calculated in a GIS environment with the procedure described above, in the introductory part of methodological issues. The applied weighted average of EF₁ for F_{ON} is equal to 0.00532 kg N-N₂O/kg N throughout the whole time series.

Animal manure N applied to soil (F_{AM})

The annual amount of animal manure N applied to soils is calculated using Equation 11.4 of the 2006 IPCC Guidelines (IPCC 2006, vol. 4, chapter 11). The amount of managed manure nitrogen available for soil application is calculated using Equation 10.34 (IPCC 2006, vol. 4, chapter 10). The amount of managed manure nitrogen in manure management systems is estimated as reported in paragraph 5.3.2 “Direct N₂O emissions from manure management” and country-specific nitrogen excretion rates (CRPA, 2006[a]; GU, 2006; Xiccato *et al.*, 2005) are used. Fra_{CLOSSMS} parameter of the Equation 10.34 is equal to:

- the managed manure nitrogen that volatilises as NH₃ and NO_x in the manure management systems (i.e. the Fra_{CgasMS} emission factor);
- the nitrogen losses from leaching and run-off at housing and storage systems;
- the losses of N₂, that are considered in response to the 2018 ESD review process²²;
- the nitrogen lost through N-NH₃ emissions from digesters biogas facilities (during storage of feedstock on the premises of the biogas facility; during open storage of the digestate);
- the losses of N-N₂O in the manure management systems.

A description of the country specific Fra_{CgasMS} parameter and the nitrogen leaching and run-off is reported in paragraph 5.3.2 “Indirect N₂O emissions from manure management”. On the basis of the data on the quantity of straw per day (per tonnes of live weight, per type of housing, for cattle and buffalo), contained in the Ministerial Decree of 25 February 2016 on the use of zootechnical effluents, combined with the manure production coefficients used in the estimation of methane emissions from storage, the quantity of straw used as bedding that ends up on agricultural land during the spreading of manure was estimated. The nitrogen content was considered and added to the nitrogen input from manure applied to soils for N₂O emissions estimate. Further information and data can be found in the Annex 7.3. The description of the agricultural residues used for bedding material considered in the animal manure applied to soils (3Da2a) category, which also involves the crop residues (3Da4) and field burning of agricultural residues (3F) categories, is reported in the Annex 7.3. To enhance transparency on the total amount of crop residues generated and shares of the crop residue amounts used for different purposes (such as bedding material (3.D.a.2.a), left on fields (3.D.a.4), burnt on-site (3.F) and off-site (1.A, 5.C.2)), a flow-chart is reported in Annex 7, in Figure A.7.1.

Fra_{CFEED}, Fra_{CFUEL} and Fra_{CCNST} parameters of the Equation 11.4 are assumed equal to zero.

The F_{AM} (t N yr⁻¹) value is estimated by summing the F_{AM} for each livestock category. In 2024, F_{AM} parameter was 391,357 t N.

Sewage sludge applied to soils (F_{SEW})

Direct and indirect N₂O emissions from the application of sewage sludge to agricultural soils were calculated using the Tier 1 methodology described in the IPCC (IPCC, 2006). Direct emissions were estimated by applying the relevant default IPCC equations, EFs and parameters (see Annex A7.3). From 1995 activity data (amount of sewage sludge) and parameters (N content) were collected from the Ministry for the Environment, Land and Sea, which is in charge of collecting and reporting data under the EU Sewage

²² The 2018 annual review of the GHG emission inventory of Italy, pursuant to Article 19(2) of Regulation (EU) No 525/2013, with a view to monitoring Italy's achievement of its greenhouse gas emission reduction or limitation target pursuant to Article 3 of Decision No 406/2009/EC (the 'Effort Sharing Decision', ESD).

Sludge Directive 86/278/EEC (MATTM, several years). From 1990 to 1994 AD and parameters were reconstructed, description is available in the Waste Chapter. The amount of sewage N applied was calculated using the amount of sewage sludge (expressed in t dry matter) and the N content of sludge.

Other organic amendments applied to soils (F_{OOA}) (including compost N applied to soils (F_{COMP}))

For the other organic fertilizers applied to soil category, the used amount, including compost and organic amendments, and N content are provided by ISTAT (as reported in the paragraph 5.1.3, 5.1.4 and 5.5.2). Data are available from 1998; for the previous years, data were reconstructed based on the trend of the available data.

Urine and dung from grazing animals (F_{PRP})

The annual amount of N deposited on pasture (Table 5.46) is calculated using Equation 11.5 (IPCC 2006, vol. 4, chapter 11). As mentioned in section 5.3.2, when estimating N_2O emissions from manure management, the amount related to manure excreted while grazing is subtracted and reported in "Agricultural soils" under urine and dung from grazing animals. In Table 5.27, nitrogen excretion rates ($\text{kg head}^{-1} \text{yr}^{-1}$) used for estimations are shown. N_2O emissions are estimated with the total nitrogen excreted from grazing (including all livestock categories), number of animals, updated values of $\text{EF}_{3\text{PRP}}$ from Table 11.1 of Chapter 11, Volume 5 of 2019 Refinement (IPCC, 2019). $\text{EF}_{3\text{PRP,CPP}}$ for cattle, poultry and pigs disaggregated for wet and dry climates, and equal to 0.006 and, 0.002 $\text{kg N-N}_2\text{O/kg N}$ excreted respectively (IPCC, 2019) was used, applying a weighted average of the two values, based on the percentages of cropland and grassland under dry and wet climates, calculated in a GIS environment with the procedure described above, in the introductory part of methodological issues; the applied weighted average is in the range 0.00452 and 0.00457 $\text{kg N-N}_2\text{O/kg N}$ excreted throughout the whole time series. $\text{EF}_{3\text{PRP,SO}}$ for sheep and other animals (goats, horses and mules and asses) was used, equal to 0.03 $\text{kg N}_2\text{O-N/kg N}$ excreted.

As recommended during the 2021 UNFCCC review, N_2O direct emissions for ostriches are estimated and reported in the IPCC category urine and dung deposited by grazing animals because the common rearing system for ostriches is free-range outdoor housing. Activity data have been provided by ISTAT for some years and for the other years the number of animals has been estimated. The default value for nitrogen excretion rate for broilers (Table 10.19 of chapter 10, volume 4 of the 2006 IPCC Guidelines) has been used.

Table 5.46 Trend of annual amount of urine and dung N deposited by grazing animals on pasture (t N yr^{-1})

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
F_{PRP} (t N)	176,718	204,710	211,343	156,521	167,949	171,474	188,025	182,745	176,915	173,629	152,430

Crop residue N, including N-fixing crops and forage, returned to soils (F_{CR})

For the estimation of nitrogen input from crop residues, the IPCC methodology is used with country specific data on above-ground residue/crop product ratio, percentage of the residue fixed and dry matter content. The total amount of crop above-ground residues is estimated ($\text{t dry matter yr}^{-1}$) by using the following parameters: annual crop production (t yr^{-1}), above-ground residue/crop product ratio, percentage of the residue fixed and dry matter content of residue by type of crop (%), while, when cultivated surface (ha) is the available activity data, only the crop residue production ($\text{t dry matter ha}^{-1} \text{yr}^{-1}$) parameter is used to assess total amount of crop above-ground residues (CESTAAT, 1988; CRPA/CNR, 1992; ENEA, 1994; Motola *et al.*, 2009). Data on annual crop production and cultivated surface are from ISTAT as reported in paragraph 5.1.3, 5.1.4 and 5.5.2. The description of the agricultural residues used for bedding material considered in animal manure applied to soils (3Da2a), which also involves the categories crop residues (3Da4) and field burning of agricultural residues (3F), is reported in the Annex 7.3. The description of the type of agricultural

residues is also included. To enhance transparency on the total amount of crop residues generated and shares of the crop residue amounts used for different purposes (such as bedding material (3.D.a.2.a), left on fields (3.D.a.4), burnt on-site (3.F) and off-site (1.A, 5.C.2)), a flow-chart is reported in Annex 7, in Figure A.7.1.

The nitrogen content of crop above-ground residues from cereals, legumes, tubers and roots, legumes forages and other forages (t N yr^{-1}) is estimated by multiplying the total amount of crop above-ground residue as dry matter with the reincorporated fraction ($1 - \text{Frac}_{\text{BURN}}$, where $\text{Frac}_{\text{BURN}}$ is the fraction of crop residue that is burned rather than left on field equal to $0.1 \text{ kg N/kg crop-N}$ (IPCC, 1997; CRPA, 1997[b])), and the nitrogen content for each crop type, in line with the Equation 11.6 (IPCC 2006, vol. 4, chapter 11). The nitrogen content is obtained by converting protein content in dry matter (CESTAAT, 1988; Borgioli, 1981), dividing by factor 6.25 ($100 \text{ g of protein}/16 \text{ g of nitrogen}$). The contribution of the below-ground nitrogen to the total input of nitrogen from crop residues has been considered and calculated by using Equation 11.7A (IPCC 2006, vol. 4, chapter 11) and the IPCC default values of ratio of below-ground residues to above-ground biomass and N content of below-ground residues. The amount of nitrogen of crop residues from perennial grasses is calculated by using the Equation 11.7A (IPCC 2006, vol. 4, chapter 11). The values related to N content of above-ground residues, ratio of below-ground residues to above-ground biomass and N content of below-ground residues used for other temporary forages are weighted averages of the IPCC values in Table 11.2, weighted with the productions of the various crops included in the category other temporary forages. The values used for the $\text{Frac}_{\text{C renew}}$ parameter for other temporary forages (not renewed annually) are derived from Baldoni and Giardini (Baldoni and Giardini, 2002) and the value for perennial grasses is from ISTAT (ISTAT, 2010).

The F_{CR} parameter is obtained by adding the nitrogen content of cultivars crop residues. In 2024, F_{CR} parameter was $497,802 \text{ t N}$ (see Table 5.47). Emissions are calculated with the updated emission factors EF_1 provided in Table 11.1 of Chapter 11, Volume 5 of 2019 Refinement, disaggregated for wet and dry climates, and equal to 0.006 and $0.005 \text{ kg N-N}_2\text{O/kg N}$ respectively (IPCC, 2019). A weighted average of the two values was used for the estimate of N_2O emissions, based on the percentages of cropland and grassland under dry and wet climates, calculated in a GIS environment with the procedure described above, in the introductory part of methodological issues. The applied weighted average of EF_1 for F_{CR} is equal to $0.00532 \text{ kg N-N}_2\text{O/kg N}$ throughout the whole time series.

Detailed information related to residues production and parameters used for emissions estimates, for each type of crop, are shown in the Annex 7 (Tables A.7.17-20). Cultivated surface and crops production data are shown in the Tables A.7.17-18 in Annex 7, reported in the NIR submitted in 2024 (National Inventory Report - Italian Greenhouse Gas Inventory 1990-2022), available at the link <https://emissioni.sina.isprambiente.it/inventario-nazionale/>.

Table 5.47 Trend of annual amount of N in crop residues (t N yr^{-1})

Year	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
$\text{F}_{\text{CR}} (\text{t N})$	415,598	561,734	533,669	520,208	452,032	447,134	508,447	489,094	435,973	488,736	497,802

Area of drained/managed organic soils (F_{OS})

In Italy, the area of organic soils cultivated annually (histosols) is estimated to be $24,285$ hectares for the year 2024, a substantially constant value for the whole time series (FAOSTAT database²³). This value is multiplied by EF_2 from Table 2.5 of 2013 Wetland Supplement as suggested by 2019 Refinement: $12.78 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$ was used, the weighted average of the values provided by the Wetland Supplement for cropland drained ($13 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$) and grassland deep drained nutrient rich temperate ($8 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$).

²³ <http://www.fao.org/faostat/en/#data/GV>

The data are consistent with figures used for estimation in the LULUCF sector. Additional information may be found in paragraph 6.9.2 *Methodological issues* of the LULUCF sector.

Indirect N₂O emissions from managed soils

For indirect emissions from agricultural soils the following parameters are estimated:

- Atmospheric deposition
- Nitrogen leaching and run-off

For estimating N₂O emissions due to atmospheric deposition of NH₃ and NO_x the IPCC Tier 2 approach was followed (Equation 11.11 of the 2006 IPCC Guidelines). Parameters used are: total use of synthetic fertilizer F_{SN} (t N yr⁻¹), $Frac_{GASF}$ parameter, total amount of organic N inputs applied to soils F_{ON} (t N yr⁻¹), total amount of urine and dung N deposited by grazing animals F_{PRP} (t N yr⁻¹), $Frac_{GASM}$ parameter and the disaggregated values of EF₄ for wet and dry climates, equal respectively to 0.014 and 0.005 kg N₂O-N per kg NH₃-N and NO_x-N emitted, provided by Table 11.3 of Chapter 11, Volume 4 of 2019 Refinement (IPCC, 2019). A weighted average of these two values was calculated for the estimate of indirect N₂O emissions from atmospheric deposition, based on the percentages of cropland and grassland under dry and wet climates, calculated in a GIS environment with the procedure described above, in the introductory part of methodological issues. The applied value of EF₄ (weighted average) is comprised in the range of 0.00785 and 0.00789 kg N₂O-N per kg NH₃-N and NO_x-N emitted throughout the time series.

$Frac_{GASF}$ parameter is estimated for the whole time series, following the IPCC definition, where the total N-NH₃ and N-NO_x emissions from fertilizers are divided by the total nitrogen content of fertilizers (see Table 5.48). NH₃ EFs from the use of synthetic fertilizers for normal and high pH factors (reported in the EMEP/EEA Guidebook (EMEP/EEA, 2023)) have been updated. To calculate a weighted average of emission factors distinguished according to soil pH type, CREA-AA²⁴ processed the national agricultural areas distinguished according to eight soil pH classes, finally calculating the area percentages for normal and high pH (Rivieccio R., 2019). NO_x emission factor for synthetic N-fertilizer (reported in the EMEP/EEA Guidebook (EMEP/EEA, 2023)) was also updated. $Frac_{GASM}$ is the fraction of applied organic N fertiliser materials (F_{ON}) and of urine and dung N deposited by grazing animals (F_{PRP}) that volatilises as NH₃ and NO_x.

$Frac_{GASM}$ is then composed of the following fractions:

- Fraction of livestock N excretion that volatilizes as NH₃ and NO_x during spreading and grazing animals - $Frac_{GASM}$ indirect (as reported in the CRT). This fraction is equal to the ratio between the amount of NH₃-N and NO_x-N emissions, and the total nitrogen excreted (see Table 5.48);
- Fraction of N from other organic N fertilizers applied (sewage sludge, other organic amendments applied to soils including compost) that volatilizes as NH₃ and NO_x. The volatilization factor for N-NH₃ and NO_x-N emissions is 7.8% for other organic N fertilizers and 11.9% for sewage sludge applied, as reported in Table 5.48.

For $Frac_{GASM}$ indirect, the ammonia emission factors from land spreading for cattle, swine, laying hens and broilers categories have been assessed, based on ISTAT statistics on spreading systems (i.e. 2010 and 2020 Agricultural Census, 2013 and 2016 Farm Structure Survey). NO_x emission factors (during spreading) were also assessed based on the nitrogen mass-flow approach (Tier 2 method of the EMEP/EEA Guidebook (EMEP/EEA, 2023)). NH₃ and NO_x emission factors from other organic N fertilizers applied (sewage sludge, other organic amendments applied to soils including compost) were also based on the EMEP/EEA Guidebook (EMEP/EEA, 2023).

The estimation of N₂O emissions due to nitrogen leaching and run-off has followed the IPCC Tier 2 approach (Equation 11.10 of the 2006 IPCC Guidelines). Parameters used are: total use of synthetic fertilizer F_{SN} (t N yr⁻¹), total amount of organic N inputs applied to soils F_{ON} (t N yr⁻¹), total amount of urine and dung

²⁴ Council for Agricultural Research and Analysis of Agricultural Economics - Agriculture and Environment

N deposited by grazing animals F_{PRP} (t N yr⁻¹), total amount of N in crop residues (above- and below-ground), including N-fixing crops and from forage F_{CR} (t N yr⁻¹), $Frac_{LEACH-(H)}$ factor 0.24 kg N/kg nitrogen of fertilizer or manure (see Table 5.48) and the emission factor 0.011 kg N₂O-N per kg nitrogen leaching/run-off (IPCC, 2019). The $Frac_{LEACH-(H)}$ IPCC default value is in line with the national literature $Frac_{LEACH-(H)}$ parameter (ADBPO, 2001; ADBPO, 1994).

The estimate of N lost through leaching and run-off includes the losses of N due to leaching from managed soils. As regards $Frac_{LEACH-(H)}$, according to the 2006 IPCC Guidelines, the leached nitrogen must be estimated only in those areas where there is a water surplus or where irrigation is employed. For the agricultural areas affected by the water surplus, the $Frac_{LEACH-(H)}$ is assumed to be equal to 0.24 kg N/kg N applied to soils or deposited by grazing animals, while a value equal to zero is assumed for the agricultural areas affected by the water deficit. To calculate the agricultural area affected by hydrological surplus, the following procedure was followed. The methodology involves estimating the annual hydrologic surplus of areas below 1,000 meters, which are assumed to be agricultural areas. Monthly surplus values are derived from the Big Bang model elaborated by ISPRA (Braca G. *et al*, 2025), whose data are in Ascii format, and the coordinate system is ETRS_1989_LAEA (Braca G. *et al*, 2021). The calculation is made in GIS environment with the help of the raster of the altimetry and the vector files (shape files) of land use categories (Corine Land Cover 2018). The surplus in each cell (which has a size of 1 km x 1 km) was calculated by summing the values of only the rainy months (October November and December) of each year (the range of values obtained varies from 0.0001 to over 1500 millimeters) from 1990 to 2024. The sum of the three months of each year was then multiplied by a boolean raster of the elevations (values 0 if above 1000 meters, 1 if below). In this way, areas above 1000 meters were excluded from the calculation. Agricultural land corresponds to the following Corine Land Cover categories: 211, 212, 213, 221, 222, 223, 231, 241, 242, 243, 244, 321, 333, corresponding to the categories "grassland" and "cropland" defined according to the IPCC. Again, a boolean raster was created (values 0 for unselected categories, 1 for selected categories). Finally, cells where a surplus occurs were considered and the total area of these cells was calculated for each year. The result was related to the total area of land below 1000 meters of altitude. The weighted average value of $Frac_{LEACH-(H)}$ relative to the entire national agricultural area will be equal to 22.7% of nitrogen applied to soils or deposited by grazing animals for 2024.

Table 5.48 Parameters used for the estimation of indirect N₂O emissions from managed soils

Year	Atmospheric deposition				N leaching and run-off		
	$Frac_{GASF}^{(1)}$ (%)	$Frac_{GASM}^{indirect (2)}$ (%)	Fraction of N from other organic N fertilizers applied (%) ⁽³⁾	Fraction of N from from sewage sludge applied (%) ⁽⁴⁾	N volatilised from managed soils (t N)	$Frac_{LEACH-(H)}^{(5)}$ (kg N/kg N)	N lost through leaching and run-off (t N)
1990	13.46	10.21	7.8	11.9	198,980	0.24	448,855
1995	13.03	9.58	7.8	11.9	195,906	0.23	482,338
2000	13.12	9.05	7.8	11.9	189,034	0.23	476,540
2005	12.89	8.87	7.8	11.9	175,966	0.24	466,381
2010	12.87	8.82	7.8	11.9	142,695	0.24	386,081
2015	13.69	8.74	7.8	11.9	146,280	0.23	374,695
2020	13.95	7.64	7.8	11.9	150,590	0.24	431,227
2021	13.81	7.67	7.8	11.9	142,628	0.24	415,347
2022	13.29	7.67	7.8	11.9	110,174	0.23	344,108
2023	14.53	7.65	7.8	11.9	138,272	0.22	367,794
2024	14.49	7.71	7.8	11.9	131,468	0.23	367,595

Note: (1) the fraction is multiplied by F_{SN} (see Table 5.44); (2) the fraction is multiplied by total N excreted (see Table 5.27); (3) the fraction is multiplied by F_{OOA} (see Table 5.45); (4) the fraction is multiplied by F_{SEW} (see Table 5.45); (5) the fraction is multiplied by F_{SN} , F_{SEW} , F_{OOA} , F_{AM} and by F_{CR} (see Table 5.47).

N₂O indirect emissions for ostriches are estimated and reported in indirect N₂O emissions from managed soils, in atmospheric deposition and nitrogen leaching and run-off. Further details on the estimate are given in 5.5.2 *Methodological issues* paragraph, in Direct N₂O emissions from managed soils, in *Urine and dung from grazing animals* (FPRP). The 2019 IPCC N₂O EFs, Fra_{CGASM} and Fra_{CLEACH-(H)} for indirect emissions have been used (Table 11.3 of chapter 11, volume 4 of the 2019 IPCC Guidelines).

5.5.3 Uncertainty and time-series consistency

Uncertainty for N₂O direct and indirect emissions from managed soils has been estimated to be 53.9%, as combination of 20% and 50% for activity data and emission factor, respectively. In Table 5.49, time series of N₂O emissions from managed soils are reported.

Table 5.49 Nitrous oxide emission trends from managed soils (kt)

Year	Direct emissions from managed soils	Indirect emissions from managed soils kt	Total
1990	19.42	10.22	29.64
1995	21.22	10.77	31.99
2000	20.71	10.57	31.29
2005	20.04	10.24	30.27
2010	16.10	8.44	24.53
2015	16.24	8.28	24.52
2020	17.95	9.31	27.27
2021	17.10	8.94	26.04
2022	13.74	7.31	21.05
2023	16.39	8.06	24.46
2024	15.86	7.98	23.84

In 2024, N₂O emissions from managed soils were 19.6% (23.84 kt N₂O) lower than in 1990 (29.64 kt N₂O). Major contributions were made by direct emissions (15.86 kt), that come mainly (86.8%) from inorganic N fertilizers (6.33 kt), crop residues returned to soils (4.16 kt) and animal manure applied to soils (3.27 kt) (see Table 5.41). Indirect emissions (7.98 kt) are mainly (67.7%) due to N₂O emissions from nitrogen leaching and run-off from crop residues returned to soils (1.95 kt), inorganic N fertilizers (1.91 kt) and animal manure applied to soils (1.54 kt) (see Table 5.41). As regards inorganic N fertilizers N₂O emissions from leaching and run-off are related to the nitrogen content in fertilizers, therefore emissions are mainly linked to the use of N fertilizers trend. Between 1996 and 1997 there was a high increase in the use of nitrogen fertilizers in Italy, thus, emissions could be identified as outlier. Between 2007/2008 (-14%) and 2008/2009 (-21%) N fertiliser distribution has decreased. In 2010 the same trend was observed. According to the Italian Fertilizer Association (AIF) the use of fertilisers is determined by their cost and particularly by the price of agricultural products. In the last years, prices have decreased and, as a result, farmers need to save costs, consequently, less fertilisers are being used (Perelli, 2007; De Corso 2008). The 12% reduction in the urea used in 2021 compared to 2020 is mainly due to the increase in the cost of raw materials (natural gas), which led the main domestic producer to suspend production for some time during the year. In addition, production was suspended due to a plant shut down for maintenance. The 2022 data are lower than annual average (for nitrogen, phosphorus pentoxide, and potassium oxide) because they follow a two-year period in which quantities purchased increased and refer to a year in which high market prices prompted operators to delay purchases in anticipation of falling prices, an event, which occurred during 2023.

5.5.4 Source-specific QA/QC and verification

Synthetic fertilizers and nitrogen content are compared with the international FAO agriculture database statistics (FAO, several years). In Table 5.50, national, FAO and EUROSTAT time series of total nitrogen

applied are reported. Differences between national data and FAO database are related to the difference in data elaboration (ISTAT, 2004) and could be attributed to different factors. First, national data are more disaggregated by substance than FAO data and the national nitrogen content is considered for each substance, while FAO utilizes default values. Besides, differences could also derive from different products' classification. As regards EUROSTAT data, the amount of nitrogen annually consumed for the growth of plant productions is estimated from the area and annual production of each crop and the amount of nitrogen required for the growth of a plant.

Table 5.50 Total annual N content in fertilizer applied from 1990 to 2024

Year	ISTAT National data (t N)	FAO database (Nitrous fertilizer consumption, t N) (*)	EUROSTAT database (Consumption of inorganic fertilizers, t N)
1990	759,510	878,960	
1995	799,614	875,000	
2000	782,701	828,000	599,471
2005	779,846	800,697	593,008
2010	528,029	498,605	586,130
2015	517,854	605,236	579,728
2020	577,451	574,530	573,473
2021	538,893	572,105	572,105
2022	299,788	570,504	570,504
2023	493,655	569,434	569,434
2024	486,401	data not available	568,092

(*) Unofficial/official figures or from international organizations

In 2021, a technical report (CREA, 2021) produced by CREA (Council for Agricultural Research and Economics), in collaboration with ISPRA, on the assessment of emissions related to the use of nitrogen fertilizers was published, which contains several analyses of nitrogen fertilizer consumption data from different data sources: IFASTAT/Fertilizer Europe, FAO, EUROSTAT, Assofertilizzanti, National Integrated Production Specifications, Farm Accountancy Data Network (FADN). These analyses suggest further investigation to better understand the differences found between these data sources and the ISTAT data used for the estimates.

Data on national sales of synthetic nitrogen fertilizers (by type of fertilizers) as provided by *Assofertilizzanti* for the period 2011-2024 have been compared to official statistics provided by ISTAT. ISTAT simple mineral nitrogen fertilizers data are about 11% lower than those of *Assofertilizzanti*, for the years 2011-2024. These differences in recent years could be attributable to rising fertilizer prices. ISTAT statistics almost certainly do not take into account that farmers tend to anticipate purchases (and thus stockpile) when expectations of rising market prices are present. The 2022 data are lower than annual average (for nitrogen, phosphorus pentoxide, and potassium oxide) because they follow a two-year period in which quantities purchased increased and refer to a year in which high market prices prompted operators to delay purchases in anticipation of falling prices, an event, which occurred during 2023 (as per ISTAT data).

In 2015, data on crop residues and on the relationship between crop residues and product were compared with studies and research provided by the Agricultural Research Council (CRA)²⁵. However, these studies were conducted in different countries from Italy, so despite the differences, the values used in the inventory, based on national studies, have not been changed.

Following the suggestion of the CRA experts, in the estimation of N₂O emissions from crop residues, the total amount of residues has been considered, without deducting the fraction removed for purposes such as feed, bedding and construction. Therefore, the data were revised using the fixed residues/removable

²⁵ CRA is a national research organization which operates under the supervision of the Ministry of Agriculture, with general scientific competence within the fields of agriculture, agro-industry, food, fishery and forestry.

residues ratio for each crop considered (ENEA, 1994), also used to estimate the emissions from category 3F (see paragraph 5.6.2).

Concerning compost data, from the waste sector only data on compost production is available. Official statistics provided by ISTAT on compost used in the agriculture sector (considered as the green and mixed amendments) are compared to data on compost from waste sector. For the year 2015, the amount of compost used is 58.1% of the compost production only from plants that treat a selected waste.

As regards $F_{\text{CLEACH-(H)}}$, Italy verified that the IPCC default is like the country-specific reference value reported from the main regional basin authority - Po Valley (ADBPO, 2001; ADBPO, 1994).

At the end of 2016, in response to the UNFCCC review process, experts on land use and weather climate were contacted to investigate the $F_{\text{CLEACH-(H)}}$ fulfilment to criteria set out in the 2006 IPCC Guidelines.

As regards the sewage sludge applied, the values used are official data provided by the Ministry of the Environment which collects them at the Italian Regions under the EU Sewage Sludge Directive. The annual variations depend on the fact that some Regions prohibit the practice of spreading in certain years, based on weather-climatic, soil and water conditions, and also over the years other types of sludge treatment, such as the anaerobic digestion, have been implemented, to the detriment of the spreading.

In 2020 a working group was set up with *Assofertilizzanti* and ISTAT to compare the statistics produced by these two bodies. Initial results have led to a revision of the data on nitrate consumption in the period 2009-2011 and the estimation of CAN fertiliser consumption.

5.5.5 Source-specific recalculations

For this submission recalculations of N_2O emissions from managed soils correspond to 78-82% of all agriculture sector's recalculations along the time series.

As regards N_2O direct emissions from agricultural soils, the following recalculations have been developed.

A major recalculation is due to the update of emission factors from Table 11.1, Chapter 11 of Volume 4 of 2019 Refinement of IPCC Guidelines in place of 2006 IPCC Guidelines values. A Tier 2 approach has been implemented using the disaggregated values of these updated factors, as described in the methodological issues section: EF_1 for synthetic fertilizers, animal manure, crop residue, sewage sludge, other organic fertilizers; EF_{1FR} for flooded rice cultivations; EF_{3PRP} for urine and dung deposited by grazing animals.

The surface of cultivated organic soils (histosols) F_{OS} was updated starting from 1993 (FAOSTAT database), and for EF_2 was introduced a new value from Table 2.5 of 2013 Wetland Supplement as suggested by 2019 Refinement in place of $8 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$ from IPCC Guidelines 2006: this new value equal to $12.78 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$ is a weighted average of the values provided by the Wetland Supplement for cropland drained ($13 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$) and grassland deep drained nutrient rich temperate ($8 \text{ kg N}_2\text{O} \cdot \text{ha}^{-1}$).

The amount of N input from sewage sludge was updated for the years 2022 and 2023.

The amount of N input from animal manure applied to soils was modified because of minor recalculations of number of heads described in paragraphs 5.2 (enteric fermentation) and 5.3 (manure management).

The impacts of the described recalculations on estimated direct N_2O emissions from managed soils are summarized in Table 5.51, per each type of N input, and expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. The reduction of total direct N_2O emissions from managed soils due to the implemented recalculations were in the range of 34-43% along the whole time series.

Table 5.51 Recalculation of reported direct N₂O emissions from managed soils

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Synthetic Fertilizers									
Recalculation [kt N ₂ O]	- 1.61	- 1.69	- 1.68	- 1.07	- 1.07	- 1.21	- 1.12	- 0.56	- 1.02
% recalculation	-14%	-14%	-14%	-13%	-14%	-14%	-14%	-13%	-14%
Animal manure									
Recalculation [kt N ₂ O]	- 3.86	- 3.67	- 3.43	- 3.18	- 3.16	- 3.09	- 3.06	- 3.00	- 3.04
% recalculation	-47%	-47%	-47%	-47%	-47%	-47%	-47%	-46%	-47%
Crop residues									
Recalculation [kt N ₂ O]	- 3.06	- 3.93	- 3.83	- 3.33	- 3.29	- 3.84	- 3.70	- 3.30	- 3.74
% recalculation	-47%	-47%	-47%	-47%	-47%	-47%	-47%	-48%	-48%
Cultivation of organic soils									
Recalculation [kt N ₂ O]	0.19	0.19	0.19	0.19	0.19	0.18	0.18	0.18	0.18
% recalculation	60%	60%	60%	60%	60%	60%	60%	60%	60%
Sewage sludge									
Recalculation [kt N ₂ O]	- 0.04	- 0.08	- 0.07	- 0.07	- 0.06	- 0.05	- 0.05	- 0.06	- 0.07
% recalculation	-47%	-47%	-47%	-47%	-47%	-47%	-47%	-51%	-58%
Other organic fert.									
Recalculation [kt N ₂ O]	- 0.12	- 0.17	- 0.16	- 0.30	- 0.61	- 0.90	- 0.81	- 1.12	- 0.79
% recalculation	-47%	-47%	-47%	-47%	-47%	-47%	-47%	-47%	-47%
Grazing animals (pasture)									
Recalculation [kt N ₂ O]	- 2.21	- 2.56	- 1.93	- 2.18	- 2.40	- 2.80	- 2.74	- 2.63	- 2.62
% recalculation	-71%	-71%	-71%	-72%	-72%	-73%	-73%	-73%	-73%
Total									
Recalculation [kt N ₂ O]	- 10.71	- 11.91	- 10.91	- 9.94	- 10.41	- 11.72	- 11.29	- 10.49	- 11.10
% recalculation	-36%	-37%	-35%	-38%	-39%	-39%	-40%	-43%	-40%

Regarding N₂O indirect emissions from agricultural soils, the following recalculations have been performed.

A major recalculation is due to the update of emission factors from Table 11.3, Chapter 11 of Volume 4 of 2019 Refinement of IPCC Guidelines in place of 2006 IPCC Guidelines values. A Tier 2 approach has been implemented using the disaggregated values of EF₄ (applied to N deposited) for wet and dry climates, as described in the introductory part of the methodological issues section. Updated values of EF₅ (applied to N leached) and of Frac_{LEACH} have been used throughout the whole time series.

Moreover, a minor change has been made in the entire time series to the percentage of cultivated area where soil water-holding capacity is exceeded as a result of rainfall, used in the estimate of nitrogen leached.

The following recalculation interested the estimates of NH₃ and NO_x, thus affecting also indirect N₂O emission from deposition:

- recalculations of N losses during manure management phases (housing, storage and anaerobic digestion phase) have determined recalculations in spreading phase (see par. 5.3.5)
- the modification of the distribution of manure management system for non-dairy cattle starting from 2020, based on 2020 Agriculture Census data, described above in the paragraph about CH₄ emissions and direct N₂O emissions from manure management, determined recalculations of NH₃ emissions and NO_x emissions from manure management and consequently in the spreading phases;
- the NH₃ EF for the spreading phase has been modified starting from 2020, due to a correction in spreading practices of liquid manure for non-dairy cattle (incorporation within 4 hours moved to medium-efficiency practices); this modification has determined an updated of EF from 2017;

- the residues/crop product mass ratios for cereals updated from 2001 based on Internship of Mounérat (Internship Mounérat N., 2024) have been used for the estimate of N in straw for bedding, determining a recalculation of NH₃ and NO_x at spreading phase for cattle and buffalo;
- for the year 2023, the update of number of heads for equines and rabbits determined a recalculation of NH₃ and NO_x emissions in all manure management and spreading phase;
- the update of cultivated surface of lupine determined a recalculation of NH₃ from N-fixing crops;
- the update of number of heads for poultry (1998-2023 for laying hens and 2001-2023 for broilers) determined a recalculation of NH₃ and NO_x at storage and spreading phase
- the update of N-excreted at pasture for dairy cattle based on 2020 Agriculture Census has determined a recalculation of NH₃ and NO_x at housing, storage, sent to anaerobic digestion and spreading from 2007 (interpolation with 2006 CRPA value); the same updated percentage of N excreted at pasture was used for non-dairy cattle and buffalo determining same recalculations.

The impacts of the described recalculations on estimated indirect N₂O emissions from managed soils are summarized in Table 5.52, per nitrogen deposited and leached, and expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission. The implemented recalculations determined an increase of total estimated indirect N₂O emissions from managed soils in the range of 5-7% throughout the time series.

Table 5.52 Recalculation of reported indirect N₂O emissions from managed soils

	1990	2000	2005	2010	2015	2020	2021	2022	2023
Atmospheric deposition									
Recalculation [kt N ₂ O]	- 0.67	- 0.64	- 0.59	- 0.48	- 0.49	- 0.55	- 0.52	- 0.41	- 0.51
% recalculation	-21%	-21%	-21%	-21%	-21%	-23%	-23%	-23%	-23%
Nitrogen Leaching/Run.off									
Recalculation [kt N ₂ O]	1.14	1.21	1.19	0.99	0.95	1.09	1.05	0.87	0.91
% recalculation	17%	17%	17%	17%	17%	17%	17%	17%	17%
Total									
Recalculation [kt N ₂ O]	0.47	0.57	0.60	0.52	0.46	0.54	0.52	0.46	0.40
% recalculation	5%	6%	6%	7%	6%	6%	6%	7%	5%

5.5.6 Source-specific planned improvements

In 2026, a project will be launched with the CRPA, which will last about a year and will include various activities related to livestock farming. In particular, based on numerous studies and data collected, and through an analysis of existing literature, data relating to rations and estimates of GE, DE, and Ym parameters for cattle by subcategory will be verified and updated, checking the estimated data in the inventory, also evaluating the protein in the ration and the corresponding nitrogen excreted, and assessing updates if necessary.

Moreover the following data will be verified and updated: types of housing, storage, and spreading techniques for cattle, pigs, poultry, and subcategories (number of animals and NH₃ emission factors); emission reduction measures for all stages of livestock management (feeding, housing, storage, spreading) for greenhouse gases (CH₄ and N₂O) and ammonia, providing assessments for each measure and constructing scenarios for reducing greenhouse gas and ammonia emissions; biogas/biomethane production.

It will be estimated the consumption of synthetic and organic fertilizers at the provincial level based on plant requirements to evaluate the sales data compiled by ISTAT and used in the inventory. Emissions will be estimated at the provincial level using the 2019 IPCC emission factors for each climate zone.

As part of the CRPA 2026-2027 project, an assessment will be carried out of the quantities of organic matrices (other than livestock waste) that are fed into anaerobic digesters to produce biogas.

5.6 Field burning of agriculture residues (3F)

5.6.1 Source category description

Methane and nitrous oxide emissions from field burning agriculture residues have not been identified as a key source. In 2024, CH₄ emissions from this source were 0.37 kt, representing 0.05% of emissions for the agriculture sector. N₂O emissions were 0.010 kt, representing 0.03% of emissions for the agriculture sector.

5.6.2 Methodological issues

The estimation of emissions from field burning of agriculture residues has been carried out based on the IPCC methodology, using different parameters, such as the amount of residues produced, the amount of dry residues, the total biomass burned, and the total carbon and nitrogen released as reported in Table 5.53.

Table 5.53 Data used for estimating field burning of agriculture residues emissions

Data	Reference
Annual crop production	ISTAT, several years [a], [b], [j]
Removable residues/product ratio	CESTAAT, 1988; Motola V. <i>et al.</i> , 2009
Fixed residues/removable residues ratio	ENEA, 1994
Fraction of dry matter in residues	IPCC, 1997; CRPA/CNR, 1992; CESTAAT, 1988; Borgioli, 1981
Fraction of the field where "fixed" residues are burned	IPCC, 1997; CRPA, 1997[b]; ANPA-ONR, 2001; CESTAAT, 1988
Fraction of residues oxidized during burning	IPCC, 2006
Fraction of carbon of dry matter of residues	IPCC, 2006; IPCC, 2019
Raw protein in residues (dry matter fraction)	CESTAAT, 1988; Borgioli, 1981
IPCC default emission rates (CH ₄ , N ₂ O)	IPCC, 2006

Activity data (annual crop production of cereals) used for estimating burning of agriculture residues are reported in Table 5.54.

The same methodology is used to estimate emissions from open burning of agriculture residues (burnt off-site). Emissions from fixed residues (stubble), burnt on open fields, are reported in this category (3F) while emissions from removable residues burnt off-site, are reported under the waste sector (open burning of waste - 5C2 category). The description of the agricultural residues used for bedding material considered in animal manure applied to soils (3Da2a), which also involves the categories crop residues (3Da4) and field burning of agricultural residues (3F), is reported in the Annex 7.3. The description of the type of agricultural residues is also included in the Annex 7.3. To enhance transparency on the total amount of crop residues generated and shares of the crop residue amounts used for different purposes (such as bedding material (3.D.a.2.a), left on fields (3.D.a.4), burnt on-site (3.F) and off-site (1.A, 5.C.2)), a flow-chart is reported in Annex 7, in Figure A.7.1.

Table 5.54 Time series of activity data (tons) used for 3F estimations

Year	Wheat	Barley	Maize	Oats	Rye	Rice	Sorghum
Agricultural production (t)							
1990	8,108,500	1,702,500	5,863,900	298,400	20,800	1,290,700	114,200
1995	7,946,081	1,387,069	8,454,164	301,322	19,780	1,320,851	214,802
2000	7,427,660	1,261,560	10,139,639	317,926	10,292	1,245,555	215,200
2005	7,717,129	1,214,054	10,427,930	429,153	7,876	1,444,818	184,915
2010	6,849,858	944,257	8,495,946	288,880	13,926	1,574,320	275,572
2015	7,394,495	955,131	7,073,897	261,366	13,183	1,505,804	294,218
2020	6,553,861	1,090,630	6,771,089	242,709	11,475	1,530,921	361,694
2021	7,118,272	1,059,803	6,060,232	233,452	10,886	1,496,545	223,459
2022	6,449,773	1,124,283	4,681,925	242,282	11,409	1,273,232	191,161
2023	6,727,837	1,158,760	5,331,336	225,553	11,030	1,386,997	239,166
2024	6,063,040	891,519	4,924,498	206,640	11,759	1,448,756	247,748

The methodology for estimating emissions refers to fixed residues burnt. The same steps are followed to calculate emissions from removable residues burnt off-site reported in 5C. Parameters taken into consideration are the following:

- Amount of “fixed” residues (t), estimated with annual crop production, removable residues/product ratio, and “fixed” residue/removable residues ratio. This last value is equal to 0.25 for all type of cereals and represents the part of the fixed residue (compared to the removable residue) that remains on the ground.
- Amount of dry residues in “fixed” residue (t dry matter), calculated with amount of fixed residues and fraction of dry matter.
- Amount of “fixed” dry residues oxidized (t dry matter), assessed with amount of dry residues in the “fixed” residues, fraction of the field where “fixed” residues are burned, and fraction of residues oxidized during burning.
- Amount of carbon from stubble burning release in air (t C), calculated with the amount of “fixed” dry residue oxidized and the fraction of carbon from the dry matter of residues.
- C-CH₄ from stubble burning (t C-CH₄), calculated with the amount of carbon from stubble burning release in air and default emissions factor equal to 2.7 g CH₄ kg⁻¹ dry matter burnt (IPCC, 2006).

Data related to the removable residues/product ratio, the “fixed” residue/removable residues ratio, the fraction of dry matter, the fraction of carbon of dry matter of residues are available for each type of cereals.

Fraction of the field where “fixed” residues is burned is 10% (IPCC, 1997; CRPA, 1997[b]) for all crops except for rice, for which the fraction varies as a function of the change in annual percentage of the reincorporated rice straw into the soil (see *straw incorporation* in the methodological issues in rice cultivation (3C) paragraph). CH₄ emissions from field burning of agriculture residues (0.37 kt CH₄ in 2024) have been estimated to multiply the C-CH₄ value (0.279 kt C-CH₄) by the ratio of molecular weights (16/12). In Table 5.55, parameters used for estimating CH₄ emissions from field burning of agriculture residues are shown.

Table 5.55 Parameters used for the estimation of CH₄ emissions from agriculture residues in 2024

Crops	Annual crop harvest production (t 1000)	Amount of “fixed” burnable residues (t 1000)	Amount of dry residue in the “fixed” residues (t 1000 dry matter)	Amount of “fixed” dry residues burnt (t 1000 dry matter)	Amount of carbon from stubble burning (t 1000 C)	C-CH ₄ from stubble burning (t C-CH ₄)
Wheat	6,063	1,442	1,230	120	45	218
Rye	12	4	3	0	0	1
Barley	892	211	181	18	7	33
Oats	207	50	43	4	2	8
Rice	1,449	322	241	5	2	8

Crops	Annual crop harvest production (t 1000)	Amount of "fixed" burnable residues (t 1000)	Amount of dry residue in the "fixed" residues (t 1000 dry matter)	Amount of "fixed" dry residues burnt (t 1000 dry matter)	Amount of carbon from stubble burning (t 1000 C)	C-CH ₄ from stubble burning (t C-CH ₄)
Maize	4,924	620	259	0	0	0
Sorghum	248	79	66	7	2	12
Total	13,794	2,728	2,023	154	58	279

For estimating N₂O emissions, the same amount of "fixed" dry residue oxidized described above were used; further parameters are:

- Amount of nitrogen from stubble burning release in air (t N), calculated with the amount of "fixed" dry residue oxidized and the fraction of nitrogen from the dry matter of residues. The fraction of nitrogen has been calculated considering raw protein content from residues (dry matter fraction) divided by 6.25.
- N-N₂O from stubble burning (t N-N₂O), calculated with the amount of nitrogen from stubble burning release in air and the default emissions factor equal to 0.07 g CH₄ kg⁻¹ dry matter burnt (IPCC, 2006). Data related to the raw protein content from residues (dry matter fraction) is available for each type of cereal. N₂O emissions from field burning of agriculture residues (0.010 kt N₂O in 2024) are estimated by multiplying the N-N₂O value (0.006 kt N) by the ratio of molecular weights (44/28).

In Table 5.56 the parameters for the estimation of N₂O emissions from field burning of agriculture residues are shown.

Table 5.56 Parameters used for the estimation of N₂O emissions from agriculture residues in 2024

Crops	Amount of "fixed" dry residues burnt (t 1000 dry matter)	Raw protein content from residues (dry matter fraction)	Fraction of nitrogen from the dry matter of residues	Amount of nitrogen from stubble burning (t 1000 N)	N-N ₂ O from stubble burning (t N-N ₂ O)
Wheat	120	0.030	0.005	0.517	4.80
Rye	0	0.036	0.006	0.002	0.01
Barley	18	0.037	0.006	0.097	0.73
Oats	4	0.040	0.006	0.025	0.17
Rice	5	0.041	0.007	0.025	0.17
Maize	0	0.000	0.007	0.000	0.00
Sorghum	7	0.037	0.006	0.035	0.26
Total	154			0.700	6.15

5.6.3 Uncertainty and time-series consistency

Uncertainties for CH₄ and N₂O emissions from field burning of agriculture residues are estimated to be 58.3% as a result of 30% and 50% for activity data and emission factor, respectively.

In 2024, emissions from field burning of agriculture residues were 0.37 kt CH₄ emissions and 0.010 kt N₂O emissions (see Table 5.57). Variation in emissions trend is related to cereal production trends. In the period 1998-2003, the biomass available from wheat and barley decreased compared to the first half of the ninety years due to the sharp drop in production because of unfavorable weather conditions.

Table 5.57 CH₄ and N₂O emission trends from field burning of agriculture residues (kt)

Year	CH ₄ (kt)	N ₂ O (kt)
1990	0.543	0.014
1995	0.530	0.014
2000	0.530	0.014
2005	0.618	0.016
2010	0.462	0.012
2015	0.449	0.012

Year	CH ₄ (kt)	N ₂ O (kt)
2020	0.414	0.011
2021	0.432	0.011
2022	0.399	0.010
2023	0.418	0.011
2024	0.373	0.010

5.6.4 Source-specific QA/QC and verification

Activity data of this category were calculated based on various parameters, and in particular the fraction of carbon and nitrogen of dry matter of residues, whose values are differentiated by crops. IPCC emission factors used (IPCC, 2006) are the ratios for carbon compounds (i.e. C-CH₄), that are mass of carbon compound released (in units of C) relative to mass of total carbon released from burning (in units of C); those for the nitrogen compounds (i.e. N-N₂O) are expressed as the ratios of mass of nitrogen compounds relative to the total mass of nitrogen released from the fuel (IPCC, 2006).

In response to the 2007 review process (UNFCCC, several years) and to verify the national assumption, which considered that 10% of the cultivated surface (cereals) is burned in Italy, a specific elaboration of data has been carried out by ISTAT, in the framework of FSS in 2003. The information, provided by ISTAT, related to the regional practices of field burning (cereals) has confirmed the abovementioned assumption (ISTAT, 2007[c]).

5.6.5 Source-specific recalculations

The modification of rice harvested yield for the year 2023 determined a recalculation of CH₄ emissions from burning of crop residues of 0.02 t CH₄ (0.006% of 2025 submission) and 0.001 t N₂O (0.006% of 2025 submission) for the year 2023.

5.6.6 Source-specific planned improvements

No specific improvements are planned.

5.7 Liming (3G)

5.7.1 Source category description

CO₂ emissions from the application of carbonate containing lime and dolomite to agricultural soils have been estimated. CO₂ emissions from application of carbonate containing lime and dolomite are estimated separately. In 2024, CO₂ emissions from liming were 3.70 kt, which represents 1.2% of CO₂ emissions of the agriculture sector (0.3% in 1990) and 0.0017% of national CO₂ emissions (0.0003% in 1990). CO₂ emissions from liming have not been identified as a key source.

5.7.2 Methodological issues

Tier 1 approach, assuming that the total amount of carbonate containing lime and dolomite is applied annually to soil, has been followed. The 2006 IPCC Guidelines equation 11.12 has been used to estimate CO₂ emissions. National statistics report an aggregate annual amount of lime and dolomite, without disaggregation between calcic limestone and dolomite (ISTAT, several years [i]; ISTAT, several years [f]). Data on the disaggregation between limestone and dolomite used in agriculture are provided by the largest lime producer in the country (UNICALCE, 2016). These values are equal to 55% and 45%, respectively.

Therefore, the average emission factor weighed is equal to 0.1245 t C/t limestone-dolomite ($=0.12 \cdot 0.55 + 0.13 \cdot 0.45$). Data on agricultural lime applications have been estimated for the period 1990-1997, since these data have not been made available for that period. Data were estimated based on the ratio of the amount of limestone or dolomite applied for the year 1998 and the area planted to crops, woody and permanent forage.

5.7.3 Uncertainty and time-series consistency

Uncertainty for CO₂ emissions from additions of carbonate limes to soils has been estimated to be 22.4%, as combination of 10% and 20% for activity data and emission factors, respectively. In 2024, CO₂ emissions from liming (3.70 kt CO₂) were almost three times the figure of 1990 (1.36 kt CO₂). An increasing trend is observed from 2002, both for limestone and dolomite application, as resulting from the official statistics published by the National Institute of Statistics (ISTAT). In Table 5.58 activity data, emission factors and CO₂ emission trend from liming are shown.

Table 5.58 CO₂ emissions from lime application

Year	Amount of limestone and dolomite (t)	EF (t C (t limestone and dolomite) ⁻¹)	C emissions (kt)	CO ₂ emissions (kt)
1990	2,969	0.1245	0.3696	1.36
1995	3,045	0.1245	0.3791	1.39
2000	4,050	0.1245	0.5042	1.85
2005	31,451	0.1245	3.9156	14.36
2010	40,115	0.1245	4.9943	18.31
2015	29,583	0.1245	3.6831	13.50
2020	21,860	0.1245	2.7216	9.98
2021	56,067	0.1245	6.9803	25.59
2022	9,250	0.1245	1.1516	4.22
2023	11,385	0.1245	1.4174	5.20
2024	8,100	0.1245	1.0085	3.70

5.7.4 Source-specific QA/QC and verification

Systematic quality control activities have been carried out in order to ensure completeness and consistency in time series and correctness in the estimation of emissions.

5.7.5 Source-specific recalculations

No specific recalculations are observed.

5.7.6 Source-specific planned improvements

No specific improvements are planned.

5.8 Urea application (3H)

5.8.1 Source category description

CO₂ emissions from application of urea to agricultural soils have been estimated. In 2024, CO₂ emissions from urea application were 420.1 kt, which represents 96.0% of CO₂ emissions of the agriculture sector (91.2% in 1990) and 0.14% of national CO₂ emissions (0.11% in 1990). CO₂ emissions from urea application have not been identified as a key source.

5.8.2 Methodological issues

Tier 1 approach, assuming that the total amount of urea is applied annually to soil, has been followed; an overall emission factor of $0.20 \text{ t C (t urea)}^{-1}$ has been used to estimate CO₂ emissions. The 2006 IPCC Guidelines equation 11.13 has been used to estimate CO₂ emissions. The source of the activity data is national statistics (ISTAT, several years [i]).

5.8.3 Uncertainty and time-series consistency

Uncertainty for CO₂ emissions from urea application to soils has been estimated to be 22.4%, as combination of 10% and 20% for activity data and emission factor, respectively. In 2024, CO₂ emissions from urea application were 9.6% (420.1 kt CO₂) lower than in 1990 (464.8 kt CO₂). In Table 5.59 activity data, emission factor and CO₂ emission trend from urea application are shown. A strong decrease is observed in the years from 2009 to 2011 due to the economic crisis in particular for urea applied to soils. In 2012, a recovery from the sharp decline was recorded as result from the official statistics provided by the National Institute of Statistics (ISTAT). See also the explanations given in the agricultural soils chapter on trends in synthetic nitrogen fertilizer data.

Table 5.59 CO₂ emissions from urea application

Year	Amount of urea (t)	EF (t C (t of urea) ⁻¹)	C emissions (kt)	CO ₂ emissions (kt)
1990	633,873	0.20	126.8	464.8
1995	698,251	0.20	139.7	512.1
2000	716,412	0.20	143.3	525.4
2005	691,255	0.20	138.3	506.9
2010	456,951	0.20	91.4	335.1
2015	579,444	0.20	115.9	424.9
2020	643,562	0.20	128.7	471.9
2021	563,865	0.20	112.8	413.5
2022	297,652	0.20	59.5	218.3
2023	578,708	0.20	115.7	424.4
2024	572,801	0.20	114.6	420.1

5.8.4 Source-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the estimation of emissions. Activity data are the same used in agriculture soils (3D) category.

5.8.5 Source-specific recalculations

No specific recalculations are observed.

5.8.6 Source-specific planned improvements

No specific improvements are planned.

5.9 Other carbon-containing fertilizers (3I)

5.9.1 Source category description

CO₂ emissions from application of Calcium Ammonium Nitrate (CAN) to agricultural soils have been estimated. In 2024, CO₂ emissions from CAN application were 14.3 kt, which represents 2.9% of CO₂ emissions of the agriculture sector (8.6% in 1990) and 0.004% of national CO₂ emissions (0.010% in 1990). CO₂ emissions from CAN application have not been identified as a key source.

5.9.2 Methodological issues

Tier 1 approach, assuming that the total amount of CAN is applied annually to soil, has been followed. Based on the data provided by *Assofertilizzanti* (personal communication) concerning the annual estimates of ammonium nitrate and CAN distributed over the country from 2011 to 2019, an annual ratio of CAN to nitrate was calculated. An overall average of these ratios was calculated for the period 2011-2019. This value was multiplied by the total amount of ammonium nitrate (<28% and >28%) distributed annually and provided by ISTAT since 1990. The carbonate content was estimated by multiplying the previously estimated series by 23%, which represents the average carbonate content in CAN (77% is the share of ammonium nitrate). An overall emission factor of 0.125 t C (t carbonates)⁻¹ has been used to estimate CO₂ emissions. The 2006 IPCC Guidelines equation 11.12 has been used to estimate CO₂ emissions. The source of the activity data is national statistics (ISTAT, several years [i]).

5.9.3 Uncertainty and time-series consistency

Uncertainty for CO₂ emissions from CAN application to soils has been estimated to be 22.4%, as combination of 10% and 20% for activity data and emission factor, respectively. In 2024, CO₂ emissions from CAN application were 67.3% (14.3 kt CO₂) lower than in 1990 (43.7 kt CO₂). In Table 5.60 activity data, emission factor and CO₂ emission trend from CAN application are shown. See the explanations given in the agricultural soils chapter on trends in synthetic nitrogen fertilizer data.

Table 5.60 CO₂ emissions from CAN application

Year	Amount of CAN (t)	Amount of carbonates content (t)	EF (t C (t of carbonates) ⁻¹)	C emissions (kt)	CO ₂ emissions (kt)
1990	416,907	95,293	0.125	11.9	43.7
1995	515,751	117,886	0.125	14.7	54.0
2000	416,818	95,273	0.125	11.9	43.7
2005	405,351	92,652	0.125	11.6	42.5
2010	263,930	60,327	0.125	7.5	27.6
2015	189,628	43,344	0.125	5.4	19.9
2020	205,804	47,041	0.125	5.9	21.6
2021	226,693	51,816	0.125	6.5	23.7
2022	129,105	29,510	0.125	3.7	13.5
2023	121,201	27,703	0.125	3.5	12.7
2024	136,413	31,180	0.125	3.9	14.3

5.9.4 Source-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the estimation of emissions. Activity data is the same used in the agriculture soils (3D) category. As recommended during the 2020 ESD review, CO₂ emissions from CAN application to soils have been estimated and reported in category 3I Other carbon-containing fertilizers.

5.9.5 Source-specific recalculations

The amount of CAN applied in the years 2020-2023 was updated based on data provided by *Assofertilizzanti*; this modification has determined the minor recalculation of CO₂ emissions reported in

Table 5.61 expressed as difference between the present submission and submission 2025, and this difference as percentage of 2025 submission.

Table 5.61 Recalculation of reported CO₂ emissions from application of CAN

	2020	2021	2022	2023
CO₂ emissions from CAN				
Recalculation [t CO ₂]	0.09	1.58	1.19	0.50
% recalculation	0.41%	7.13%	9.63%	4.12%

5.9.6 Source-specific planned improvements

No specific improvements are planned.

6 LAND USE, LAND USE CHANGE AND FORESTRY

6.1 Sector overview

GHG emissions and CO₂ removals occur because of changes in land use and management activities as well as because of forestry activities and disturbances. The sector is responsible for 62.6 Mt of CO₂ eq. net removal from the atmosphere in 2024.

Methods applied to estimate the GHG emissions and removals from the sector are derived from the 2006 IPCC Guidelines for National Greenhouse Gas Inventories (2006 IPCC Guidelines) and from 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories (2019 Refinement) for HWP estimation; similarly, all factors for which national data are not available have been taken from the 2006 IPCC Guidelines and from 2019 Refinement. For category 4A (Forest Land) estimates were supplied by a growth model, applied to national forest inventory (NFI) data, consistently with the TACCC principles implemented by IPCC methods, and with mostly country specific factors and parameters.

CO₂ emissions from forest fires are included in the net carbon stock changes reported in CRT Table 4A, instead of in CRT Table 4(IV), since C losses by forest fires are included in the carbon stock changes estimation by the For-est model (see annex 11).

Greenhouse gas removals and emissions in the main categories of the LULUCF sector in 2024 are shown in Figure 6.1.




Figure 6.1 Greenhouse gas removals and emissions in LULUCF sector in 2024 [kt CO₂ eq.] by LULUCF sector categories

In Table 6.1 emissions and removals time series is reported.

Table 6.1 Trend in greenhouse gas net emissions/removals (kt) from the LULUCF sector in the period 1990-2024

GHG Source and Sink Categories	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂	-14,267	-35,549	-30,792	-44,531	-47,514	-47,813	-44,280	-45,299	-45,609	-58,218	-64,610
A. Forest Land	-20,805	-34,381	-30,158	-39,005	-40,235	-42,297	-40,135	-42,324	-43,926	-52,912	-57,888
B. Cropland	1,866	1,138	796	-602	184	1,585	2,999	1,326	1,345	1,240	77
C. Grassland	4,324	-2,079	-1,743	-5,725	-8,487	-8,394	-7,310	-4,564	-3,559	-5,955	-5,846
D. Wetlands	NE,NO	5	8	8	130	130	32	NE,NO	NE,NO	NE,NO	NE,NO
E. Settlements	738	474	759	1,297	1,037	1,075	933	1,050	1,047	1,047	1,049
F. Other Land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
G. HWP	-389	-707	-454	-503	-142	88	-799	-787	-516	-1,637	-2,002
H. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
CH₄	29.55	9.69	17.78	9.60	10.51	8.53	9.76	21.22	16.91	12.54	9.62
A. Forest Land	12.13	2.47	6.11	2.51	2.14	2.94	4.30	11.48	7.63	5.90	3.15
B. Cropland	3.51	3.43	3.45	3.44	3.42	3.45	3.38	3.46	3.42	3.38	3.41
C. Grassland	13.90	3.79	8.21	3.65	4.95	2.15	2.08	6.28	5.86	3.26	3.05
D. Wetlands	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
E. Settlements	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO
F. Other Land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
G. HWP	-	-	-	-	-	-	-	-	-	-	-
H. Other	-	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO	NE,NO
N₂O	1.85	0.96	1.18	0.77	0.82	0.49	0.85	1.55	1.33	1.14	1.03
A. Forest Land	0.67	0.14	0.34	0.14	0.12	0.16	0.24	0.64	0.42	0.33	0.17
B. Cropland	0.27	0.43	0.17	0.16	0.16	0.00	0.26	0.27	0.27	0.26	0.27
C. Grassland	0.80	0.20	0.44	0.19	0.26	0.11	0.13	0.43	0.42	0.34	0.38
D. Wetlands	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
E. Settlements	0.11	0.20	0.23	0.28	0.28	0.21	0.22	0.22	0.21	0.21	0.21
F. Other Land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
G. HWP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
H. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
LULUCF (kt CO₂ equivalent)	-12,949	-35,023	-29,981	-44,057	-47,002	-47,445	-43,782	-44,294	-44,784	-57,565	-64,068

The outcomes of the key category analysis for 2024, for both level and/or trend assessment with IPCC Approach 1 and Approach 2, are listed in Table 6.2.

Table 6.2 Key* categories identified in the LULUCF sector

<i>gas</i>	<i>Categories</i>	<i>2024</i>
4.A.1 CO ₂	Forest land remaining forest land – Living biomass	key (L, T)
4.A.1 CO ₂	Forest Land remaining Forest Land - DOM (deadwood+litter)	key (T)
4.A.2 CO ₂	Land Converted to Forest Land -Living biomass	key (L, T)
4.A.2 CO ₂	Land Converted to Forest Land - DOM (deadwood+litter)	key (L)
4.A.2 CO ₂	Land Converted to Forest Land - soils	key (L, T)
4.B.1 CO ₂	Cropland Remaining Cropland - mineral soils	key (L, T)
4(II) CO ₂	Cropland Remaining Cropland - organic soils	key (L2, T2)
4.B.2 CO ₂	Land Converted to Cropland - mineral soils CO2	key (L2)
4.C.1 CO ₂	Grassland Remaining Grassland - living biomass	key (L, T)
4.C.2 CO ₂	Land Converted to Grassland - mineral soils	key (L, T)
4.E.2 CO ₂	Land converted to Settlements	key (L, T)
4.G CO ₂	Harvest Wood Products	key (L, T)

* L = key category in level assessment under both Approach 1 and 2

T = key category in trend assessment under both Approach 1 and 2

L1, T1 = key category in level or trend assessment under Approach 1 only

L2, T2 = key category in level or trend assessment under Approach 2 only

Background data for the land representation originates from the NFIs²⁶ (1985, 2005, 2015 and preliminary data for 2025) and from the National Land-Use Inventory IUTI referring to years 1990, 2000 and 2008. Additional data on non-forest categories were collected for the year 2018, through all the phases in the framework of the III NFI that was carried out on an IUTI's subgrid (i.e., 301,300 points, across the entire country territory).

Due to the technical characteristics of the IUTI assessment (i.e., classification of orthophotos), it was not possible to clearly distinguish among some subcategories included in *cropland* and *grassland* categories (e.g., annual pastures vs grazing land), and between them (e.g., annual crops and grazing land). Therefore, although the total aggregated area of the two categories *cropland* and *grassland* together is derived from the IUTI data, the area of each of their subcategories is disaggregated using as proxies the national statistics (ISTAT, [b], [c]) on annual crops, perennial woody crops, grazing land, and grassland. The NFI data have a higher hierarchical order than that of IUTI, so that differences among the two datasets have been reconciled by adjusting²⁷ the grassland category (subcategory natural grassland). National statistics (ISTAT) have been used to assess the time series for the period 1971-1989, in relation to different land-use categories (i.e., annual statistics on forest land, annual crops and perennial woody crops, grazing lands, forage crops, permanent pastures, natural grassland and lands once used for agricultural purposes (set-aside) since 1971). National statistics do not include data for settlements and wetlands areas; for these land use categories, time series for the period 1971-1989 have been extrapolated, based on the IUTI 1990 assessment, and following the classification hierarchy.

Annual figures for areas in transition between different land uses have been derived by applying a rule-based method, informed by expert judgement, based on known patterns of land-use changes in Italy, while ensuring that the total national area remains constant.

The rules applied are the following:

²⁶ National Forest Service, Ministry of Agricultural, Food and Forestry Policies (MIPAAF), Forest Monitoring and Planning Research Unit (CRA-MPF)

²⁷ Where the NFI area of forest land was larger than that of IUTI an equivalent portion of grassland area, as classified by IUTI, was reclassified as forest land while if the NFI area was smaller an equivalent area of forest land in IUTI was reclassified as grassland. Such adjustments were implemented at regional level.

- when the forest land area increases, an equivalent area is transferred from grassland;
- when the cropland area increases, an equivalent area is transferred from grassland;
- when the grassland area increases, an equivalent area is transferred from cropland;
- when the forest land decreases, an equivalent area is transferred to settlements; indeed, in Italy land-use changes from forest to other uses are allowed in very limited circumstances (railways, highways constructions or other public utility projects) and only upon formal authorization, as stated in art. 4.2 of the Law Decree n. 227 of 2001. Further, land-use changes of burnt forest areas are forbidden by national legislation (Law Decree 21 November 2000, n. 353, art.10.1);
- when the settlements area increases more than the deforested area, an equivalent area is transferred from grassland, and if the grassland decreases are not larger enough, the remaining portion is transferred from cropland and, where needed, from other land (see tables 6.43, 6.44).

Based on the land use and land-use change data derived from NFIs and IUTIs classifications after the application of the rule-based approach for land representation, a time series of land-use matrices, one for each year of the period 1990–2024, have been compiled. Furthermore, land-use changes have been derived, by land-use change matrices, smoothing their area over a 5-year period, harmonizing the whole time series (i.e., the 2015–2010 difference in area for each subdivision is divided by five, and the resulting value is added, year by year, to the previous year area to deduce the current area). The smoothing period affects the assessment of the area, depending on the amount of the difference between the two reference years (i.e., 2015–2010), as well as on the number of years included in the smoothing period. The smoothing process also affects the annual land-use change data.

In addition, it should be noted that the smoothing process is applied at the most disaggregated level (i.e., annual and woody crops within the cropland category, and grazing land and shrublands within the grassland category) and has been implemented from 1971 through the most recent reporting year (2024).

In Tables 6.3a and 6.3b land use data, with and without smoothing, are provided.

Table 6.3a Land use areas before smoothing

<i>kha</i>	FL	CL	GL	WL	SL	OL	Total
1990	7,590	10,841	8,891	510	1,644	658	30,134
1991	7,668	10,857	8,768	511	1,672	658	30,134
1992	7,746	10,874	8,646	511	1,699	658	30,134
1993	7,824	10,891	8,523	511	1,727	658	30,134
1994	7,902	10,908	8,400	512	1,754	658	30,134
1995	7,980	10,924	8,278	512	1,782	657	30,134
1996	8,058	10,929	8,167	513	1,810	657	30,134
1997	8,136	10,919	8,071	513	1,837	657	30,134
1998	8,213	10,805	8,079	514	1,865	657	30,134
1999	8,291	10,697	8,082	514	1,892	657	30,134
2000	8,369	10,487	8,186	515	1,920	656	30,134
2001	8,447	10,351	8,216	515	1,948	656	30,134
2002	8,525	10,293	8,168	516	1,975	656	30,134
2003	8,603	10,031	8,324	516	2,003	656	30,134
2004	8,681	10,059	8,191	517	2,030	656	30,134
2005	8,759	9,879	8,265	517	2,058	656	30,134
2006	8,805	9,534	8,536	518	2,086	655	30,134
2007	8,850	9,593	8,404	518	2,113	655	30,134
2008	8,896	9,551	8,372	519	2,141	655	30,134
2009	8,941	9,069	8,787	526	2,156	655	30,134
2010	8,986	9,159	8,630	534	2,170	655	30,134
2011	9,032	8,947	8,773	541	2,185	655	30,134
2012	9,077	8,641	9,012	549	2,200	655	30,134
2013	9,123	8,977	8,609	556	2,214	655	30,134
2014	9,168	8,952	8,566	564	2,229	655	30,134
2015	9,214	8,845	8,605	571	2,244	655	30,134
2016	9,398	8,929	8,314	579	2,258	655	30,134
2017	9,583	8,982	8,054	586	2,273	655	30,134
2018	9,768	8,990	7,847	586	2,288	655	30,134
2019	9,953	9,001	7,636	586	2,302	655	30,134
2020	10,138	8,987	7,451	586	2,317	655	30,134
2021	10,374	8,976	7,210	586	2,332	655	30,134
2022	10,611	9,048	6,887	586	2,346	655	30,134
2023	10,848	9,116	6,567	586	2,361	655	30,134
2024	11,085	8,925	6,507	586	2,376	655	30,134

Table 6.3b Land use areas after smoothing

<i>kha</i>	FL	CL	GL	WL	SL	OL	Total
1990	7,590	10,841	8,891	510	1,644	658	30,134
1991	7,668	10,857	8,768	511	1,672	658	30,134
1992	7,746	10,874	8,646	511	1,699	658	30,134
1993	7,824	10,891	8,523	511	1,727	658	30,134
1994	7,902	10,908	8,400	512	1,754	658	30,134
1995	7,980	10,924	8,278	512	1,782	657	30,134
1996	8,058	10,837	8,259	513	1,810	657	30,134
1997	8,136	10,749	8,241	513	1,837	657	30,134
1998	8,213	10,662	8,223	514	1,865	657	30,134
1999	8,291	10,574	8,204	514	1,892	657	30,134
2000	8,369	10,487	8,186	515	1,920	656	30,134
2001	8,447	10,365	8,202	515	1,948	656	30,134
2002	8,525	10,244	8,218	516	1,975	656	30,134
2003	8,603	10,122	8,233	516	2,003	656	30,134
2004	8,681	10,000	8,249	517	2,030	656	30,134
2005	8,759	9,879	8,265	517	2,058	656	30,134
2006	8,805	9,769	8,301	518	2,086	655	30,134
2007	8,850	9,660	8,337	518	2,113	655	30,134
2008	8,896	9,551	8,372	519	2,141	655	30,134
2009	8,941	9,355	8,501	526	2,156	655	30,134
2010	8,986	9,159	8,630	534	2,170	655	30,134
2011	9,032	9,096	8,625	541	2,185	655	30,134
2012	9,077	9,033	8,620	549	2,200	655	30,134
2013	9,123	8,971	8,615	556	2,214	655	30,134
2014	9,168	8,908	8,610	564	2,229	655	30,134
2015	9,214	8,845	8,605	571	2,244	655	30,134
2016	9,398	8,874	8,374	574	2,258	655	30,134
2017	9,583	8,902	8,143	577	2,273	655	30,134
2018	9,768	8,930	7,912	580	2,288	655	30,134
2019	9,953	8,959	7,681	583	2,302	655	30,134
2020	10,138	8,987	7,451	586	2,317	655	30,134
2021	10,374	8,972	7,215	586	2,332	655	30,134
2022	10,611	8,956	6,979	586	2,346	655	30,134
2023	10,848	8,941	6,743	586	2,361	655	30,134
2024	11,085	8,925	6,507	586	2,376	655	30,134

Italy uses the IPCC default land-use transition period of 20 years for each land-use change category. Consequently, to determine the area of lands converted to other land-use categories for the inventory years 1990–2024, land-use change matrices have also been prepared for the period 1971–1989.

The relevant equations of 2006 IPCC Guidelines (vol. 4, chapter 2, eq. 2.15, 2.16, 2.24, 2.25) have been applied; once a land has converted to a land-use category, the annual changes in carbon stocks in mineral soils have been reported for 20 years subsequent the conversion.

In the following Table 6.4, the land-use matrices are reported in two columns, for some of the reporting years. The annual matrices starting from the 1989-1990 period to 2023-2024 are in the left column, while the 20-year matrices starting from the 1971-1990 period to the 2005-2024 are in the right column. Annual matrices for the years 1990-2024 are reported in CRT Tables 4.1.

Table 6.4 Land use change matrices for the years 1990-1995-2000-2010-2020-2024 [kha]

		1990						total 1989
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1989	Forest	7,511				0.72		7,512
	Grassland	78.68	8,891	0.00	0.00	1.73	-	8,971
	Cropland		0	10,841	0.00	25	-	10,866
	Wetland				510			510
	Settlements					1,616		1,616
	Other Land					0.00	658	658
	total 1990	7,590	8,891	10,841	510	1,644	658	30,134
	Land converted to:	78.7	0.0	0.0	0.0	27.6	0.0	

		1995						total 1994
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1994	Forest	7,901				0.72		7,902
	Grassland	78.68	8,278	16.77	0.47	26.70	-	8,400
	Cropland		0	10,908	0.00	0	-	10,908
	Wetland				512			512
	Settlements					1,754		1,754
	Other Land					0.18	657	658
	total 1995	7,980	8,278	10,924	512	1,782	657	30,134
	Land converted to:	78.7	0.0	16.8	0.5	27.6	0.0	

		2000						total 1999
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1999	Forest	8,291				0.72		8,291
	Grassland	78.68	8,126	0	0.00	0.00	-	8,204
	Cropland		60.32	10,487	0.47	26.70	-	10,574
	Wetland				514			514
	Settlements					1,892		1,892
	Other Land					0.18	656	657
	total 2000	8,369	8,186	10,487	515	1,920	656	30,134
	Land converted to:	78.7	60.3	0.0	0.5	27.6	0.0	

		2005						total 2004
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2004	Forest	8,678				3.69		8,681
	Grassland	81.65	8,168	-	-	-	-	8,249
	Cropland		97.46	9,879	0.47	23.73	-	10,000
	Wetland				517			517
	Settlements					2,030		2,030
	Other Land					0.18	656	656
	total 2005	8,759	8,265	9,879	517	2,058	656	30,134
	Land converted to:	81.7	97.5	0.0	0.5	27.6	0.0	

		2010						total 2009
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2009	Forest	8,937				3.69		8,941
	Grassland	49.13	8,452	-	-	-	-	8,501
	Cropland		177.88	9,159	7.52	10.98	-	9,355
	Wetland				526			526
	Settlements					2,156		2,156
	Other Land					0.00	655	655
	total 2010	8,986	8,630	9,159	534	2,170	655	30,134
	Land converted to:	49.1	177.9	0.0	7.5	14.7	0.0	

		2015						total 2014
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2014	Forest	9,164				3.69		9,168
	Grassland	49.13	8,561	-	-	-	-	8,610
	Cropland		44	8,845	7.52	10.98	0.00	8,908
	Wetland				564			564
	Settlements					2,229		2,229
	Other Land					0.00	655	655
	total 2015	9,214	8,605	8,845	571	2,244	655	30,134
	Land converted to:	49.1	44.1	0.0	7.5	14.7	0.0	

		2020						total 2019
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2019	Forest	9,949				3.69		9,953
	Grassland	188.51	7,451	28.31	3.01	10.98	-	7,681
	Cropland		0	8,959	-	-	-	8,959
	Wetland				583			583
	Settlements					2,302		2,302
	Other Land					0.00	655	655
	total 2020	10,138	7,451	8,987	586	2,317	655	30,134
	Land converted to:	188.5	0.0	28.3	3.0	14.7	0.0	

		1990						total 1971
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1971	Forest	6,901				14.4		6,916
	Grassland	689	8,566	136	0.00	33	0	9,423
	Cropland		325	10,704	0.00	174	0	11,203
	Wetland				510			510
	Settlements					1,423		1,423
	Other Land					0.00	658	658
	total 1990	7,589.8	8,890.9	10,840.5	510.1	1,644.0	658.3	30,134
	Land converted to:	688.5	325.0	136.1	0.0	220.8	0.0	

		1995						total 1976
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1976	Forest	7,056				14.4		7,071
	Grassland	923	7,985	220	2.37	166	0	9,297
	Cropland		292	10,704	0.00	150	0	11,147
	Wetland				510			510
	Settlements					1,451		1,451
	Other Land					0.90	657	658
	total 1995	7,980	8,278	10,924	512	1,782	657	30,134
	Land converted to:	923	292	220	2	331	0	

		2000						total 1981
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1981	Forest	7,117				14.4		7,131
	Grassland	1,252	7,592	84	2.37	142	0	9,073
	Cropland		594	10,403	2.37	283	0	11,283
	Wetland				510			510
	Settlements					1,478		1,478
	Other Land					1.80	656	658
	total 2000	8,369	8,186	10,487	515	1,920	656	30,134
	Land converted to:	1,252	594	84	5	442	0	

		2005						total 1986
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1986	Forest	7,183				17.4		7,200
	Grassland	1,577	7,488	84	2.37	142	0	9,293
	Cropland		777	9,795	4.74	390	0	10,966
	Wetland				510			510
	Settlements					1,506		1,506
	Other Land					2.71	656	658
	total 2005	8,759	8,265	9,879	517	2,058	656	30,134
	Land converted to:	1,577	777	84	7	552	0	

		2010						total 1991
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1991	Forest	7,558				32.3		7,590
	Grassland	1,429	7,242	84	2.37	134	0	8,891
	Cropland		1,387	9,075	21.19	357	0	10,841
	Wetland				510			510
	Settlements					1,644		1,644
	Other Land					3.25	655	658
	total 2010	8,986	8,630	9,159	534	2,170	655	30,134
	Land converted to:	1,429	1,387	84	24	526	0	

		2015						total 1996
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
1996	Forest	7,932				47.1		7,980
	Grassland	1,281	6,997	0	0.00	0	0	8,278
	Cropland		1,608	8,845	58.79	412	0	10,924
	Wetland				512			512
	Settlements					1,782		1,782
	Other Land					2.35	655	657
	total 2015	9,214	8,605	8,845	571	2,244	655	30,134
	Land converted to:	1,281	1,608	0	59	462	0	

		2020						total 2001
		Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2001	Forest	8,307				62.0		8,369
	Grassland	1,830	6,144	142	15.04	55	0	8,186
	Cropland		1,306	8,845	56.42	279	0	10,487
	Wetland				515			515
	Settlements					1,920		1,920
	Other Land					1.44	655	656
	total 2020	10,138	7,451	8,987	586	2,317	655	30,134
	Land converted to:	1,830	1,306	142	71	397	0	

	2024						total 2022
	Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2023	Forest	10,844			3.69		10,848
	Grassland	240.48	6,502	0.00	0.00	-	6,743
	Cropland		4.46	8,925	-	10.98	8,941
	Wetland				586		586
	Settlements				2,361		2,361
	Other Land				0.00	655	655
total 2024		11,085	6,507	8,925	586	2,376	30,134
Land converted to:		240.5	4.5	0.0	0.0	14.7	0.0

20 years matrix	2024						total 2005
	Forest	Grassland	Cropland	Wetlands	Settlements	Other Land	
2005	Forest	8,607			73.9		8,681
	Grassland	2,477	5,560	142	15.04	55	8,249
	Cropland		946	8,784	54.52	216	10,000
	Wetland				517		517
	Settlements					2,030	2,030
	Other Land				0.72	655	656
Total 2024		11,085	6,507	8,925	586	2,376	30,134
Land converted to:		2,477	946	142	70	345	0

6.2 Forest Land (4A)

6.2.1 Description

Under this category, CO₂ emissions and removals from living biomass and dead organic matter (DOM), in forest land remaining forest land and from living biomass, DOM and soil organic matter (SOM) in land converted to forest land have been reported.

Forest land removals share 86.7% of total CO₂ eq. LULUCF net removals in 2024. CO₂ removals are mainly due to the living biomass, i.e., 93.9%, while DOM and SOM contribute only to 3.2% and 2.9%. In table 6.5, the key categories in the forest land categories are reported.

Table 6.5 Key* categories identified in the forest land category

gas	Categories	2024
4.A.1 CO ₂	Forest land remaining forest land – Living biomass	key (L, T)
4.A.1 CO ₂	Forest Land remaining Forest Land - DOM (deadwood+litter)	key (T)
4.A.2 CO ₂	Land Converted to Forest Land -Living biomass	key (L, T)
4.A.2 CO ₂	Land Converted to Forest Land - DOM (deadwood+litter)	key (L)
4.A.2 CO ₂	Land Converted to Forest Land - soils	key (L, T)

* L = key category in level assessment under both Approach 1 and 2

T = key category in trend assessment under both Approach 1 and 2

L1, T1 = key category in level or trend assessment under Approach 1 only

L2, T2 = key category in level or trend assessment under Approach 2 only

Management practices in the Italian forests are guided by the Legislative Decree n. 227 of 18 May 2001, although the design and implementation of specific guidelines have been carried out at regional level since, according to the Italian Constitutional Law, the forest management is a regional competence. The Legislative Decree n. 227/2001 provides general guidance on forest management:

- protect forest ecosystem functions, genetic resources, water basins and landscape;
- avoid conversion of forest land to other land uses, and where occurring apply compensative reforestations with endemic species;
- avoid conversion from forest stands to coppices;
- avoid clear-cut;
- conserve biodiversity, including true conservation of old trees and dead wood.

6.2.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

The forest definition adopted under the Convention is the same used for the NFIs²⁸. The forest definition includes areas where trees 1) fulfil the required threshold or 2) "have the potential to reach *in situ*" such required thresholds. For instance, *abandoned land with regenerating forest* is classified as forest in consideration of the potential that vegetation has to reach the forest thresholds, while those that are not

²⁸ The detailed definition is reported on the website of the NFIs http://www.sian.it/inventarioforestale/jsp/q_features.jsp (forest definition: <http://www.sian.it/inventarioforestale/jsp/linkmetodo/definizionilink1.jsp>)

expected to evolve into forests do not and will never meet the forest definition; for this reason, this kind of shrubland is included in the *grassland* category and is defined as other wooded land. The assessment of vegetation potential to meet thresholds is carried out in the field (phase 2 of the NFI), and it is mainly based on the time needed to reach the forest thresholds, which should not exceed 20 years. This means that shrublands that are expected to evolve into forest vegetation within such a time frame are classified as forests.

Forest land area is that of the NFIs. For any forest area growth, it is assumed that new forest land area can only come from grassland.

The Italian Ministry of Agriculture and Forests (MAF) and the Experimental Institute for Forest Management (ISAFa) carried out the National Forest Inventories. The first NFI was based on a regular sampling grid of 3 km by 3 km, (MAF/ISAFa, 1988), the second NFI (INFC2005) used a grid of 1 km by 1 km, so as the third NFI (INFC2015). The fourth NFI (NFI2025) is currently ongoing; its preliminary data (i.e., classification of forest area in 2023) has been used. In addition, the Italian Forest Map (CFI2020), available through the National Information System for Forests and Forest Supply Chains (SINFor²⁹), has been used to assess 2020 area data of "Forest" and of "Other Wooded Land". The last-mentioned data from NFI2025 and CFI2020 affected the interpolation of 2016-2019 and 2021-2022 area data of "Forest" and of "Other Wooded Land", resulting in a consequent recalculation carried out in 2025 submission. The forest area in 2024 has been derived through extrapolation of the abovementioned time series.

6.2.3 Land-use definitions and the classification systems used and their correspondence to the LULUCF categories

The forest definition adopted by Italy in the framework of the Kyoto Protocol has been used. This definition is in line with the definition of the Food and Agriculture Organization of the United Nations; therefore, the following threshold values for tree crown cover, land area and tree height have been applied:

- a minimum area of land of 0.5 hectares;
- a minimum tree crown cover of 10 per cent;
- minimum tree height of 5 meters.

6.2.4 Methodological issues

Forest Land remaining Forest Land

To model C stock changes in forest land Italy uses the *For-est* model together with NFIs data, which include C pools as defined in Table 6.6.

Table 6.6 Carbon pools, ecosystem components in the NFI surveys³⁰

Forest carbon pools	Ordinary survey	Supplementary survey (Third phase)	Thresholds
Aboveground biomass	Biomass of trees with DBH ≥ 4.5 cm (trees-AGB) Number or subjects of regeneration and shrubs	Ratio dry matter to wet & allometric Ratio dry matter to wet	All woody AGB included
Belowground biomass		Ratio root to shoot	σ > 2 mm
Deadwood	Volume of coarse woody debris (CWD)	Basic densities	σ ≥ 9.5 cm
	Volume of stumps	Basic densities	σ ≥ 9.5 cm
	Volume of standing dead trees (STD)	Basic densities	As for living trees
	Fine woody debris: not measured (FWD)	Wet weight per unit area; dry matter to wet ratio	2.5 ≤ σ < 9.5 cm
Litter	not measured	Wet weight per unit area; dry matter to wet ratio	Fine woody debris σ ≤ 2.5 cm, plus all other non-living biomass σ ≤ 2 mm
Soil	not measured	Organic carbon per unit area	all organic carbon for an increment of 30 cm, plus all other biomass and dead mass σ < 2 mm

²⁹ National Information System for Forests and Forest Supply Chains (SINFor): <https://sinfor.sian.it/#/carta>

³⁰ Specific documentation and information on the definitions of the NFI pools (e.g. the diameter threshold for deadwood and how this pool is differentiated from litter, which soil horizons are included in the soil pool and which pool contains the humus layer) are available at the NFI website:

<https://www.inventarioforestale.org/it/node/72> (i.e.,
https://www.inventarioforestale.org/sites/default/files/datiinventario/manuale_fase3%2B_v4_definitiva_REGp.pdf;
https://www.inventarioforestale.org/sites/default/files/datiinventario/pubbl/INFC2015_Guida_per_i_rilievi_in_campo_2016-12.pdf)

The model applies the IPCC classification and definitions of carbon pools, including living biomass (aboveground and belowground), dead organic matter (dead wood and litter), and soil organic matter. Further information on the model is provided in Annex 11, while additional methodological details are available in Federici et al. (2008).

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes from dead organic matter and litter pools has been significantly modified. The litter pool has been assumed to be in equilibrium, applying the IPCC default methodology.

The annual deadwood carbon stock changes have been calculated using a decay model based on the harvest wood product methodology (IPCC 2006, chapter 12, Eq. 12.1), as described in equations 6.1. The deadwood model reflects the impacts of C inflows from harvest residues, mortality and fires on forest deadwood dynamics. The resulting deadwood stock and stock changes are consistent with the measured stocks derived from the Italian NFIs.

Equation 6.1

$$DW_{i+1} = (e^{-k} * DW_i) + \frac{1 - e^{-k}}{k} * DW\_Inflow_i$$

$$DW\_Inflow_i = DW\_mortality + Harvest\_inflow + Fire\_biomass$$

$$\Delta DW_i = DW_{i+1} - DW_i$$

where

i = year

DW_i = deadwood carbon stock at the beginning of year i , kt C

k = first-order decay constant

$DW\_mortality$ = input to the deadwood pool from tree mortality, kt C

$Harvest\_inflow$ = input to the deadwood pool from harvest residues, kt C

$Fire\_biomass$ = input to the deadwood from biomass killed but not fully combusted during fire, kt C.

$DW\_mortality$ has been estimated by dividing the tree mortality by an average national BEF (Table 6.7). The $Harvest\_inflow$ has been estimated by multiplying the harvest residues for the average national wood basic density (Table 6.7) and the carbon ratio 0.47g C/g d.m. (IPCC, 2006). $Fire\_biomass$ has been estimated by applying the complement of a mean national combustion factor to the total carbon stock affected by fire and dividing the result by the BEF, included in Table 6.7. The combustion factor, derived from the For-Fires model, indicates the share of biomass fully burned, while its complement represents the portion affected but not combusted. Dividing by the BEF isolates the fraction of killed biomass attributable to stems and large branches, which is the component that can realistically become deadwood. Biomass gains and losses have been calculated with the model For-est, while harvest residue inputs were derived from the annual harvest volumes, as documented in Annex 11.

In Table 6.7, the abovementioned factors and parameters, used in the estimation of deadwood carbon stock changes, are reported.

Table 6.7 Factors and parameters used to estimate deadwood carbon stock changes

Factor	Value	unit	Source
Mortality per standing biomass	0.0116	fraction of standing biomass per year	2003 IPCC GPGs for LULUCF - Page 3.37, table 3.2.2 Biome: Evergreen Forest
BEF	1.4	ratio of volume	Average of national BEFs reported in Table A11.4, Annex 11
Wood Basic Density	0.523	t m ³	Average of national wood basic densities reported in Table A11.4, Annex 11
Harvest residue	0.05	ratio of harvest	Expert judgment

Factor	Value	unit	Source
C ratio	0.47	g C/g d.m.	IPCC 2006
Complement of combustion factor	0.336250314	ratio of biomass	For-fires model (linked to revised estimate of mean combustion factor)
k	0.159966167	t C ha ⁻¹	Country specific value, estimated from NFIs values

Only a portion of the biomass affected by fire is oxidized and emitted. This portion is assessed based on the mean combustion factor derived from the For-fire model (Annex 12). The remaining fraction is transferred to the dead organic matter pool, as previously described. In Figure 6.2, aboveground biomass losses due to harvest and forest fires, expressed as a percentage of total aboveground carbon stock in forest land, are shown.




Figure 6.2 Losses by harvest and fires in relation to aboveground carbon

CO₂ emissions due to wildfires in forest land remaining forest land are included in CRT Table 4.A.1, carbon stocks change in living biomass - losses. Non-CO₂ gases are estimated separately from the aboveground biomass loss calculated by the *For-est* model; from the aboveground biomass loss, the amount of C oxidized during the fire event is estimated using combustion factors specific to each fire event. CH₄ and N₂O emissions are estimated and reported (see paragraph 6.11.2 and Annex 12). Non-CO₂ emissions from fires have been estimated and reported in CRT Table 4(IV).

Organic soils in forest land remaining forest land do not occur (NO).

CO₂ emissions due to wildfires in land converted to forest land are included in CRT Table 4.A.2, carbon stocks change in living biomass - losses.

Italy has decided not to account for the SOC changes in mineral soils from Forest land remaining Forest land, providing transparent and verifiable information to demonstrate that SOM in mineral soils is not a source.

Carbon stock changes in mineral soils, for Forest land remaining Forest land have been inferred from stock changes estimated in the aboveground biomass through linear regression, i.e., $SOC = f(C_{Aboveground})$; consequently, the carbon stock changes in mineral soils are calculated as:

$$\Delta OC = f(C_{Aboveground})_{time2} - f(C_{Aboveground})_{time1}$$

per forestry use –stands (conifers, broadleaves, mixed stands) and coppices. These equations have been calculated on data collected within the European project BioSoil³¹, for SOM, and a Life+ project FutMon³² (Further Development and Implementation of an EU-level Forest Monitoring System), for the aboveground biomass. SOC stock values in mineral soils were assessed down to 40 cm, standardized at 30 cm, with layer-based sampling (0-10, 10-20, 20-40 cm) on 227 forest plots on a 15x18 km grid. SOC stock values have been estimated in each layer using layer depths, soil carbon concentrations (704 values), bulk densities (543 measured data, 163 estimated data in the field or by means of pedotransfer functions) and volumes of coarse fragments (704 values estimated in the field). BioSoil also assessed OF and OH layers in which organic material is in various states of decomposition (down to humus) and included these in the SOC stock estimations.

In Table 6.8 the regressions calculated to infer SOC stocks [t C ha⁻¹] from the aboveground biomass [t C ha⁻¹] are shown.

Table 6.8 Regressions to estimate the SOC stocks (t C ha⁻¹) in the upper 30 cm as a function of aboveground biomass in the different Italian forest typologies

<i>Inventory typology</i>	<i>Regressions aboveground biomass – SOC (t C ha⁻¹)</i>	<i>R²</i>	<i>Standard error</i>
<i>stands</i>	norway spruce	y = 0.2218x + 73.005	0.0713
	silver fir	y = 0.2218x + 73.005	0.0713
	larches	y = 0.2218x + 73.005	0.0713
	mountain pines	y = 0.2218x + 73.005	0.0713
	mediterranean pines	y = 0.2218x + 73.005	0.0713
	other conifers	y = 0.2218x + 73.005	0.0713
	european beech	y = 0.2502x + 79.115	0.0925
	turkey oak	y = 0.2502x + 79.115	0.0925
	other oaks	y = 0.2502x + 79.115	0.0925
	other broadleaves	y = 0.2502x + 79.115	0.0925
<i>coppices</i>	european beech	y = 0.2683x + 70.208	0.073
	sweet chestnut	y = 0.2683x + 70.208	0.073
	hornbeams	y = 0.2683x + 70.208	0.073
	other oaks	y = 0.2683x + 70.208	0.073
	turkey oak	y = 0.2683x + 70.208	0.073
	evergreen oaks	y = 0.2683x + 70.208	0.073
	other broadleaves	y = 0.2683x + 70.208	0.073
	conifers	y = 0.2218x + 73.005	0.0713
<i>plantations</i>	eucalyptuses coppices	y = 0.2683x + 70.208	0.073
	other broadleaves coppices	y = 0.2683x + 70.208	0.073
	poplars stands	y = 0.2502x + 79.115	0.0925
	other broadleaves stands	y = 0.2502x + 79.115	0.0925
	conifers stands	y = 0.2218x + 73.005	0.0713
<i>protective</i>	rupicolous forest	y = 0.3262x + 68.648	0.1338
	riparian forest	y = 0.3262x + 68.648	0.1338

Different trends in SOC stocks per hectare, for the different forest inventory typologies, have been inferred, as shown in Table 6.9.

³¹ BioSoil project –http://www3.corpoforestale.it/flex/cm/pages/ServeBLOB.php/L/IT/IDPagina/487/UT/systemPrint;http://www.inbo.be/content/page.asp?pid=EN_MON_FSCC_condition_report

³² FutM on: Life+ project for the "Further Development and Implementation of an EU-level Forest Monitoring System"; <http://www.futmon.org;http://www3.corpoforestale.it/flex/cm/pages/ServeAttachment.php/L/IT/D/D.e54313ecaf7ae893e249/P/BLOB%3AID%3D397>

Table 6.9 SOC stocks per hectare in the upper 30 cm, for the different forest inventory typologies

	Inventory typology	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
		SOC stocks (t C ha ⁻¹)										
stands	norway spruce	85.42	84.86	84.33	84.01	83.92	83.87	83.18	83.08	82.96	82.83	82.66
	silver fir	87.17	86.23	85.35	85.11	85.21	85.44	84.71	84.61	84.53	84.43	84.32
	larches	83.77	83.14	82.57	82.41	82.59	82.81	82.33	82.30	82.26	82.21	82.10
	mountain pines	83.81	84.64	85.34	86.39	87.46	88.66	88.38	88.37	88.38	88.39	88.43
	mediterranean pines	83.23	84.88	86.27	87.86	89.05	90.43	90.11	90.00	89.97	89.98	90.14
	other conifers	80.05	80.79	81.39	82.23	83.16	84.18	84.19	84.23	84.28	84.34	84.40
	european beech	98.73	98.50	98.41	98.77	99.16	99.91	98.95	98.63	98.42	98.26	98.24
	turkey oak	94.76	95.04	95.30	95.91	96.30	96.96	96.25	95.97	95.79	95.65	95.69
	other oaks	89.21	89.55	89.89	90.63	91.15	91.78	91.30	91.14	91.03	90.96	91.04
	other broadleaves	89.88	89.97	90.00	90.55	91.06	91.74	91.15	91.03	90.97	90.93	90.98
coppices	european beech	83.23	82.80	82.46	82.46	82.84	83.47	83.00	82.92	82.83	82.81	82.82
	sweet chestnut	84.10	87.09	89.55	92.16	94.93	97.99	97.82	97.95	98.04	98.30	98.55
	hornbeams	76.40	76.08	75.83	75.74	75.83	76.04	75.81	75.78	75.75	75.76	75.77
	other oaks	75.53	75.95	76.18	76.41	76.68	77.13	77.08	77.03	77.01	77.04	77.10
	turkey oak	79.18	78.68	78.26	78.03	78.01	78.23	77.86	77.81	77.76	77.77	77.79
	evergreen oaks	79.62	79.44	79.28	79.29	79.38	79.71	79.32	79.23	79.13	79.14	79.21
	other broadleaves	78.61	80.22	81.52	82.79	84.00	85.17	84.77	84.78	84.77	84.85	84.90
	conifers	80.00	80.43	80.84	81.46	82.24	83.17	83.16	83.19	83.22	83.29	83.36
plantations	eucalyptuses coppices	83.72	87.06	88.15	88.83	88.99	88.93	87.57	87.18	86.79	86.75	87.13
	other broadleaves coppices	84.15	86.95	88.27	89.17	89.80	90.19	89.29	89.23	89.19	89.33	89.50
	poplars stands	87.84	91.09	93.52	95.76	97.42	98.38	97.39	97.48	97.61	97.72	97.70
	other broadleaves stands	86.85	86.68	86.87	87.44	88.12	89.00	89.11	89.10	89.15	89.27	89.40
	conifers stands	82.30	84.01	86.25	89.32	92.46	96.02	97.82	98.07	98.34	98.82	99.33
protective	rupicolous forest	76.80	77.31	77.81	78.44	79.09	79.75	79.46	79.39	79.33	79.30	79.30
	riparian forest	83.66	83.16	82.77	82.54	82.71	82.86	81.90	81.80	81.69	81.61	81.47

From the SOC stock values reported in Table 6.9, the SOC stock change values have been calculated for each inventory typology group and reported in Table 6.10.

Table 6.10
SOC stock changes in the upper 30 cm of mineral soils at national level

Inventory typology group	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
	SOC stocks (t C)										
stands	1,954	2,327	2,161	2,460	1,849	1,917	6,265	6,356	6,501	6,604	6,664
coppices	3,403	3,742	3,584	3,692	2,758	2,939	8,969	8,834	8,819	9,266	9,950
rupicolous and riparian forests	564	641	615	642	452	453	1,564	1,584	1,589	1,620	1,620
plantations	227	196	194	191	122	104	371	314	323	325	389
Total	6,149	6,905	6,554	6,984	5,181	5,413	17,169	17,087	17,233	17,815	18,623

A comparison of the model results versus data measured in the framework of the II NFI (INFC2005) has been carried out, and the results are shown in the following Table 6.11.

Table 6.11 Comparison between SOC stock estimates in the upper 30 cm depth for the entire national forest land territory derived from NFI 2005 and the For-est model

	NFI 2005	For-est model	differences	
	t C= Mg	t C= Mg	t C= Mg	%
SOC stock	703,524,894	710,577,508	7,052,614	+1.00

Land converted to Forest Land

The area of land converted to forest land always comes from grassland not subject to any specific management practice (i.e., under natural conditions). It is assumed that other conversions do not occur, and there is no evidence that those do occur. Accordingly, methods and factors for grassland converted to forest land are applied to estimate C stock changes and associated GHG emissions and removals.

Italy applies a 20-years conversion period and an approach 2 for land representation, so that, in any inventory year, the area reported under this category is the cumulated area of all conversions occurred in that year plus the area converted in the 19 previous years.

As for forest land remaining forest land, carbon stock changes in living biomass are calculated using the same *For-est* model.

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes from dead organic matter and litter pools has been significantly modified.

The litter carbon stock changes have been estimated for land converted to forest land based on the default litter stocks from the 2006 IPCC Guidelines used to derive a weighted average stock (i.e., 2.67 t C ha⁻¹) and the 2006 IPCC equation 2.23.

For land converted to forest land, annual changes in deadwood carbon stocks were calculated using a decay model described in equations 6.1, applying the factors and parameters reported in Table 6.6.


To estimate carbon stock changes in mineral soils, the IPCC default method has been applied. A country-specific SOC stock for natural grassland has been set at 78.9 t C ha⁻¹, based on a review of the literature on soil carbon in mountain meadows, pastures, set-aside lands as well as undisturbed abandoned land, in Italy (Masciandaro and Ceccanti, 1999; Del Gardo *et al.*, 2003; Benedetti *et al.*, 2004; Viaroli and Gardi, 2004; La Mantia *et al.*, 2007; Xiloyannis, 2007; IPLA, 2007; ERSAF, 2008; CRPA, 2009). For forest soils, the time series of SOC stocks is reported in Table 6.12 according to the previously described methodology (forest land remaining forest land).

Table 6.12 Soil Organic Carbon (SOC) stocks for *forest land remaining forest land*

<i>years</i> Years	SOC stock t C ha ⁻¹
1985-1994	79.809
1995-1999	80.174
2000-2004	80.586
2005-2009	81.121
2010-2014	81.682
2015-2020	81.945
2021-2024	81.738

In Figure 6.3, the C stock changes in land converted to forest land are shown.

Figure 6.3 C stock changes in land converted to forest land (kt C)



Land converted to forest land does not occur (NO) on organic soils.

CO₂ emissions due to wildfires in land converted to forest land are included in CRT Table 4.A.2, carbon stocks change in living biomass - losses. Non-CO₂ emissions from fires have been estimated and reported in CRT Table 4(IV); details on the methodology used to estimate emissions are reported in paragraph 6.11.2 and annex 12.

6.2.5 Uncertainty and time series consistency

To assess the overall uncertainty of the time series 1990–2024, Approach 1 of 2006 IPCC Guidelines (IPCC, 2006) has been applied. Input uncertainties for activity data and emission factors are derived from the country specific information and from the defaults provided in the 2006 IPCC Guidelines (IPCC, 2006).

In Table 6.13, the values of carbon stock of each pool, for the year 1985, and the associated uncertainties are reported for the entire forest land area.

Table 6.13 Carbon stocks and uncertainties for year 1985 and current increment related uncertainty

Carbon stocks <i>t CO₂eq. ha⁻¹</i>	<i>Aboveground biomass</i>	V _{AG}	139.92
	<i>Belowground biomass</i>	V _{BG}	31.6
	<i>Dead wood</i>	V _D	3.3
	<i>Litter</i>	V _L	2.7
Uncertainty	<i>Growing stock</i>	E _{NFI}	3.2%
	<i>Current increment (Richards)³³</i>	E _{NFI}	51.6%
	<i>Harvest</i>	E _H	30%
	<i>Fires</i>	E _F	30%
	<i>Drain and grazing</i>	E _D	30%
	<i>Mortality</i>	E _M	30%
	<i>BEF</i>	E _{BEF1}	30%
	<i>R</i>	E _R	30%

³³ The current increment is estimated by the Richards function (first derivative); uncertainty has been assessed considering the standard error of the linear regression between the estimated values and the corresponding current increment values reported in the National Forest Inventory

<i>Deadwood</i>	E_{DEF}	4.6%
<i>Litter</i>	E_L	10%
<i>Wood Basic Density (WDB)</i>	E_{BD}	30%
<i>C Conversion Factor</i>	E_{CF}	2%

The uncertainties of each carbon pool and the overall uncertainty for 1985 are shown in Table 6.14.

Table 6.14 C stock uncertainties for the year 1985

<i>Aboveground biomass</i>	E_{AG}	42.59%
<i>Belowground biomass</i>	E_{BG}	52.10%
<i>Dead wood</i>	E_D	42.84%
<i>Litter</i>	E_L	43.75%
Overall uncertainty	E_{1985}	34.85%

The overall uncertainty related to 1985 (the year of the first National Forest Inventory) has been propagated through the years, till 2024, following Approach 1. The uncertainties related to the carbon pools and the overall uncertainty for 2024 are shown in Table 6.15.

Table 6.15 Uncertainties for the year 2024

<i>Aboveground biomass</i>	E_{AG}	42.65%
<i>Belowground biomass</i>	E_{BG}	52.14%
<i>Dead wood</i>	E_D	42.89%
<i>Litter</i>	E_L	43.80%
Overall uncertainty	E	35.36%

Following Approach 1 and the abovementioned methodology, the overall uncertainty in the estimates produced by the described model has been quantified; in Table 6.16, the uncertainties of the 1985-2024 period are reported.

Table 6.16 Overall uncertainties 1985 – 2024 (%)

1985	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
34.9	35.0	35.1	35.2	35.2	35.3	35.4	35.4	35.4	35.4	35.4	35.4

The overall uncertainty in the model estimates between 1990 and 2024 has been assessed by subtracting uncertainties with Approach 1 (IPCC 2006, Vol.1, Ch. 3, Equation 3.2), resulting in an overall uncertainty equal to 25.0%.


6.2.6 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the sum of sub-categories; where possible, activity data comparison among different sources (FAO database³⁴, ISTAT data³⁵) has been made. Data entries have been checked several times during the compilation of the inventory; attention has been focused on the categories showing significant changes between two years in succession. Land use matrices have been accurately checked and cross-checked to ensure that data were properly reported. An independent verification of the living biomass net change with data from the second NFI, for the year 2005 (Tabacchi et al., 2010), was performed. In Figure 6.4, the outcome of the comparison is shown.

³⁴ FAO, 2015, FAOSTAT, <http://faostat3.fao.org/home/E>


³⁵ ISTAT, several years [a], [b], [c]

Figure 6.4 Comparison between carbon stock changes, for living biomass pool, by the National GHG Inventory (ISPRA) and estimated data of NFI2005 (II NFI) measurements (modified from Tabacchi *et al.*, 2010)



The nomenclature used in the NFI2005 and NFI2015 is different from that elaborated for the first national forest inventory. Therefore, a comparison among NFI2005-NFI2015 current increment data and *For-est* model current increment data is possible only for a non-exhaustive number of inventory typologies. In the following Figure 6.5, the comparison has been reported both for NFI2005 and for NFI2015. The comparisons refer to the years 2005 and 2018, which are the mean years for the field survey of the second and third forest inventories, respectively.

Figure 6.5 Average national current increment: comparison among NFIs (INFC) data and For-est model estimates for the year 2005 (panel A – NFI2005) and for 2018 (panel B – NFI2015)




Generally, the current increment estimated with the For-est model is in quite good agreement with the INFC measured current increments. The main noticeable differences from the comparisons refer to the different nomenclature used by the INFC and the For-est model, resulting in an assignment of some forest areas to the forest typologies by the For-est model with respect to the field data of the forest inventories. Some examples: *stand Norway spruce* (with a remarkable overestimate of INFCs current increment compared to For-est) while, for the *stand mountain pines*, the current increment estimated by the For-est is higher than the INFCs ones; similar situation with the categories *coppice other oaks* – *coppices turkey oak* – *coppices evergreen oaks*, where the mismatch may be explained with a different allocation (i.e., area) of the abovementioned categories.

An additional verification activity has been carried out, comparing the implied carbon stock change per area (IEF), related to the living biomass, with the IEFs reported by other Parties. The 2023 submission³⁶ has been considered to deduce the different IEFs; in Figure 6.6, the comparison is shown, considering the

³⁶ [GHG Review Tools \(unfccc.int\)](https://unfccc.int)

IEFs for both the forest land remaining forest land (FL-FL) and land converted to forest land (L-FL) subcategories, for the living biomass.

Figure 6.6



Implied carbon stock change per area for the living biomass

6.2.7 Category-specific recalculations

A remarkable recalculation occurred in the 2026 submission, compared to the 2025 submission. The recalculation is due to the implementation of the revised estimates submitted to the European Commission in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841.

In tables 6.17 and 6.18, the recalculations in forest land category, by subcategory and by carbon pool, are reported. The revision of DOM estimates in 2026 submission resulted in a large deviation in the whole time series. The deviation occurring in 2023 reporting year, comparing the 2025 and 2024 submissions, is due to an update of the burned area in one administrative Italian region.

Table 6.17 Recalculation in CO₂ emissions from forest land category, by subcategory

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ - kt</i>								
Forest land	-20,805	-30,158	-39,005	-40,235	-42,297	-40,135	-42,324	-43,926	-52,912
FL-FL	-17,396	-23,992	-30,045	-31,962	-34,704	-30,826	-31,840	-32,444	-38,922
L-FL	-3,409	-6,166	-8,961	-8,274	-7,594	-9,309	-10,484	-11,483	-13,990
2025 submission	<i>CO₂ - kt</i>								
Forest land	-17,852	-26,549	-35,049	-36,507	-40,303	-41,177	-42,007	-44,145	-54,970
FL-FL	-15,002	-21,420	-27,403	-29,397	-33,531	-32,341	-32,345	-33,491	-41,466
L-FL	-2,849	-5,130	-7,646	-7,111	-6,772	-8,836	-9,662	-10,654	-13,504
recalculation	<i>%</i>								
Forest land	14.20	11.97	10.14	9.26	4.71	-2.60	0.75	-0.50	-3.89
FL-FL	13.76	10.72	8.79	8.02	3.38	-4.91	-1.59	-3.23	-6.54
L-FL	16.42	16.81	14.67	14.06	10.82	5.07	7.84	7.21	3.48

Table 6.18 Recalculation in CO₂ emissions from forest land category, by carbon pool

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	CO ₂ - kt								
Forest land	-20,805	-30,158	-39,005	-40,235	-42,297	-40,135	-42,324	-43,926	-52,912
- living biomass	-16,444	-24,786	-32,983	-34,928	-38,759	-36,416	-37,479	-39,722	-49,072
- dom	-4,144	-4,800	-5,147	-4,366	-2,633	-2,426	-3,513	-2,765	-2,293
- soils	-217	-573	-876	-941	-905	-1,293	-1,332	-1,440	-1,548
2025 submission	CO ₂ - kt								
Forest land	-17,852	-26,549	-35,049	-36,507	-40,303	-41,177	-42,007	-44,145	-54,970
- living biomass	-16,444	-24,786	-32,983	-34,928	-38,759	-36,416	-37,479	-39,509	-50,226
- dom	-1,191	-1,191	-1,191	-639	-639	-3,509	-3,199	-3,199	-3,199
- soils	-217	-573	-876	-941	-905	-1,253	-1,329	-1,437	-1,545
recalculation	%								
Forest land	14.20	11.97	10.14	9.26	4.71	-2.60	0.75	0.50	-3.89
- living biomass	-	-	-	-	-	-	-	0.54	-2.35
- dom	71.27	75.19	76.86	85.37	75.74	-44.65	8.95	-15.70	-39.5
- soils	-	-	-	-	-	3.13	0.18	0.18	0.18

Furthermore, the revision of the 2020-2023 harvest data carried out by the SINFor triggered a recalculation of the biomass losses in the 2026 submission.

6.2.8 Category-specific planned improvements

Italy is currently implementing a change in the land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

6.3 Cropland (4B)

6.3.1 Description

Under this category, CO₂ emissions from living biomass and soils have been reported, for cropland remaining cropland and for land converted to cropland.

Cropland net emissions share 1.0% of the total 2024 LULUCF CO₂eq. net emissions; in particular, the soil pools represent 64.3% of the whole cropland emissions and removals while the remaining 35.7% originates from living biomass pool.

CO₂ emissions and removals from mineral soils under cropland remaining cropland have been identified as key category in trend assessment with Approach 1 and 2, while CO₂ emissions and removals from mineral soils under land converted to cropland have been identified as key category in level assessment with Approach 2.

6.3.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

Information on the land representation is reported in section 6.1. For the cropland category, as already discussed, it is assumed that the only conversion occurring is from grassland to cropland. The IPCC default land use transition period of 20 years has been applied.

6.3.3 Land-use definitions and the classification systems used and their correspondence to the LULUCF categories

Cropland includes all annual and perennial crops.

Due to the technical characteristics of the IUTI assessment (i.e., classification of orthophotos), it was not possible to clearly distinguish among some subcategories in *cropland* and non-woody *grassland* categories (e.g., grazing lands and unmanaged/natural grasslands). Therefore, although the total aggregated area of the two categories, *cropland* and *grassland*, together is derived from the IUTI data, the area of each of their subcategories is disaggregated using as proxies the national statistics (ISTAT, [b], [c]) on annual crops and perennial woody crops.

6.3.4 Methodological issues

Activity data for cropland remaining cropland have been subdivided into annual and perennial crops. Changes in the biomass C stock have been estimated for perennial crops in both cropland remaining cropland and land converted to cropland, while for annual crops in land converted to cropland only.

Soil carbon stock changes have been estimated and reported for annual and perennial crops in both cropland remaining cropland and land converted to cropland subcategories.

Living biomass – perennial crops

For perennial crops, biomass carbon stock changes have been estimated based on the annual rates of biomass gain and loss (IPCC 2006, Vol. 4, Chapter 2, Equation 2.7).

The annual carbon stock in living biomass and the woody crops area annually undergoing woody biomass removal (e.g., biomass cleared and replanted with a different crop) have been estimated; in addition, the total woody crops area has subdivided into age classes, considering three main woody crop types (i.e., olives, vineyards, and other fruit). The estimation process has been carried out at NUTS2 (regional) level, based on the available data from national statistics (ISTAT, [b], [c]) for the different woody crop species³⁷ and harvest/maturity cycles.

The carbon stock change in living biomass during the plantation cycle is estimated based on an annual constant net gain (accumulation rate), per perennial crop type and age class. The parameters of the logistic growth curves of the three orchard categories of the LIFE project MEDINET³⁸ (Canaveira et al., 2018) were used. Table 6.19 summarizes the aboveground and belowground biomass carbon stock at the end of the maturity cycle for each perennial crop type. These values correspond to the total biomass carbon stocks removed during the harvesting. The applied methodology aligns with Tier 2 characteristics and adopts a conservative approach to estimate carbon emissions from above and below-ground biomass.

³⁷ Olive, vineyard (for wine grapes and other), citrus trees (orange, mandarine, clementine, lemon, grapefruit, bergamot, cedar, chinotto), apple, peach, pear, apricot, cherry, kiwifruit, other fruits (carob, fig, plum, hazelnut, almond, raspberry)

³⁸ MEDINET (Mediterranean Network for Reporting Emissions and Removals in Cropland and Grassland): <https://www.lifemedinet.com/>

Table 6.19 Harvest/maturity cycle, aboveground and belowground biomass carbon stock at harvest

Crops	Harvest/maturity cycle yr	Aboveground C stock		Belowground C stock	
		t C ha ⁻¹	std dev (t C ha ⁻¹)	t C ha ⁻¹	std dev (t C ha ⁻¹)
olive	50	9.13	1.07	2.60	0.09
vineyards (wine grapes)	20	5.60	0.50	4.46	0.34
vineyards (for others)	30	5.62	0.50	4.48	0.35
orchards, pear, apple, cherry	25	8.91	1.32	5.75	0.32
peach, apricot	15	8.94	1.29	5.72	0.65
kiwifruit	20	8.90	1.31	5.73	0.68
other fruits	20	8.90	1.31	5.73	0.68

Net biomass carbon stock changes are equal to -317 kt C for 1990, and -219 kt C for 2024, a time series is summarised in Table 6.20.

Table 6.20 Change in carbon stock in living biomass

Area	aboveground biomass			belowground biomass			net change in C stock	
	Gains	Losses	Net change	Gains	Losses	Net change		
	<i>kha</i>	<i>kt C</i>	<i>kt C</i>	<i>kt C</i>	<i>kt C</i>	<i>kt C</i>		
1990	2,698	486	-693	-207	316	-425	-110	-317
1995	2,712	443	-534	-91	285	-367	-82	-173
2000	2,606	376	-693	-316	240	-533	-293	-609
2005	2,577	360	-467	-107	234	-305	-71	-178
2010	2,574	360	-441	-81	236	-320	-84	-165
2015	2,405	319	-665	-346	214	-451	-237	-582
2020	2,455	328	-836	-507	231	-485	-254	-762
2021	2,443	323	-556	-233	230	-355	-126	-358
2022	2,431	325	-670	-346	232	-352	-120	-466
2023	2,420	323	-658	-335	233	-398	-165	-500
2024	2,408	314	-463	-149	227	-297	-70	-219

Soils – annual and perennial crops

For mineral soils, the estimation method is based on changes in SOC stocks over a finite period due to changes in management practices. According to the 2006 IPCC Guidelines (IPCC, 2006), the change in mineral SOC stocks (vol. 4, chapter 2, eq. 2.25) is the result of a change in management practices in a unit of land across time. The SOC stock changes in annual and perennial crops have been estimated considering the following cropland management practices reported in table 6.21.

Table 6.21 Cropland management practices

cropland subcategory	management practices	definition	CAP regulations
annual crops	Arable land (Ordinary)	A kind of agriculture that does not evidence any kind of soil carbon stock technical maintenance	
	Organic arable land	Management of waste crop; Organic manure; Extended crop rotation; Selection of better crop varieties; Cover crops	Reg. (EEC) n. 2078/92, Reg. (EC) n. 834/2007 and Reg. (EC) n. 889/2008, RDPs 2000-2006: Reg. (EC) n. 1257/99, RDPs 2007-2013: Reg. (EC) n. 1698/2005 and Reg. (EC) n. 74/2009
	Sustainable arable land	Crop rotation; Grassing; Specific erosion prevention; Cover crops; Minimum tillage	National decree on sustainable agriculture n. 2722/2008; RDPs 2000-2006: Reg. (EC) n. 1257/99; RDPs 2007-2013: Reg. (EC) n. 1698/2005 and Reg. (EC) n. 74/2009
	Set aside	Natural grassing; At least one mowing	Reg. (EEC) N. 1765/1992; National decree on cross compliance implementation n. 30125/2009 and subsequent revisions
	Conservative practices	Zero tillage; Organic manure; Grassing; Cover crops; Minimum tillage; Crop rotation	RDPs 2007-2013: Reg. (EC) n. 1698/2005 and Reg. (EC) n. 74/2009
perennial crops	Woody crops (Ordinary)	A kind of agriculture that does not evidence any kind of soil carbon stock technical maintenance	
	Organic woody crops	Management of waste crop; Organic manure; Extended crop rotation; Selection of better crop varieties; Cover crops	Reg. (EEC) n. 2078/92, Reg. (EC) n. 834/2007 and Reg. (EC) n. 889/2008, RDPs 2000-2006: Reg. (EC) n. 1257/99, RDPs 2007-2013: Reg. (EC) n. 1698/2005 and Reg. (EC) n. 74/2009
	Sustainable management	Crop rotation; Grassing; Specific erosion prevention; Cover crops; Minimum tillage	National decree on sustainable agriculture n. 2722/2008; RDPs 2000-2006: Reg. (EC) n. 1257/99; RDPs 2007-2013: Reg. (EC) n. 1698/2005 and Reg. (EC) n. 74/2009

In the following Table 6.22 the data source for each management practice is listed.

Table 6.22 Cropland management practices and relative data sources

cropland subcategory	management practice	data source
annual crops	Ordinary	ISTAT
	Organic	National Information system on organic agriculture (SINAB)
	Sustainable	Annual Implementation Reports (RAE); Annual Report on Operational Programs: 2000-2024; Integrated Crop Management National Quality System (SQNPI)
	Set aside	Eurostat: 1990-2016; AGEA: 2021-2024
	Conservative practices	Annual Implementation Reports (RAE): 2008-2024
perennial crops	Ordinary	ISTAT
	Organic	National Information system on organic agriculture (SINAB)
	Sustainable	Annual Implementation Reports (RAE) and Annual Report on Operational Programs: 2000-2024

The annual areas subject to the abovementioned management practices, at regional level, have been estimated, also considering the transition to and from different management practices (e.g., ordinary annual crops to organic annual crops, ordinary annual crops to sustainable annual crops, etc.). Specifically,

Italy assumes that the surface increment or decrement related to each improved management practice (i.e., organic, sustainable, set aside, conservative) is due to a corresponding decrement or increment in the surface of the ordinary management practice of the same cropland subcategory (i.e., annual crops and perennial crops). Land management changes have been estimated since 1971. Changes in carbon stocks in mineral soils have been calculated by applying formulation B of equation 2.25 of the IPCC, 2006 (vol. 4, chapter 2). The IPCC default transition period, i.e., 20 years, has been considered.

The SOC_{ref} classification of the soils is based on the default reference SOC stocks for mineral soils (tC/ha in 0-30 cm) provided in table 2.3 of the 2019 Refinement. The identification of country-specific SOC_{ref} has been performed using a combination of the following map layers:

- IPCC climate zones (JRC) - <https://esdac.jrc.ec.europa.eu/content/support-renewable-energy-directive#tabs-0-description=0>
- Corine Land cover 2006 (cropland: legend codes: 2.1, 2.2 and 2.4) - <http://sia.eionet.europa.eu/CLC2006>
- Soil map of Italy (reclassified according to the main groups of soil types as in table 2.3 of 2019 Refinement, vol. 4) - Carta dei suoli d'Italia³⁹
- Map of Italy with administrative boundaries.

Overlapping the abovementioned layers, the Italian soils have been classified according to the IPCC soil classes (table 2.3, vol. 4, chapter 2 of the 2019 Refinement), and their related climate zones, as a percentage, in each region. According to the thereby defined distribution of the soil types and climate zones in each Italian region, it was possible to define the SOC_{ref}. The stock change factors (F_{LU}, F_{MG}, F_I), appropriate for the national circumstances, have been selected among the default values provided in table 5.5 of the 2019 Refinement (vol. 4, chapter 5) and have been applied considering the percentage of moist and dry climates in each administrative region. The F factors considered for each management practice are reported in the following table 6.23.

Table 6.23 Stock change factors

	Management practice	F _{LU}		F _{MG}		F _I	
		Moist	Dry	Moist	Dry	Moist	Dry
annual crops	Ordinary	0.69	0.76	1	1	0.92	0.95
	Organic	0.69	0.76	1	1	1.44	1.37
	Sustainable	0.69	0.76	1.05	0.99	1	1
	Set aside	0.82	0.93	1.10	1.04	0.92	0.95
	Conservative	0.69	0.76	1.10	1.04	1.11	1.04
perennial crops	Ordinary	0.72	0.72	1	1	1	1
	Organic	0.72	0.72	1.05	0.99	1.44	1.37
	Sustainable	0.72	0.72	1.05	0.99	0.92	0.95

The SOC stocks per hectare in the mineral soil, calculated with the previously described procedure, are shown in table 6.24, per region and per management practices, both for annual and for perennial crops. Estimates of SOC stock changes in annual and perennial crops are reported in table 6.25.

³⁹ Costantini E.A.C., L'Abate G., Barbetti R., Fantappiè M., Lorenzetti R., Magini S. (2013), <https://esdac.jrc.ec.europa.eu/content/carta-dei-suoli-ditalia-soil-map-italy>

Table 6.24 SOC stocks per region and management practice

Region	annual crops					perennial crops		
	Ordinary	Organic	Sustainable	Set aside	Conservative	Ordinary	Organic	Sustainable
	SOC stock (t C ha ⁻¹) ¹					SOC stock (t C ha ⁻¹) ¹		
Piemonte	37.28	56.92	41.39	48.39	47.24	40.60	59.41	38.92
Valle D'Aosta	47.75	74.55	54.35	62.38	63.08	53.94	81.29	52.06
Liguria	36.83	56.62	41.21	47.90	47.28	40.57	59.92	38.97
Lombardia	42.17	65.19	47.47	54.94	54.69	46.86	69.72	45.10
Trentino – Alto Adige	46.35	72.54	52.90	60.59	61.51	52.57	79.48	50.78
Veneto	33.50	50.78	36.90	43.38	41.88	36.07	52.29	34.50
Friuli - Venezia Giulia	43.08	67.43	49.17	56.32	57.18	48.86	73.88	47.20
Emilia - Romagna	26.95	40.03	29.02	34.67	32.44	28.11	39.66	26.70
Toscana	25.32	37.42	27.11	32.51	30.19	26.21	36.73	24.85
Umbria	33.38	50.60	36.77	43.23	41.74	35.95	52.11	34.38
Marche	25.75	38.15	27.65	33.09	30.84	26.75	37.62	25.39
Lazio	29.90	44.50	32.27	38.49	36.12	31.28	44.24	29.73
Abruzzo	27.81	41.38	30.01	35.79	33.60	29.10	41.17	27.66
Molise	21.11	30.74	22.24	26.96	24.48	21.36	29.35	20.16
Campania	29.36	42.68	30.87	37.48	33.93	29.63	40.61	27.94
Puglia	17.81	25.73	18.60	22.68	20.35	17.81	24.22	16.76
Basilicata	18.96	27.45	19.85	24.16	21.76	19.03	25.95	17.92
Calabria	23.52	34.40	24.90	30.09	27.50	23.96	33.11	22.64
Sicilia	19.40	27.97	20.21	24.69	22.09	19.34	26.24	18.19
Sardegna	29.84	43.17	31.21	38.02	34.19	29.90	40.74	28.16

Table 6.25 SOC stock changes in the mineral soil for annual and perennial crops

	area		SOC stock change		
	annual crops - mineral soil	perennial crops	annual crops	perennial crops	total
	kha	kha	kt C	kt C	kt C
1990	7,982.3	2,698.5	215.7	1.1	216.8
1995	7,968.5	2,712.3	385.4	17.7	403.1
2000	7,773.6	2,605.9	635.0	82.6	717.5
2005	7,193.7	2,577.4	575.6	90.9	666.4
2010	6,476.7	2,574.4	305.5	131.9	437.5
2015	6,417.1	2,404.9	221.2	127.5	348.7
2020	6,367.1	2,455.1	229.3	134.8	364.1
2021	6,363.6	2,443.3	283.3	119.8	403.1
2022	6,360.0	2,431.4	345.6	155.9	501.5
2023	6,356.4	2,419.6	402.5	158.3	560.7
2024	6,352.8	2,407.7	434.2	165.4	599.6

Cropland includes not only mineral soils but also organic soils. The area of cropland on organic soils is derived from the FAOSTAT⁴⁰ database, which overlays:

- the Histosols classes from the *Harmonized World Soil Database*⁴¹ and
- the three “cropland” classes from the global land cover dataset, GLC2000⁴².

This source identifies three main areas of cropland on organic soils: one near the Venice lagoon, one on the Po estuary, and one in Tuscany (Massaciuccoli lake basin). According to national literature, these areas

⁴⁰ FAOSTAT database: <https://www.fao.org/faostat/en/#data/GV>

⁴¹ FAO/IIASA/ISRIC/ISSCAS/JRC, 2012. Harmonized World Soil Database (version 1.2). FAO, Rome, Italy and IIASA, Laxenburg, Austria.

⁴² EC-JRC. 2003. Global Land Cover 2000 database. Available at <http://bioval.jrc.ec.europa.eu/products/glc2000/glc2000.php>

are essentially cultivated with annual crops, and no information is available that would suggest any land-use conversion to or from other categories; they are therefore treated as cropland remaining cropland. The literature also indicates that drainage is the predominant management practice in these soils.

Consistent with the IPCC 2006 Guidelines, which assume zero carbon stock change in biomass for cropland remaining cropland under annual cropping systems, emissions have been estimated only for soils. Accordingly, GHG emissions from cropland on drainage organic soils are reported under CRT 4(II), and the methodology is described in section 6.9.

Land converted to Cropland

In accordance with the IPCC methodology, estimates of carbon stock change in living biomass and in SOM in mineral soils have been provided. Italy applies a 20-year conversion period and an approach 2 for land representation, so that, in any inventory year, the area reported under this category is the cumulated area of all conversions that occurred in that year plus the area converted in the 19 previous years.

Direct and indirect N₂O emissions arising from nitrogen mineralization associated with loss of soil organic matter have also been estimated and reported in CRT Table 4(III).

The biomass carbon stock change, for land converted to cropland, is estimated at Tier 1 (equation 2.16, vol. 4, chapter 2 of the 2006 IPCC Guidelines), and it is equal to the removal of biomass from the initial land use plus the carbon stocks of one year of growth in perennial crops or the average biomass stock in annual crops following the conversion. Since only conversion from grassland to cropland has occurred, the biomass removal is that of grassland (i.e., managed grazing land), and the value applied, as dry matter, is the default reported in Table 6.4 of the 2006 IPCC Guidelines (vol. 4, chapter 6) for warm temperate – dry climate, i.e., 6.1 t d.m. ha⁻¹. In accordance with national expert judgement, it has been assumed that the final crop type in all land converted to cropland is ordinary perennial crop; consequently, for perennial crop, the carbon stock gain of one year of growth has been taken from table 5.9 of the 2006 IPCC Guidelines (vol. 4, chapter 5), for temperate region i.e., 2.1 t C ha⁻¹. Conversion to cropland is quite a rare event in the time series of land matrices (table 6.4 and CRT Tables 4.1).

Changes in carbon stocks in mineral soils in land converted to cropland have been estimated applying formulation B of the IPCC equation 2.25 (2006 IPCC Guidelines, vol. 4, chapter 2). As described for cropland remaining cropland and grassland remaining grassland (see par. 6.3), SOC_{ref} was defined according to the distribution of the soil types and climate zones in each Italian region, both for cropland and grassland. The stock change factors (F_{LU}, F_{MG}, F_i) adapted to the national circumstances have been derived from the default values provided in Table 5.5 of the 2019 Refinement (vol. 4, chapter 5) and Table 6.2 of the 2019 Refinement (vol. 4, chapter 6) for cropland and grassland, respectively. Then, they have been applied considering the percentage of moist and dry climates in each administrative region. SOC values for cropland are reported in table 6.24, according to the different management practices considered and disaggregated by region.

Carbon stocks change in living biomass and soils in land converted to cropland are reported in table 6.26.

Table 6.26 Change in carbon stock in living biomass and soil in land converted to cropland

year	Conversion Area		Carbon stock	
	annual change kha	20 years change kha	Living biomass kt C	Soils kt C
1990	0	136.1	0	-204.2
1995	16.8	220.0	-12.9	-330.5
2000	0	83.8	0	-126.3
2005	0	83.8	0	-126.3
2010	0	83.8	0	-126.3
2015	0	0.0	0	0
2020	28.3	141.6	-21.7	-204.2
2021	0.0	141.6	0.0	-204.2
2022	0.0	141.6	0.0	-204.2
2023	0.0	141.6	0.0	-204.2
2024	0.0	141.6	0.0	-204.2

6.3.5 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of the 2006 IPCC Guidelines (IPCC, 2006). Input uncertainties dealing with activity data and emission factors have been assessed based on the information provided in the 2006 Guidelines and 2019 Refinement (IPCC, 2006 - IPCC, 2019). For 2024, the uncertainty related to the cropland remaining cropland has been assessed to be equal to 13.0% for living biomass, and to 30.4% for mineral soils. For land converted to cropland, the uncertainty has been estimated to be 70.7% for living biomass and to 90.1% for mineral soils. The uncertainty related to the cropland category is equal to 66.1% for 2024, considering also the high uncertainty related to the emissions from organic soils (reported under reported under CRT 4(II), and described in section 6.9.

6.3.6 Category-specific QA/QC and verification

Category-specific quality control activities include comparison with alternative data sources (FAO database⁴³, ISTAT data⁴⁴). Land use matrices have been accurately checked and cross-checked to ensure that data were properly reported. Several QA activities are carried out in different phases of the inventory process. All the LULUCF categories have been embedded in the overall QA/QC system of the Italian GHG inventory.

6.3.7 Category-specific recalculations

Recalculations occurred in the 2026 submission compared with the 2025 submission, as presented in tables 6.26 and 6.27, for both living biomass and soils. These changes affect the subcategories cropland remaining cropland and land converted to cropland. The reasons are as follows:

- A methodological change in the estimation of emissions from organic soils, implemented to address the recommendations issued under the 2025 Comprehensive Review of Member States greenhouse gas inventories pursuant to the Governance Regulation (EU) 2018/1999 and the LULUCF Regulation (EU) 2018/841. Emissions from drained organic soils are now estimated and reported under CRT Table 4(II), rather than CRT Table 4.B. The methodology is described in Section 6.9 of this document. This methodological change affects the entire time series, the soil carbon pool (Table 6.27), and the cropland remaining cropland subcategory (Table 6.8).

⁴³ FAO, 2005. FAOSTAT, <http://faostat3.fao.org/home/E>

⁴⁴ ISTAT, several years [a], [b], [c]

- A change in activity data for a specific annual crop from 2020 onwards, based on updated information from the national statistical source (ISTAT). Due to the land-use smoothing process and the land-use change rules described in Section 6.1, this update has two main effects:
 - o a revision of cropland area also for the 2016–2020 period;
 - o a revision of land-use transitions to and from annual cropland, particularly transitions between annual crops and perennial crops, and between annual crops and grassland.
 This affects both living biomass and soil carbon pools (Table 6.27), and both cropland remaining cropland and land converted to cropland (Table 6.28).
- An update of activity data for annual and perennial woody crops under sustainable management for a few regions from 2020 onwards. This affects only the soil carbon pool (Table 6.27) and the cropland remaining cropland subcategory (Table 6.28).

Table 6.27 Recalculation in CO₂ emissions for cropland category, for carbon pool

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ - kt</i>								
- living biomass	1,161	2,233	654	607	2,136	2,872	1,314	1,707	1,835
- soils	-46	-2,168	-1,981	-1,141	-1,279	-587	-729	-1,090	-1,307
2025 submission	<i>CO₂ - kt</i>								
- living biomass	1,161	2,233	654	607	2,136	3,009	1,971	2,340	1,953
- soils	821	-1,305	-1,112	-276	-412	540	641	526	539
Recalculation*	<i>%</i>								
- living biomass	-	-	-	-	-	-5	-50	-37	-6
- soils	-1,873	-40	-44	-76	-68	-192	-188	-148	-141

*The methodological change in the estimation of emissions from organic soils has a significant impact on cropland net emissions reported in CRT Table 4.B, potentially leading to a shift from net emissions in the 2025 submission to net removals in the 2026 submission. This requires a slight adjustment to the recalculation formula to clearly reflect the reduction in net emissions, using the denominator in absolute value.

Table 6.28 Recalculation in CO₂ emissions for CL-CL and L-CL

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ eq. - kt</i>								
Cropland	1,114	65	-1,326	-534	857	2,285	585	617	528
CL-CL	366	-398	-1,789	-997	857	1,457	-164	-132	-221
L-CL	749	463	463	463	NO	828	749	749	749
2025 submission	<i>CO₂ eq. - kt</i>								
Cropland	1,981	928	-457	331	1,722	3,549	2,612	2,866	2,491
CL-CL	1,233	465	-921	-132	1,722	2,404	1,215	1,224	607
L-CL	749	463	463	463	NO	1,145	1,397	1,642	1,884
Recalculation*	<i>%</i>								
Cropland	-78	-1,336	-66	-162	-101	-55	-347	-364	-372
CL-CL	-237	-217	-49	-87	-101	-65	-840	-1,031	-375
L-CL	-	-	-	-	NO	-38	-87	-119	-152

*The recalculated percentage was estimated using the denominator in absolute value.

6.3.8 Category-specific planned improvements

Italy is currently implementing a change in the land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

6.4 Grassland (4C)

6.4.1 Description

Under this category, CO₂ emissions from living biomass, and soil organic matter, in grassland remaining grassland and land converted to grassland have been reported.

Grassland category is responsible for 6,927 kt of CO₂ eq. net removals in 2024, sharing 10.4% of total CO₂ eq. LULUCF net removals. Living biomass pool accounts for 54.0% of the grassland CO₂ emissions and removals, while soil pool is responsible for 41.3% of the category emissions and removals and the remaining 4.8% is represented by the dead organic matter pool.

CO₂ emissions and removals from living biomass under grassland remaining grassland are key categories in level and trend assessment both with Approach 1 and Approach 2, as well as mineral soils under land converted to grassland.

6.4.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

Information on the land representation is reported in section 6.1. For the grassland category, as already discussed, it is assumed that the only conversion occurring is from cropland to grassland. The IPCC default land use transition period of 20 years is applied.

6.4.3 Land-use definitions and the classification systems used and their correspondence to the LULUCF categories

Grassland includes all grazing land, natural grassland, and other wooded land that do not fulfil the forest definition (as shrublands).

Due to the technical characteristics of the IUTI assessment (i.e., classification of orthophotos), it was not possible to clearly distinguish between some subcategories in *cropland* and non-woody *grassland* categories (e.g., annual crops, annual pastures versus grazing land). Therefore, although the total aggregated area of the 2 categories *cropland* and *grassland* together is derived from the IUTI data, the area of each of their subcategories is disaggregated using as proxies the national statistics (ISTAT, [b], [c]) on grazing lands, forage crops, permanent pastures, natural grassland, and lands once used for agriculture purposes, but set-aside since 1971. However, the area of the subcategory other wooded land, i.e., shrublands, has been derived from the NFIs (CRA-MPF, NFI1985, NFI2005, NFI2015, and the preliminary data of NFI2025), based on IUTI data (par. 6.1), through linear interpolations for the periods 1985-2005, 2005-2015, and linear extrapolation for the period 2015-2024.

6.4.4 Methodological issues

Grassland remaining Grassland

Grazing land

This land mostly includes annual biomass, and according to IPCC Tier 1 methodological approach, carbon gains and losses in the biomass and DOM and pools are assumed in long-term equilibrium. As a result, no net C stock changes are estimated for these pools.

For mineral soils, the estimation method is based on changes in SOC stocks over a finite period following changes in management that impact soil organic C. According to the 2006 IPCC Guidelines (IPCC, 2006), the change in mineral SOC stocks (vol. 4, chapter 2, eq. 2.25) is the result of a change in management practices in a unit of land across time. SOC stock changes have been estimated considering natural (unmanaged) grazing land and managed grazing land subcategories. The latter is reported in table 6.29.

Table 6.29 Grazing land management practices and data sources

Management practices	Definition	CAP regulations	Data source
Managed grazing land (ordinary)	Renewal and/or thickening of crops; connection to zootechnics	National decree on cross compliance implementation n. 30125/2009 and subsequent revisions	ISTAT
Organic grazing land	Renewal and/or thickening of crops; connection to zootechnics	RDPs 2000-2006: Reg. (EC) n. 1257/1999; RDPs 2007 - 2013: Reg. (EC) n. 1998/2005 and Reg. (EC) n. 74/2009; Reg. (EC) n. 834/2007 and Reg. (EC) n. 889/2008; Reg. (EC) n. 1804/2007	National Information system on organic agriculture (SINAB)

The annual areas subject to the abovementioned management practices, at regional level, have been estimated, considering the transition to and from different management practices (i.e., managed grazing land to organic grazing land and vice versa). Land management changes have been estimated since 1971. Changes in organic carbon stocks in mineral soils have been calculated by applying formulation B of equation 2.25 (IPCC GLs, 2006; vol. 4, chapter 2). The IPCC default transition period, i.e., 20 years, has been considered.

The SOC_{ref} classification of the soils is based on the default reference SOC stocks for mineral soils (tC/ha in 0-30 cm) provided in table 2.3 of 2019 Refinement. The identification of country specific SOC_{ref} have been performed using a combination of the following map layers:

- IPCC climate zones (JRC) - <https://esdac.jrc.ec.europa.eu/content/support-renewable-energy-directive#tabs-0-description=0>
- Corine Land cover 2006 (Grassland: legend codes: 2.3 and 3.2) - <http://sia.eionet.europa.eu/CLC2006>
- Soil map of Italy (reclassified according to the main groups of soil types as in Table 2.3 of 2019 Refinement, vol. 4) - Carta dei suoli d'Italia⁴⁵
- Map of Italy with administrative boundaries.

Overlapping the abovementioned layers, the Italian soils have been classified according to the IPCC soil classes (table 2.3, vol. 4, chapter 2 of the 2019 Refinement), and their related climate zones as percentage in each region. According to the thereby defined distribution of the soil types and climate zones in each Italian region, it was possible to define the SOC_{ref} using 2019 Refinement default values. The stock change factors (F_{LU}, F_{MG}, F_i), appropriate for the national circumstances, have been selected among the default values provided in table 6.2 of the 2019 Refinement (vol.4, chapter 6). The F factors considered are reported in the following table 6.30.

⁴⁵ Costantini E.A.C., L'Abate G., Barbetti R., Fantappiè M., Lorenzetti R., Magini S. (2013), <https://esdac.jrc.ec.europa.eu/content/carta-dei-suoli-ditalia-soil-map-italy>

Table 6.30 Stock change factors for grazing land subcategories

Grazing land subcategory	F _{LU}		F _{MG}		F _I	
	Moist	Dry	Moist	Dry	Moist	Dry
Ordinary management	1	1	1	1	1.11	1.11
Organic management	1	1	1.14	1.14	1.11	1.11
Natural (unmanaged)*	1	1	0.90	0.90	1.11	1.11

* The same factors of natural (unmanaged) grazing land subcategory are also used to estimate other wooded land SOC stock (see next section)

The SOC stocks per hectare in mineral soil, calculated with the abovementioned procedure, are shown in table 6.31, per region and per management practices. Estimates of SOC stock changes in grazing land are reported in table 6.32.

Table 6.31 SOC stocks on hectares basis per region and management practice

Region	grazing land		
	Ordinary management SOC stock (t C ha ⁻¹)	Organic management SOC stock (t C ha ⁻¹)	Natural (unmanaged)* SOC stock (t C ha ⁻¹)
Piemonte	75.57	86.15	61.27
Valle D'Aosta	65.73	74.93	53.29
Liguria	70.21	80.04	56.93
Lombardia	63.25	72.10	51.28
Trentino – Alto Adige	62.93	71.74	51.02
Veneto	83.77	95.50	67.92
Friuli - Venezia Giulia	81.51	92.92	66.09
Emilia - Romagna	69.60	79.34	56.43
Toscana	44.37	50.58	35.97
Umbria	67.73	77.21	54.92
Marche	68.15	77.69	55.25
Lazio	67.80	77.29	54.97
Abruzzo	79.65	90.81	64.58
Molise	62.15	70.85	50.39
Campania	64.69	73.75	52.45
Puglia	26.59	30.31	21.56
Basilicata	43.53	49.63	35.30
Calabria	46.81	53.36	37.95
Sicilia	33.99	38.75	27.56
Sardegna	56.30	64.18	45.65

* The same SOC stocks on hectares basis of natural (unmanaged) grazing land subcategory are estimated for other wooded land (see next section)

Table 6.32 SOC stock changes in in mineral soil for grazing land

	area kha	net change in C stock kt C
1990	7,031	-43.6
1995	6,392	275.8
2000	5,941	326.5
2005	5,779	399.3
2010	5,402	467.2
2015	5,026	163.4
2020	4,043	-22.5
2021	3,871	-89.9
2022	3,699	-105.1
2023	3,527	-161.5
2024	3,355	-210.5

Grassland includes not only mineral soils but also organic soils. The area of grassland on organic soils is derived from the FAOSTAT⁴⁶ database, which overlays:

- the map of Histosols classes in the *Harmonized World Soil Database*⁴⁷, and
- the grassland area in the global land cover dataset, GLC2000⁴⁸.

This source identifies three main areas of cropland on organic soils: one near the Venice lagoon, one on the Po estuary, and one in Tuscany (Massaciuccoli lake basin). These areas are essentially managed grazing lands, and no information is available that would suggest any land-use conversion to or from other categories; they are therefore treated as grassland remaining grassland, specifically as grazing land remaining grazing land. The literature also indicates that drainage is the predominant management practice in these soils.

GHG emissions from grazing land on drainage organic soils are reported under CRT 4(II), and the methodology is described in section 6.9.

Other wooded land

Other wooded land includes all woody vegetation types that do not fit the forest definition as, for example, the “macchia mediterranea” (Italian translation for “Mediterranean maquis”). Other wooded lands are considered in the NFIs although they do not meet the forest minimum height threshold; this subcategory is here defined as “shrublands”. In this land, the total biomass changes (aboveground and belowground) are estimated by the *For-est* model at the regional scale (NUTS2). A detailed description of the model is reported in Annex 11.

In table 6.33, the biomass expansion factor (BEF) to expand growing stock volume to aboveground shrub volume, the wood basic density (WBD) conversion factor to convert volume in mass of dry matter, the root/shoot ratio (R) to estimate the belowground biomass, and the carbon fraction (CF) to convert dry matter are reported.

Table 6.33 Expansion and Conversion Factors for shrublands

Inventory typology	BEF <i>aboveground biomass / growing stock</i>	WBD <i>dry weight t d.m./ fresh volume m³</i>	R <i>root to shoot ratio</i>	CF <i>carbon stock t C/ biomass t d.m.</i>
<i>shrublands</i>	1.49	0.63	0.62	0.47

Almost all new other wooded land surfaces are the result of a land-cover change (from natural grassland to other wooded land) within the grassland land use category (grassland remaining grassland). The DOM pools have been estimated using coefficient values and assuming a constant, linear, accumulation rate of both dead wood and litter across the conversion time, till the coefficient value is achieved when the land cover changes to other wooded land. In practice, in each conversion year 1/20 of the dead wood mass coefficient and of the litter mass coefficient are reported as net CO₂ removals.

Both the dead wood and the litter mass coefficient, see table 6.33, have been estimated from data taken for the Italian national forest inventory, in 2008 and 2009 across the country from the plots of the national forest inventory network (<http://www.sian.it/inventarioforestale/jsp/necromassa.jsp>). The mass (wet matter) collected on the ground in those plots has been converted into dry matter using basic densities appropriately calculated in a specific study (Di Cosmo et al., 2013). The data collected, aggregated at the regional level, are accessible at the NFI website: http://www.sian.it/inventarioforestale/jsp/dati_carquant_tab.jsp.

⁴⁶ FAOSTAT database: <https://www.fao.org/faostat/en/#data/GV>

⁴⁷ FAO/IIASA/ISRIC/ISSCAS/JRC, 2012. Harmonized World Soil Database (version 1.2). FAO, Rome, Italy and IIASA, Laxenburg, Austria.

⁴⁸ EC-JRC. 2003. Global Land Cover 2000 database. Available at <http://bioval.jrc.ec.europa.eu/products/glc2000/glc2000.php>

The definition of the deadwood pool, coherent with the definition adopted by the NFI, is “*All non-living woody biomass not contained in the litter, either standing, lying on the ground, or in the soil. Dead wood includes wood lying on the surface, stumps larger than or equal to 10 cm in diameter and standing trees with DBH > 4,5 cm*”. In table 6.34 dead wood and litter coefficients are reported.


Table 6.34 Dead wood and litter coefficients [live/dead ratio]

Inventory typology	dead wood <i>t C ha⁻¹</i>	litter <i>t C ha⁻¹</i>
Shrublands	1.510	1.990

As for soils pool, following the ERT recommendation, Italy has decided to apply the IPCC Tier1, assuming that, the carbon stock in soil organic matter, for other wooded land, does not change. Land conversions from natural (unmanaged) grazing land to other wooded land are possible because of land abandonment and woody encroachment. However, for these two subcategories of grassland, the same SOC stocks are estimated based on the factors of table 6.2 of the 2019 Refinement (vol.4, chapter 6) as shown in tables 6.30 and 6.31. Therefore, carbon stock changes in soils pool, for other wooded land in grassland remaining grassland, have not been reported.

In Figure 6.7, other wooded land areas and net changes in carbon stock, for the different pools, are reported, for the period 1990-2024.

Figure 6.7 Other wooded land areas and net changes in carbon stock, for the different pools



Land converted to Grassland

In accordance with the IPCC methodology, estimates of carbon stock change in living biomass and in SOC stock in mineral soils have been provided. Italy applies a 20-years conversion period and an approach 2 for land representation, so that in any inventory year the area reported under this category is the cumulated area of all conversions occurred in that year plus the area converted in the 19 previous years. As a result of conversion to grassland, it is assumed that the dominant vegetation is removed entirely, after which some type of grass is planted or otherwise established; alternatively, grassland can result from the abandonment of the preceding land use, and the area is taken over by grassland.

Three land-use changes have occurred in Italy:

1. annual crops to managed grazing land (previous vegetation removal and subsequent plantation);
2. annual crops to natural (unmanaged) grazing land (abandonment without vegetation removal);
3. woody crops to other wooded land (abandonment without vegetation removal).

The estimates of biomass C stock changes are based on the following reasoning:

1. the annual crop biomass (before) is entirely removed, and the grassland (after) is planted. Tier 1 is used with default factors:
 C_{BEFORE} : 4.7 tC ha⁻¹ value before the conversion;
 C_{AFTER} : 2.867 tC ha⁻¹ (6.1 t dry matter/ha) in the biomass pool in the conversion year, as suggested by IPCC 2006 (vol. 4, ch. 6, table 6.4) for warm temperate dry climate.
2. the annual crops (before) are abandoned with no abrupt biomass change (i.e., change is not deliberate and therefore is not associated with land preparation operations like clearing and burning), and natural (unmanaged) grazing land occurs (after):
 ΔC_{growth} : 2.867 tC ha⁻¹ (6.1 t d.m. ha⁻¹) in the biomass pool in the conversion year, as suggested by IPCC 2006 (vol.4, chapter 6, table 6.4) for warm temperate dry climate grasslands.
3. The woody crops (before) are abandoned with no abrupt biomass change (i.e., change is not deliberate and therefore is not associated with land preparation operations like clearing and burning), and other wooded land occurs (after):
 ΔC_{growth} : 2.867 tC ha⁻¹ (6.1 t d.m. ha⁻¹) in the biomass pool in the conversion year, as suggested by IPCC 2006 (vol.4, chapter 6, Table 6.4) for warm temperate dry climate grasslands.

After the Second World War, wide portions of cropland and managed grazing land have been abandoned in the less accessible and productive areas both in Europe and in Italy (see Pellis et al., 2019 and the references therein). The resulting conversion is generally defined as woody encroachment (a specific kind of secondary succession). Generally, this type of conversion is quite slow, and its speed depends on climatic and pedological parameters. The literature on the argument is mainly based on chronosequence approaches (based on the space-for-time substitution concept) and does not measure annual C stock change in the annual transition from cropland to grassland, but a general C stock change rate over a long period (generally from cropland/grassland to forest). For example, according to Alberti et al. (2008), in the Italian Eastern Alps, the linear regression of biomass increment after agricultural abandonment is 1.69 t C ha⁻¹ yr⁻¹, but it is significantly affected by the late stages of the secondary successions identified. In a Sicilian study, Novara et al. (2013) found that annual and perennial herbs colonize abandoned perennial crops with a dry matter of 4.95 t d.m. ha⁻¹. The references suggest that in the years following the LUC there is a biomass increase. Because of the limited literature on the national territory, we therefore preferred to use the 6.1 t d.m. ha⁻¹ factor suggested by the 2006 IPCC Guidelines (vol. 4, chapter 6, table 6.4).

The total C emissions [kt C] due to changes in carbon stocks in living biomass in land converted to grassland are reported in table 6.35.

Table 6.35 Change in carbon stock in living biomass in land converted to grassland

year	Conversion Area		ΔC kt C
	annual change kha	20 years change kha	
1990	0	325.0	0
1995	0	292.5	0
2000	60	594.1	135.8
2005	97	777.0	188.0
2010	178	1,387.4	280.1
2015	44	1,608.0	124.6
2020	0	1,306.4	0
2021	4	1,216.4	9
2022	4	1,126.3	10
2023	4	1,036.3	12
2024	4	946.3	12

Changes in SOC stocks in mineral soils in land converted to grassland have been estimated applying formulation B of the IPCC equation 2.25 (vol. 4, chapter 2). SOC stocks for the different subcategories of grassland are reported in table 6.31, according to the different management practices considered and broken down by region. C emissions [kt C] due to SOC change in mineral soil in land converted to grassland are summarized in table 6.36.

Table 6.36 Change in carbon stock in soils

year	Conversion Area		Carbon stock
	annual change kha	20 years change kha	kt C
1990	0	325.0	306.7
1995	0	292.5	272.0
2000	60	594.1	579.1
2005	97	777.0	846.3
2010	178	1,387.4	1,500.7
2015	44	1,608.0	1,709.5
2020	0	1,306.4	1,402.4
2021	4	1,216.4	1,300.9
2022	4	1,126.3	1,189.9
2023	4	1,036.3	1,085.2
2024	4	946.3	990.0

6.4.5 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of 2006 IPCC Guidelines (IPCC, 2006). Input uncertainties dealing with activity data and emission factors have been assessed based on the information provided in the 2006 Guidelines and 2019 Refinement (IPCC, 2006 - IPCC, 2019). For 2024, the uncertainty related to the grassland remaining grassland has been assessed to be equal to 36.3% for living biomass, to 30.7% for DOM (deadwood and litter pool), to 30.4% for mineral soils. For land converted to grassland, the uncertainty has been estimated to be 70.7% for living biomass, to 56.2% for DOM (deadwood and litter pool) and to 90.1% for mineral soils. The uncertainty related to the grassland category is equal to 57.5%, for 2024, considering also the high uncertainty related to the emissions from organic soils reported under CRT 4(II), and described in section 6.9.

6.4.6 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the sum of sub-categories. Where possible, activity data comparison among different sources (FAO database⁴⁹, ISTAT data⁵⁰) has been made. Data entries have been checked several times during the compilation of the inventory; attention has been focused on the categories showing significant changes between two years in succession. Land use matrices have been accurately checked and cross-checked to ensure that data were properly reported. Several QA activities are carried out in different phases of the inventory process. The applied methodologies have been presented and discussed during several national workshops and expert meetings, collecting findings and comments to be incorporated in the estimation process. All the LULUCF categories have been embedded in the overall QA/QC-system of the Italian GHG inventory.

⁴⁹ FAO, 2005. FAOSTAT, <http://faostat3.fao.org/home/E>

⁵⁰ ISTAT, several years [a], [b], [c]

6.4.7 Category-specific recalculations

Recalculations occurred in the 2026 submission compared with the 2025 submission, as presented in Tables 6.37 and 6.38, for both living biomass and soils. These changes affect the subcategories grassland remaining grassland and land converted to grassland. The reasons are as follows:

- A methodological change in the estimation of emissions from organic soils, implemented to address the recommendations issued under the 2025 Comprehensive Review of Member States greenhouse gas inventories pursuant to the Governance Regulation (EU) 2018/1999 and the LULUCF Regulation (EU) 2018/841. Emissions from drained organic soils are now estimated and reported under CRT Table 4(II), rather than CRT Table 4.C. The methodology is described in Section 6.9 of this document. This methodological change affects the entire time series, the soil carbon pool (Table 6.37), and the grassland remaining grassland subcategory (Table 6.38).
- A change in activity data for a specific annual crop from 2020 onwards, based on updated information from the national statistical source (ISTAT). Due to the land-use smoothing process and the land-use change rules described in Section 6.1, this update affects the balance between cropland and grassland areas from 2016 onwards (see Section 6.3.8 for further details). For grassland remaining grassland (Table 6.38) and the soil pool (Table 6.37), the effect is visible in the 2017–2020 period, when a small amount of land previously tracked as grassland converted to cropland in the 2025 submission remains classified as grassland in the 2026 submission. As it refers to grazing land remaining grazing land, there is no effect on biomass and DOM pools. Conversely, from 2021 onwards, a small amount of land is now tracked as cropland converted to grassland (annual crops to grazing land), whereas this transition was not captured in the previous submission. This affects the land converted to grassland subcategory (Table 6.38) and both living biomass and soil pools (Table 6.37).
- An error in the 2023 estimate of biomass for other wooded land has been fixed.

Table 6.37 Recalculation in the grassland category, for CO₂ net emissions

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ - kt</i>								
- living biomass	344	-1,280	-2,341	-2,959	-2,187	-2,600	-2,015	-1,319	-3,351
- DOM	-114	-114	-114	-88	-88	-375	-375	-375	-375
- soils	-965	-3,321	-4,567	-7,216	-6,867	-5,060	-4,440	-3,978	-3,387
2025 submission	<i>CO₂ - kt</i>								
- living biomass	344	-1,280	-2,341	-2,959	-2,187	-2,600	-1,983	-1,280	-3,479
- DOM	-114	-114	-114	-88	-88	-375	-375	-375	-375
- soils	-954	-3,310	-4,557	-7,205	-6,857	-5,125	-4,582	-4,176	-3,625
Recalculation*	<i>%</i>								
- living biomass	-	-	-	-	-	-	1.56	2.90	-3.80
- DOM	-	-	-	-	-	-	-	-	-
- soils	1.09	0.31	0.23	0.14	0.15	-1.28	-3.19	-5	-7.03

*The methodological change in the estimation of emissions from organic soils has a significant impact on grassland net emissions reported in CRT Table 4.C, potentially leading to a shift from net emissions in the 2025 submission to net removals in the 2026 submission. This requires a slight adjustment to the recalculation formula to clearly reflect the reduction in net emissions, using the denominator in absolute value.

Table 6.38 Recalculation in grassland category, for GL-GL and L-GL

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ - kt</i>								
Grassland	-735	-4,715	-7,022	-10,263	-9,142	-8,035	-6,829	-5,671	-7,112
<i>GL-GL</i>	389	-2,094	-3,230	-3,733	-2,417	-2,893	-2,028	-1,270	-3,090
<i>L-GL</i>	-1,124	-2,621	-3,793	-6,530	-6,725	-5,142	-4,801	-4,401	-4,023
2025 submission	<i>CO₂ - kt</i>								
Grassland	-725	-4,705	-7,012	-10,253	-9,132	-8,100	-6,939	-5,831	-7,478
<i>GL-GL</i>	400	-2,083	-3,219	-3,723	-2,407	-2,957	-2,184	-1,496	-3,544
<i>L-GL</i>	-1,124	-2,621	-3,793	-6,530	-6,725	-5,142	-4,755	-4,335	-3,934
Recalculation*	<i>%</i>								
Grassland	-1.42	-0.22	-0.15	-0.1	-0.11	0.81	1.61	2.83	5.14
<i>GL-GL</i>	-2.69	-0.5	-0.33	-0.28	-0.43	2.24	7.7	17.81	14.71
<i>L-GL</i>	-	-	-	-	-	-	-0.96	-1.49	-2.21

*The recalculated percentage was estimated using the denominator in absolute value.

6.4.8 Category-specific planned improvements

Italy is currently implementing a change in the land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

6.5 Wetlands (4D)

6.5.1 Description

Under this category, activity data from land converted to wetlands are reported. Neither wetlands remaining wetlands nor land converted to wetlands are a key category.

6.5.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

Wetlands area has been estimated within the national land representation, applying the methodology described in section 6.1. During the period 1990-2024 conversions of annual cropland and natural grassland to wetlands have occurred.

6.5.3 Land-use definitions and the classification systems used and their correspondence to the LULUCF categories

Wetlands include land covered or saturated by water, for all or part of the year (MAMB, 1992). Reservoirs or water bodies regulated by human activities have not been considered.

6.5.4 Methodological issues

Italy applies a 20-year conversion period and an approach 2 for land representation, so that, in any inventory year, the area reported under this category is the cumulated area of all conversions occurred in that year plus the area converted in the 19 previous years. Only CO₂ emissions from flooded lands have been estimated. In wetlands remaining wetlands no activities are implemented. According to equation 7.10 of the 2006 IPCC guidelines (vol. 4, chapter 7), the biomass stock after flooding is assumed to be zero, while, for the biomass immediately before flooding, default values reported in the 2006 IPCC guidelines have been used. For grassland (B_{before}) the value reported in Table 6.4 (vol. 4, chapter 6) for warm temperate dry climate, 6.1 t d.m. ha⁻¹, has been used; while for cropland (B_{before}) the value equal to 10 t d.m. ha⁻¹ has been used (vol. 4, chapter 6) for cropland containing annual crops. The carbon fraction of 4.7 t of carbon ha⁻¹ has been used.

C stocks [kt C] in living biomass are reported in tables 6.39 and 6.40, for cropland converted to wetlands and grassland converted to wetlands, respectively.

Table 6.39 Change in carbon stocks in living biomass in cropland converted to wetlands

	annual change	20 years change	B after	B before	ΔC converted
	<i>kha</i>	<i>kha</i>	<i>t d.m. ha⁻¹</i>	<i>t d.m. ha⁻¹</i>	<i>kt C</i>
1990	0.00	0.00	0.00	10.00	0.00
1995	0.00	0.00	0.00	10.00	0.00
2000	0.47	2.37	0.00	10.00	-2.23
2005	0.47	4.74	0.00	10.00	-2.23
2010	7.52	21.19	0.00	10.00	-35.34
2015	7.52	58.79	0.00	10.00	-35.34
2020	0.00	56.42	0.00	10.00	0.00
2021	0.00	55.95	0.00	10.00	0.00
2022	0.00	55.47	0.00	10.00	0.00
2023	0.00	55.47	0.00	10.00	0.00
2024	0.00	55.47	0.00	10.00	0.00

Table 6.40 Change in carbon stocks in living biomass in grassland converted to wetlands

	annual change	20 years change	B after	B before	ΔC converted
	<i>kha</i>	<i>kha</i>	<i>t d.m. ha⁻¹</i>	<i>t d.m. ha⁻¹</i>	<i>kt C</i>
1990	0.00	0.00	0.00	6.10	0.00
1995	0.47	2.37	0.00	6.10	-1.36
2000	0.00	2.37	0.00	6.10	0.00
2005	0.00	2.37	0.00	6.10	0.00
2010	0.00	2.37	0.00	6.10	0.00
2015	0.00	0.00	0.00	6.10	0.00
2020	3.01	15.04	0.00	6.10	-8.62
2021	0.00	15.04	0.00	6.10	0.00
2022	0.00	15.04	0.00	6.10	0.00
2023	0.00	15.04	0.00	6.10	0.00
2024	0.00	15.04	0.00	6.10	0.00

6.5.5 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of the 2006 IPCC Guidelines (IPCC, 2006), resulting equal to 106% for wetlands category. Input uncertainties for

activity data and emission factors have been assessed based on the information provided in the 2006 IPCC Guidelines (IPCC, 2006).

6.5.6 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the sum of sub-categories; where possible, activity data comparison among different sources (FAO database⁵¹, ISTAT data⁵²) has been made. Data entries have been checked several times during the compilation of the inventory; particular attention has been focused on the categories showing significant changes between two years in succession. Land use matrices have been accurately checked and cross-checked to ensure that data were properly reported. Several QA activities are carried out in different phases of the inventory process. All the LULUCF categories have been embedded in the overall QA/QC-system of the Italian GHG inventory.

6.5.7 Category-specific recalculations

No recalculation occurs in the 2026 submission, compared to the 2025 submission.

6.5.8 Category-specific planned improvements

Italy is currently implementing a change in the land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

6.6 Settlements (4E)

6.6.1 Description

Under this category, CO₂ emissions from living biomass and soil, from land converted to settlements, have only been reported. In 2024, settlements emissions share 1.6% of absolute CO₂ eq. LULUCF emissions and removals. CO₂ emissions and removals from land converted to settlements have been identified as a key category, in the level and in trend assessment, with Approach 1 and Approach 2.

6.6.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

Information on the land representation is reported in section 6.1.

6.6.3 Land-use definitions and the classification systems used and their correspondence to the LULUCF categories

All artificial surfaces, transportation infrastructures (urban and rural), power lines and human settlements of any size, including parks, have been included in this category.

⁵¹ FAO, 2015. FAOSTAT, <http://faostat3.fao.org/home/E>

⁵² ISTAT, several years [a], [b], [c]

6.6.4 Methodological issues

Settlements remaining Settlements

Following the 2006 IPCC Tier 1 approach, no C stock changes have been estimated for any of the C pools.

Land converted to Settlements

The 2006 IPCC Guidelines equations 2.15 and 2.16 (Vol. 4, chapter 2) have been used to estimate changes in biomass and DOM carbon stocks. According to IPCC Tier 1, biomass and DOM stocks in the settlements category are assumed to be 0, which means that a complete loss of biomass and DOM stocks due to the land use change.

As reported in table 6.4, in the period 1990-2024 conversions to settlements have occurred from the following categories: forest land, grassland, cropland and other land.

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes for land converted to settlements has been significantly modified. The revised estimate considers the 20-year transition period and assumes an SOC value for settlements equal to 80% of the previous land use category, in accordance with the 2006 IPCC Guidelines (Vol. 4, Chapter 8). In addition, SOC values for annual and woody crops, as well as for grasslands, have been updated. The same regional-level SOC values used for estimating soil carbon stock changes in cropland remaining cropland, and grassland remaining grassland have been adopted here as well.

Carbon stock changes in forest land converted to settlements have been estimated for living biomass, dead organic matter and mineral soils, using forest land carbon stocks estimated, at regional level, by the *For-est* model described in paragraph 6.2.4 and in Annex 11.

Concerning forest soils, the SOC stocks reported in Table 6.41 have been considered; the time range reported in the first column of the abovementioned table provides the time references for the SOC stocks' use.

Table 6.41 Soil organic carbon (SOC) stocks for forest land

<i>years</i>	SOC stock <i>t C ha⁻¹</i>
1985-1994	79.809
1995-1999	80.174
2000-2004	80.586
2005-2009	81.121
2010-2014	81.682
2015-2020	81.945
2021-2024	81.738

In Table 6.42, C stock changes [kt C] in living biomass, dead organic matter and soils in forest land converted to settlements are reported.

Table 6.42 Change in carbon stocks in forest land converted to settlements

Year	Forest land to settlements				Total Carbon stock kt C
	conversion Area kha	living biomass kt C	dead organic matter kt C	soils kt C	
1990	0.72	-32.09	-3.06	-0.58	-35.72
1995	0.72	-33.24	-3.05	-0.58	-36.87
2000	0.72	-34.23	-3.04	-0.58	-37.85
2005	3.69	-183.39	-15.53	-3.00	-201.92
2010	3.69	-192.82	-15.45	-3.02	-211.29
2015	3.69	-204.16	-15.37	-3.03	-222.56
2020	3.69	-198.14	-15.30	-3.03	-216.47
2021	3.69	-197.14	-15.27	-3.02	-215.43
2022	3.69	-196.30	-15.24	-3.02	-214.55
2023	3.69	-196.36	-15.20	-3.02	-214.59
2024	3.69	-196.85	-15.21	-3.02	-215.08

For cropland converted to settlements, carbon stock changes have been estimated, for annual or perennial crop biomass, using default factors shown in the following table 6.43 (IPCC, 2006, Table 8.4, vol. 4, chapter 8) as shown in Table 6.43. The SOC stock value has been updated using the same regional level values used to estimate SOC stock changes in cropland remaining cropland: the average SOC stock values are equal to 29.9 t C ha⁻¹ for annual crops and 31.7 t C ha⁻¹ for woody crops.

Table 6.43 Stock change factors for cropland

Biomass carbon stock t C ha ⁻¹	
Annual cropland	4.7
Perennial woody cropland	10

For grassland converted to settlements, changes in carbon stocks have been estimated for living biomass, using the IPCC default value equal to 6.1 t d.m. ha⁻¹ (warm temperate dry climate, table 6.4, IPCC 2006). The SOC stock value has been updated using the same regional-level values used to estimate SOC stock changes in grassland remaining grassland: the average SOC value is equal to 59.5 t C ha⁻¹. In Table 6.44, the C stock changes [kt C] in living biomass in cropland and grassland converted to settlements are reported.

Table 6.44 Change in carbon stocks in living biomass in cropland and grassland converted to settlements

Year	cropland to settlements		grassland to settlements	
	conversion area kha	carbon stock kt C	conversion area kha	carbon stock kt C
1990	25.15	-151.84	1.73	-4.96
1995	0.00	0.00	26.70	-76.56
2000	26.70	-160.96	0.00	0.00
2005	23.73	-144.62	0.00	0.00
2010	10.98	-68.09	0.00	0.00
2015	10.98	-67.42	0.00	0.00
2020	0.00	0.00	10.98	-31.48
2021	0.00	0.00	10.98	-31.48
2022	0.00	0.00	10.98	-31.48
2023	10.98	-67.70	0.00	0.00
2024	10.98	-67.65	0.00	0.00

In table 6.45, SOC changes [kt C] in mineral soils in cropland and grassland converted to settlements are reported.

Table 6.45 Change in carbon stocks in soil in cropland and grassland converted to settlements

Year	cropland to settlements		grassland to settlements	
	conversion area kha	carbon stock kt C	conversion area kha	carbon stock kt C
1990	25.15	-7.64	1.73	-1.03
1995	0.00	0.00	26.70	-15.88
2000	26.70	-8.11	0.00	0.00
2005	23.73	-7.21	0.00	0.00
2010	10.98	-3.34	0.00	0.00
2015	10.98	-3.34	0.00	0.00
2020	0.00	0.00	10.98	-6.53
2021	0.00	-3.34	0.00	0.00
2022	0.00	-3.34	0.00	0.00
2023	10.98	-3.34	0.00	0.00
2024	10.98	-3.34	0.00	0.00

Concerning other land converted to settlements, change in carbon stocks has not been estimated, in line with the 2006 IPCC Guidelines (IPCC, 2006), as other land does not contain any significant carbon stocks.

6.6.5 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of 2006 IPCC Guidelines (IPCC, 2006), resulting in equal to 106% for settlements category. Input uncertainties dealing with activity data and emission factors have been assessed based on the information provided in the 2006 IPCC Guidelines (IPCC, 2006).

6.6.6 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness in the sum of sub-categories; where possible, activity data comparison among different sources (FAO database⁵³, ISTAT data⁵⁴) has been made. Data entries have been checked several times during the compilation of the inventory; particular attention has been focused on the categories showing significant changes between two years in succession. Land use matrices have been accurately checked and cross-checked to ensure that data were properly reported. Several QA activities are carried out in different phases of the inventory process. All the LULUCF categories have been embedded in the overall QA/QC-system of the Italian GHG inventory.

6.6.7 Category-specific recalculations

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes for land converted to settlements has been significantly modified. The revised estimate considers the 20-year transition period and assumes an SOC value for settlements equal to 80% of the previous land use category, in accordance with the 2006 IPCC Guidelines (Vol. 4, Chapter 8). In addition, SOC values for annual and woody crops, as well as for grasslands, have been updated. These revisions have triggered a remarkable recalculation in 2026 submissions, compared to the 2025 submission, as shown in table 6.46.

⁵³ FAO, 2015, FAOSTAT, <http://faostat3.fao.org/home/E>

⁵⁴ ISTAT, several years [a], [b], [c]

Table 6.46 Recalculation in settlements category

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ - kt</i>								
Settlements	738	759	1,297	1,037	1,075	933	1,050	1,047	1,047
2025 submission	<i>CO₂ - kt</i>								
Settlements	6,640	8,272	6,492	4,402	4,445	5,152	5,145	5,142	5,142
recalculation	<i>%</i>								
Settlements	-800.06	-990.28	-400.47	-324.66	-313.26	-452.12	-389.82	-391.1	-391.17

The change in F_{SOM} , due to the abovementioned soil carbon stock change, triggered the recalculation of the direct and indirect N₂O emissions, as shown in Tables 6.54, 6.55 and 6.57.

6.6.8 Category -specific planned improvements

Italy is currently implementing a change in the land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

6.7 Other Land (4F)

Under this category, CO₂ emissions from living biomass, dead organic matter and soils, from land converted to other land should be accounted for; no data is reported since the conversion to other land is not occurring.

6.8 Direct and indirect N₂O emissions from N inputs to managed soils (4(I))

N₂O emissions from N inputs to managed soils of cropland and grassland are reported in the agriculture sector; therefore, only N inputs to managed soils in forest land should be included in this section. All the related emissions are reported in Agriculture sector, following the 2006 IPCC Guidelines (IPCC, 2006, par. 11.2.1.3, vol. 4, chapter 11).

6.9 Emissions and removals from drainage and rewetting and other management of organic and mineral soils (4(II))

6.9.1 Description

Under this section, CO₂ and CH₄ emissions from drained organic soils under the cropland and grassland land-use categories are reported. Organic soils emissions under cropland remaining cropland are key category only in level and trend assessment with Approach 2.

Drained organic soils account for 822.31 kt CO₂ eq in 2024, representing 1.23% of total net CO₂eq emissions. Drained organic soils under cropland account for 96% of these emissions, while those under grassland account for the remaining 4%.

6.9.2 Methodological issues

The areas of organic soils are derived from the FAOSTAT⁵⁵ database, which overlays:

- the map of Histosols classes in the *Harmonized World Soil Database*⁵⁶, and
- the grassland and “cropland” classes in the global land cover dataset, GLC2000⁵⁷.

Table 6.47 summarizes the organic soil areas for cropland and grassland.

Table 6.47 Area of organic soils divided into cropland and grassland

year	Cropland drained organic soils ha	Grassland drained organic soils ha
1990	23,641	1,143
1995	23,590	1,140
2000	23,537	1,137
2005	23,694	1,145
2010	23,588	1,140
2015	23,588	1,126
2020	23,206	1,079
2021	23,206	1,079
2022	23,206	1,079
2023	23,206	1,079
2024	23,206	1,079

The areas concerned are mainly located in the Veneto region (near the Venice Lagoon), in the Emilia-Romagna region (around the Po River delta), and in Tuscany (in the area of Lake Massaciuccoli). These areas were almost entirely subjected to artificial drainage starting from the late 19th century and the first half of the 20th century for agricultural or grazing purposes (Gambolati et al., 2003; Gambolati et al., 2005; Carbognini et al., 2006; Giannini et al., 2020). Drainage is still ongoing through networks of ditches and pumping stations (Fornasiero et al., 2002; Gambolati et al., 2003; Gambolati et al., 2005; Carbognini et al., 2006; Ciccolini et al., 2013; Giannini et al., 2020). Only a few publications document the presence of experimental areas subjected to rewetting (Ciccolini et al., 2013; Giannini et al., 2017; Giannini et al., 2020). Since these cases are extremely limited in terms of surface area (e.g. 15 hectares, as reported by Ciccolini et al., 2013; Giannini et al., 2020), are not common across the national territory, and no specific information is available on whether such activities have continued, Italy conservatively assumes that all organic soils under cropland and grassland remain drained.

⁵⁵ FAOSTAT database: <https://www.fao.org/faostat/en/#data/GV>

⁵⁶ FAO/IIASA/ISRIC/ISSCAS/JRC, 2012. Harmonized World Soil Database (version 1.2). FAO, Rome, Italy and IIASA, Laxenburg, Austria.

⁵⁷ EC-JRC. 2003. Global Land Cover 2000 database. Available at <http://bioval.jrc.ec.europa.eu/products/glc2000/glc2000.php>

The methodology to estimate GHG emissions follows Chapter 2 of the 2013 Supplement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories: Wetlands (hereafter referred to as the IPCC 2013 Wetlands Supplement). Equations 2.2, 2.3 and 2.4 have been used to estimate CO₂ emissions, while equation 2.6 was used for CH₄ emissions. N₂O emissions were estimated consistently and are reported under Agriculture sector, as described in Section 5.5 (Direct N₂O emissions from managed soils in areas of drained/managed organic soils – FOS) of this document.

Considering the emission factors, no national data is available on drainage depth or nutrient status of these soils. However, following the guidance of the IPCC 2013 Wetlands Supplement, these areas were assumed to be deep-drained and, where required, nutrient-rich, in line with the 2006 IPCC Guidelines assumption (Chapter 7, p. 12). These assumptions represent the most conservative approach.

Table 6.48 specifies, for cropland and grassland drained organic soils, the drainage and nutrient status assumed, the climatic zone, the mean emission factor applied, the corresponding IPCC 2013 Wetlands Supplement table number and equation applied.

The last term of Equation 2.2 in the IPCC 2013 Wetlands Supplement - CO₂ emissions from fires on organic soils ($L_{fire}-CO_2-C$) - is assumed to be zero, as no data are available on this topic.

Table 6.48 Summary of the CO₂ emission factors applied, specifying the equations in which they were used and the sources from which they were derived

Land-use category	Specification	Climate/Vegetation zone	Emission factor (t CO ₂ -C ha ⁻¹ yr ⁻¹)	IPCC 2013 WS table	Emission component
CL	Cropland, drained	Boreal and Temperate	7.9	2.1	on-site
GL	Grassland, deep-drained, nutrient-rich	Temperate	6.1	2.1	on-site
CL and GL	-	Temperate	0.31	2.2	DOC_DRAINED

CH₄ emissions have been estimated using Equation 2.6 of the IPCC 2013 Wetlands Supplement. This equation requires the parameter $Frac_{ditch}$, as defined at the end of page 2.22 of the source.

Among national literature sources, only Fornasiero et al. (2002) provide a detailed description of the drainage system, but only for a specific area (Zennare Basin, near the Venetian lagoon):

"The drainage network is made from a small number of channels approximately 5 m wide and 1.5 m deep, connected to a fine system of small ditches that subdivide the basin into rectangular fields of about 30–50 × 200–500 m and control the depth of the water table."

Assuming average field dimensions of 40 × 350 m (width × length) and channel widths of 5 m, a $Frac_{ditch}$ value of approximately 0.1236 has been obtained. This value appears relatively high and leads to conservative emission estimates. The emission factors used in the IPCC 2013 Wetlands Supplement equation 2.6 are reported and described in Table 6.49.

Table 6.49 Summary of the CH₄ emission factors applied, specifying the equations in which they were used and the sources from which they were derived

Land-use category	Specification	Climate/Vegetation zone	Emission factor (kg CH ₄ ha ⁻¹ yr ⁻¹)	IPCC 2013 WS table	Emission component
CL	Cropland, drained	Boreal and Temperate	0	2.3	CH ₄ _land
GL	Grassland, deep-drained, nutrient-rich	Temperate	16	2.3	CH ₄ _land
CL and GL	Deep-drained Grassland Cropland	Boreal / Temperate	1165	2.4	CH ₄ _ditch

The resulting emission estimates are presented in Table 6.50, disaggregated into cropland and grassland

Table 6.50 Estimates of CO₂ and CH₄ emissions from drained organic soils, split between cropland and grassland

year	Cropland drained organic soils		Grassland drained organic soils	
	kt -CO ₂	kt -CH ₄	kt -CO ₂	kt -CH ₄
1990	711.68	3.41	26.85	0.18
1995	710.13	3.40	26.79	0.18
2000	708.53	3.39	26.72	0.18
2005	713.28	3.41	26.92	0.18
2010	710.08	3.40	26.79	0.18
2015	710.08	3.40	26.46	0.18
2020	698.59	3.34	25.36	0.17
2021	698.59	3.34	25.36	0.17
2022	698.59	3.34	25.36	0.17
2023	698.59	3.34	25.36	0.17
2024	698.59	3.34	25.36	0.17

6.9.3 Uncertainty

Uncertainty was quantified using uncertainty propagation methods consistent with IPCC guidance and was incorporated into the Cropland and Grassland estimates presented in Sections 6.3.5 and 6.4.5.

6.9.4 Category-specific recalculations

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841 for organic soils under cropland and grassland, a literature analysis on this topic was carried out. This review led to the conclusion that all organic soil areas identified using the methodology described in this section, and falling under cropland and grassland, are subject to drainage. Consequently, these emissions were estimated using the methodology presented here and were moved from CRT Tables 4.B and 4.C to CRT Table 4(II).

Therefore, the recalculations in this section amount to 100%, as these estimates are entirely new compared with previous submissions (Table 6.51).

Table 6.51 Recalculation for drained organic soils (CRT Table 4(II))

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	CO ₂ eq - kt								
Drained organic soils	838.94	835.21	840.82	837.04	836.65	822.31	822.31	822.31	822.31
<i>Cropland</i>	807.03	803.45	808.83	805.21	805.21	792.18	792.18	792.18	792.18
<i>Grassland</i>	31.91	31.76	31.99	31.83	31.44	30.13	30.13	30.13	30.13
2025 submission	CO ₂ eq - kt								
Drained organic soils	NO	NO	NO	NO	NO	NO	NO	NO	NO
<i>Cropland</i>	NO	NO	NO	NO	NO	NO	NO	NO	NO
<i>Grassland</i>	NO	NO	NO	NO	NO	NO	NO	NO	NO
recalculation	%								
Drained organic soils	100	100	100	100	100	100	100	100	100
<i>Cropland</i>	100	100	100	100	100	100	100	100	100
<i>Grassland</i>	100	100	100	100	100	100	100	100	100

6.10 Direct and indirect N₂O emissions from N mineralization/immobilization associated with loss/gain of soil organic matter resulting from change of land use or management of mineral soils (4(III))

6.10.1 Direct N₂O emissions from N mineralization/immobilization

6.10.1.1 Description

Under this category, direct N₂O emissions from N mineralization associated with loss of soil organic matter in mineral soils in land converted to cropland, grassland remaining grassland, and to settlements are reported.

6.10.1.2 Methodological issues

N₂O emissions from mineralization of soil organic matter in mineral soils occur in land converted to cropland, from grassland remaining grassland, and land converted to settlements. The 2006 IPCC Guidelines eq. 11.1 and 11.8 (vol. 4, chapter 11) have been used to estimate the direct N₂O emissions. IPCC default values, from 2006 Guidelines have been used, namely 15 for the C/N ratio and 0.01 kg N₂O-N/kg N as EF.

In tables 6.52, 6.53 and table 6.54 N₂O emissions from land-use conversion to cropland, from grassland remaining grassland, and from land-use conversion to settlements are reported, respectively.

Table 6.52 Direct N₂O emissions from land-use conversion to cropland

year	Carbon stock change kt C	F _{SOM} kt N	N ₂ O _{net-min} -N kt N ₂ O-N	N ₂ O emissions kt N ₂ O
1990	-204.2	13.61	0.14	0.21
1995	-330.5	22.03	0.22	0.35
2000	-126.3	8.42	0.08	0.13
2005	-126.3	8.42	0.08	0.13
2010	-126.3	8.42	0.08	0.13
2015	NO	-	NO	NO
2020	-204.2	13.61	0.14	0.21
2021	-204.2	13.61	0.14	0.21
2022	-204.2	13.61	0.14	0.21
2023	-204.2	13.61	0.14	0.21
2024	-204.2	13.61	0.14	0.21

Table 6.53 Direct N₂O emissions from grassland

year	Carbon stock change kt C	F _{SOM} kt N	N ₂ O _{net-min} -N kt N ₂ O-N	N ₂ O emissions kt N ₂ O
1990	-43.6	2.91	0.03	0.05
1995	275.8	-	NO	NO
2000	326.5	-	NO	NO
2005	399.3	-	NO	NO
2010	467.2	-	NO	NO
2015	163.4	-	NO	NO
2020	-22.5	1.50	0.01	0.02
2021	-89.9	6.00	0.06	0.09

	Carbon stock change	FSOM	N ₂ O _{net-min} -N	N ₂ O emissions
<i>year</i>	<i>kt C</i>	<i>kt N</i>	<i>kt N₂O-N</i>	<i>kt N₂O</i>
2022	-105.1	7.01	0.07	0.11
2023	-161.5	10.77	0.11	0.17
2024	-210.5	14.03	0.14	0.22

Table 6.54 Direct N₂O emissions from land-use conversion to settlements

	Carbon stock change	FSOM	N ₂ O _{net-min} -N	N ₂ O emissions
<i>year</i>	<i>kt C</i>	<i>kt N</i>	<i>kt N₂O-N</i>	<i>kt N₂O</i>
1990	-83.7	5.58	0.06	0.09
1995	-155.8	10.39	0.10	0.16
2000	-182.1	12.14	0.12	0.19
2005	-217.0	14.46	0.14	0.23
2010	-216.9	14.46	0.14	0.23
2015	-166.4	11.10	0.11	0.17
2020	-170.8	11.38	0.11	0.18
2021	-168.4	11.23	0.11	0.18
2022	-166.1	11.07	0.11	0.17
2023	-163.8	10.92	0.11	0.17
2024	-161.4	10.76	0.11	0.17

6.10.1.3 Category-specific recalculations

In the 2026 submission, a recalculation was performed (see Table 6.55) compared with the 2025 submission, due to the following reasons:

- Following the recommendation raised during the 2025 Comprehensive Review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes for land converted to settlements has been revised. As described in Section 6.6.7, the updated estimate applies the 20year transition period and assumes an SOC value for settlements equal to 80% of the previous land use category, in accordance with the 2006 IPCC Guidelines (Vol. 4, Chapter 8). In addition, SOC values for annual crops, woody crops, and grasslands have been updated. These revisions triggered a substantial recalculation in the 2026 submission, including for direct N₂O emissions across the entire time series.
- For both cropland and grassland land use categories, a change in the activity data for a specific annual crop from 2020 onwards, based on updated information from the national statistical source (ISTAT). As described in Sections 6.3.7 and 6.4.7, due to the land use smoothing process and the land use change rules outlined in Section 6.1, this update affects the balance between cropland and grassland areas from 2016 onwards. The effect is evident not only in CO₂ emissions but also, consequently, in the N₂O emissions shown in Table 6.55.

Table 6.55 Recalculation in direct N₂O emissions from N mineralization/immobilization associated with loss/gain of soil organic matter resulting from change of land use or management of mineral soils

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>N₂O - kt</i>								
Direct N ₂ O emissions	0.35	0.32	0.36	0.36	0.17	0.42	0.48	0.5	0.55
2025 submission	<i>N₂O - kt</i>								
Direct N ₂ O emissions	1.96	1.78	1.86	1.1	0.97	1.51	1.63	1.69	1.8
recalculation	<i>%</i>								
Direct N ₂ O emissions	-463.12	-450.7	-416.09	-206.09	-455.92	-263.51	-235.38	-239.55	-225.01

6.10.2 Indirect N₂O emissions from N mineralization/immobilization

6.10.2.1 Description

Direct N₂O emissions from N inputs of synthetic and organic fertilizer to managed soils in any land use categories are reported in the agriculture sector; accordingly, the indirect N₂O emissions are reported in the agriculture sector too. In this category, only the indirect N₂O emissions from N mineralization associated with loss of soil organic matter are reported.

6.10.2.2 Methodological issues

Indirect N₂O emissions from nitrogen leaching and runoff have been estimated with method (equation 11.10) and default values (Table 11.3) from the 2006 IPCC Guidelines (vol. 4, ch. 11). In particular, 0.3 for the $F_{\text{CLEACH-(H)}}$ and 0.0075 kg N₂O-N/kg N default values have been adopted for the EF₅. Indirect N₂O emissions are shown in table 6.56.

Table 6.56 Indirect N₂O emissions from managed soils - Nitrogen leaching and run-off

<i>year</i>	<i>F_{SOM} kt N</i>	<i>N₂O_{net-min} -N kt N₂O-N</i>	<i>N₂O emissions kt N₂O</i>
1990	19.19	0.04	0.07
1995	32.42	0.07	0.11
2000	20.56	0.05	0.07
2005	22.88	0.05	0.08
2010	22.88	0.05	0.08
2015	11.10	0.02	0.04
2020	25.00	0.06	0.09
2021	24.84	0.06	0.09
2022	24.68	0.06	0.09
2023	24.53	0.06	0.09
2024	24.37	0.05	0.09

6.10.2.3 Category-specific recalculations

In the 2026 submission, a recalculation was performed (see Table 6.57) compared with the 2025 submission, for the same reasons described in Section 6.10.1.3. In summary, a methodological revision was applied to the SOC stock-change estimates for settlements, and an update of activity data was introduced for cropland and grassland. The methodological change resulted in a recalculation of emissions across the entire time series, while the activity data update affected the estimates from 2016

onwards. In addition, indirect N₂O emissions from soils have now been accounted for settlements category, emissions that were not included in previous submissions.

Table 6.57 Recalculation in indirect N₂O emissions from N mineralization associated with loss of soil organic matter

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>N₂O - kt</i>								
Indirect N ₂ O emissions	0.07	0.07	0.08	0.08	0.04	0.09	0.09	0.09	0.09
2025 submission	<i>N₂O - kt</i>								
Indirect N ₂ O emissions	0.05	0.03	0.03	0.03	NO	0.07	0.08	0.1	0.11
recalculation	<i>%</i>								
Indirect N ₂ O emissions	29.07	59.05	63.21	63.2	100	24.69	6.8	-11.81	-30.44

6.11 Biomass Burning (4(IV))

6.11.1 Description

Under this source category, CH₄ and N₂O emissions from wildfires occurring in forest land and CO₂, CH₄ and N₂O emissions from wildfires occurring in cropland and grassland categories are estimated. Areas affected by fires encompassed in settlements category have been reported, but no emissions are estimated, since the emissions have been assumed to be insignificant. An approximate estimate of GHG emissions from settlements has been carried out based on the 2006 IPCC (i.e., value for shrublands, table 2.4, vol. 4, chapter 2, namely 26.7 t dm/ha). This resulted in a maximum of 8.89 kt CO₂ eq. in 2017 (4.26 kt CO₂ eq. in 2024), which is less than 500 kt CO₂ eq. and represents about 0.006 per cent of the national totals without LULUCF in 2024, which is less than 0.05 per cent of the national totals without LULUCF in 2024.

CH₄ and N₂O emissions from wildfires occurring in forest land have been estimated on a specific model (For-Fires), which is described in Annex 12. CO₂ emissions due to forest fires in forest land remaining forest land and land converting to forest land have been estimated as described in Section 6.2.4 and included in CRT Table 4.A, under carbon stock change - losses.

Statistics related to fires occurring in other land use categories (i.e., cropland, grassland, and settlements) have been collected from the Carabinieri Force (the Armed Forces and Police Authority where the State Forestry Service is embedded, following the legislative decree 19/08/2016, n. 177), currently in charge of the data collection related to burned area. The CO₂ emissions due to wildfires in cropland and grassland are only those referred to woody vegetation (perennial crops and other wooded lands). CO₂ emissions from biomass burning in annual crops and grazing lands are not reported since they are largely balanced by the CO₂ uptake.

Non-CO₂ emissions from fires have been estimated and reported in CRT table 4(IV), while NO_x, CO and NMVOC emissions from fires have been reported in CRT table 4.

6.11.2 Methodological issues

The biomass loss due to forest fires has been estimated following the methodology described in Section 6.2.4, which also outlines the approach used to estimate CO₂ emissions in CRT Table 4.A, under carbon

stock change - losses. Detailed information on the estimation of non-CO₂ emissions from forest fires is provided in Annex 12.

Forest, cropland, and grassland burned biomass have been estimated following the 2006 IPCC methodology (vol. 4, chapter 2, eq. 2.27), and then, multiplied by the IPCC default emission factors (table 2.5, IPCC, 2006) to estimate CH₄, N₂O, CO and NO_x wildfire emissions. Italy assumes the mass of croplands and grasslands affected by wildfires is entirely lost, meaning the combustion factor of equation 2.27 of 2006 IPCC methodology (vol. 4, chapter 2) is set to 1.

In table 6.58 CH₄ and N₂O emissions resulting from mass burning in forest land category are reported.

Table 6.58 CH₄ and N₂O emissions from biomass burning in forest land category

year	Forest land remaining forest land		Land converted to forest land	
	CH ₄ kt	N ₂ O kt	CH ₄ kt	N ₂ O kt
1990	11.03	0.61	1.10	0.06
1995	2.19	0.12	0.29	0.02
2000	5.20	0.29	0.91	0.05
2005	2.06	0.11	0.45	0.03
2010	1.79	0.10	0.35	0.02
2015	2.50	0.14	0.43	0.02
2020	3.73	0.21	0.57	0.03
2021	9.28	0.51	2.20	0.12
2022	6.08	0.34	1.55	0.09
2023	4.64	0.26	1.26	0.07
2024	2.45	0.14	0.71	0.04

In table 6.59 CO₂, CH₄ and N₂O emissions resulting from mass burning in cropland and grassland categories are reported.

Table 6.59 CO₂, CH₄ and N₂O emissions from biomass burning in cropland and grassland categories

year	Cropland			Grassland		
	CO ₂ kt	CH ₄ kt	N ₂ O kt	CO ₂ kt	CH ₄ kt	N ₂ O kt
1990	39.82	0.11	0.01	5,032.03	13.72	0.76
1995	11.46	0.03	0.00	1,324.25	3.61	0.20
2000	23.18	0.06	0.00	2,945.32	8.03	0.44
2005	10.73	0.03	0.00	1,270.28	3.46	0.19
2010	8.55	0.02	0.00	1,748.79	4.77	0.26
2015	17.63	0.05	0.00	721.49	1.97	0.11
2020	14.65	0.04	0.00	699.92	1.91	0.11
2021	42.96	0.12	0.01	2,240.02	6.11	0.34
2022	29.23	0.08	0.00	2,086.33	5.69	0.31
2023	13.31	0.04	0.00	1,131.97	3.09	0.17
2024	26.26	0.07	0.00	1,056.72	2.88	0.16

6.11.3 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of 2006 IPCC Guidelines (IPCC, 2006), resulting equal to 70.2% for biomass burning under forest land, to 92.2% for cropland and to 92.2% for grassland. Input uncertainties dealing with activity data and emission factors have been assessed based on the information provided in the 2006 IPCC Guidelines (IPCC, 2006).

6.11.4 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness. Data entries have been checked several times during the compilation of the inventory. Several QA activities are carried out in different phases of the inventory process. In particular, the applied methodologies have been presented and discussed during several national workshops and expert meetings, collecting findings and comments to be incorporated in the estimation process. All the LULUCF categories have been embedded in the overall QA/QC-system of the Italian GHG inventory.

6.11.5 Category-specific recalculations

As shown in table 6.60, a recalculation was introduced in the 2026 submission for GHG emissions from biomass burning, compared to the 2025 submission. The recalculation affected forest land (CH₄ and N₂O) and grassland in 2023, due to the correction of an error in the estimation of the activity data for these two land-use categories affected by fires in Sicily in 2023.

Table 6.60 Recalculation of emissions from biomass burning occurring in forest land, cropland and grassland

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>Forest land</i>									
CH ₄ - kt	12.13	2.47	6.11	2.51	2.14	2.94	4.30	11.48	7.63	5.90
N ₂ O - kt	0.67	0.14	0.34	0.14	0.12	0.16	0.24	0.64	0.42	0.33
	<i>Cropland</i>									
CO ₂ - kt	39.82	11.46	23.18	10.73	8.55	17.63	14.65	42.96	29.23	13.31
CH ₄ - kt	0.11	0.03	0.06	0.03	0.02	0.05	0.04	0.12	0.08	0.04
N ₂ O - kt	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.00
	<i>Grassland</i>									
CO ₂ - kt	5,032.03	1,324.25	2,945.32	1,270.28	1,748.79	721.49	699.92	2,240.02	2,086.33	1,131.97
CH ₄ - kt	13.72	3.61	8.03	3.46	4.77	1.97	1.91	6.11	5.69	3.09
N ₂ O - kt	0.76	0.20	0.44	0.19	0.26	0.11	0.11	0.34	0.31	0.17
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
2025 submission	<i>Forest land</i>									
CH ₄ - kt	12.13	2.47	6.11	2.51	2.14	2.94	4.30	11.48	7.63	4.32
N ₂ O - kt	0.67	0.14	0.34	0.14	0.12	0.16	0.24	0.64	0.42	0.24
	<i>Cropland</i>									
CO ₂ - kt	39.82	11.46	23.18	10.73	8.55	17.63	14.65	42.96	29.23	13.31
CH ₄ - kt	0.11	0.03	0.06	0.03	0.02	0.05	0.04	0.12	0.08	0.04
N ₂ O - kt	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.00
	<i>Grassland</i>									
CO ₂ - kt	5,032.03	1,324.25	2,945.32	1,270.28	1,748.79	721.49	699.92	2,240.02	2,086.33	934.26
CH ₄ - kt	13.72	3.61	8.03	3.46	4.77	1.97	1.91	6.11	5.69	2.55
N ₂ O - kt	0.76	0.20	0.44	0.19	0.26	0.11	0.11	0.34	0.31	0.14
	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
recalculation	<i>Forest land</i>									
CH ₄ - kt	-	-	-	-	-	-	-	-	-	26.77
N ₂ O - kt	-	-	-	-	-	-	-	-	-	26.77
	<i>Cropland</i>									
CO ₂ - kt	-	-	-	-	-	-	-	-	-	-
CH ₄ - kt	-	-	-	-	-	-	-	-	-	-

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
N ₂ O - kt	-	-	-	-	-	-	-	-	-	-
<i>Grassland</i>										
CO ₂ - kt	-	-	-	-	-	-	-	-	-	17.47
CH ₄ - kt	-	-	-	-	-	-	-	-	-	17.47
N ₂ O - kt	-	-	-	-	-	-	-	-	-	17.47

6.11.6 Category-specific planned improvements

No improvements are planned for the next submission.

6.12 Harvested wood products (HWP) (4G)


6.12.1 Description

Under this source category, annual changes in carbon stocks and associated CO₂ emissions and removals from the Harvested Wood Products (HWP) pool are estimated, following the production approach as outlined in the 2019 Refinement (IPCC, 2019), that revises and corrects errors included in the HWP chapter in the 2006 IPCC Guidelines. CO₂ emissions and removals from HWP have been identified as key category in level and trend assessment with Approach 1 and 2

6.12.2 Methodological issues

Emissions from this source are mainly influenced by the trend in forest harvest rates: in 2024, the net removals from harvested wood products were -2001.5 kt CO₂. The figure 6.8 shows the trend of HWP in use for the period 1961-2024, disaggregated into sawnwood, wood-based panels and paper & paperboard.

Figure 6.8 HWP in use for the period 1961-2024




The activity data (production of sawnwood, wood-based panels and paper and paperboard) are derived from FAO forest product statistics (Food and Agriculture Organization of the United Nations: forest product statistics, <http://faostat3.fao.org/download/F/FO/E>).

The estimates have been carried out based on the 2019 Refinement methodology. The Tier 1 approach, first order decay, was applied to the HWP categories (sawnwood, wood-based panels and paper and paperboard) according to equation 12.2 of the 2019 Refinement (IPCC, 2019, vol. 4, ch. 12), corresponding

to the equation 12.1 of the 2006 IPCC Guidelines (IPCC, 2006, vol. 4, ch. 12). Equation 12.8 of the 2019 Refinement (IPCC, 2019, vol. 4, ch. 12) has been applied to estimate the annual fraction of the feedstock coming from domestic harvest for the HWP categories sawnwood and wood-based panels. The change in carbon stocks was estimated separately for each product category; the default values (table 12.2 in IPCC, 2019) have been applied. Emission factors for specific product categories were calculated with default half-lives of 35 years for sawnwood, 25 years for wood panels and 2 years for paper (Table 12.3, IPCC 2019).

The annual change in stock for the period 1961-2024, disaggregated into sawnwood, wood-based panels and paper & paperboard, is reported in figure 6.9.

Figure 6.9 Annual change in stock (kt C) for the period 1990-2024



6.12.3 Uncertainty and time series consistency

Uncertainty estimates for the period 1990–2024 have been assessed following Approach 1 of 2006 IPCC Guidelines (IPCC, 2006), resulting equal to 55.9% in 2024. The uncertainties of activity data and emission factors used in the estimation process have been assessed based on the uncertainties of the default factors provided in the 2019 Refinement (IPCC, 2019) and the uncertainties of used statistical data.

6.12.4 Category-specific QA/QC and verification

Systematic quality control activities have been carried out to ensure completeness and consistency in time series and correctness. Data entries have been checked several times during the compilation of the inventory. Several QA activities are carried out in different phases of the inventory process. All the LULUCF categories have been embedded in the overall QA/QC-system of the Italian GHG inventory.

6.12.5 Category-specific recalculations

The HWP recalculation occurred in the 2026 submission, compared to the 2025 submission, is shown in table 6.61. The recalculation is due to the revision of FAOSTAT data for wood-based panels, for the years 2020-2023, for paper&paperboard for the years 2022-2023 and for the 2023 data related to the industrial roundwood. Small deviations, comparing the 2026 and 2025 submissions, in the 1990-2020 time series are due to the legacy effect of the FAOSTAT revisions of production, import, and export data prior to 1990.

Table 6.61 Recalculation of emissions and removals from HWP category

	1990	2000	2005	2010	2015	2020	2021	2022	2023
2026 submission	<i>CO₂ eq. - kt</i>								
HWP	-389	-454	-503	-142	88	-799	-787	-516	-1,637
2025 submission	<i>CO₂ eq. - kt</i>								
HWP	-388	-454	-503	-142	89	-646	-358	-426	-524
recalculation	<i>%</i>								
HWP	-0.43	-0.11	-0.08	-0.24	0.33	-23.69	-119.83	-21.14	-212.45

6.12.6 Category-specific planned improvements

No improvements are planned for the next submission.

7 WASTE

7.1 Sector overview

The waste sector comprises four source categories:

- 1 solid waste disposal (5A);
- 2 biological treatment of solid waste (5B);
- 3 incineration and open burning of waste (5C);
- 4 wastewater treatment and discharge (5D).

The waste sector share of GHG emissions in the national greenhouse gas total is presently 5.51% (and was 3.66% in 1990).

The trend in greenhouse gas emissions from the waste sector is summarized in Table 7.1. It clearly shows that methane emissions from solid waste disposal sites (landfills) are by far the largest source category within this sector.

Emissions from waste incineration facilities without energy recovery are reported under category 5C, whereas emissions from waste incineration facilities, which produce electricity or heat for energetic purposes, are reported under category 1A4a.

Under 5B, CH₄, N₂O and NMVOC emissions from compost production and CH₄ emissions from anaerobic digestion of solid waste are reported.

Emissions from methane recovered, used for energy purposes, in landfills and wastewater treatment plants are estimated and reported under category 1A4a.

Table 7.1 Trend in greenhouse gas emissions from the waste sector 1990 – 2024 (kt)

GAS/ SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CO₂ (kt)											
5C. Waste incineration	512.01	458.23	208.26	230.15	171.76	87.76	73.11	90.10	84.49	77.60	76.36
CH₄ (kt)	618.33	728.23	804.84	796.17	734.33	664.24	670.85	661.21	656.41	659.40	651.85
5A. Solid waste disposal on land	488.25	604.93	687.98	680.10	622.46	559.49	568.74	558.63	554.46	558.66	550.69
5B. Biological treatment of waste	0.19	0.43	1.86	3.66	4.65	4.83	4.52	4.5089	4.2706	4.0498	4.0891
5C. Waste incineration	1.90	2.08	2.02	2.70	2.67	2.67	2.60	2.57	2.36	2.44	2.41
5D. Wastewater treatment	127.99	120.79	112.98	109.71	104.56	97.25	94.99	95.49	95.32	94.24	94.66
N₂O (kt)	4.42	4.38	5.10	5.84	6.62	6.37	6.28	6.37	6.20	6.19	6.22
5B. Biological treatment of waste	0.07	0.16	0.68	1.33	1.69	1.75	1.64	1.6311	1.5444	1.4609	1.4732
5C. Waste incineration	0.12	0.11	0.08	0.10	0.09	0.08	0.08	0.08	0.07	0.08	0.07
5D. Wastewater treatment	4.22	4.10	4.33	4.41	4.85	4.53	4.57	4.66	4.59	4.65	4.67

In the following box, key and non-key sources of the waste sector are presented based on level, trend or both. Methane emissions from landfills result as a key category at level assessment calculated with Approach 1 and Approach 2 while at trend assessment are key categories only considering uncertainty; N₂O emission from biological treatment of waste is a key category at level and at trend assessment only considering the uncertainty; methane emission from wastewater treatment is a key source at level

assessment with Approach 1 and Approach 2 and at trend assessment only with the approach 2; N₂O emissions from wastewater treatment result as a key category at level and at trend assessment only with the Approach 2, taking into account the uncertainty. When including the LULUCF sector in the key source analysis, CH₄ emissions from landfills are also key categories at trend assessment with the approach 1.

Key-source identification in the waste sector with the IPCC Approach 1 and Approach 2 (without LULUCF) for 2024

5A	CH ₄	Emissions from solid waste disposal sites	Key (L, T2)
5B	N ₂ O	Emissions from biological treatment of waste	Key (L2, T2)
5D	CH ₄	Emissions from wastewater treatment	Key (L, T2)
5D	N ₂ O	Emissions from wastewater treatment	Key (L2, T2)
5B	CH ₄	Emissions from biological treatment of waste	Non-key
5C	CO ₂	Emissions from waste incineration	Non-key
5C	CH ₄	Emissions from waste incineration	Non-key
5C	N ₂ O	Emissions from waste incineration	Non-key

7.2 Solid waste disposal on land (5A)

7.2.1 Source category description

The source category solid waste disposal on land is a key category for CH₄, both in terms of level and trend, but at trend assessment only considering uncertainty. The share of CH₄ emissions is presently 35.9% (and was about 22.2% in the base year 1990) of the CH₄ national total. For this source category, also NMVOC emissions are estimated, assuming that non-methane volatile organic compounds are 1.3 weight per cent of VOC (Gaudioso et al., 1993): this assumption refers to US EPA data (US EPA, 1990).

Methane is emitted from the degradation of waste disposed of in municipal landfills, both managed and unmanaged. The main parameters that influence the estimation of emissions from landfills are, apart from the amount of waste disposed into managed landfills, the waste composition, the fraction of methane in the landfill gas and the amount of landfill gas collected and treated. These parameters are strictly dependent on the waste management policies throughout the waste streams which start from waste generation, flow through collection and transportation, separation for resource recovery, treatment for volume reduction, stabilization, recycling and energy recovery and terminate at landfill sites.

Urban waste disposal in landfill sites is still one of the main disposal practices but the percentage of waste disposed in landfills dropped from 91.1% in 1990 to 21.9% in 2024. This trend is strictly dependent on policies that have been adopted in the last 30 years in waste management. In fact, at the same time, waste incineration as well as composting and mechanical and biological treatment have shown a remarkable rise due to the enforcement of legislation. Also recyclable waste collection, which at the beginning of nineties was a scarce practice and waste were mainly disposed in bulk in landfills or incineration plants, has been increasing: in 2024, the percentage of municipal solid waste separate collection is about 67.7% (the legislative targets fixed 50% in 2009), characterized by a strong growth in recent years.

In particular, in Italy the first legal provision concerning waste management was issued in 1982 (Decree of President of the Republic 10 September 1982, n.915), as a consequence of the transposition of some European Directives on waste (EC, 1975; EC, 1976; EC, 1978). In this decree, uncontrolled waste dumping as well as unmanaged landfills are forbidden, but the enforcement of these measures has been concluded only in 2000. Thus, from 2000 municipal solid wastes are disposed only into managed landfills.

For the year 2024, the non hazardous landfills in Italy disposed 4,429 kt of MSW and 2,116 kt of industrial wastes, as well as 44 kt of sludge from urban wastewater treatment plants.

Since 1999, the number of MSW landfills has decreased by more than 500 plants up to 102 in 2024, despite the decrease of the amount of wastes disposed of is less pronounced. This because both uncontrolled landfills and small controlled landfills have been progressively closed, especially in the south

of the country, where the use of modern and larger plants was opted in order to serve large territorial areas.

Concerning the composition of waste which is disposed in municipal landfills, this has been changed over the years, because of the modification of waste production due to changes in the life-style and not only to a forceful policy on waste management.

The Landfill European Directive (EC, 1999) has been transposed into national decree only in 2003 by the Legislative Decree 13 January 2003 n. 36 and applied to the Italian landfills since July 2005, but the effectiveness of the policies will be significant in the future. Moreover, a following law decree (Law Decree 30 December 2008, n.208) moved to December 2009 the end of the temporary condition regarding waste acceptance criteria, thus the composition of waste accepted in landfills is expected to change slowly.

Finally, methane emissions are expected especially from non hazardous waste landfills due to biodegradability rate of the wastes disposed of; in the past, provisions by law forced only non hazardous waste landfills to have a collecting gas system.

7.2.2 Methodological issues

Emission estimates from solid waste disposal on land have been carried out using the IPCC Tier 2 methodology, through the application of the First Order Decay Model (FOD) with the start of the decay reaction on 1 January in the year after disposal.

Parameter values used in the landfill emissions model are:

- 1) total amount of waste disposed;
- 2) fraction of Degradable Organic Carbon (DOC);
- 3) fraction of DOC dissimilated (DOC_F);
- 4) fraction of methane in landfill gas (F);
- 5) oxidation factor (O_x);
- 6) methane correction factor (MCF);
- 7) methane generation rate constant (k);
- 8) landfill gas recovered (R).

It has been assumed that all the landfills, both managed and unmanaged, started operations in the same year, and have the same parameters, although characteristics of individual landfill sites can vary substantially.

Moreover, the share of waste disposed of into uncontrolled landfills has gradually decreased, as specified previously, and in the year 2000 it has been assumed equal to 0; nevertheless, emissions still have been occurring due to the waste disposed in the past years. The unmanaged sites have been considered "shallow" according to the IPCC classification.

Municipal solid waste

Basic data on waste production and landfills system are those provided by the national Waste Cadastre. The Waste Cadastre is formed by a national branch, hosted by ISPRA, and by regional and provincial branches. The basic information for the Cadastre is mainly represented by the data reported through the Uniform Statement Format (MUD), complemented by information provided by regional permits, provincial communications and by registrations in the national register of companies involved in waste management activities.

These figures have been elaborated and published by ISPRA yearly since 1999: the yearbooks report waste production data, as well as data concerning landfilling, incineration, composting and generally waste life-cycle data (ISPRA, several years).


For inventory purposes, a database of waste production, waste disposal in managed and unmanaged landfills and sludge disposal in landfills was created and it has been assumed that in Italy waste landfilling started in 1950.

The complete database from 1975 of waste production, waste disposal in managed and unmanaged landfills and sludge disposal in landfills is reconstructed on the basis of different sources (MASE, several years [a]; FEDERAMBIENTE, 1992; AUSITRA-Assoambiente, 1995; ANPA-ONR, 1999 [a], [b]; APAT, 2002; ISPRA, several years), national legislation (Legislative Decree 5 February 1997, n. 22), and regression models (Colombari et al., 1998).

Since waste production data are not available before 1975, they have been reconstructed on the basis of proxy variables. Gross Domestic Product data have been collected from 1950 (ISTAT, several years [a]) and a correlation function between GDP and waste production has been derived from 1975; thus, the exponential equation has been applied from 1975 back to 1950.

Consequently, the amount of waste disposed of into landfills has been estimated, assuming that from 1975 backwards the percentage of waste landfilled is constant and equal to 80%; this percentage has been derived from the analysis of available data. As reported in the Figure 7.1, in the period 1973 – 1991 data are available for specific years (available data are reported in dark blue, whereas estimated data are reported in light blue). From 1973 to 1991 waste disposal increased, because the most common practice in waste management; from early nineties, thanks to a change in national policies, waste disposal in landfill has started to decrease, in favor of other waste treatments.

Figure 7.1 Percentage of MSW disposal on land (%)



In the following Table 7.2, the time series of MSW production and MSW disposed of into non hazardous landfills from 1990 is reported. The amount of waste disposed of in managed landfills is yearly provided by the national Waste Cadastre since 1995. The time series has been reconstructed backwards on the basis of several studies reporting data available for 1973, 1988, 1991, 1994 (Tecneco, 1972; MASE, several years [a]).

The amount of waste disposed of in unmanaged landfills has been estimated as a percentage of the waste disposed of in managed landfills. Different studies provided information about the percentage of waste in unmanaged sites for 1973, 1979, 1991 (Tecneco, 1972; ISTAT, 1984, MASE, several years [a]) and data in other years are extrapolated. These studies show that the share of waste disposed of into uncontrolled landfills has gradually decreased, from 72.8%, in 1973, to 53.4% in 1979 and 26.6% in 1991, which is a

consequence of the progressive implementation of the national legislation. Since 2000 the percentage of waste in unmanaged landfills is equal to zero because of legal enforcement described in 7.2.1.

Uncontrolled landfills have been monitored since 1982 when the D.P.R. 915/82 (Decree of the President of the Republic 915/82) introduced this requirement but the effective reduction of uncontrolled landfills occurred only following the D. Lgs. 22/97 with the implementation of European Directives. From 1997 the amount of waste disposed in uncontrolled landfills (landfills not fulfilling the technological standard but allowed with special permits) strongly decreased till 2000 when they were not allowed anymore. Since 2000 police forces as Corpo Forestale dello Stato and Carabinieri (NOE - Environmental Care Command) protect and supervise compliance with the law; if an illegal disposal of waste is revealed they proceed to the seizure and site remediation. The Law 68/2015 introduced in the Italian Penal Code a new Title entirely dedicated to crimes against the environment (Law 22 maggio 2015, n. 68).

Industrial waste

Industrial waste assimilated to municipal solid waste (AMSW) could be disposed of in non hazardous landfills. Composition of AMSW must be comparable to municipal solid waste composition. From 2001, data on industrial waste disposed of in municipal landfills are available from Waste Cadastre. For previous years, assimilated municipal solid waste production has been reconstructed, and the same percentage of MSW disposed of in landfill has been applied also to AMSW. The complete database of AMSW production from 1975 to 2000 has been reconstructed starting from data available for the years 1988 (ISTAT, 1991) and 1991 (MASE, several years [a]) with a linear interpolation, and with a regression model based on Gross Domestic Product (Colombari et al., 1998). From 1975 back to 1950 AMSW production has been derived as a percentage of MSW production; this percentage has been set equal to 15%, which is approximately the value obtained from the only data available (MSW and AMSW production for the years 1988 and 1991).

The time series of AMSW and domestic sludge disposed of into non hazardous landfills from 1990 is reported is also reported in Table 7.2.

Table 7.2 Trend of MSW production and MSW, AMSW and domestic sludge disposed in landfills, 1990 – 2024

ACTIVITY DATA	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
MSW production (Gg)	22,231	25,780	28,959	31,664	32,479	29,524	28,941	29,051	29,269	29,933
MSW disposed in landfills for non hazardous waste (Gg)	17,432	22,459	21,917	17,226	15,015	7,819	5,817	5,173	4,599	4,429
Assimilated MSW disposed in landfills for non hazardous waste (Gg)	2,828	2,978	2,825	2,914	2,639	3,222	2,910	2,469	1,970	2,116
Sludge disposed in managed landfills for non hazardous waste (Gg)	2,454	1,531	1,326	544	345	387	253	64	41	44
Total Waste to managed landfills for non hazardous waste (Gg)	16,363	21,897	26,069	20,684	18,000	11,428	8,980	7,705	6,609	6,589
Total Waste to unmanaged landfills for non hazardous waste (Gg)	6,351	5,071	0	0	-	-	-	-	-	-
Total Waste to landfills for non hazardous waste (Gg)	22,714	26,968	26,069	20,684	18,000	11,428	8,980	7,705	6,609	6,589

Sludge from urban wastewater plants

Sludge from urban wastewater treatment plants has also been considered, because it can be disposed of at the same landfills as municipal solid waste and assimilated, once it meets specific requirements. The fraction of sludge disposed in landfill sites has been estimated to be 75% in 1990, decreasing to 1% in 2024.

Based on their characteristics, sludge from urban wastewater treatment plants is also used in agriculture, sludge spreading on land, and in compost production, or treated in incineration plants.

The percentage of each treatment (landfilling, soil spreading, composting, incinerating and stocking) has been reconstructed within the years starting from 1990: for that year, percentages have been set based on data on tonnes of sludge treated in a given way available from a survey conducted by the National Institute of Statistics on urban wastewater plants for the year 1993 (ISTAT, 1998 [a] and [b]; De Stefanis P. et al., 1998).

From 1990 onwards each percentage has been varied on the basis of data available for specific years: in particular, data on sludge use in agriculture have been communicated by the Ministry for the Environment concerning the reference time period from 1995 (MASE, several years [a]); data on sludge used in compost production are published from 1999, while data on sludge disposed into landfills are published from 2001 (ISPRA, several years).

The total production of sludge from urban wastewater plants is communicated, every three years, by the Ministry of the Environment from 1995 (MASE, several years [b]) in the framework of the reporting commitments established by the European Sewage Sludge Directive (EC, 1986) transposed into the national Legislative Decree 27 January 1992, n. 99.

Moreover, sewage sludge production is available from different sources also for the years 1987, 1991 (MASE, several years [a]) and 1993 (ISTAT, 1998 [a] and [b]). Thus, for the missing years data have been extrapolated.

As for the waste production, sludge production time series has been reconstructed from 1950. Starting from the number of wastewater treatment plants in Italy in 1950, 1960, 1970 and 1980 (ISTAT, 1987), the equivalent inhabitants have been derived.

To summarize, from 1987 both data on equivalent inhabitants and sludge production are available (published or estimated), thus it is possible to calculate a *per capita* sludge production: the parameter results equal on average to 80 kg inhab.⁻¹yr⁻¹. Consequently, this value has been multiplied to equivalent inhabitants from 1987 back to 1950.

In Table 7.3, time series of sewage sludge production and landfilling is reported.

Table 7.3 Trend of total sewage sludge production and landfilling, 1990 – 2024

ACTIVITY DATA	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total sewage sludge production (Gg)	3,272	2,437	3,402	4,299	3,698	3,069	3,390	3,238	3,197	3,203	3,453
Sewage sludge landfilled (Gg)	2,454	1,531	1,326	544	346	387	253	106	64	41	44
Percentage (%)	75.0	62.8	39.0	12.7	9.4	12.6	7.5	3.3	2.0	1.3	1.3

Waste composition

One of the most important parameters that influences the estimation of emissions from landfills is the waste composition. An in-depth survey has been carried out, to diversify waste composition over the years. Based on the waste composition, waste streams have been categorized into three main types: rapidly biodegradable waste, moderately biodegradable waste and slowly biodegradable waste, as reported in Table 7.4. Methane emissions have been estimated separately for each mentioned biodegradability class and the results have been consequently added up.

Table 7.4 Waste biodegradability

Waste biodegradability	Rapidly biodegradable	Moderately biodegradable	Slowly biodegradable
Food	X		
Sewage sludge	X		
Screened waste (organic)	X		
Garden and park		X	
Paper, paperboard			X
Nappies			X
Textiles, leather			X
Wood			X

Based on data available on waste composition (Tecneco, 1972; CNR, 1980; Ferrari G., 1996), three slots (1950-1970; 1971-1990; 1991- 2005) have been individuated to which different waste composition has been assigned.

Waste composition used from 2005 back to 1971 (CNR, 1980; Ferrari G., 1996) has been better specified, on the basis of data available from those publications. Screened waste (< 20mm) has been included in emissions estimation, because 50% of it has been assumed as organic and thus rapidly biodegradable. This assumption has been strengthened by expert judgments and sectoral studies (Regione Piemonte, 2007; Regione Umbria, 2007).

In more recent years, taking advantage of the collaboration of the branch of ISPRA that deals with waste, it has been possible to carry out characterizations of the waste based on the data collected at national level from the relevant land registry. This operation is obviously very expensive from a computational point of view, so today it is possible to carry out an in-depth analysis every 10 years, also making use of the regional studies periodically carried out at local level.

So, a fourth slot (2006- 2015) has been individuated based on the analysis of several regional waste composition and the analysis of waste disposed of into non hazardous landfills specified by the European Waste Catalogue (EWC) code for the year 2007, available from Waste Cadastre database (ISPRA, 2010). Data on waste composition refer to recent years and they are representative of the national territory, deriving from the North of Italy (Regione Piemonte, 2007; Regione Veneto, 2006; Regione Emilia Romagna, 2009), the Centre (Regione Umbria, 2007; Provincia di Roma, 2008) and the South (Regione Calabria, 2002; Regione Sicilia 2004). This last waste composition, adopted from 2006, includes compost residues which are disposed of into landfills because their parameters are not in compliance with those set by the law: compost residues are reported under garden and park waste component, as they are considered moderately biodegradable. The complete AD time series has been reconstructed by filling gaps with the combination of the methods provided in the 2006 IPCC guidelines (mainly overlap and interpolation). Furthermore, the consistency between the last two classifications is ensured by the high detail of the most recent data which has made it possible to univocally associate the waste deposited in landfills in the last period with those of the previous period. This also ensures consistency in the application of the k values.

The moisture content and the organic carbon content are from national studies (Andreottola and Cossu, 1988; Muntoni and Poletti, 2002).

Finally, starting from the settings of the previous work carried out on the 2007 data, the municipal waste sent to landfill was classified into the different classes considered in the 2006 IPCC Guidelines in order to obtain the three categories mentioned above (slowly, moderately and rapidly biodegradable) and a fifth slot (2016 – up to now) has been realized. These values were compared with various regional studies conducted over the last 10 years on the characterization of waste in landfills. The studies taken into consideration were drawn from the PRGRs of Piemonte (Regione Piemonte, 2016), Emilia Romagna (Regione Emilia Romagna, 2016), Toscana (Regione Toscana, 2014), Lazio (Regione Lazio, 2020), Calabria (Regione Calabria, 2016), Campania (Regione Campania, 2016) and Sardinia (Regione Sardegna, 2016). Compared to the previous processing (based on 2007 data), the fractions of food residues (-6%) and

cellulosic materials (-8%) decrease, related to the better penetration and effectiveness of separate waste collection, which are able to better intercept these fractions and subtract them from landfill disposal. On the other hand, the fraction defined here as underscreen (*sottovaglio*) and linked to the increase in TMB (Biological Mechanical Treatments) treatments of waste which has led to an increase in treatment residues. Furthermore, from various studies and hypotheses reported in the PRGRs (Regional Waste Management Plan), an increase in the organic fraction in the underscreen was noted, which was assumed to be equal to 70%.

In Tables 7.5, 7.6, 7.7, 7.8 and 7.9 waste composition of each national survey mentioned above, and waste composition derived from the analysis of EWC code is reported, together with moisture content, organic carbon content and consequently degradable organic carbon both in waste type *i* and in bulk waste, DOC calculation is described in following paragraphs. Waste types containing most of the DOC and thus involved in methane emissions are highlighted in bold type.

Since sludge is not included in waste composition, because it usually refers to waste production and not to waste landfilled, it has been added to each waste composition, recalculating the percentage of waste type.

Table 7.5 Waste composition and Degradable Organic Carbon calculation, 1950 - 1970

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Organic	32.7%	60%	48%	19%	62.73
Garden and park	3.6%	50%	48%	24%	8.71
Paper, paperboard	29.7%	9%	50%	46%	135.11
Plastic	2.9%	2%	70%		
Inert	26.9%				
Sludge	4.2%	75%	48%	12%	5.05
DOC					211.61

Table 7.6 Waste composition and Degradable Organic Carbon calculation, 1971 – 1990

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Organic	33.3%	60%	48%	19%	64.02
Garden and park	3.7%	50%	48%	24%	8.89
Paper, paperboard, textile and wood	19.6%	9%	50%	46%	89.29
Plastic	6.3%	2%	70%		
Inert	6.2%				
Metal	2.6%				
Screened waste (< 2 cm)					
- organic	8.1%	60%	48%	19%	15.46
- non organic	8.1%				
Sludge	12.0%	75%	48%	12%	14.40
DOC					192.06

Table 7.7 Waste composition and Degradable Organic Carbon calculation, 1991 - 2005

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Organic	24.7%	60%	48%	19%	47.36
Garden and park	4.2%	50%	48%	24%	10.09

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Paper, paperboard	25.5%	8%	44%	40%	103.36
Nappies	2.7%	8%	44%	40%	10.98
Textiles	4.8%	10%	55%	50%	23.98
Leather and rubbers	2.1%	2%	70%		
Light plastics	8.9%	2%	70%		
Rigid plastics	3.0%	2%	70%		
Inert and glasses	5.9%				
Metal	2.9%				
Bulky waste	0.5%				
Various	1.5%				
Screened waste (< 2 cm)					
- organic	3.4%	60%	48%	19%	6.60
- non organic	3.4%				
Sludge	6.3%	75%	48%	12%	7.55
DOC					209.92

Table 7.8 Waste composition and Degradable Organic Carbon calculation, 2006 – 2015

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Organic	21.9%	60%	48%	19%	42.07
Garden and park	5.6%	50%	48%	24%	13.53
Wood	1.6%	20%	50%	40%	6.47
Paper, paperboard, nappies	23.9%	8%	44%	40%	96.72
Textiles and leather	3.0%	10%	55%	50%	14.86
Plastics	11.8%	2%	70%		
Metals and Aluminium	2.3%				
Inert and glasses	6.4%				
Bulky waste	2.2%				
Various	6.5%				
Screened waste (< 2 cm)					
- organic	5.4%	60%	48%	19%	10.43
- non organic	5.4%				
Sludge	3.9%	75%	48%	12%	4.68
DOC					188.76

Table 7.9 Waste composition and Degradable Organic Carbon calculation, 2016 – 2022

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Organic	15.9%	60%	48%	19%	30.61
Garden and park	4.3%	50%	48%	24%	10.36
Wood	2.1%	20%	50%	40%	8.54
Paper, paperboard, nappies	16.1%	8%	44%	40%	65.03
Textiles and leather	2.5%	10%	55%	50%	12.50
Plastics	11.7%	2%	70%		

WASTE COMPONENT	Composition by weight (wet waste)	Moisture content	Organic carbon content (dry matter)	DOC content in % of wet waste	DOC _i (kgC/tMSW)
Metals and Aluminium	5.8%				
Inert and glasses	9.5%				
Bulky waste	0.0%				
Various	8.7%				
Screened waste (< 2 cm)					
- organic	14.7%	60%	48%	19%	28.16
- non organic	6.3%				
Sludge	2.4%	75%	48%	12%	2.85
DOC					158.05

Degradable organic carbon (DOC) and Methane generation potential (L₀)

Degradable organic carbon (DOC) is the organic carbon in waste that is accessible to biochemical decomposition and should be expressed as Gg C per Gg of waste. The DOC in waste bulk is estimated based on the composition of waste and can be calculated from a weighted average of the degradable carbon content of various components of the waste stream. The following equation estimates DOC using default carbon content values.

$$DOC = \sum_i (DOC_i * W_i)$$

Where:

DOC = fraction of degradable organic carbon in bulk waste, kg C/kg of wet waste

DOC_i = fraction of degradable organic carbon in waste type *i*,

W_i = fraction of waste type *i* by waste category

Degradable organic carbon in waste type *i* can be calculated as following:

$$DOC_i = C_i * (1 - u_i) * W_i$$

Where:

C_i = organic carbon content in dry waste type *i*, kg C/ kg of waste type *i*

u_i = moisture content in waste type *i*

W_i = fraction of waste type *i* by waste category

Once known the degradable organic carbon, the methane generation potential value (L₀) is calculated as:

$$L_0 = MCF * DOC * DOC_F * F * 16/12$$

Where:

MCF = methane correction factor

DOC_F = fraction of DOC dissimilated

F = fraction of methane in landfill gas

Fraction of degradable organic carbon (DOC_F) is an estimate of the fraction of carbon that is ultimately degraded and released from landfill and reflects the fact that some degradable organic carbon does not degrade, or degrades very slowly, under anaerobic conditions in the landfill.

DOC_F value is dependent on many factors like temperature, moisture, pH, composition of waste: the default value 0.5 has been used. Based on the previous review process, Italy started an assessment of DOC_F values in order to improve the estimates and find out, if possible, separate country specific DOC_F values thanks a strict collaboration with the ISPRA branch that manage the Italian waste cadaster.

The methane correction factor (MCF) accounts for that unmanaged SWDS (solid waste disposal sites) produce less CH₄ from a given amount of waste than managed SWDS, because a larger fraction of waste decomposes aerobically in the top layers of unmanaged SWDS. The MCF should be also interpreted as the 'waste management correction factor' because it reflects the management aspects.

The MCF value used for unmanaged landfill is the default IPCC value reported for uncategorised landfills: in fact, in Italy, before 2000 the existing unmanaged landfills were mostly shallow, because they resulted in uncontrolled waste dumping instead of real deep unmanaged landfills. Based on the qualitative information available regarding the national unmanaged landfills, the default IPCC value used has been considered the most appropriate to represent national circumstances also in consideration of the type of waste landfilled and the humidity degree of landfills. It is assumed that landfill gas is 50% VOC. Wetlands are distinguished from dry areas by associating each type of area with landfills in their respective territories, more information is available in the following paragraph. As it is estimated that sewage sludge has been disposed of only into landfills localized in the dry zone, the values of methane generation potential for the rapidly biodegradable fraction are slightly different. The following Table 7.10 summarizes the methane generation potential values (L₀) generated, distinguished for managed and unmanaged landfills.

Table 7.10 Methane generation potential values by waste composition, landfill typology and moisture conditions

L ₀ (m ³ CH ₄ /tRSU)	1950 - 1970		1971 - 1990		1991 - 2005		2006 - 2015		2016-20XX	
	dry	wet	dry	wet	dry	wet	dry	wet	dry	wet
Rapidly biodegradable										
- Managed landfill	89.7	94.6	85.4	94.6	87.2	94.6	91.4	94.6	92.0	94.6
- Unmanaged landfill	53.8	56.7	51.3	56.7	52.3	56.7	54.8	56.7	55.2	56.7
Moderately biodegradable										
- Managed landfill	118.2	118.2	118.2	118.2	118.2	118.2	118.2	118.2	118.2	118.2
- Unmanaged landfill	70.9	70.9	70.9	70.9	70.9	70.9	70.9	70.9	70.9	70.9
Slowly biodegradable										
- Managed landfill	224.1	224.1	224.1	224.1	205.9	205.9	204.0	204.0	204.6	204.6
- Unmanaged landfill	134.5	134.5	134.5	134.5	123.5	123.5	122.4	122.4	122.7	122.7

Finally, oxidation factors have been assumed equal to 0.1 for managed landfills and 0 for unmanaged according to the IPCC 2006 Guidelines where 0.1 is suggested for well managed landfills.


Methane generation rate constant (k)

The methane generation rate constant *k* in the FOD method is related to the time necessary for DOC in waste to decay to half its initial mass (the 'half life' or t_{1/2}).

The maximum value of *k* applicable to any single SWDS is determined by a large number of factors associated with the composition of the waste and the conditions at the site. The most rapid rates are associated with high moisture conditions and rapidly degradable material such as food waste. The slowest decay rates are associated with dry site conditions and slowly degradable waste such as wood or paper. Thus, for each rapidly, moderately and slowly biodegradable fraction, and for each site conditions a different maximum methane generation rate constant has been assigned, as reported in Table 7.11. Different *k* values for rapidly, moderately and slowly biodegradable waste splitted up into dry or wet zones are applied to the different parts of the model. As above reported, consistency has been ensured in the application of a weighted average *k* value for slowly degradable waste but, more, Italy - applying the FOD model for the individual *k* values - noted that non underestimation occurred. Furthermore, Italian experts believe that the application of the weighted average, especially for slowly biodegradable waste, constitutes a more realistic representation of the phenomenon.

The methane generation rate constant k values derive from the 2006 IPCC Guidelines. Italy has investigated more deeply the country specific conditions and revised the k -values considering the subdivision of the national territory in dry or wet zones on the basis of georeferenced data (30 km grid) consisting of the monthly average climatic summaries (period 1986-2015) of precipitation and evapotranspiration referring to the rainy period (October-December) and to the entire national territory provided by the Research Centre for Agriculture and Environments CREA-AA (CREA, 2017). Subsequently the ratio between precipitation (MAP = Mean Annual Precipitation) and evapotranspiration (PET = Potential Evapotranspiration) has been calculated and dry and wet zones distinguished following the 2006 Guidelines. Results have been reported in Figure 7.2., more information in (ISPRA, 2018).

Figure 7.2 Distribution of moisture conditions as defined by the 2006 IPCC GL



On the basis of the location of the solid waste disposal sites and of the distribution of dry or wet zones, the appropriate k values have been set; in particular, as reported in Table 7.10: 1) dry zones, rapidly biodegradable waste half life=12 years and $k=0.06$, moderately biodegradable half life=14 years and $k=0.05$, slowly biodegradable half life=20 years and $k=0.03$; 2) wet zones, rapidly biodegradable waste half life=4 years and $k=0.17$, moderately biodegradable half life=7 years and $k=0.10$, slowly biodegradable half life=14 years and $k=0.05$. Information and data about the fraction of waste landfilled in dry or wet zones are reported in (ISPRA, 2018). In particular, in 1990 MSW have been landfilled for 81% in dry zones and 19% in wet zones and assimilated MSW for 84% in dry and 16% in wet zones. In 2020 MSW have been landfilled for 92% in dry zones and 8% in wet zones while assimilated MSW keep the same distribution.

Table 7.11 Half-life values and related methane generation rate constant

MOISTURE CONDITIONS	WASTE TYPE	Half life	Methane generation rate constant
DRY	Rapidly biodegradable	12 year	0.06
	Moderately biodegradable	14 years	0.05
	Slowly biodegradable	20 years	0.03
WET	Rapidly biodegradable	4 year	0.17
	Moderately biodegradable	7 years	0.10
	Slowly biodegradable	14 years	0.05

Landfill gas recovered (R)

Landfill gas recovered data have been reconstructed based on information on extraction plants (De Poli and Pasqualini, 1991; Acaia et al., 2004; Asja, 2003) and electricity production (TERNA, several years).

Only managed landfills have a gas collection system, and the methane extracted can be used for energy production or can be flared.

The amount of methane recovery in landfills has increased as a result of the implementation of the European Directive on the landfill of waste (EC, 1999); the amounts of methane recovered and flared have been estimated taking into account the amount of energy produced, the energy efficiency of the methane recovered, the captation efficiency and the efficiency in recovering methane for energy purposes assuming that the rest of methane captured is flared. The emissions from biogas recovered from landfills and used for energy purposes are reported in the energy sector in "1A4a biomass" category together with wood, the biomass fraction of incinerated waste and biogas from wastewater plants. In Table 7.12 consumptions and low calorific values are reported for the year 2023.

Table 7.12 1A4a biomass detailed activity data. Year 2023

Fuels	Consumption (Gg)	LCV (TJ/Gg)
Wood and similar	Wood	301.68
	Steam Wood	0.00
Incinerated waste (biomass)	2,243.13	11.26
Biogas from landfills	180.65	54.41
Biogas from wastewater plants	24.35	54.41

The total CH₄ recovered is the sum of methane flared and methane used for energy purposes (see figure 7.3). Until 2000, the methane used for energy production is estimated starting from the electricity produced annually ($E = \text{GWh} \times 3.6 = \text{TJ}$) by landfills (TERNA, several years) assuming an energy conversion efficiency equal to 0.3, typical efficiency value for engines that produce electricity from biogas (Colombo, 2001), and a LCV (Lower Calorific Value) equal to 50.038 TJ/Gg:

$$((E/0.3)/50.038) \times 1000 = \text{CH}_4 \text{ Mg/year}$$

The LCV used for biogas derives from national experts and it is verified with energy and quantitative data about biogas production from waste supplied by TERNA (National Independent System Operator).

Since 2001, TERNA directly provides the amounts of biogas recovered for energy purposes, in this case the LCV has been derived from the comparison with the supplied energy data.


For the years 1987, 1988, 1989 and 1990, the methane flared is supplied by the plants (De Poli and Pasqualini, 1991); from 1991 to 1997 the methane flared has been extrapolated from the previous years; finally, for the following years the methane flared has been estimated using information based on monitored data supplied by the main operators (Asja, 2003 and Acaia, 2004) regarding the efficiency in recovering methane for energy purposes with respect to the total methane collected. This efficiency value increased from 56% of the total, in 1998, to 65% since 2002. In particular, the flared quantity of methane in 1990, reported by (De Poli and Pasqualini, 1991), is equal to 1,170,000 m³/day which result in 108,858 Mg/y and, in 1990, this amount corresponds to the total methane recovered. Since 1991 TERNA (National Independent System Operator) supplies the amount of biogas collected with energy recovery while (ASJA,

2003) and (Acaia et al., 2004) supply the percentage (flared / with energy recovered) equal to 35% in 2000 (survey on landfills in the Lombardy region, year 2000, 32 plants) and 30% in the following years (Asja landfills produced 35% of energy from landfill gas at the national level in 2001-2002). After 2002 this value, 30 % flared of total biogas collected, has been keep constant not considering further improving in efficiency in recovering methane for energy purposes with respect to the total methane collected.

Furthermore, Italy has started to collect plant data derived from IPPC permits to check data about collected and/or flared gases. There are no complete and available data bases, but it is necessary to make a documentary study, plant by plant. The documents analyzed at the time (some of these are available on the website <http://ippc-aia.arpa.emr.it/ippc-aia/CercalmpiantiTipo.aspx>) seem to confirm current estimates (biogas flared = 30/35% of collected biogas).

Total methane collected is estimated, in 2024, equal to 31% of the total methane produced. In 2023, 75% of collected methane is used for energy purposes.

Figure 7.3 Methane recovery distinguished in flared amount and energy purposes (Mg)



CH₄ and NMVOC emission time series

The time series of CH₄ emissions is reported in Table 7.13; emissions from the amount used for energy purposes are estimated and reported under category 1A4a.

Whereas waste production continuously increases, from 2001 solid waste disposal on land has decreased as a consequence of waste management policies, although fluctuations in the amounts of industrial waste and sludge could influence this trend. At the same time, the increase in the methane-recovered percentage has led to a reduction in net emissions. Further reduction is expected in the future because of the increase in waste recycling.

Table 7.13 VOC produced, recovered and CH₄ and NMVOC net emissions, 1990 – 2024 (kt)

EMISSIONS	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Managed Landfills											
VOC produced (kt)	396.4	565.5	772.3	916.7	977.6	955.6	872.6	853.9	835.5	815.5	815.5
VOC recovered (kt)	108.9	144.1	220.4	323.7	412.7	433.6	318.5	307.4	290.2	262.1	262.1
VOC recovered (%)	27.5	25.5	28.5	35.3	42.2	45.4	36.5	36.0	34.7	32.1	32.1

EMISSIONS	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
CH ₄ net emissions (kt)	255	374.3	490.3	526.7	501.8	463.7	492.2	485.4	484.4	491.6	491.6
NMVOC net emissions (kt)	3.4	4.9	6.5	6.9	6.6	6.1	6.5	6.4	6.4	6.5	6.5
Unmanaged Landfills											
VOC produced (kt)	235.9	233.6	200.3	155.4	122.3	97.1	77.6	74.2	71.0	68.0	68.0
VOC recovered (kt)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.0
CH ₄ net emissions (kt)	232.8	230.6	197.7	153.4	120.7	95.8	76.6	73.3	70.1	67.1	67.1
NMVOC net emissions (kt)	3.1	3.0	2.6	2.0	1.6	1.3	1.0	1.0	0.9	0.9	0.9

7.2.3 Uncertainty and time-series consistency

The uncertainty in CH₄ emissions from solid waste disposal sites has been estimated both by Approach 1 and Approach 2 of the IPCC guidelines. Following Approach 1, the combined uncertainty is estimated to be 22.4%, 10% and 20% for activity data and emission factors, respectively, as suggested by the IPCC Guidelines (IPCC, 2006).

Emissions from landfills (Table 7.13) are influenced, apart from the amount of waste landfilled, also from waste composition and site conditions, as for each biodegradability class different parameters are used in the model.

The total amount of waste disposed of into managed landfills increased until 2000 (in 2000 the landfilling of waste in unmanaged landfills has stopped too), then it decreased from 2000 to 2003, while from 2003 to 2008 it is quite stable. Since 2009, due to the increase in collection and recycling, but also to the economic crisis, the amount of waste disposed of in landfills is significantly decreased. It is important to remind that the total amount of waste disposed of is the sum of municipal solid wastes (which have decreased due to the enforcement of the legislation), sludge and industrial waste (only those similar to the municipal ones), which are subjected to fluctuation.

As previously reported, five waste compositions have been used, changing from 1950 to 2024 as well as the percentage of rapidly, moderately and slowly biodegradable fraction. The combination of the amount of waste landfilled and the waste composition has led to an increase of methane production from 1990 to the period 2005-2010 and a reduction in the last years.

At the same time, biogas recovery has increased up to 2013, but from 2000 the recovery rate is higher: in 2013 the methane recovered is about 43% of the methane produced. Methane emissions for 2013 result mainly from the amount of waste landfilled in the previous three years (2010-2012) and the observed decline is explained by the sharp decrease in the amount of solid waste disposed in landfills in these years.

7.2.4 Source-specific QA/QC and verification

The National Waste cadastre is managed by ISPRA and is formed by a national branch hosted by ISPRA and regional and provincial branches hosted by the Regional Agencies for the Protection of the Environment. So the system requires continuous and systematic knowledge exchange and QA/QC checks to ensure homogeneity of information concerning waste production and management throughout the entire Italian territory. At central level, ISPRA provides assessment criteria and procedures for data validation, through the definition of uniform standard procedures for all regional branches. The national branch, moreover, ensures spreading of the procedures and training of technicians in each regional branch. Data is validated by ISPRA detecting potential errors and data gaps, comparing among different data sources and asking for further explanation to the regional branches whenever needed. Moreover, ISPRA has started a number of sectoral studies with a view to defining specific waste production coefficients related to each production process. So, through the definition of such 'production factors' and the knowledge of statistical information on production, it is possible to estimate the amount of waste originated from each sector for the selected territorial grid cell and compare the results to the statistical data on waste production.

For general QC checks on emission estimates and related parameters, each inventory expert fills in, during the inventory compilation process, a format with a list of questions to be answered which helps the compiler avoid potential errors and is also useful to prove the appropriateness of the methodological choices.

Further verifications have been carried out to check the k values for slowly degrading waste; the FOD model has been applied using the k value calculated as a weighted average between paper and wood but also imputing the different and appropriate values for paper and for wood. Based on 2019 submission data, the methane produced in the first case is 632,294 Mg in 1990 and 1,013,714 Mg in 2017; in the second one the methane produced is equal to 616,283 Mg in 1990 and 1,013,062 Mg in 2017. Moreover, the sum of methane produced with the first model from 1990 to 2017 is equal to 26,943,609 Mg while using two distinct k values the sum results in 26,697,478 demonstrating that there is not an underestimation.


As regards the choice in k values, an in-depth survey has been conducted, and results have been reported in a technical note (ISPRA, 2018).

A comparison of the IPCC waste model (MS excel) with the model used by Italy for the simulation of biogas production was carried out. To adequately compare the two calculation models, 4 outputs were created corresponding to the categories used in the Italian model: wet-managed (SWDS in wet zone and well managed), wet unmanaged (SWDS in wet zone and not managed), dry managed (SWDS in dry zone and well managed) and dry unmanaged (SWDS in dry zone and not managed). By using the same activity data and the same parameters in both models, almost identical results are obtained as can be seen from the following figures demonstrating the correct implementation of the physicochemical relationships in the Italian model. The differences shown in the table are largely within the uncertainty of the estimate.

Table 7.14 Comparison between the Italian (sub 2021) and the IPCC spreadsheet for biogas production

	IPCC model	Italian model	difference
	CH ₄ kt	CH ₄ kt	%
1990			
wet managed 1990	80	84	4.4%
wet unmanaged 1990	50	53	5.8%
dry managed 1990	277	273	-1.3%
dry unmanaged 1990	183	183	0.4%
tot 1990	589	593	0.6%
2019			
wet managed 2019	113	113	0.4%
wet unmanaged 2019	9	10	8.8%
dry managed 2019	711	698	-1.8%
dry unmanaged 2019	70	71	2.0%
tot 2019	903	892	-1.1%

Figure 7.4 Comparison between the Italian (sub 2021) and the IPCC spreadsheet for biogas production



Italy investigated the possibility to estimate the emissions from certain episodes of illegal dumping. There is no quantitative data about this issue but from a qualitative point of view it was known that waste was prevalently industrial waste rich in heavy metals and inorganic chemicals, generally no or slowly biodegradable. Anyhow, the waste has been collected and temporarily stored in "ecoballe", therefore officially registered and sent to appropriate treatments resulting in the data reported by the National database (for example in the case of events in the Naples region). Moreover, an in-depth analysis of EWC codes of waste disposed of in landfills has been done for the year 2007 and 2019, thanks to the complete database of Waste Cadastre kindly supplied by ISPRA Waste Office. This accurate analysis has permitted to verify the correctness of waste typology assumptions used for the estimations.

Finally, an important improvement in waste data collection has been implemented by ISPRA and the Regional Agencies for the Protection of the Environment, consequently the waste statistical report includes the urban waste data referred to last years allowing timely reporting.

Based on the last review processes, CO₂ emissions from HWP in SWDS are under investigation. Since the previous submissions, as discussed during the review process in an intersectoral way (LULUCF and waste team), a revision of the method used to estimate the HWP in Solid Waste Disposal Sites has been applied: the waste team has implemented the HWP sheet used in the IPCC FOD model to estimate the long-term storage of C in waste disposal sites and the annual change in total long-term C storage in HWP waste. Having demonstrated in the past years the consistency of the Italian calculation model with the IPCC one, the consistency of the HWP estimates with those of the landfill (same activity data) is also ensured, pending the implementation of the calculation within the Italian model.

7.2.5 Source-specific recalculations

In Table 7.15, municipal and industrial (assimilated to MSW) wastes disposed into non hazardous landfills are reported also for submission 2025.

Table 7.15 MSW and AMSW disposed into landfills time series, 1990 – 2024 (t), and differences in percentage between Submission 2026 and Submission 2025.

Year	Submission 2026			Submission 2025			% MSW	% AMSW	% Total
	MSW to landfill (t)	AMSW to landfill (t)	Total waste (except sludge) to landfill (t)	MSW to landfill (t)	AMSW to landfill (t)	Total waste (except sludge) to landfill (t)			
1990	17,431,760	2,827,867	20,259,627	17,431,760	2,827,867	20,259,627	-	-	-
1995	22,458,880	2,977,672	25,436,552	22,458,880	2,977,672	25,436,552	-	-	-
2000	21,917,417	2,825,340	24,742,757	21,917,417	2,825,340	24,742,757	-	-	-
2005	17,225,728	2,913,697	20,139,425	17,225,728	2,913,697	20,139,425	-	-	-
2006	17,525,881	2,480,830	20,006,711	17,525,881	2,480,830	20,006,711	-	-	-
2007	16,911,545	2,776,637	19,688,182	16,911,545	2,776,637	19,688,182	-	-	-
2008	16,068,760	3,703,220	19,771,980	16,068,760	3,703,220	19,771,980	-	-	-
2009	15,537,822	3,180,904	18,718,726	15,537,822	3,180,904	18,718,726	-	-	-
2010	15,015,119	2,639,270	17,654,389	15,015,119	3,508,400	18,523,519	-	-25%	-5%
2011	13,205,749	2,882,686	16,088,435	13,205,749	2,882,686	16,088,435	-	-	-
2012	11,720,316	2,291,946	14,012,262	11,720,316	2,291,946	14,012,262	-	-	-
2013	10,914,353	2,511,711	13,426,064	10,914,353	2,511,711	13,426,064	-	-	-
2014	9,331,898	2,912,908	12,244,806	9,331,898	2,912,908	12,244,806	-	-	-
2015	7,818,795	3,221,646	11,040,441	7,818,795	3,221,646	11,040,441	-	-	-
2016	7,431,611	2,512,938	9,944,549	7,431,611	2,512,938	9,944,549	-	-	-
2017	6,926,548	3,899,413	10,825,961	6,926,548	3,899,413	10,825,961	-	-	-
2018	6,496,000	3,511,898	10,007,898	6,496,000	3,511,898	10,007,898	-	-	-
2019	6,283,307	3,256,299	9,539,606	6,283,307	3,256,299	9,539,606	-	-	-
2020	5,817,128	2,909,686	8,726,814	5,817,128	2,909,686	8,726,814	-	-	-
2021	5,618,640	2,962,608	8,581,248	5,618,640	2,962,608	8,581,248	-	-	-
2022	5,172,950	2,468,969	7,641,919	5,172,950	2,468,969	7,641,919	-	-	-
2023	4,598,588	1,969,772	6,568,360	4,612,726	1,969,772	6,582,498	-0.3%	-	-0.2%
2024	4,428,645	2,116,219	6,544,864						

In Table 7.16 differences in percentage between emissions from landfills reported in the updated time series and 2025 submission are presented. Some recalculations occurred since 2011 because of the correction of an error in 2010 and so differences start from 2011 considering the delay time. In 2023 the update of activity data is considered too.

Table 7.16 Differences in percentage between emissions from landfills reported in the updated time series and 2025 submission

EMISSIONS	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
Managed Landfills										
VOC produced (kt)	-	-	-	-	-0.0003%	-0.2%	-0.2%	-0.2%	-0.2%	-0.2%
VOC recovered (kt)	-	-	-	-	-	-	-	-	-	-
CH ₄ net emissions (kt)	-	-	-	-	-0.0004%	-0.4%	-0.3%	-0.3%	-0.3%	-0.2%
NM VOC net emissions (kt)	-	-	-	-	-0.0004%	-0.4%	-0.3%	-0.3%	-0.3%	-0.2%
Unmanaged Landfills										
VOC produced (kt)	-	-	-	-	-	-	-	-	-	-
VOC recovered (kt)	-	-	-	-	-	-	-	-	-	-
CH ₄ net emissions (kt)	-	-	-	-	-	-	-	-	-	-
NM VOC net emissions (kt)	-	-	-	-	-	-	-	-	-	-

7.2.6 Source-specific planned improvements

Currently, more recent data on the fraction of CH₄ in landfill gas and on the amount of landfill gas collected and treated are under investigation.

7.3 Biological treatment of solid waste (5B)

7.3.1 Source category description

Biological treatment of solid waste is a key category for N₂O emissions at level (for 2024) and trend assessment but only with Approach 2. Under this source category CH₄ and N₂O emissions from compost production and CH₄ emissions from anaerobic digestion of waste have been reported. NMVOC emissions from compost production have been estimated too. The amount of waste treated in composting and digestion plants has shown a great increase from 1990 to 2024 (from 283,879 Mg to 6,138,321 Mg for composting and from 79,440 Mg to 2,480,018 Mg for anaerobic digestion).

Information on input waste to composting plants are published yearly by ISPRA since 1996, including data for 1993 and 1994 (ANPA, 1998; ISPRA, several years), while for 1987 and 1995 only data on compost production are available (MASE, several years [a]; AUSITRA-Assoambiente, 1995); based on this information the whole time series has been reconstructed. Regarding anaerobic digestion, the same sources of information have been used to reconstruct the time series until 2004 while ISPRA publishes yearly more accurate data from 2005.

7.3.2 Methodological issues

Composting

The composting plants are classified in two different kinds: plants that treat a selected waste (food, market, garden waste, sewage sludge and other organic waste, mainly from the agro-food industry); and mechanical-biological treatment plants, where the unselected waste is treated to produce compost, refuse derived fuel (RDF), and a waste with selected characteristics suitable for landfilling or incinerating systems.

It is assumed that 100% of the input waste to the composting plants from selected waste is treated as compost, while in mechanical-biological treatment plants 30% of the input waste is treated as compost on the basis of national studies and references (Favoino and Cortellini, 2001; Favoino and Girò, 2001).

In previous submissions, literature data (Hogg D., 2001) have been used for the emission factor, 0.029 g CH₄ kg⁻¹ treated waste, corresponding to the minimum of the range proposed by 2006 IPCC Guidelines on a wet weight basis. This choice has been taken because in the 2006 IPCC Guidelines the default value (4 g CH₄/kg waste treated) is clearly shifted towards high values because most of world plants does not use advanced technologies. The majority of references reported in Table 4.1 of 2006 IPCC Guidelines that have found high emission factors referred to composting time of 10-14 months, low turning frequency and no aeration system. In Italy, almost all of the plants are industrial plants (216/279 > 1000 Mg/year in 2014), with enclosed areas for rotting and decomposition served by biofilters, turning when needed (to maintain the right porosity) and, above all, forced ventilation or suction system. Following the discussion started during the effort sharing decision review (EU, 2016) a specific survey on methane emission factor from composting and the relationship with technologies and management practices has been conducted (ISPRA, 2017) resulting in a new emission factor equal to 0.65 kg CH₄/Mg waste treated on a wet weight basis. As reported in the IPCC Guidelines, Table 4.1, the emission factors for dry waste are estimated from those for wet waste assuming a moisture content of 60% in wet waste.

NMVOC emissions have also been estimated: emission factor (51 g NMVOC kg⁻¹ treated waste) is from international scientific literature too (Finn and Spencer, 1997). In Table 7.17 and in Figure 7.5, activity data expressed in wet weight, CH₄, N₂O and NMVOC emissions are reported.

Anaerobic digestion


The anaerobic digestion plants too are subdivided into the same two different kinds: plants that treat a selected waste and mechanical-biological treatment plants.

It is assumed that 100% of the input waste to the plants from selected waste is treated as anaerobic digestion, while in mechanical-biological treatment plants 15% of the input waste is considered as anaerobically digested. The default IPCC 2006 emission factor has been used. Since the plants are closed systems, emissions are related to the possibility of gas leaks estimated to be 5 % of potential emissions.

Table 7.17 CH₄, N₂O and NMVOC emissions from biological treatment of solid waste, 1990 – 2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Activity data											
Amount of waste to composting process (kt ww)	283.88	657.22	2,834.31	5,550.89	7,030.81	7,288.30	6,818.91	6,796.34	6,435.01	6,087.15	6,138.32
Amount of waste to composting process (kt dw)	113.55	262.89	1,133.72	2,220.36	2,812.32	2,915.32	2,727.57	2,718.53	2,574.00	2,434.86	2,455.33
Amount of waste to anaerobic digestion (kt ww)	79.44	127.43	467.80	1,407.20	1,976.36	2,303.17	2,309.97	2,283.16	2,195.80	2,328.98	2,480.02
Amount of waste to anaerobic digestion (kt dw)	31.78	50.97	187.12	562.88	790.54	921.27	923.99	913.26	878.32	931.59	992.01
CH₄											
Compost production (kt)	0.18	0.43	1.84	3.61	4.57	4.74	4.43	4.42	4.18	3.96	3.99
Anaerobic digestion (kt)	0.00	0.01	0.02	0.06	0.08	0.09	0.09	0.09	0.09	0.09	0.10
N₂O											
Compost production (kt)	0.068	0.158	0.680	1.332	1.687	1.749	1.637	1.631	1.544	1.461	1.473
NMVOC											
Compost production (kt)	0.014	0.033	0.144	0.282	0.357	0.370	0.346	0.345	0.327	0.309	0.312

Figure 7.5 Waste treated in compost and anaerobic plants in 2024



7.3.3 Uncertainty and time-series consistency

The uncertainty in CH₄ emissions from biological treatment of waste is estimated to be about 100% in annual emissions, 20% and 100% concerning activity data and emission factors respectively. The uncertainty in N₂O emissions from biological treatment of waste is estimated to be about 100% in annual emissions, 20% and 100% concerning activity data and emission factors, respectively.

7.3.4 Source-specific QA/QC and verification

This source category is covered by the general QA/QC procedures. Moreover, as concerns composting, an in-depth survey has been conducted in 2017 investigating literature and plant data. Results are reported in (ISPRA, 2017).

7.3.5 Source-specific recalculations

No recalculations occur.

Table 7.18 CH₄ and N₂O recalculations for biological treatment of solid waste, 1990 – 2023

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
CH₄										
Compost production (kt)	-	-	-	-	-	-	-	-	-	-
Anaerobic digestion (kt)	-	-	-	-	-	-	-	-	-	-
N₂O										
Compost production (kt)	-	-	-	-	-	-	-	-	-	-

7.3.6 Source-specific planned improvements

Anaerobic digestion of solid waste is under investigation to collect more information about technologies and emission factors and biogas production.

7.4 Waste incineration (5C)

7.4.1 Source category description

Existing incinerators in Italy are used for the disposal of municipal waste, together with some industrial waste, sanitary waste and sewage sludge for which the incineration plant has been authorized by the competent authority. Other incineration plants are used exclusively for industrial and sanitary waste, both hazardous and not, and for the combustion of waste oils, whereas there are few plants where residual waste from waste treatments, as well as sewage sludge, are treated. Since 2007, the activity of co-incineration in industrial plants, especially to produce wooden furniture, has increased significantly, resulting in an increase in the relevant emissions related to the proportion of waste burned.

Emissions from incineration of human bodies in crematoria have been estimated too.

As mentioned above, emissions from waste incineration facilities with energy recovery are reported under category 1A4a (Combustion activity, commercial/institutional sector, see Table 7.12) in the "Other fuel" and "Biomass" subcategory for the fossil and biomass fraction of wastes, respectively, whereas emissions from other types of waste incineration facilities are reported under category 5C (Waste incineration). For 2024, almost 99% of the total amount of urban waste incinerated is treated in plants with energy recovery system.

A complete database of the incineration plants is now available, updated with the information reported in the yearly report on waste production and management published by ISPRA (ISPRA, several years).

Emissions from removable residues from agricultural production are included in the IPCC category 5C: the total residues amount and carbon content have been estimated by both IPCC and national factors. The detailed methodology is reported in Chapter 5 (5.6.2).

CH₄ and N₂O emissions from biogenic, plastic and other non-biogenic wastes have been calculated.

7.4.2 Methodological issues

Regarding GHG emissions from incinerators, the methodology reported in the IPCC Good Practice Guidance (IPCC, 2000) has been applied, combined with that reported in the CORINAIR Guidebook (EMEP/CORINAIR, 2007; EMEP/EEA, 2009; EMEP/EEA, 2023). A single emission factor for each pollutant has been used combined with plant specific waste activity data. Since 2010, NO_x, SO₂ and CO emission factors for urban waste incinerators have been updated on the basis of data provided by plants (ENEA-federAmbiente, 2012; De Stefanis P., 2012).

As regards incineration plants, emissions have been calculated for each type of waste: municipal, industrial, hospital, sewage sludge and waste oils.

A complete database of these plants has been built, on the basis of various sources available for the period of the entire time series, extrapolating data for the years for which no information was available (MASE, several years [a]; ANPA-ONR, 1999 [a] and [b]; APAT, 2002; AUSITRA-Assoambiente, 1995; Morselli, 1998; FEDERAMBIENTE, 1998; FEDERAMBIENTE, 2001; AMA-Comune di Roma, 1996; ENI S.p.A., 2001; COOU, several years; Fondazione per lo sviluppo sostenibile e FISE UNIRE, 2016).

For each plant a lot of information is reported, among which the year of construction and possible upgrade, the typology of combustion chamber and gas treatment section, if it is provided with energy recovery (thermal or electric), and the type and amount of waste incinerated (municipal, industrial, etc.).

Different procedures were used to estimate emission factors, according to the data available for each type of waste, except CH₄ and N₂O emission factors that are derived from EMEP Corinair (EMEP/CORINAIR, 2007).

Specifically:

- 1 for municipal waste, emission data from a large sample of Italian incinerators were used (FEDERAMBIENTE, 1998; ENEA-federAmbiente, 2012);
- 2 for industrial waste and waste oil, emission factors have been estimated on the basis of the allowed levels authorized by the Ministerial Decree 19 November 1997, n. 503 of the Ministry of Environment;
- 3 for hospital waste, which is usually disposed of alongside municipal waste, the emission factors used for industrial waste were also applied;
- 4 for sewage sludge, in absence of specific data, reference was made to the emission limits prescribed by the Guidelines for the authorisation of existing plants issued on the Ministerial Decree 12 July 1990.

In Table 7.19, emission factors are reported in kg per ton of waste treated, for municipal, industrial, hospital waste, waste oils and sewage sludge.

Table 7.19 Waste incineration emission factors

POLLUTANT/WASTE TYPOLOGY	NMVOC (kg/t)	CO (kg/t)	CO ₂ fossil (kg/t)	N ₂ O (kg/t)	NO _x (kg/t)	SO ₂ (kg/t)	CH ₄ (kg/t)
Municipal waste since 2010	0.46	0.07	467.50	0.1	0.62	0.02	0.06
Municipal waste 1990 – 2009	0.46	0.07	295.17	0.1	1.15	0.39	0.06
Hospital waste	0.7	0.08	1200	0.1	0.604	0.026	0.06
Sewage sludge	0.25	0.6	0	0.227	3	1.8	0.06
Waste oils	7.4	0.08	3000.59	0.1	2	1.28	0.06
Industrial waste (similar to MW) since 2010	7.4	0.56	600	0.1	2	1.28	0.06
Industrial waste (similar to MW) 1990 - 2009	7.4	0.56	1200	0.1	2	1.28	0.06

Here below (Tables 7.20, 7.21, 7.22, 7.23), details about data and calculation of specific emission factors are reported. Emission factors have been estimated on the basis of a study conducted by ENEA (De Stefanis, 1999), based on emission data from a large sample of Italian incinerators (FEDERAMBIENTE, 1998; AMA-Comune di Roma, 1996), legal thresholds (Ministerial Decree 19 November 1997, n. 503 of the Ministry of Environment; Ministerial Decree 12 July 1990), the last study conducted by ENEA and federAmbiente (ENEA-federAmbiente, 2012) and expert judgements.

The CO₂ implied emission factor for waste incineration varies annually and depends on the fossil carbon fraction in line with the variation of waste composition that varies yearly on the basis of the amount of annual municipal, industrial and hospital waste and the quantity of sewage sludge to burn.

In details, from 1990 to 2009 CO₂ emission factor for municipal waste has been calculated considering a carbon content equal to 23%; moreover, on the basis of the IPCC Guidelines (IPCC, 2006) and referring to the average content analysis on a national scale (De Stefanis P., 2002), a distinction was made between CO₂ from fossil fuels (generally plastics) and CO₂ from renewable organic sources (paper, wood, other organic materials). Only emissions from fossil fuels, which are equivalent to 35% for municipal waste, were included in the inventory. In the last submissions, further improvement has been carried out; with the aim to upgrade the C content in municipal waste an analysis on waste composition in recent years has been conducted resulting in a carbon content for municipal waste equal to 25.5% (ISPRA, 2010) and a subdivision between fossil and renewable fuels equal to 50-50%. These updates have been applied starting from 2010. Regarding the other waste components, C in sludge is considered completely organic, while C in industrial and hospital waste are considered completely fossil carbon according to the national definitions of these types of wastes. Mortal remains are not part of hospital waste but are included in the activity data used to estimate emissions from crematories; C in this case is considered completely organic. CO₂ emission factors for industrial, oils and hospital waste have been derived as the average of values of investigated industrial plants.

On the other hand, CO₂ emissions from the incineration of sewage sludge were not included at all, while all emissions relating to the incineration of hospital and industrial waste were considered.

In this way, the resulting CO₂ emission factor for waste incineration varies in line with the variations of waste composition as can be seen in table 5.C of the CRT tables.

In Table 7.24 activity data are reported by type of waste.

Table 7.20 Municipal waste emission factors

MUNICIPAL WASTE	Average concentration values (mg/Nm ³)		Standard specific flue gas volume (Nm ³ /KgMSW)		E.F. (g/Mg)	
	1990-2009	2010-	1990-2009	2010-	1990-2009	2010-
SO ₂	78.00	2.17	5	6.7	390	18
NO _x	230.00	97.08			1,150	621
CO	14.00	12.30			70	73
N ₂ O					100	100
CH ₄					59.80	59.80
NMVOC					460.46	460.46
C content, % weight	23	25.5				
CO ₂					843.3 (kg/Mg)	935.4(kg/Mg)

Table 7.21 Industrial waste and oils emission factors

Industrial and oil waste	Average concentration values (mg/Nm ³)		Standard specific flue gas volume (Nm ³ /KgMSW)		E.F. (g/Mg)	
	1990-2009	2010-	1990-2009	2010-	1990-2009	2010-
SO ₂	160.00	160.00	8	8	1,280	1,280
NO _x	250.00	250.00			2,000	2,000
CO	70.00	70.00			560	560
N ₂ O					100	100
CH ₄					59.80	59.80
NMVOC					7400	7400
CO ₂ industrial waste					1200 (kg/Mg)	600 (kg/Mg)
CO ₂ oils					1200 (kg/Mg)	1200 (kg/Mg)

Table 7.22 Hospital waste emission factors

HOSPITAL WASTE	Average concentration values (mg/Nm ³)	Standard specific flue gas volume (Nm ³ /KgMSW)	E.F. (g/t)
SO ₂	3.24	8	26
NO _x	75.45		604
CO	9.43		75
N ₂ O			100
CH ₄			59.80
NMVOC			700
CO ₂			1,200 (kg/t)

Table 7.23 Sewage sludge emission factors

SEWAGE SLUDGE	Average concentration values (mg/Nm ³)	Standard specific flue gas volume (Nm ³ /KgMSW)	E.F. (g/t)
SO ₂	300	6	1,800
NO _x	500		3,000
CO	100		600
N ₂ O			100
CH ₄			59.80
NMVOC			251
CO ₂			700 (kg/t)

Table 7.24 Amount of waste incinerated by type, 1990 – 2024 (Gg)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total Waste incinerated	1,656	2,149	3,062	4,964	6,950	7,535	7,468	7,474	7,360	7,573	7,585

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
- with energy recovery	911	1,558	2,750	4,721	6,769	7,431	7,398	7,363	7,262	7,485	7,499
- without energy recovery	745	591	312	244	181	103	70	111	98	88	86
Total Waste incinerated - Carbon content (Gg)	439	560	773	1,309	1,961	2,123	2,139	2,133	2,098	2,157	2,157
MSW incinerated	1,026	1,437	2,325	3,220	4,337	4,698	4,227	4,305	4,277	4,433	4,486
- with energy recovery	626	1,185	2,161	3,168	4,284	4,698	4,227	4,305	4,277	4,433	4,486
- without energy recovery	399	251	164	52	53	0	0	0	0	0	0
MSW incinerated - Carbon content (Gg)	236	330	535	741	1,106	1,199	1,078	1,098	1,091	1,131	1,145
Industrial Waste incinerated											
Other waste											
- with energy recovery	473	536	604	1,602	2,472	2,709	3,133	3,035	2,967	3,053	3,014
- without energy recovery	258	330	508	1,446	2,372	2,676	3,107	2,994	2,936	3,022	2,983
Other waste - Carbon content (Gg)	215	206	96	155	100	33	26	40	32	31	31
Hospital waste	155	175	198	524	809	887	1,025	993	971	999	986
- with energy recovery	134	152	110	126	135	102	107	114	100	74	73
- without energy recovery	25	41	77	106	113	57	64	63	49	29	28
Hospital waste - Carbon content (Gg)	109	111	34	21	23	45	44	51	50	45	44
Sludge	44	50	36	41	44	33	35	37	33	24	24
- with energy recovery	20.72	23.18	21.50	15.60	5.98	25.10	0.00	19.57	15.70	11.53	11.32
- without energy recovery	0.00	0.00	3.40	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Sludge - Carbon content (Gg)	20.72	23.18	18.11	15.60	5.98	25.10	0.00	19.57	15.70	11.53	11.32
Waste oil	3.96	4.43	4.10	2.98	1.14	4.79	0.00	3.74	3.00	2.20	2.16
- with energy recovery	2.66	1.41	0.82	0.67	0.18	0.46	0.29	0.40	0.20	0.60	0.59
- without energy recovery	1.77	0.94	0.55	0.54	0.18	0.46	0.29	0.40	0.20	0.60	0.59
Waste oil - Carbon content (Gg)	0.89	0.47	0.27	0.12	0.00	0.00	0.00	0.00	0.00	0.00	0.00

CH₄ and N₂O emissions from agriculture residues removed, collected and burnt 'off-site', as a way to reduce the amount of waste residues, are reported in the waste incineration sub-sector.

Removable residues from agriculture production are estimated for each crop type (cereal, green crop, permanent cultivation) taking into account the amount of crop produced, the ratio of removable residue in the crop, the dry matter content of removable residue, the ratio of removable residue burned, the fraction of residues oxidised in burning, the carbon and nitrogen content of the residues. Most of these wastes refer especially to pruning of olives and wine, because of the typical national cultivation.

Emissions due to stubble burning, which are emissions only from the agriculture residues burned on field, are reported in the agriculture sector, under 3.F, more info is also reported in the Annex 7. Under the waste sector the burning of removable agriculture residues that are collected and could be managed in different ways (disposed in landfills, used to produce compost or used to produce energy) is reported.

Different percentages of the removable agriculture residue burnt for different residues are assumed, varying from 10% to 90%, according to national and international literature. Moreover, these removable wastes are assumed to be all burned in open air (e.g. on field) taking in consideration the higher (without abatement) available CO, NMVOC, PM, PAH and dioxins emission factors. The amount of these wastes treated differently is not supplied, but they are included in the respective sectors (landfill, composting, biogas production for energy purposes, etc.).

The methodology is the same used to calculate emissions from residues burned on fields, in the category 3F, described in detail in Chapter 5.

Based on carbon and nitrogen content of the residues, CH₄ and N₂O emissions have been calculated, both accounting nearly for 100% of the whole emissions from waste incineration. CO₂ emissions have been calculated but not included in the inventory as biomass. All these parameters refer both to the IPCC Guidelines (IPCC, 2006) and country-specific values (CESTAAT, 1988; Borgioli, 1981).

The amount of biomass from pruning used for domestic heating is reported in the energy sector in the 1A4b category as biomass fuel.

As recommended during the 2019 UNFCCC review, to enhance transparency on the total amount of crop residues generated and shares of the crop residue amounts used for different purposes (such as bedding material (3.D.a.2.a), left on fields (3.D.a.4), burnt on-site (3.F) and off-site (1.A, 5.C.2)), a flow-chart is reported in Annex 7, in Figure A.7.1.

As regard incineration of corpses in crematoria, activity data have been supplied by a specific branch of Federutility, which is the federation of energy and water companies (SEFIT, several years).

In Table 7.25 time series of cremation as well as annual deaths and crematoria in Italy are reported.

Table 7.25 Cremation time series (activity data), 1990 – 2024

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
Cremations (no. of corpses)	5,809	15,436	30,167	48,196	77,379	137,168	247,840	259,915	252,075	253,355
Deaths (no. of corpses)	543,700	555,203	560,241	567,304	587,488	653,000	746,146	713,499	660,600	646,000
Mortal remains (no.)	1,000	1,750	1,779	9,880	18,899	34,178	29,266	45,986	44,210	45,259
Cremation percentage	1.07	2.78	5.38	8.50	13.17	21.01	33.22	36.43	38.16	39.22
Crematoria (no.)	ND	31	35	43	53	70	87	91	91	91

The major emissions from crematoria are nitrogen oxides, carbon monoxide, sulphur dioxide, particulate matter, mercury, hydrogen fluoride (HF), hydrogen chloride (HCl), NMVOCs, other heavy metals, and some POPs.

In Table 7.26 emission factors for cremation are reported; all emission factors are from (SEFIT, 2015; SEFIT, 2019) except for CH₄ and N₂O, assumed equal to MSW emission factor because values were not available. CO₂ emissions have not been calculated for the inventory as human body is 'biomass'.

Table 7.26 Cremation emission factors

POLLUTANT/WASTE TYPOLOGY	NMVOC (kg/body)	CO (kg/body)	N₂O (kg/t)	NO_x (kg/body)	SO₂ (kg/body)	CH₄ (kg/t)
Cremation	0.009	0.005	0.1	0.474	0.009	0.06

CO₂ emissions from open burning of waste are also considered. Open burning of waste is forbidden in Italy but sometimes it illegally occurs. Estimates are based on 2006 IPCC Guidelines, in particular the

paragraph 5.3.2 to define the amount of waste open burned using data about population, the fraction of "rural people", the per capita waste production and estimating the rate of the waste amount that is burned relative to the total amount of waste treated on the bases of recent national data (Bfrac=0.4%). In the following table activity data and CO₂ emissions have been reported. To improve completeness, in the previous submissions CH₄ and N₂O emissions have been estimated too. The methodology used is always that of the 2006 IPCC guidelines. The 2006 IPCC Guidelines report as default value Bfrac=0.6. In recent years the most important fires (industrial warehouses) involved 1800 Mg in Corteolona in 2018 and 8400 Mg in Pomezia in 2017 which means negligible quantities even considering an order of magnitude higher. For example, if they were 100,000 Mg of open burning waste annually, they would be equivalent, from 1990 to 2018, to approximately 0.4% to 0.3% (instead of the 60% represented by the default). More 2006GL stated that "For countries that have well-functioning waste collection systems in place, it is good practice to investigate whether any fossil carbon is open burned. In a developed country, Pfrac can be assumed to be the rural population for a rough estimate. In a region where urban population exceeds 80 percent of total population, one can assume no open burning of waste occurs." and Pfrac in Italy (Istat, 2017 "Forme, livelli e dinamiche dell'urbanizzazione in Italia") is less than 10% (9-9.4%) which means that rural population is more than 90% and open burning of urban waste can be considered negligible.

Table 7.26 Open burning of waste time series, 1990 – 2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Pfrac	9.4%	9.4%	9.0%	9.0%	9.0%	9.0%	9.0%	9.0%	9.0%	9.0%	9.0%
Bfrac	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%	0.4%
MSW _B (kt)	8.36	9.69	10.43	11.40	11.69	10.63	10.42	10.65	10.46	10.54	10.78
CO ₂ (kt) fossil	2.47	2.86	3.08	3.36	5.47	4.97	4.87	4.98	4.89	4.93	5.04
CO ₂ (kt) organic	4.58	5.31	5.71	6.25	5.47	4.97	4.87	4.98	4.89	4.93	5.04
CH ₄ (kt)	0.05	0.06	0.07	0.07	0.08	0.07	0.07	0.07	0.07	0.07	0.07
N ₂ O (kt)	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001

7.4.3 Uncertainty and time-series consistency

The combined uncertainty in emissions from waste incineration is estimated to be about 22.4%, 10% and 20% for activity data and emission factors respectively.

The time series of activity data, distinguished in Municipal Solid Waste and other (including cremation), is shown in Table 7.28; CO₂ emission trends for each type of waste category are reported in Table 7.29, both for plants without energy recovery, reported under 5C, and plants with energy recovery, reported under 1A4a. In Table 7.30 N₂O and CH₄ emissions are summarized, including those from open burning and cremation.

In the period 1990-2024, total CO₂ emissions have increased by 284%, but whereas emissions from plants with energy recovery have increased by nearly 640%, emissions from plants without energy recovery decreased by -86% (Table 7.28). While CO₂ emission trend reported in 5C is influenced by the amount of waste incinerated in plants without energy recovery, CH₄ and N₂O emission trend are related to the open burning, as already reported above.

Table 7.28 Waste incineration activity data, 1990 – 2024 (kt)

Activity Data	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
MSW Production (kt)	22,231	25,780	28,959	31,664	32,479	29,524	28,941	29,618	29,051	29,269	29,933
MSW Incinerated (%)	4.6%	5.6%	8.0%	10.2%	13.4%	15.9%	14.6%	14.5%	14.7%	15.1%	15.0%
- in energy recovery plants	2.8%	4.6%	7.5%	10.0%	13.2%	15.9%	14.6%	14.5%	14.7%	15.1%	15.0%
MSW to incineration (kt)	1,026	1,437	2,325	3,220	4,337	4,698	4,227	4,305	4,277	4,433	4,486

Activity Data	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Industrial, Sanitary, Sewage Sludge and Waste Oil to incineration (kt)	631	712	737	1,744	2,613	2,836	3,240	3,169	3,083	3,140	3,098
Cremation (no. of corpses)	5,809	15,436	30,167	48,196	77,379	137,168	247,840	244,186	259,915	252,075	253,355
Total Waste to incineration, excluding cremation (5C and 1A4a) (kt)	1,656	2,149	3,062	4,964	6,950	7,535	7,468	7,474	7,360	7,573	7,585

Table 7.29 CO₂ emissions from waste incineration (without and with energy recovery), 1990 – 2024 (kt)

CO ₂ Emissions	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Incineration of domestic or municipal wastes (kt)	117.83	74.12	48.26	15.32	24.74	0.00	0.00	0.00	0.00	0.00	0.00
Incineration of industrial wastes (except flaring) (kt)	257.99	247.11	115.74	186.50	114.43	29.23	15.57	24.15	19.11	18.73	18.38
Incineration of hospital wastes (kt)	131.07	132.73	40.36	24.61	27.12	53.57	52.68	60.97	60.49	53.94	52.94
Incineration of waste oil (Gg)	2.66	1.41	0.82	0.36	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Incineration of corpses	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Waste incineration (5C) (kt)	510	455	205	227	166	83	68	85	80	73	71
Waste incineration reported under 1A4a (kt) – not biomass	530	798	1,341	2,799	3,892	3,904	3,917	3,886	3,820	3,920.6	3,921.4
Waste incineration reported under 1A4a (kt)- biomass	343	650	1,185	1,737	2,259	3,050	3,840	3,809	3,761	3,885.8	3,887.3
Total waste incineration – fossil (kt)	1,039	1,254	1,546	3,026	4,058	3,987	3,986	3,971	3,899	3,993.2	3,992.7

Table 7.30 N₂O and CH₄ emissions from waste incineration (cremation and open burning included), 1990 – 2024 (kt)

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
<u>N₂O</u> (kt)											
Waste incineration (5C)	0.12	0.11	0.08	0.10	0.09	0.08	0.08	0.08	0.07	0.08	0.07
MSW incineration reported under 1A4a – not biomass	0.05	0.08	0.13	0.27	0.46	0.51	0.53	0.52	0.50	0.53	0.53
MSW incineration reported under 1A4a – biomass	0.04	0.08	0.14	0.21	0.21	0.23	0.21	0.22	0.21	0.22	0.22
<u>CH₄</u> (kt)											
Waste incineration (5C)	1.90	2.08	2.02	2.70	2.67	2.67	2.60	2.57	2.36	2.44	2.41
MSW incineration reported under 1A4a – not biomass	0.03	0.05	0.08	0.16	0.28	0.30	0.32	0.31	0.30	0.32	0.31
MSW incineration reported under 1A4a – biomass	0.02	0.05	0.08	0.12	0.13	0.14	0.13	0.13	0.12	0.13	0.13

7.4.4 Source-specific QA/QC and verification

Several verifications were carried out based on the analysis of documentation supplied in the framework of IPPC permits and of environmental reports.

7.4.5 Source-specific recalculations

As is the case every year, recent years have been affected by changes related to the updating of activity data. This applies both to national statistical data through the 2023 update and to data relating to

individual plants, as one plant was eliminated starting in 2019 as it was a cement factory whose contribution is already estimated at 1A2f.

Recalculations occur from 2010 because of an updated distribution of biogenic/fossil activity data. The comparison between the estimates and recent ETS data (incinerators declared for the first time) allows Italy to improve waste characterization for non-urban waste (often referred to as industrial waste in the NID) burnt in the municipal plants. Only certain categories (specific EER code, i.e., residues from waste treatment) can be incinerated in those plants, and it is correct that such waste be considered the same as municipal waste, 50% fossil and 50% biogenic. Using this assumption since 2020, the inventory estimates reported in 1.A.4. and the ETS data have a better match. In 2024, the ETS estimates show approximately 3.7 kt fossil CO₂ with 32 reporting facilities, while the inventory estimates show 3.9 kt fossil CO₂ with four additional facilities. As regards emissions without energy recovery reported in 5C, this change led to a decrease in CO₂ emissions in 2020-2023 while between 2010 and 2020, linear smoothing was applied, considering the evolution of waste composition and assuming a regular trend. This led to an overall recalculation of -3.2% in 2010 until -28.3% in 2023.

Table 7.31 Differences in percentages between time series reported in the updated time series and 2025 submission

GAS/SUBSOURCE	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023
CO₂ (kt)										
Waste incineration (5C)	-	-	-	-	-3.2%	-11.7%	-18.6%	-22.1%	-19.4%	-28.3%
MSW incineration reported under 1A4a - fossil	-	-	-	-	-21.9%	-28.7%	-32.4%	-31.8%	-30.6%	-32.1%
N₂O (kt)										
Waste incineration (5C)	-	-	-	-	-	-	-	-	-	-2.3%
%MSW incineration reported under 1A4a - fossil	-	-	-	-	-	-	-0.2%	-0.2%	1.6%	-0.6%
CH₄ (kt)										
Waste incineration (5C)	-	-	-	-	-	-	-	-	-	0.1%
MSW incineration reported under 1A4a - fossil	-	-	-	-	-	-	-0.2%	-0.2%	1.6%	-0.6%

7.4.6 Source-specific planned improvements

No further improvements are planned for the next submission.

7.5 Wastewater handling (5D)


7.5.1 Source category description

Under source category 5D, CH₄, N₂O and NMVOC are estimated both from domestic and industrial wastewater. The principal by-product of the anaerobic decomposition of the organic matter in wastewater is methane gas. Normally, CH₄ emissions are not encountered in untreated wastewater because even small amounts of oxygen tend to be toxic to the organisms responsible for the production of methane. Occasionally, however, as a result of anaerobic decay in accumulated bottom deposits, methane can be produced. Again, wastewater collected in closed underground sewers is not believed to be a significant source of CH₄ (IPCC, 2006).

In 2024, 99.6% of population is served by sewer systems, whereas 93% of population is served by wastewater treatment plants (BLUE BOOK, several years; COVIRI, several years; ISTAT [d], [e], several years). In 1990, the percentage of population served by sewer system was 57%, whereas only 52% of population was served by wastewater treatment plants (BLUE BOOK, several years; COVIRI, several years; ISTAT [d], [e], several years).

In Italy, domestic wastewaters follow the treatment systems and discharge pathways reported in Figure 7.5, whereas in brown are enhanced CH₄ sources.

Figure 7.5 Domestic wastewater treatment system and discharge pathways



Methane is produced from the anaerobic treatment process used to stabilize wastewater sludge.

The plant typology is usually distinguished in 'primary' (only physical-chemical unit operations such as sedimentation), 'secondary' (biological unit process) or 'advanced' treatments, defined as those additional treatments needed to remove suspended and dissolved substances remaining after conventional secondary treatment.

In urban areas, wastewater handling is managed mainly using secondary treatment, with aerobic biological units: a wastewater treatment plant standard design consists of bar racks, grit chamber, primary sedimentation, aeration tanks (with return sludge), settling tank, and chlorine contact chamber. The stabilization of sludge occurs in aerobic or anaerobic reactors; where anaerobic digestion is used, the reactors are covered and provided of gas recovery.

On the contrary, in rural areas, wastewater is treated in Imhoff tanks or in other on-site systems, such as latrines.

For high strength organic waste, such as some industrial wastewater, anaerobic process is recommended also for wastewater besides sludge treatment.

It is assumed that industrial wastewater is treated 85% aerobically and 15% anaerobically (IRSA-CNR, 1998). About this issue, investigation on industries with in-situ wastewater treatment plants is planned to revise the typology of treatment (aerobic vs anaerobic).

Emissions from methane recovered, used for energy purposes, in wastewater treatment plants are estimated and reported under category 1A4a, as reported in Table 7.12.

7.5.2 Methodological issues

Emissions from domestic wastewater – CH₄

CH₄ emissions from domestic wastewater are estimated using a Tier 2 approach, according to the 2006 IPCC Guidelines (IPCC, 2006).

The general equation used to estimate CH₄ emissions from domestic wastewater is:

$$\text{CH}_4 \text{ emissions} = [\sum_{i,j} (U_i * T_{ij} * EF_j)] * (\text{TOW} - S) - R \text{ (kg CH}_4\text{/yr)}$$

where:

TOW = total organics in wastewater in inventory year (kg BOD/yr)

S = organic component removed as sludge in inventory year (kg BOD/yr)

U_i = fraction of population in income group i in inventory year

T_{ij} = degree of utilisation of treatment/discharge pathway or system, j, for each income group fraction i in inventory year

i = income group: rural and urban high income (urban low income is not considered in national inventory, for the typical Italian urbanization)

j = each treatment/discharge pathway or system

EF_j = emission factor (kg CH₄/kg BOD)

R = amount of CH₄ recovered in inventory year (kg CH₄/yr)

An in-depth analysis of national circumstances has been made, collecting many statistical data on population and on urban wastewater treatment plants (BLUE BOOK, several years; COVIRI, several years; ISTAT, 1984; ISTAT, 1987; ISTAT, 1991; ISTAT, 1993; ISTAT [a], [b], 1998; ISTAT [d], [e], several years).

Some data, such as the degree of collected or treated wastewater are available for specific year, so the entire time series has been reconstructed with interpolation of data.

In the following tables (7.32, 7.33, 7.34), domestic wastewater population data are reported.

Table 7.32 Population data for domestic wastewater, 1990 – 2024 (*1000)

Population AD	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total Population	56,778	56,844	56,961	58,289	59,948	60,164	59,236	59,030	58,997	58,971	58,934
Urban high-income Population	52,947	53,134	53,372	54,867	56,602	56,938	56,132	55,950	55,941	55,940	55,927
Rural Population	3,831	3,710	3,589	3,422	3,347	3,225	3,104	3,080	3,056	3,032	3,007
Population served by collected wastewater systems (%)	57.0	69.8	86.0	83.0	90.1	99.4	99.5	99.6	99.6	99.6	99.6
Population served by wastewater treatment plants (%)	51.9	58.0	60.0	69.0	76.1	82.2	88.2	89.4	90.6	91.8	93.0

Table 7.33 Urban high-income Population for domestic wastewater, 1990 – 2024 (*1000)

Urban high-income Population	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Population not served by collected wastewater systems	22,761	16,042	7,472	9,327	5,588	342	267	252	238	224	210
Population served by collected wastewater systems	30,186	37,092	45,900	45,540	51,013	56,597	55,865	55,698	55,704	55,716	55,717
Pop. collected and treated	15,678	21,507	27,540	31,422	38,830	46,501	49,277	49,803	50,481	51,166	51,840
Pop. collected untreated	14,508	15,585	18,360	14,117	12,183	10,096	6,589	5,896	5,223	4,550	3,877

Urban high-income Population	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
<i>sea/lake/river discharge</i>	8,705	9,351	11,016	8,470	7,310	6,058	3,953	3,537	3,134	2,730	2,326
<i>flowing sewer discharge</i>	5,803	6,234	7,344	5,647	4,873	4,038	2,635	2,358	2,089	1,820	1,551

Table 7.34 Rural Population data for domestic wastewater, 1990 – 2024 (*1000)

Rural Population	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Population not served by collected wastewater systems	1,647	1,120	502.5	581.8	330.4	19.4	14.7	13.9	13.0	12.1	11.3
Population served by collected wastewater systems	2,184	2,590	3,087	2,840	3,016	3,206	3,090	3,066	3,043	3,019	2,996
<i>Pop. treated in Imhoff tanks</i>	421	647	845	468	635	967	1,174	1,192	1,210	1,229	1,247
<i>Pop. treated in latrines</i>	1,763	1,943	2,242	2,373	2,381	2,239	1,915	1,874	1,832	1,791	1,749

The emission factor for a wastewater treatment and discharge pathway and system is a function of the maximum CH₄ production potential B₀ and the methane correction factor (MCF) for the wastewater treatment and discharge system, as indicated as following:

$$EF_j = B_0 * MCF_j$$

The default B₀ value (0.6 kg CH₄/kg BOD) and default MCF values have been used.

Type of treatment and discharge pathway or system	MCF
Untreated system	
Sea, river and lake discharge	0.1
Flowing sewer	0
Treated system	
Centralized, aerobic treatment plants	0.05
Anaerobic digester for sludge	0.8
Imhoff tanks	0.5
Latrines	0.1

The total amount of organically degradable material in the wastewater is calculated from the human population and the BOD generation per person:

$$TOW = P * BOD * 0.001 * I * 365$$

where:

TOW = total organics in wastewater in inventory year (kg BOD/yr)

P = country population in inventory year (person)

BOD = country specific per capita BOD in inventory year (g/person/day)

0.001 = conversion from grams to kg BOD

I = correction factor for additional industrial BOD discharged into sewers (I = 1.25, IPCC 2006).

Parameter I, equal to 1.25 has been applied both for collected and uncollected wastewater, in order to consider illegal wastewater spills from industry or craft activities that are not taking into account in official statistics and other industries and establishments (e.g., restaurants, butchers or grocery stores) that can co-discharged with domestic wastewater. Furthermore, I = 1.25 is also applied to Imhoff and latrines: in fact, these systems are used in rural areas where many households have small craft and agricultural activities (such as animal stalls) close to the dwelling.

The organic load in biochemical oxygen demand per person is equal to 60 g BOD₅ capita⁻¹ d⁻¹, as defined by national legislation and expert estimations (Legislative Decree 11 May 1999, no.152; Masotti, 1996; Metcalf and Eddy, 1991).

The total organics in sludge (TOW sludge) has been estimated half of total organics in wastewater, according to international literature (Metcalf and Eddy, 1991), that states that the typical reduction in volatile solids achieved in anaerobic digestion for mixed sludge (primary plus secondary) varies from 45 to 60 percent.

In the following table 7.35, the total amount of organically degradable material expressed in tons, calculated for each treatment/discharge pathway or system is reported.

Table 7.35 Total organically degradable material in domestic wastewater, 1990 – 2024 (t BOD)

TOW (t BOD)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Urban high-income											
Population											
TOW uncollected wastewater	623,069	439,148	204,547	255,337	152,984	9,352	7,299	6,892	6,508	6,125	5,741
TOW wastewater treatment plant	429,195	588,761	753,901	860,185	1,062,969	1,272,957	1,348,948	1,363,349	1,381,913	1,400,656	1,419,126
TOW sludge	214,598	294,381	376,951	430,093	531,485	636,478	674,474	681,674	690,957	700,328	709,563
TOW untreated (sea/lake/river)	238,289	255,979	301,560	231,876	200,113	165,825	108,219	96,836	85,784	74,740	63,678
TOW untreated (flowing sewer)	158,860	170,653	201,040	154,584	133,409	110,550	72,146	64,557	57,190	49,827	42,452
Rural Population											
TOW uncollected wastewater	45,088	30,665	13,755	15,925	9,045	530	404	379	356	332	309
TOW Imhoff	11,535	17,705	23,129	12,799	17,378	26,467	32,143	32,640	33,136	33,633	34,130
TOW latrines	48,263	53,197	61,366	64,955	65,192	61,300	52,433	51,297	50,161	49,024	47,887

As previously reported, in Italy wastewater handling is managed mainly using a secondary treatment, with aerobic biological units. The stabilization of sludge occurs in aerobic or anaerobic reactors covered and provided of gas recovery. All the anaerobic digestion systems are equipped with systems to collect the methane produced. The methane collected is partly flared and partly used for energy purposes. The total methane recovered is estimated based on the methane production and the efficiency of capture. Where anaerobic digestion of sludge is used, the reactors are covered and provided of gas recovery and the efficiency of capture is equal to 100%. In fact, in Italy, anaerobic digestion tanks for sludge stabilization in wastewater treatment plants are built with fixed covered: fixed covered provide a free space between the roof of the digester and the liquid surface. Gas storage is provided so that when the liquid volume is changed, gas, not air, will be drawn into the digester, and gas will not be lost by displacement.

CH₄ emissions from sludges have been subtracted from the total amount of CH₄ produced, because emissions from sludge from wastewater treatment are considered in landfills, agricultural soils and incineration.

Moreover, CH₄ recovery has been distinguished between flaring and CH₄ recovery for energy generation, which has been reported in the Energy Sector.

Emissions from domestic wastewater –N₂O

Nitrous oxide (N₂O) emissions can occur as direct and indirect emissions. Direct emissions occur from nitrification and denitrification in wastewater treatment plants, whereas indirect emissions are those from wastewater after disposal of effluent into waterways, lakes or sea.

Emissions from advanced centralized wastewater treatment plants are typically much smaller than those from effluent and are estimated using the method reported in Box 6.1 of the Volume 5, Chapter 6 of new 2006 IPCC Guidelines (IPCC, 2006).

Direct emissions

$$N_2O_{PLANTS} = P * T_{PLANT} * F_{IND-COM} * EF_{PLANT}$$

where:

N_2O_{PLANTS} = total N_2O emissions from plants in inventory year (kg N_2O /yr)

P = human population

T_{PLANT} = degree of utilization of modern, centralized wastewater treatment plants (%)

$F_{IND-COM}$ = fraction of industrial and commercial co-discharged protein (default = 1.25)

EF_{PLANT} = emission factor, 3.2 g N_2O /person/year

Indirect emissions

$$N_2O_{EMISSIONS} = N_{EFFLUENT} * EF_{EFFLUENT} * 44/28$$

where:

$N_2O_{EMISSIONS}$ = N_2O emissions in inventory year (kg N_2O /yr)

$N_{EFFLUENT}$ = nitrogen in the effluent discharged to aquatic environments (kg N/yr)

$EF_{EFFLUENT}$ = emission factor for N_2O emissions from discharged to wastewater assumed equal to 0.005 (kg N_2O -N/kg N)

Moreover:

$$N_{EFFLUENT} = N_{EFFLUENT\ TOT} - N_{SLUDGE} = (P * Protein * F_{NPR} * F_{NON-COM} * F_{IND-COM}) - N_{SLUDGE}$$

where:

$N_{EFFLUENT}$ = nitrogen in the effluent discharged to aquatic environments (kg N/yr)

P = human population

Protein = annual per capita protein consumption (kg/person/yr)

F_{NPR} = fraction of nitrogen in protein (default = 0.16 kg N/kg protein)

$F_{NON-COM}$ = fraction of non-consumed protein added to the wastewater

$F_{IND-COM}$ = fraction of industrial and commercial co-discharged protein (default = 1.25)

N_{SLUDGE} = nitrogen removed with sludge (kg N/yr)

The time series of the protein intake is from the yearly FAO Food Balance (FAO, several years) and refers to the Italian value. The estimation procedure checks for consistency with sludge produced and sludge applications, as sludge applied to agriculture soils, sludge incinerated, sludge composting and sludge deposited in solid waste disposal. Sludge spreading is subtracted from nitrogen in the effluent discharged to aquatic environments and is not accounted for twice.

For the parameter $F_{NON-COM}$ the value of 1.1 it is assumed, because, even if Italy is a developed country, garbage disposals of food that is not consumed and may be washed down the drain are not used.

Emissions from industrial wastewater – CH₄

The methane estimation concerning industrial wastewaters makes use of the IPCC method based on wastewater output and the respective degradable organic carbon for each major industrial wastewater

source. Default emission factors of methane per Chemical Oxygen Demand (COD) equal to 0.25 kg CH₄ kg⁻¹ COD, suggested in the 2006 IPCC Guidelines (IPCC, 2006), has been used for the whole time series.

It is assumed that industrial wastewaters are treated 85% aerobically and 15% anaerobically (IRSA-CNR, 1998). As previously reported, investigation on industries with in-situ wastewater treatment plants is planning in order to revise the typology of treatment (aerobic vs anaerobic).

Data has been collected for several industrial sectors (iron and steel, refineries, organic chemicals, food and beverage, paper and pulp, textiles and leather industry). The total amount of organic material, for each industry selected, has been calculated multiplying the annual production (t year⁻¹) by the amount of wastewater consumption per unit of product (m³ t⁻¹) and by the degradable organic component (kg COD (m³)⁻¹). Moreover, the fraction of industrial degradable organic component removed as sludge has been assumed equal to zero. The yearly industrial productions are reported in the national statistics (ISTAT, several years [a], [b] and [c]), whereas the wastewater consumption factors and the degradable organic component are either from 2006 IPCC Guidelines (IPCC, 2006) or from national references. National data have been used in the calculation of the total amount of both COD produced and wastewater output specified as follows: refineries (UNEM, several years), organic chemicals (FEDERCHIMICA, several years), beer (Assobirra, several years), wine, milk and sugar sectors (ANPA-ONR, 2001), pulp and paper sector (ANPA-FLORYS, 2001; Assocarta, several years), and leather sector (ANPA-FLORYS, 2000; UNIC, several years).

In Table 7.36 detailed references for 2024 are reported: for these national data, slight differences within the years can occur.

Emissions from industrial wastewater – N₂O

N₂O emissions from industrial wastewater have been estimated based on the emission factors equal to 0.25 g N₂O/m³ of wastewater production (EMEP/CORINAIR, 2007). EMEP/EEA Guidelines, after 2007 version, does not report any N₂O E.F but, about the methodology to estimate N₂O emissions from industrial wastewater, they refer to 2006 IPCC Guidelines. In 2006 IPCC Guidelines it is written that industrial wastewater may be treated on site or released into domestic wastewater. In the national inventory, the fraction of industrial wastewater released into domestic wastewater is estimated because of the parameter F_{IND-COM}. For the fraction treated on site 0.25 g N₂O/m³ has been applied to the volume of wastewater generated for type of industry.

The wastewater production is resulting from the model for the estimation of methane emissions from industrial wastewater.

Table 7.36 Wastewater generation and COD values, 2024

	Wastewater generation (m ³ /t)	References	COD (g/l)	References
Coke	1.5	IPCC, 2000	0.1	IPCC, 2000
Petroleum Refineries	UNIONE ENERGIA PER LA MOBILITÀ supplies Total COD generated per year			
Organic Chemicals	22.3	FEDERCHIMICA, several years	3	IPCC, 2000
Paints	5.5	IPCC, 2000	5.5	IPCC, 2000
Plastics and Resins	0.6	IPCC, 2000	3.7	IPCC, 2000
Soap and Detergents	3	IPCC, 2000	0.9	IPCC, 2000
Vegetables, Fruits and Juices	20	IPCC, 2000	5.2	IPCC, 2000
Sugar Refining	4	ANPA-ONR, 2001	2.5	ANPA-ONR, 2001
Vegetable Oils	3.1	IPCC, 2000	1.2	IPCC, 2000
Dairy Products	3.87	ANPA-ONR, 2001	2.7	ANPA-ONR, 2001
Wine and Vinegar	3.8	ANPA-ONR, 2001	0.2	ANPA-ONR, 2001
Beer and Malt	420 (l/hl)	Assobirra, several years	2.9	IPCC, 2000
Alcohol Refining	24	IPCC, 2000	11.0	IPCC, 2000
Meat and Poultry	13	IPCC, 2000	4.1	IPCC, 2000
Fish Processing	13	same value of Meat and Poultry	2.5	IPCC, 2000

	Wastewater generation (m ³ /t)	References	COD (g/l)	References
Paper	25	Assocarta, several years	0.1	ANPA-FLORYS, 2001; Assocarta, several years
Pulp	25	Assocarta, several years	0.1	ANPA-FLORYS, 2001; Assocarta, several years
Textiles (dyeing)	60	IPCC, 1995	1.0	IPCC, 2000
Textiles (bleaching)	350	IPCC, 1995	1.0	IPCC, 2000
Leather	0.12	UNIC, several years	4.02	UNIC, several years

In Table 7.37, N₂O emissions from industrial wastewater are reported, together with the deriving nitrogen in effluent (kt N-N₂O), that is reported in the CRF table 5.D. In the CRF Reporter GHG inventory software the table related to the category 5.D.2 requests, among the others, the N in effluent (kt) as well as the IEF (kg N₂O-N/kg N); N in effluent is calculated with the following formula, assuming the default emission factor 0.25 kg N₂O-N/kg N (IPCC, 2006):

$$\text{N in effluent (kt)} = \text{N}_2\text{O emissions (kt)} / \text{IEF (kg N}_2\text{O-N/kg N)} * 28/44$$

As N₂O emissions from industrial wastewater are estimated on the basis of the cubic meters of wastewater produced by a specific industry and the emission factor equal to 0.25 g N₂O/m³ (EMEP/CORINAIR, 2007), it was not possible to report this value in the CRTs: consequently, we were forced to derive the N in effluent from the N₂O emissions by multiplying for the conversion factor 28/44 and dividing for the IEF 0.25 kg N₂O-N/kg N, the maximum for a cautionary reason.

Table 7.37 N₂O emissions from industrial wastewater, 1990 – 2024 (kt)

N ₂ O Emissions (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Industrial wastewater											
Industrial wastewater production (1000 m ³)	908,840	928,479	920,614	867,085	717,846	659,246	654,586	690,830	664,493	632,380	647,674
EF (g/m ³)	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
N ₂ O Emissions (kt N ₂ O)	0.227	0.232	0.230	0.217	0.179	0.165	0.164	0.173	0.166	0.158	0.162
N in effluent (kt)	0.578	0.591	0.586	0.552	0.457	0.420	0.417	0.440	0.423	0.402	0.412

Emissions from domestic and industrial wastewater – NMVOC

Emissions from NMVOC has been also estimated, both from domestic and industrial wastewaters, using a default emission factor derived from Guidebook published by the European Environmental Agency with the CLRTAP Task Force on Emission Inventories and Projections (EMEP/EEA, 2023).

In Table 7.38 NMVOC emissions from domestic and industrial wastewater are reported for the whole time series.

Table 7.38 NMVOC emissions from domestic and industrial wastewater, 1990 – 2024 (kt)

NMVOC Emissions (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Domestic wastewater											
Equivalent inhabitants (*1000)	46,436	60,015	65,601	73,426	76,847	75,239	91,124	92,532	93,940	95,348	96,757
Domestic wastewaters production (10 ⁶ m ³)	4,237	5,476	5,986	6,700	7,012	6,866	8,315	8,444	8,572	8,701	8,829
Per capita water supply (lt./person*die)	250	250	250	250	250	250	250	250	250	250	250
EF (mg/m ³)	15	15	15	15	15	15	15	15	15	15	15

NM VOC Emissions (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
NM VOC Emissions (t)	63.6	82.1	89.8	100.5	105.2	103.0	124.7	126.7	128.6	130.5	132.4
Industrial wastewater											
Industrial wastewaters	908,840	928,479	920,614	867,085	717,846	659,246	654,586	690,830	664,493	632,380	647,674
production (1000 m ³)											
EF (mg/m ³)	15	15	15	15	15	15	15	15	15	15	15
NM VOC Emissions (t)	13.6	13.9	13.8	13.0	10.8	9.9	9.8	10.4	10.0	9.5	9.7

7.5.3 Uncertainty and time-series consistency

The combined uncertainty in CH₄ and N₂O emissions from wastewater handling is estimated to be about 102% in annual emissions, 100% and 20% for activity data and emission factor respectively, as derived by the IPCC Guidelines (IPCC, 2000; IPCC, 2006).

Concerning domestic wastewater, CH₄ emission trends are shown in Table 7.39, whereas the emission trend for N₂O emissions is shown in Table 7.40.

Table 7.39 CH₄ emissions from domestic wastewater, 1990 – 2024 (t)

CH ₄ Emissions (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Urban high-income Population											
CH ₄ uncollected wastewater	37,384	26,349	12,273	15,320	9,179	561	438	414	391	368	344
CH ₄ wastewater treatment plant	6,438	8,831	11,309	12,903	15,945	19,094	20,234	20,450	20,729	21,010	21,287
CH ₄ anaerobic digestion	103,007	141,303	180,936	206,444	255,113	305,510	323,748	327,204	331,659	336,157	340,590
CH ₄ untreated (sea/lake/river)	14,297	15,359	18,094	13,913	12,007	9,950	6,493	5,810	5,147	4,484	3,821
CH ₄ untreated (flowing sewer)	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Rural Population											
CH ₄ uncollected wastewater	2,705	1,840	825	956	543	32	24	23	21	20	19
CH ₄ Imhoff	3,460	5,312	6,939	3,840	5,213	7,940	9,643	9,792	9,941	10,090	10,239
CH ₄ latrines	2,896	3,192	3,682	3,897	3,912	3,678	3,146	3,078	3,010	2,941	2,873
CH ₄ total produced	170,188	202,185	234,057	257,272	301,910	346,765	363,726	366,770	370,897	375,071	379,173
CH ₄ recovered	103,007	141,303	180,936	206,444	255,113	305,510	323,748	327,204	331,659	336,157	340,590
CH ₄ flared	103,007	140,583	179,473	205,802	250,613	285,108	302,042	306,196	312,356	314,749	320,191
CH ₄ energy recovery	0.000	719	1,463	643	4,500	20,401	21,706	21,008	19,303	21,408	20,399
CH₄ total emissions	67,181	60,882	53,121	50,828	46,798	41,255	39,978	39,566	39,238	38,913	38,583

Table 7.40 N₂O emissions from domestic wastewater, 1990 – 2024 (t)

N ₂ O Emissions (t)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
N ₂ O emissions from wastewater effluent (Indirect emissions)	3,911	3,787	4,010	4,037	4,514	4,208	4,244	4,329	4,262	4,334	4,354
N ₂ O emissions from wastewater treatment plants (Direct emissions)	86.9	84.2	91.1	155.2	151.9	160.6	158.1	157.5	157.5	157.4	157.3
N₂O total emissions	3,997	3,871	4,101	4,192	4,666	4,368	4,402	4,487	4,419	4,491	4,511

The amount of total industrial wastewater production is reported, for each sector, in Table 7.41.

CH₄ emission trend for industrial wastewater handling for different sectors is shown in Table 7.42, whereas the emission trend for N₂O emissions from industrial wastewater handling is shown again in Table 7.43.

Concerning CH₄ emissions from industrial wastewater, neither wastewater flow nor average COD value change much over time, therefore emissions are stable and mainly related to the production data.

Table 7.41 Total industrial wastewater production by sector, 1990 – 2024 (1000 m³)

Wastewater production (1000 m ³)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Iron and steel	9.53	7.78	6.76	6.86	6.17	2.97	2.17	2.02	2.43	1.83	1.84
Oil refinery	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Organic chemicals	210.94	212.32	215.05	214.74	214.12	213.80	213.67	213.72	213.57	213.35	213.33
Food and beverage	179.12	177.38	182.74	185.66	186.26	177.91	181.45	184.11	183.78	179.53	182.84
Pulp and paper	377.17	402.95	387.28	366.02	232.69	202.64	216.88	244.80	220.72	188.85	201.30
Textile industry	108.46	103.05	101.57	75.49	64.36	48.90	29.92	33.74	30.46	36.69	32.75
Leather industry	23.62	25.00	27.22	18.32	14.25	13.03	10.51	12.44	13.54	12.13	15.62
Total	908.84	928.48	920.61	867.09	717.85	659.25	654.59	690.83	664.49	632.38	647.67

Table 7.42 CH₄ emissions from anaerobic industrial wastewater treatment, 1990 – 2024 (kt)

CH ₄ Emissions (kt)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Iron and steel	0.036	0.029	0.025	0.026	0.023	0.011	0.008	0.008	0.009	0.007	0.007
Oil refinery	5.850	5.625	4.250	4.750	4.750	4.750	4.750	4.750	4.750	4.750	4.750
Organic chemicals	23.794	23.911	24.173	24.177	24.069	23.998	24.014	24.027	24.006	23.985	23.987
Food and beverage	22.946	22.112	22.871	23.197	23.447	22.575	22.736	23.188	23.535	22.871	23.207
Pulp and paper	0.923	0.986	1.055	0.997	0.544	0.552	0.591	0.667	0.601	0.514	0.548
Textile industry	4.067	3.864	3.809	2.831	2.414	1.834	1.122	1.265	1.142	1.376	1.228
Leather industry	3.192	3.378	3.677	2.901	2.517	2.272	1.788	2.024	2.040	1.827	2.352
Total	60.81	59.91	59.86	58.88	57.76	55.99	55.01	55.93	56.08	55.33	56.08

Table 7.43 N₂O emissions from industrial wastewater, 1990 – 2024 (kt)

N ₂ O Emissions (kt)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Industrial wastewater	0.227	0.232	0.230	0.217	0.179	0.165	0.164	0.173	0.166	0.158	0.162

7.5.4 Source-specific QA/QC and verification

Where information is available, wastewater flows and COD concentrations are checked with those reported yearly by the industrial sectoral reports or technical documentation developed in the framework of the Integrated Pollution and Prevention Control (IPPC) Directive of the European Union (<http://eippcb.jrc.es>).

Moreover, in the framework of EPER/E-PRTR registry the methodology used to estimate emissions from wastewater handling can be used by the operators of wastewater treatment plants to check if their emission data exceed the reporting threshold values.

Finally, a Ph.D. thesis on GHG emissions from wastewater handling has been carried out at Environmental, Hydraulic, Infrastructures and Surveying Engineering Department (DIAR) of Politecnico di Milano (Solini, 2010), where national methodology has been compared with that reported in 2006 IPCC Guidelines (IPCC, 2006) and with a methodology developed in the framework of a previous thesis Ph.D. for the estimation of emissions from wastewater treatment plants located in Regione Lombardia.

7.5.5 Source-specific recalculations

Recalculations regard the update of landfilled sludge data for the year 2022 and 2023 as well as the update of the annual production for years 2021, 2022 and 2023 for some industries (pulp and paper, meat and poultry industry and coke production). Moreover, the revision of population for 2022 and 2023 has been made.

7.5.6 Source-specific planned improvements

According to the 2021 annual submission review process, where the ERT encouraged the Party to pursue investigation into a different methodology for estimating total biogas production and revise the amount of CH₄ flared, a draft methodology has been applied, with substantial differences in biogas production. Total gas production is estimated usually from the percentage of volatile solids reduction: typical values vary from 0.75 to 1.12 m³/kg of volatile solids destroyed (Metcalf and Eddy, 1991): unfortunately, data on volatile solids abatement are still not available at present. Gas production can also be crudely estimated on a per capita basis: the normal yield is 15 to 22 m³/10³person-day in primary plants treating normal domestic wastewater; in secondary treatment plants the gas production increase to about 28 m³/10³person-day. Applying this parameter, the total gas production and consequently the CH₄ production has been estimated as reported in the following Table 7.44. Differences are very important, thus investigations are ongoing, concerned also volatile solids destroyed.

Table 7.44 CH₄ production from anaerobic digestion of sludge, estimated with IPCC methodology and Metcalf and Eddy parameters

Total Gas Production in anaerobic digestion	1990	1995	2000	2005	2010	2015	2020	2023	2024
TOW sludge (kg BOD/year)	214,597,690	294,380,746	376,950,614	430,092,574	531,484,619	636,478,432	674,474,078	681,674,296	690,956,750
CH ₄ anaerobic digestion - IPCC Guidelines (kg CH ₄ /year)	103,006,891	141,302,758	180,936,295	206,444,436	255,112,617	305,509,647	323,747,558	327,203,662	331,659,240
CH ₄ anaerobic digestion - Metcalf and Eddy (kg CH ₄ /year)	54,211,645	74,366,432	95,225,223	108,649,939	134,263,586	160,787,112	170,385,568	172,204,486	174,549,418

Further improvements are welcome as soon as additional data are available. We expect that environmental reports from industry will be improved but in recent years there has been a reversal of this trend with less and less data and information being published. Investigation on industries with in-situ wastewater treatment plants is started but no results are available at the moment. Moreover, specific survey on those industries that produce considerable amounts of wastewater with significant organic carbon levels are planned, to revise the methodology for estimating emissions from industrial wastewater, according to the 2019 IPCC Guidelines.

Moreover, Italy plans to conduct a survey on wastewater generation and COD values. The first step consists in finding the sustainability reports of the various trade associations and major industrial groups to acquire the most up-to-date but already available information. Any insights will be made in subsequent submissions through meetings and comparisons with industrial associations. ISPRA is collaborating, in the framework of other issues not specifically referred to the inventory, with Secam, a company founded in 1989, currently Italy's leading manufacturer and supplier of chemicals for industry and civil and industrial wastewater treatment services that could help us to set some parameters country specific.

8 RECALCULATIONS AND IMPROVEMENTS

8.1 Explanations and justifications for recalculations

To meet the requirements of transparency, consistency, comparability, completeness and accuracy of the inventory, the entire time series from 1990 onwards is checked and revised every year during the annual compilation of the inventory. Measures to guarantee and improve these qualifications are undertaken and recalculations should be considered as a contribution to the overall improvement of the inventory.

Recalculations are elaborated on account of changes in the methodologies used to carry out emission estimates, changes due to different allocation of emissions as compared to previous submissions, changes due to error corrections and in consideration of new available information.

The revisions that lead to relevant changes in GHG emissions are pointed out in the specific sectoral chapters and summarized in the following section 8.4.1.

8.2 Implications for emission levels

The last time series is summarized in Table 8.1 by gas; differences in emission levels due to recalculations are also reported.

Improvements in the calculation of emission estimates have led to a recalculation of the entire time series of the national inventory. Considering total GHG emissions without LULUCF, estimates show a decrease in comparison with the last year submission, equal to 0.41% for 1990 and a decrease of 1.98% for 2023. Considering the national total with the LULUCF sector, the year 1990 has decreased by 2.21% and the 2023 emission levels decreased by 3.50%. Detailed explanations of these recalculations are provided in the sectoral chapters.

Table 8.1 Differences in time series between the 2026 and 2025 submissions due to recalculations

	subm	1990	1995	2000	2005	2010	2015	2020	2022	2023
CO₂ net emissions/removals (kt CO₂-eq.)	2026	423,941	413,046	438,806	456,835	387,059	311,845	256,426	291,187	251,103
	2025	432,937	424,242	448,286	466,925	395,390	318,933	262,124	299,836	257,900
<i>Differences</i>		-2.08%	-2.64%	-2.11%	-2.16%	-2.11%	-2.22%	-2.17%	-2.88%	-2.64%
CO₂ emissions (without LULUCF) (kt CO₂-eq.)	2026	438,208	448,596	469,598	501,365	434,573	359,658	300,706	336,796	309,321
	2025	438,208	448,596	469,598	501,365	435,672	361,244	302,600	340,115	312,291
<i>Differences</i>		0.00%	0.00%	0.00%	0.00%	-0.25%	-0.44%	-0.63%	-0.98%	-0.95%
CH₄ emissions (kt CO₂-eq.)	2026	55,843	57,411	58,331	55,062	53,078	49,328	47,327	45,593	44,620
	2025	55,744	57,269	58,184	55,035	53,126	49,535	47,594	46,091	45,355
<i>Differences</i>		0.18%	0.25%	0.25%	0.05%	-0.09%	-0.42%	-0.56%	-1.08%	-1.62%
CH₄ emissions (without LULUCF) (kt CO₂-eq.)	2026	55,016	57,139	57,833	54,793	52,784	49,089	47,054	45,120	44,269
	2025	55,017	57,097	57,786	54,867	52,932	49,397	47,419	45,716	45,161
<i>Differences</i>		0.00%	0.07%	0.08%	-0.13%	-0.28%	-0.62%	-0.77%	-1.30%	-1.98%
N₂O emissions (kt CO₂-eq.)	2026	23,094	24,468	25,331	24,609	16,850	15,220	15,503	13,909	14,570
	2025	25,668	27,512	28,144	27,193	19,062	17,694	18,412	16,702	17,596
<i>Differences</i>		-10.03%	-11.06%	-9.99%	-9.50%	-11.61%	-13.98%	-15.80%	-16.72%	-17.20%
N₂O emissions (without LULUCF) (kt CO₂-eq.)	2026	22,603	24,213	25,018	24,404	16,631	15,091	15,277	13,558	14,268
	2025	24,757	26,715	27,456	26,605	18,661	17,365	17,902	16,032	16,987
<i>Differences</i>		-8.70%	-9.37%	-8.88%	-8.27%	-10.88%	-13.10%	-14.66%	-15.43%	-16.01%
HFCs (kt CO₂-eq.)	2026	372	1,100	3,748	9,669	12,790	11,786	9,415	8,279	7,726
	2025	372	1,100	3,748	9,669	12,805	12,503	10,347	9,350	8,736
<i>Differences</i>		0.00%	0.00%	0.00%	0.00%	-0.12%	-5.73%	-9.00%	-11.46%	-11.56%
PFCs (kt CO₂-eq.)	2026	2,615	1,351	1,363	1,759	1,377	1,540	516	462	297
	2025	2,615	1,351	1,363	1,759	1,377	1,540	516	462	297
<i>Differences</i>		0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
Unspecified mix (kt CO₂-eq.)	2026		24	24	24	24	24	22	22	29
	2025		24	24	24	24	24	22	22	29

	subm	1990	1995	2000	2005	2010	2015	2020	2022	2023
<i>Differences</i>			0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
SF₆ (kt CO₂-eq.)	2026	421	700	621	565	405	483	252	405	367
	2025	421	700	621	565	405	483	252	405	367
<i>Differences</i>		0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
NF₃ (kt CO₂-eq.)	2026		77	13	33	20	28	16	20	20
	2025		77	13	33	20	28	16	20	20
<i>Differences</i>			0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
Indirect CO₂ (kt CO₂-eq.)	2026	1,391	1,296	1,173	1,155	976	815	876	790	843
	2025	1,391	1,401	1,430	1,393	1,355	1,296	1,254	1,214	1,187
<i>Differences</i>		0.00%	-7.48%	-17.95%	-17.06%	-27.93%	-37.08%	-30.11%	-34.94%	-28.96%
Total (with LULUCF) (kt CO₂-eq.)	2026	507,677	499,472	529,411	549,712	472,579	391,070	330,352	360,667	319,575
	2025	519,148	513,570	541,571	562,371	483,205	401,572	340,172	373,694	331,153
<i>Differences</i>		-2.21%	-2.75%	-2.25%	-2.25%	-2.20%	-2.62%	-2.89%	-3.49%	-3.50%
Total (without LULUCF) (kt CO₂-eq.)	2026	520,626	534,495	559,393	593,769	519,581	438,515	374,134	405,451	377,139
	2025	522,781	536,955	561,797	596,055	522,892	443,414	379,963	412,928	384,742
<i>Differences</i>		-0.41%	-0.46%	-0.43%	-0.38%	-0.63%	-1.10%	-1.53%	-1.81%	-1.98%

8.3 Implications for emission trends, including time series consistency

Recalculations account for an improvement in the overall emission trend and consistency in time series. The trend 1990-2023, without LULUCF, results in a reduction of emissions equal to 27.6% whereas it was 26.4% in the last year's submission. The trend with LULUCF results in a reduction of emissions equal to 37.1%, whereas the decrease was equal to 36.2% in last year's submission.

8.4 Recalculations, response to the review process and planned improvements

This chapter summarizes the recalculations and improvements made to the Italian GHG inventory since the last year submission. In addition to a new year, the inventory is updated annually by a revision of the existing activity data and emission factors to include new information available; the update could also reflect the revision of methodologies. Revisions always apply to the whole time series. The inventory may also be expanded by including categories not previously estimated if sufficient information on activity data and suitable emission factors has been identified and collected.

8.4.1 Recalculations

All sectors were involved in changes due to updates of activity data and some emission factors. Specifically:

Energy

Recalculations affected the years 2021 and 2022 because of the update of non-ferrous metal activity data and lime production. CH₄ and N₂O emissions from charcoal production from 1A1 have been included considering the methodology in the 2019 IPCC refinements

As regards Aviation, in 2026 submission estimates of CH₄ and N₂O have been recalculated by Eurocontrol from 2002, due to a new evaluation of taxi times.

Road transport estimates have been revised from 2015 based on the new availability of activity data and fuels specifications information.

Recalculations regarding Navigation occurred as a result of the revision of ISTAT data about the number of ships arriving in Italian ports in 2023.

IPPU

Recalculations mainly affected the last three years of the time series for the update of activity data in sectors 2A, 2B, 2D and 2F. The update of activity data for clinker production and lime production (2021-2023) and of the CO₂ EF for Glass production in 2023 has led to changes in the last years of the time series. The update of the activity data of Calcium carbide production and use has led to recalculations in CO₂ emissions in 2023. As for CO₂ emissions from lubricants' use (2.D.1) and from the use of urea in the engines (2.D.3.a), recalculations occurred from 2005 and 2006, respectively, due to the update of the data resulting from COPERT model. As for 2F, a technical correction has been made to the estimate of emissions from the Fire protection sub-sector as part of the ESR review process. The technical correction resulted in a reduction in emissions from firefighting compared to Submission 2025; for 2023 the updated emissions in kt CO₂eq are approximately 65% lower than the emissions estimated in the previous submission. A minor recalculation occurred in sector 2F1 -refrigeration and air conditioning (except for Domestic refrigeration). Other revisions affected the levels of indirect CO₂ emissions for the update of activity data regarding the domestic solvent use throughout the period.

Agriculture

The major recalculations concern the N₂O emissions from agriculture soils and the N₂O and CH₄ emissions from manure management.

For N₂O emissions from agriculture soils, the main recalculations were carried out as the updated EFs for direct and indirect emissions and frac leach value from the 2019 Refinement of IPCC Guidelines have been applied.

For N₂O emissions from manure management, the main recalculations were carried out as the updated EFs for direct and indirect emissions and frac leach value from the 2019 Refinement of IPCC Guidelines have been applied for all manure management systems.

The main recalculations of CH₄ emissions from manure management for cattle were carried out as the EFs were applied only to housed livestock to avoid double counting of emissions from pasture which are calculated separately.

LULUCF

The recalculation occurred in the sector is due to the following elements reported in table 8.3:

Table 8.3 Drivers for recalculation in the LULUCF sector

	CO ₂	CH ₄	N ₂ O
Forest land	- Revision of the DOM estimation methodology following the 2025 Comprehensive Review under Governance and LULUCF Regulation affecting the entire time-series. - Update of the burned-area value for one Italian region, affecting only the year 2023.	<u>Biomass burning:</u> Update of the burned-area value for one Italian region, affecting only the year 2023.	
Cropland	- Methodological revision for estimating emissions from drained organic soils (moved from CRT Table4.B to Table 4(II)), implemented following the 2025 Comprehensive Review under the Governance and LULUCF Regulations. This affects the entire time series. - Update of activity data for a specific annual crop from 2020 onwards, based on revised national statistics. Due to land use smoothing rules, this results in revised cropland areas for 2016–2020 and updated land	<u>Drained organic soils:</u> Methodological revision for estimating emissions from drained organic soils (included in Table 4(II)), implemented following the 2025 Comprehensive Review under the Governance and LULUCF Regulations. This affects the entire time series, the soil carbon pool, and the cropland remaining cropland subcategory.	<u>Direct/indirect N₂O emissions:</u> Update of activity data for a specific annual crop from 2020 onwards, based on revised national statistics (ISTAT). Due to land use smoothing rules, this affects the cropland–grassland balance from 2016 onwards and results in changes in N₂O emissions as a consequence of the CO₂ emissions revision.

	use transitions involving annual cropland. This affects both living biomass and soil carbon pools, and both cropland remaining cropland and land converted to cropland. - Update of activity data for annual and perennial woody crops under sustainable management in a few regions from 2020 onwards, affecting only the soil carbon pool and the cropland remaining cropland subcategory.	
Grassland	<u>C-stock change (CRT 4.C):</u> - Methodological revision for estimating emissions from drained organic soils (moved from CRT Table 4.C to Table 4(II)), implemented following the 2025 Comprehensive Review under the Governance and LULUCF Regulations. This affects the entire time series. - Updated activity data for a specific annual crop (ISTAT, from 2020). Effects on cropland–grassland balance from 2016; adjustments in grassland remaining grassland (2017–2020), and new transitions from cropland to grassland from 2021 onwards. - Correction of an error in the 2023 biomass estimate for other wooded land. <u>Biomass burning:</u> Update of the burned-area value for one Italian region, affecting only the year 2023.	<u>Drained organic soils:</u> Methodological revision for estimating emissions from drained organic soils (included in Table 4(II)), implemented following the 2025 Comprehensive Review under the Governance and LULUCF Regulations. This affects the entire time series, the soil carbon pool, and the grassland remaining grassland subcategory. <u>Biomass burning:</u> Update of the burned-area value for one Italian region, affecting only the year 2023. <u>Direct/indirect N₂O emissions:</u> Update of activity data for a specific annual crop from 2020 onwards, based on revised national statistics (ISTAT). Due to landuse smoothing rules, this affects the grassland–cropland balance from 2016 onwards and results in changes in N₂O emissions as a consequence of the CO₂ emissions revision. <u>Biomass burning:</u> Update of the burned-area value for one Italian region, affecting only the year 2023.
Wetlands	-	
Settlements	- Revision of carbon stock change estimates for land converted to settlements following the 2025 Comprehensive Review under the Governance and LULUCF Regulations, applying the 20-year transition period and assuming settlement SOC = 80% of the previous land-use category (IPCC 2006). Updates to SOC values for annual crops, woody crops and grasslands included. Significant impact on the entire time series.	<u>Direct/indirect N₂O emissions:</u> Changes in N₂O emissions resulting from the CO₂ emissions revision following the 2025 Comprehensive Review under the Governance and LULUCF Regulations.
HWP	Recalculation due to revised FAOSTAT data for wood-based panels (2020–2023), paper & paperboard (2022–2023), and industrial roundwood (2023). Minor deviations for 1990–2020 reflect legacy effects of FAOSTAT revisions prior to 1990.	

Waste

Recalculations occur in N₂O and CH₄ emissions in waste incineration because of the recalculation of open burning of agricultural waste emission factors from 2001 because of the implementation of data from a survey concerning the amount of agricultural residues.

8.4.2 Response to the UNFCCC review process

A complete list of improvements following the UNFCCC review process is reported in Annex 9.

Improvements regarded the completeness and transparency of the information reported in the NID.

Most of the recommendations have been addressed in the last submissions. Additional information has been provided in all the sectors, more information on methodology used to estimate emissions for industrial processes (especially for F-gases estimations), estimates for the agriculture sector and LULUCF has been recalculated and the description of country specific methods and the rationale behind the choice of emission factors, activity data and other related parameters for different sector has been better detailed.

8.4.3 Planned improvements (e.g., institutional arrangements, inventory preparation)

Specific improvements are identified in the relevant chapters and specified in the 2026 QA/QC plan; they are summarized in the following.

For the energy and industrial sectors, the database where information collected in the framework of different EU legislation, Large Combustion Plant, E-PRTR and Emissions Trading, is annually updated and improved. The database has helped to highlight the main discrepancies in information and detecting potential errors leading to better use of these data in the national inventory. Energy data submitted to the international organizations in the framework of the Joint Questionnaire OECD/IEA/EUROSTAT will be compared with the national energy statistics with the aim to reduce the differences with the international statistics. A revision of biomass and waste fuel consumption time series is planned for the next submission based on energy data communicated by the Ministry of Environment to the Joint Questionnaire OECD/IEA/EUROSTAT, after a verification and comparison with data up to now used and available in the National Energy Balance reports.

Improvements for road transport sector will be connected to the availability of information regarding activity data, calculation factors and parameters, development of the methodology and update of the software.

For maritime activities further improvements will be related to activity data verification on ship movements and emission estimates with the National Institute of Statistics. It is planned the creation of an emission estimation database which calculate every year emissions at harbor level taking in account of the information officially provided by Italy to Eurostat per type of ship, class of tonnage and movement statistics.

For the Industrial processes sector, investigations concerning the replacement of natural raw material in clinker manufacture and in lime production are planned to better explain differences of the average emission factors in the time series. Many improvements are planned for Fgases emissions estimates and in the professional refrigeration sub-sector to try gathering more information and data on the equipment manufactured and sold over the years, the average charge, the operating emission factor in order to estimate the manufacturing and lifetime emissions.

For the agriculture and waste sectors, improvements will be related to the availability of new information on emission factors, activity data as well as parameters necessary to carry out the estimates. For agriculture, based on regional livestock management data, checks will be made on the data used to estimate national emissions on livestock manure management. In the coming years, the Permanent census of agriculture will provide valuable information on animal and agronomic production methods. In addition, estimates of CH₄ emissions from enteric fermentation from cattle, sheep, and buffaloes will be made by applying the 2019 IPCC guidelines, and a comparison with current estimates will be made.

The improvement of the waste production and management database, handled by another unit of ISPRA, is ongoing, facilitating the extrapolation and elaboration of the huge amount of information contained in the database. Analysis and elaboration e.g. on waste composition will be easier and will allow improvements in the emission estimates in the future submission.

For the LULUCF, the key planned improvement is the change in land classification system, using the Oper-Foris Collect Earth tool. A complete survey to achieve a land classification has been carried out in 2024, supplying land use and land use data for a time series, starting from 2010; the results of the abovementioned land classification are currently under evaluation, by comparing them against the used data and ancillary available statistics and information. The land classification system will hopefully be adopted for reporting starting with the 2027 submission.

Additional studies will regard the comparison between local inventories and national inventory and exchange of information with the 'local inventories' national expert group.

Further analyses will concern the collection of statistical data and information to estimate uncertainty in specific sectors by implementing Approach 2 of the IPCC guidelines. Italy plans to reassess the uncertainty for the same categories reported in the annex of the NID because these are the main categories for which the analysis makes sense in consideration of the information available on parameters and underlying distributions. We will try to extend the analysis to some other key categories in the IPPU sector (chemical and mineral).

9 REFERENCES

References for the main chapters and the annexes are listed here and are organized by chapter and annex.

9.1 INTRODUCTION and TRENDS IN GREENHOUSE GAS EMISSIONS

EC, 2009. Decision No 406/2009/EC on the effort of Member States to reduce their greenhouse gas emissions to meet the Community's greenhouse gas emission reduction commitments up to 2020.

EMEP/CORINAIR, 2007. Atmospheric Emission Inventory Guidebook. Technical report No 16/2007.

EMEP/EEA, 2019. Air Pollutant Emission Inventory Guidebook. EEA. Technical report No 13/2019.

IPCC, 2003. Good Practice Guidance for Land Use, Land-Use Change and Forestry. IPCC Technical Support Unit, Kanagawa, Japan.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

IPCC 2019. 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories <https://www.ipcc-nggip.iges.or.jp/public/2019rf/index.html>.

ISPRA, 2013. Quality Assurance/Quality Control plan for the Italian Emission Inventory. Procedures Manual. October 2013.

ISPRA, 2018. National Greenhouse Gas Inventory System in Italy.

ISPRA, 2022. La disaggregazione a livello provinciale dell'inventario nazionale delle emissioni. ISPRA, 369/2022.

ISPRA, 2026 [a]. Quality Assurance/Quality Control plan for the Italian Emission Inventory.

ISPRA, 2026 [b]. Dioxide Intensity Indicators. Internal document.

ISPRA, 2026 [c]. Italian Emission Inventory 1990-2026. Italian Informative Report 2026.

9.2 ENERGY

ACI, several years. Dati e statistiche. Automobile Club d'Italia, Roma. <https://aci.gov.it/attivita-e-progetti/studi-e-ricerche/>.

AISCAT, several years. AISCAT Information - Monthly Edition. <https://www.aiscat.it/category/aiscat-informazioni-edizione-mensile/>.

ANAS, several years. Osservatorio del traffico. <https://www.stradeanas.it/it/le-strade/osservatorio-del-traffico>.

ANCMA, several years. Data available on website at: <http://www.ancma.it/statistiche>.

ANPA, 2001. Redazione di inventari nazionali delle emissioni in atmosfera nei settori del trasporto aereo e marittimo e delle emissioni biogeniche. Rapporto finale. Gennaio 2001.

APAT, 2003. Analisi dei fattori di emissione di CO₂ dal settore dei trasporti. Ilacqua M., Contaldi M., Rapporti n° 28/2003.

ARERA, several years. Regulatory Authority for Energy Networks and Environment, Data and Statistics. <https://www.arera.it/dati-e-statistiche>.

ARPAT, several years. Monitoraggio delle aree geotermiche toscane. Also available on the website <http://www.arpat.toscana.it/documentazione/report/report-geotermia>.

ASSOCARTA, several years. Rapporto Ambientale dell'industria cartaria italiana. Also available on the website <http://www.assocarta.it>.

CNR STEMS, Innovhub SSI, 2020. Database of fuel consumption and emission factors derived from national measurements campaign. Internal documentation.

CONFETRA, several years. Il trasporto merci su strada in Italia. Data and reports available on website at: <http://www.confetra.it/it/centrostudi/statistiche.htm>.

EDISON, several years. Rendiconto ambientale e della sicurezza.

EEA, 2000. COPERT III, Computer Programme to Calculate Emissions from Road Transport - Methodology and Emission Factors, European Environment Agency, Technical report No 49, November 2000.

EMEP/CORINAIR, 1996. Atmospheric Emission Inventory Guidebook. February 1996.

EMEP/CORINAIR, 2007. Atmospheric Emission Inventory Guidebook. Technical report No 16/2007.

EMEP/EEA, 2009. Air Pollutant Emission Inventory Guidebook. EEA. Technical report No 9/2009.

EMEP/EEA, 2016. Air Pollutant Emission Inventory Guidebook. EEA. Technical report No 21/2016.

EMEP/EEA, 2019. Air Pollutant Emission Inventory Guidebook. EEA. Technical report No 13/2019.

EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook. EEA.

EMISIA SA, 2024. COPERT 5 v.5.8.1, Computer programme to calculate emissions from road transport. <http://www.emisia.com/copert/>.

ENAC/MIT, several. Annuario Statistico. Ente Nazionale per l'Aviazione Civile, Ministero delle Infrastrutture e dei Trasporti.

ENEA-federAmbiente, 2012. Rapporto sul recupero energetico da rifiuti urbani in Italia. 3° ed.

ENEL, several years. Dati statistici sull'energia elettrica in Italia. ENEL.

ENI, several years [a]. La congiuntura economica ed energetica. ENI.

ENI, several years [b]. Health Safety Environment report. ENI.

EUROCONTROL, several years. EUROCONTROL Fuel and Emissions Inventory. Data provided to EU Member States.

Frustaci F., 1999. Metodi di stima ed analisi delle emissioni inquinanti degli off-road. Thesis in Statistics.

Giordano R., 2007. Trasporto merci: criticità attuali e potenziali sviluppi nel contesto europeo. National road transporters central committee.

Innovhub, 2018. Fuel consumption, regulated and unregulated exhaust emission tests on five Euro 6 b/c bifuel LPG passenger cars.

Innovhub, several years. Report on the physico-chemical characterization of fossil fuels used in Italy. Fuel Experimental Station.

IPCC, 1997. Revised 1996 IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Guidelines and Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.

IPCC, 2000. Good Practice Guidance and Uncertainty Management in National Greenhouse Gas Inventories. IPCC National Greenhouse Gas Inventories Programme, Technical Support Unit, Hayama, Kanagawa, Japan.

IPCC 2006, 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan

IPCC 2019. 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories <https://www.ipcc-nggip.iges.or.jp/public/2019rf/index.html>.

ISPRA, 2023. Aggiornamento delle modalità di calcolo delle emissioni navali con particolare riferimento all'ambito portuale a livello nazionale e locale, ISPRA 382/2023.

ISPRA, several years. Fuel Quality Monitoring Annual Report.

ISTAT, several years [a]. Annuario Statistico Italiano. Istituto Nazionale di Statistica.

ISTAT, several years [b]. Trasporto merci su strada. Istituto Nazionale di Statistica. <https://esploradati.istat.it/databrowser/#/it/dw/categories/IT1,Z0700SER,1.0/DCSC TRAMERCIS1>.

MASE, several years [a]. Bilancio Energetico Nazionale (BEN). Ministero dell'Ambiente. <https://sisen.mase.gov.it/dgsaie/>.

MASE, several years [b]. Bollettino Petrolifero Trimestrale (BPT). Ministero dell'Ambiente. <https://sisen.mase.gov.it/dgsaie/>.

MASE, several years [c]. Elenco dei pozzi idrocarburi perforati in Italia. Ministero dello Sviluppo Economico, Direzione Generale per le Risorse Minerarie ed Energetiche. <https://unmig.mite.gov.it/ricerca-e-coltivazione-di-idrocarburi/pozzi-produttivi/>.

MIT, several years. Conto Nazionale delle Infrastrutture e dei Trasporti (CNIT). Ministero delle Infrastrutture e dei Trasporti. <http://www.mit.gov.it/comunicazione/pubblicazioni>.

Romano D., Gaudio D., De Lauretis R., 1999. Aircraft Emissions: a comparison of methodologies based on different data availability. Environmental Monitoring and Assessment. Vol. 56 pp. 51-74.

SNAM, several years. Bilancio di sostenibilità.

STOGIT, several years, Bilancio di sostenibilità.

Techne, 2009. Stima delle emissioni in atmosfera nel settore del trasporto aereo e marittimo. Final report. TECHNE Consulting, March 2009.

TERNA, several years. Dati statistici sugli impianti e la produzione di energia elettrica in Italia. Gestore Rete Trasmissione Nazionale. <https://www.terna.it/it/sistema-elettrico/statistiche>.

UCINA, several years, La nautica in cifre.

UNEM, several years. Previsioni di domanda energetica e petrolifera in Italia. Unione Energia per la Mobilità

Williams, A., 1993. Methane Emissions - Paper Presented at the 29 Consultative Conference of the Watt Committee on Energy, Edited by Professor Alan Williams, Department of Fuel and Energy, University of Leeds, UK.

9.3 INDUSTRIAL PROCESSES AND PRODUCT USE

ACI, several years. Dati e statistiche. Automobile Club d'Italia, Roma. <http://www.aci.it/index.php?id=54>.

AIA, several years [a]. Personal Communication. Associazione Italiana Aerosol.

AIA, several years [b]. Relazioni annuali sulla produzione italiana aerosol. Associazione Italiana Aerosol.

AIET, 2007. Impatto ambientale degli apparecchi elettrici MT ed AT. Rivista AIET n° 6, giugno 2007.

AITEC, 2004. Posizione dell'industria cementiera in merito al Piano Nazionale di Allocazione delle emissioni di gas ad effetto serra. Roma 19/03/2004.

ALCOA, 2004. Primary Aluminium in Italy. ALCOA.

ALCOA, 2010. Personal Communication. ALCOA.

ALCOA, several years. Personal Communication.

ANDIL, 2000. Primo rapporto ambientale dell'industria italiana dei laterizi. Assolaterizi, Associazione nazionale degli industriali dei laterizi.

ANDIL, several years. Indagine conoscitiva sui laterizi. Assolaterizi, Associazione nazionale degli industriali dei laterizi.

ANIE, 2001. Il gas SF₆ e l'ambiente: un impegno che continua. ANIE Federazione

ANIE, several years. Personal Communication. ANIE Federazione.

APAT, 2003. Il ciclo industriale dell'acciaio da forno elettrico. Agenzia per la Protezione dell'Ambiente e per i servizi tecnici, Rapporti 38/2003.

APEM, 1992. Air Pollution Engineering Manual. Air&Waste Management Association, 1992.

APPLiA Italia, several years. Personal Communication.

Assocandele, 2015. Personal Communication.

Assocasa, several years. Personal Communication.

Assoclima, several years [a]. Statistiche Assoclima
www.anima.it/associazioni/elenco/assoclima/attivita/pubblicazioni/studi-di-mercato.kl .

Assoclima, several years [b]. Personal communication.

Assogastecnici, several years. Personal Communication.

ASSOMET, several years. I metalli non ferrosi in Italia. Associazione nazionale industrie metalli non ferrosi.

ASSOPIASTRELLE, 2004. L'industria italiana delle piastrelle di ceramica e la Direttiva 2003/87.

ASSOPIASTRELLE, several years. Indagine statistica nazionale. Industria italiana delle piastrelle di ceramica. Assopiastrelle, Associazione nazionale dei produttori di piastrelle di ceramica e di materiali refrattari.

Assovetro, several years. Statistical data available on the official web site of the National Glass Industry Association <http://www.assovetro.it/>

ASSURE, 2005. Personal Communication. European Association for Responsible Use of HFCs in Fire Fighting.

AVISA, several years. Personal Communication.

Benndorf R., 1999. Situation in Deutschland. ACCC-Workshop 'N₂O und das Kyoto-Ziel', Umweltbundesamt (Berlin), Wien.

Boehringer Ingelheim, several years. Personal Communication. Boehringer Ingelheim Istituto De Angeli.

CAGEMA, 2005. Politiche e misure per la riduzione delle emissioni di gas serra: il settore della calce. Associazione dell'industria italiana della calce, del gesso e delle malte.

CAPIEL, 2002. Switchgear and SF₆ gas. CAPIEL.

CARBITALIA S.p.A., several years. Personal Communication.

Chiesi Farmaceutici, several years. Personal Communication. Chiesi Farmaceutici S.p.A.

Clean Gas, 2001. Personal Communication. Clean Gas.

CNH, several years. Personal Communication. Case New Holland.

Co.Da.P., 2005. Personal Communication.

Confindustria Ceramica, several years. Personal Communication.

CoReVe, several years. Programma specifico di prevenzione. Risultati del riciclo.

CTN/ACE, 2000. Rassegna delle informazioni disponibili sulle emissioni di diossine e furani dal settore siderurgico e della metallurgia ferrosa. A cura di Pasquale Spezzano.

DPR 43/2012. Decreto del Presidente della Repubblica, 27 gennaio 2012, n. 43. Regolamento recante attuazione del regolamento (CE) n. 842/2006 su taluni gas fluorurati ad effetto serra.

DPR 146/2018. Decreto del Presidente della Repubblica, 16 novembre 2018, n. 146. Regolamento di esecuzione del regolamento (UE) n. 517/2014 sui gas fluorurati a effetto serra e che abroga il regolamento (CE) n. 842/2006.

EC, 1999. Council Directive 1999/13/EC of 11 March 1999 on the limitation of emissions of volatile organic compounds due to the use of organic solvents in certain activities and installations. Official Journal of the European Communities 29 March 1999.

EC, 2000. Regulation (EC) n. 2037/2000 of the European Parliament and of the Council of 29 June 2000 on substances that deplete the ozone layer.

EC, 2002. Screening study to identify reduction in VOC emissions due to the restrictions in the VOC content of products. Final Report of the European Commission, February 2002.

EC, 2004. Directive 2004/42/EC of the European Parliament and of the Council of 21 April 2004 on the limitation of emissions of volatile organic compounds due to the use of organic solvents in decorative paints and varnishes and vehicle refinishing products and amending Directive 1999/13/EC. Official Journal of the European Communities 30 April 2004.

EC, 2006. Regulation n. 842/2006 of the European Parliament and of the Council of 17 May 2006 on certain fluorinated greenhouse gases.

EDIPOWER, several years. Rapporto di Sostenibilità. EDIPOWER.

EDISON, several years. Bilancio Ambientale. EDISON.

EMEP/CORINAIR, 2007. Atmospheric Emission Inventory Guidebook. Technical report No 16/2007.

EMEP/EEA, 2009. Atmospheric Emission Inventory Guidebook. Technical report No 9/2009.

EMEP/EEA, 2013. Air Pollutant Emission Inventory Guidebook. Technical report n. 12/2013.

EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook 2023. Technical guidance to prepare national emission inventories. EEA report 06/2023.

ENDESA, 2004. Personal Communication. ENDESA.

ENDESA, several years [a]. Rapporto ambiente e sicurezza. ENDESA.

ENDESA, several years [b]. Rapporto di sostenibilità. ENDESA.

ENEL, several years. Rapporto ambientale. ENEL.

ENEA/USLRMA, 1995. Lavanderie a secco.

Enichem, several years. Rapporto ambientale.

ENIRISORSE, several years. Statistiche metalli non ferrosi. ENIRISORSE.

EPA, 2006. Uses and air emissions of liquid PFC heat transfer fluids from the electronics sector. EPA-430-R-06-901.

EU, 2006. Directive 2006/40/EC of the European Parliament and of the Council of 17 May 2006 relating to emissions from air conditioning systems in motor vehicles and amending Council Directive 70/156/EEC

EU, 2014. Regulation n. 517/2014 of the European Parliament and of the Council of 16 April 2014 on fluorinated greenhouse gases and repealing Regulation (EC) N. 842/2006 Text with EEA relevance.

FAO, several years. Food balance. <http://faostat3.fao.org/home/E>.

FEDERACCIAI, 2004. Personal Communication.

FEDERACCIAI, several years. La siderurgia in cifre. Federazione Imprese Siderurgiche Italiane.

FEDERBETON/AITEC [a], several years. Rapporto di Filiera. Federbeton

FEDERBETON/AITEC [b], several years. Rapporto di sostenibilità. Federbeton

FEDERCHIMICA, several years. La chimica in cifre. Federazione Nazionale dell'Industria Chimica.

FIAT, several years [a]. Personal Communication.

Folchi R., Zordan E., 2004. Il mercato degli esplosivi in Italia. Costruzioni, 28/1/2004.

Gastec Vesta, 2017. Personal Communication

GSK, several years. Personal Communication. GlaxoSmithKline S.p.A.

IAI, 2003. The Aluminium Sector Greenhouse Gas Protocol (Addendum to the WBCSD/WRI Greenhouse Gas Protocol). Greenhouse Gas Emission Monitoring and Reporting by the Aluminium Industry. International Aluminium Institute, May 2003.

IAI, 2006. The Aluminium Sector Greenhouse Gas Protocol (Addendum to the WBCSD/WRI Greenhouse Gas Protocol). Greenhouse Gas Emission Monitoring and Reporting by the Aluminium Industry. International Aluminium Institute, October 2006.

ILVA, 2006. Analisi ambientale iniziale. Rev. 2, March 2006. IPPC permitting process.

INFN, several years. Personal communication.

IPCC, 1997. Revised 1996 IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Guidelines and Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.

IPCC, 2000. Good Practice Guidance and Uncertainty Management in National Greenhouse Gas Inventories. IPCC National Greenhouse Gas Inventories Programme, Technical Support Unit, Hayama, Kanagawa, Japan.

IPPC, 2001. Best Available Techniques Reference Document on the Production of Iron and Steel. Integrated Pollution Prevention and Control. European Commission. December 2001.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

ISPESL, 2005. Profilo di rischio e soluzioni. Metallurgia. Produzione ferroleghie. Edited by A. Borroni.

ISPRA, 2018. Studio sulle alternative agli idrofluorocarburi (HFC) in Italia. Rapporto 286/2018

ISPRA – MATTM, 2013. Analisi del mercato della refrigerazione e del condizionamento in Italia nel periodo 1990-2013, verbale incontro Associazioni Nazionali - Roma, 7 novembre 2013

ISPRA, 2025. *Emission of fluorinated substances from ODS*. Technical Document

ISTAT, several years. ISTAT database: <https://esploradati.istat.it/databrowser/#/it/dw/categories>.

ISTAT, several years [a]. Annuario Statistico Italiano.

ISTAT, several years [b]. Bollettino mensile di statistica.

ISTAT, several years [c]. Statistica annuale della produzione industriale <http://www.istat.it/it/archivio/73150>.

ISTAT, several years [d]. Personal communication.

Istituto De Angeli, several years. Personal Communication. Istituto De Angeli.

Italghisa, 2011. Personal communication

IVECO, several years. Personal Communication.

LFoundry, several years. Personal Communication.

Linde Gas, 2015. Personal Communication.

Lusofarmaco, several years. Personal Communication. Istituto Luso Farmaco d'Italia S.p.A.

Lux, 2015. Personal Communication.

Magnesium Components Verrès, several years. Personal Communication.

Menarini, several years. Personal Communication. Industrie farmaceutiche riunite.

MICRON, several years. Personal Communication. Micron Technology Italia S.r.l.

MSE, several years. Consuntivo produzione nazionale clinker. Ministero Sviluppo Economico.

MASE, several years. Bollettino Petroliifero Trimestrale (BPT). Ministero dell'Ambiente. <https://sisen.mase.gov.it/dgsaie/bollettino-petroliifero>.

Norsk Hydro, several years. Personal Communication.

Numonyx, several years. Personal Communication. Numonyx Italy S.r.l.

Offredi P., several years. Professione Verniciatore del Legno. Personal communication.

Polimeri Europa, several years. Personal Communication. Polimeri Europa S.p.A.

Radici Chimica, 1993. Progetto CORINAIR. Produzione acido adipico: descrizione del processo utilizzato da Radici Chimica. Radici Group, Novara.

Radici Chimica, 2013. Annual report to the Italian PRTR.

Radici Chimica, several years. Personal Communication.

RAEE, 2017. MANUALE PER LE AZIENDE DI TRATTAMENTO DEL CDC RAEE. Frigoriferi e Congelatori.

Sanofi Aventis, several years. Personal Communication. Sanofi Aventis Italia.

Siemens, several years. Personal communication.

Siteb, several years. Rassegna del bitume.

Solsonica, 2015. Personal communication.

Solvay, 2003. Bilancio di Sostenibilità Solvay 2002. Solvay Solexis S.p.A.

Solvay, several years. Personal Communication. Solvay Solexis S.p.A.

Solvay, 1998. Personal communication. Solvay Solexis S.p.A.

Solvay 2006. Personal communication. Solvay Solexis S.p.A.

Solvay Fluor, several years. Personal Communication.

Sotacarbo, 2004. Progetto integrato miniera centrale. Studio di fattibilità sito di Portovesme.

Spinetta Marengo, 2011. Verbale riunione Spinetta Marengo.

ST Microelectronics, several years. Personal Communication. ST Microelectronics.

Syensqo, 2024. Personal Communication.

Syndial, several years. Personal Communication. Syndial S.p.A. – Attività diversificate.

TERNA, several years. Rapporto di Sostenibilità. TERNA.

UN, several years. Industrial Commodity Statistics Yearbook. United Nation.

UNEM, several years. Previsioni di domanda energetica e petrolifera italiana.

UNIC, several years. Report di sostenibilità, several years.

UNIPRO, several years. Rapporto Annuale - Consumi cosmetici in Italia.

UNRAE, several years. Personal Communication. Unione Nazionale Rappresentanti Autoveicoli Esteri.

USEPA, 1997. "Compilation of Air Pollutant Emission Factors". AP-42, U.S. Environmental Protection Agency, Office of Air Quality Planning and Standards. Research Triangle Park, North Carolina. October 1997.

USGS, several years. Mineral yearbook. Ferroalloys.

Varian, several years. Personal communication.

Versalis, several years. Personal Communication. Versalis S.p.A.

WG1, 2013. Comments on Appendix A&B of the "Preparatory study for the Review of Regulation 842/2006 on certain fluorinated greenhouse gases (Working document 1).

YARA, 2007. Technical documentations from IPPC permit issuing process.

YARA, several years. Personal Communication.

9.4 AGRICULTURE

ADBPO, 1994. Piano delle direttive e degli interventi urgenti per la lotta all'eutrofizzazione delle acque interne e del mare Adriatico. Autorità di bacino del fiume Po. Parma – Italia.

ADBPO, 2001. Progetto di Piano stralcio per il controllo dell'Eutrofizzazione (PsE). Autorità di bacino del fiume Po. Relazione generale. Parma – Italia.

Agraria, 2009. Rivista di Agraria.org N. 82 del 1° giugno 2009. Publication online: Ovini tecniche di allevamento <http://www.rivistadiagraria.org/articoli/anno-2009/ovini-tecniche-di-allevamento/>.

AIA, several years[a]. Controlli della produttività del latte in Italia – Cattle: Median of days open for the first 5 calving intervals - Statistiche Ufficiali. Associazione Italiana Allevatori. Italia <http://bollettino.aia.it/>.

AIA, several years[b]. Controlli della produttività del latte in Italia – Sheep: Sex ratio in alive and dead newborn; single and double birth ratio - Statistiche Ufficiali. Associazione Italiana Allevatori. Italia <http://bollettino.aia.it/>.

AIA, several years[c]. Controlli della produttività del latte in Italia– Sheep: Median of lactations from 90 to 300 days by breed - Statistiche Ufficiali. Associazione Italiana Allevatori. Italia <http://bollettino.aia.it/>.

ANPA-ONR, 2001. I rifiuti del comparto agro-alimentare, Studio di settore. Agenzia Nazionale per la Protezione dell’Ambiente. Rapporto n. 11/2001. Roma –Italia.

APAT, 2004[a]. Linee guida per l'utilizzazione agronomica degli effluenti di allevamento, Fase 2 Effluenti zootecnici, Risultati di una indagine campionaria sulle caratteristiche degli effluenti di allevamento, a cura di CRPA. Reggio Emilia – Italia.

APAT, 2004[b]. Linee guida per l'utilizzazione agronomica degli effluenti di allevamento, Fase 2 Effluenti zootecnici, Risultati di una indagine campionaria sulle tipologie di stabulazione e di stoccaggio, a cura di CRPA. Reggio Emilia – Italia.

ARA, 2017. Associazione Regionale Allevatori della Sardegna. Publication online: Specie allevate in Sardegna – Ovini.

ASSONAPA, 2006. Database of goat and sheep animal consistency and breeds. Associazione Nazionale della Pastorizia Ufficio Centrale dei Libri Genealogici e dei Registri Anagrafici, Italy.

Baldoni R., Giardini L., 1989. Coltivazione erbacee. Editor Patron, p 1072. Bologna, Italia.

Baldoni R., Giardini L., 2002. Coltivazione erbacee. Editor Patron, Volume 3.

Barile V.L., 2005. Improving reproductive efficiency in female buffaloes. *Livest. Prod. Sci.* 92, 83–194.

BDN, several years. Data provided by the National Livestock Registry Database (BDN) established by the Italian Ministry of Health at the "G. Caporale" Institute in Teramo. https://www.vetinfo.it/j6_statistiche/#/.

Bertora C., Cucu M. A., Lerda C., Peyron M., Bardi L., Gorra R., Sacco D., Celi L., Said-Pullicino D., 2018. Dissolved organic carbon cycling, methane emissions and related microbial populations in temperate rice paddies with contrasting straw and water management. *Agriculture, ecosystems & environment*, 265, 292-306.

Bittante G., Gallo L., Schiavon S., Contiero B., Fracasso A., 2004. Bilancio dell'azoto negli allevamenti di vacche da latte e vitelloni. In (Xiccato et al., 2004) Bilancio dell'azoto in allevamenti di bovini, suini e conigli – Progetto interregionale - Legge 23/12/1999 n. 499, art. 2 - report finale, Regione Veneto.

Bonazzi G., Crovetto M., Della Casa G., Schiavon S., Sirri F., 2005, Evaluation of Nitrogen and Phosphorus in Livestock manure: Southern Europe (Italy). In Workshop: Nutrients in livestock manure, Bruxelles, 14 February 2005.

Borgioli E., 1981. Nutrizione e alimentazione degli animali domestici. Edagricole, p. 464.

Braca G., Bussettin M., Lastoria B., Mariani S., Piva F., 2025. Elaborazioni modello BIGBANG versione 9.0, Istituto Superiore per la Protezione e la Ricerca Ambientale – ISPRA https://groupware.sinanet.isprambiente.it/bigbang-data/library/bigbang_90/ascii_grid/surplus.

Braca G., Bussettin M., Lastoria B., Mariani S., Piva F., 2021. Il Bilancio Idrologico Gis BAsed a scala Nazionale su Griglia regolare – BIGBANG: metodologia e stime. Rapporto sulla disponibilità naturale della risorsa idrica. Istituto Superiore per la Protezione e la Ricerca Ambientale, Rapporti 339/21, Roma. <https://www.isprambiente.gov.it/it/pubblicazioni/rapporti/il-bilancio-idrologico-gis-based-a-scala-nazionale-su-griglia-regolare-bigbang>.

Butterbach-Bahl K., Papen H., Rennenberg H., 1997. Impact of rice transport through cultivars on methane emission from rice paddy fields. *Plant, Cell and Environment*. 20:1175-1183.

CESTAAT, 1988. Impieghi dei sottoprodotti agricoli ed agroindustriali, Vol. 1. Centro Studi sull'Agricoltura, l'Ambiente e il Territorio, p. 311.

Consorzio per la tutela del formaggio Mozzarella di Bufala Campana, 2002. Modello di Regolamento per la gestione igienica ed alimentare dell'allevamento bufalino in relazione alla produzione della mozzarella di bufala campana DOP. Edit. Consorzio per la tutela del formaggio mozzarella di bufala campana (Campana Mozzarella Consortium).

CREA, 2025. Annuario dell'agricoltura italiana 2024 VOLUME LXXVIII. CREA - Centro di ricerca Politiche e Bioeconomia 2025 <https://www.crea.gov.it/web/politiche-e-bioeconomia/-/annuario-dell-agricoltura-italiana>.

CRPA, 1993. Manuale per la gestione e utilizzazione agronomica dei reflui zootecnici. Regione Emilia-Romagna, Assessorato agricoltura.

CRPA, 1996. Biogas e cogenerazione nell'allevamento suino. Manuale pratico. ENEL, Direzione studi e ricerche, Centro ricerche ambiente e materiali. Milano – Italia.

CRPA, 1997[a]. Piani Regionali di Risanamento e tutela della qualità dell'aria. Quadro delle azioni degli enti locali per il settore zootecnico delle aree padane. Allegato 2. Relazione di dettaglio sulla metodologia adottata per la quantificazione delle emissioni di metano. Febbraio 1997.

CRPA, 1997[b]. Piani Regionali di Risanamento e tutela della qualità dell'aria. Quadro delle azioni degli enti locali per il settore zootecnico delle aree padane. Relazione di dettaglio sulla metodologia adottata per la quantificazione delle emissioni di protossido di azoto. Settembre 1997.

CRPA, 2000. Aggiornamento dell'inventario delle emissioni in atmosfera di ammoniaca, metano e protossido di azoto dal comparto agricolo. Centro Ricerche Produzioni Animali. Gennaio 2000.

CRPA, 2004[a]. L'alimentazione della vacca da latte. Edizioni L'Informatore Agrario. Terza edizione, Centro Ricerche Produzioni Animali.

CRPA, 2004[b]. Personal communication, expert in dairy cattle feeding from the Research Centre on Animal Production (CRPA), Maria Teresa Pacchioli.

CRPA, 2004[c]. Personal communication, expert in greenhouse gases emissions from the agriculture sector from the Research Centre on Animal Production (CRPA), Laura Valli.

CRPA, 2005. Personal communication, working group with experts in animal feeding from the Research Centre on Animal Production (CRPA), Maria Teresa Pacchioli and Paola Vecchia.

CRPA, 2006[a]. Progetto MeditAIRaneo: settore Agricoltura. Relazione finale. Technical report on the framework of the MeditAIRaneo project for the Agriculture sector, Reggio Emilia – Italia.

CRPA, 2006[b]. Predisposizione di scenari di emissione finalizzati alla progettazione di interventi per la riduzione delle emissioni nazionali di ammoniaca ed alla valutazione di misure e di progetti per la tutela della qualità dell'aria a livello regionale. Final report. Reggio Emilia – Italy.

CRPA, 2008[a]. Le scelte politiche energetico-ambientali lanciano il biogas. L'Informatore Agrario 3/2008, p.28-32 (with annex).

CRPA, 2009. Valutazione dell'entità delle emissioni ammoniacali derivanti dall'applicazione al suolo dei fertilizzanti, delle loro possibilità di riduzione e individuazione degli elementi per un monitoraggio statistico delle tecniche di applicazione utilizzate. Final report. Reggio Emilia – Italy.

-
- CRPA, 2010. Personal communication - experts Laura Valli and Maria Teresa Pacchioli from the Research Centre on Animal Production (expert consultation on N excretion and national production systems). Reggio Emilia, Italy.
- CRPA, 2011. "Il biogas accelera la corsa verso gli obiettivi 2020". Supplemento a L'Informatore Agrario n. 26/2011.
- CRPA, 2013. "Biogas, il settore è strutturato e continua a crescere". Supplemento a L'Informatore Agrario n. 11/2013.
- CRPA, 2016[a]. Personal communication - experts Nicola Labartino and Laura Valli from the Research Centre on Animal Production (expert consultation on N excretion and national production systems). Reggio Emilia, Italy.
- CRPA, 2016[b]. Personal communication – expert Laura Valli from the Research Centre on Animal Production (expert consultation on N excretion and national production systems). Reggio Emilia, Italy.
- CRPA, 2018. Studio per la valutazione degli effetti sulle emissioni delle trasformazioni in corso nel settore degli allevamenti. Report. Reggio Emilia – Italy
- CRPA/AIEL, 2008. Energia dal biogas prodotto da effluenti zootecnici, biomasse dedicate e di scarto. Ed. Associazione Italiana Energie Ambientali (AIEL).
- CRPA/CNR, 1992. Indagine sugli scarti organici in Emilia-Romagna.
- Dan J., Krüger M., Frenzel P., Conrad R., 2001. Effect of a late season urea fertilization on methane emission from a rice field in Italy. *Agri. Ecos. Env.* 83: 191–199.
- Dannenberg S., Conrad R., 1999. Effect of rice plants on methane production and rhizospheric metabolism in paddy soil. *Biogeochemistry* 45: 53–71.
- De Corso E., 2008. World fertilizer market between food crisis and global economy simulations with partial equilibrium models. Tesi di laurea. Facoltà di Agraria, Università Cattolica del Sacro Cuore. 98p.
- De Roest and Speroni, 2005. Il bilancio dell'azoto negli allevamenti di latte. *Agricoltura*. Marzo 2005, 112-114.
- De Rosa M., Trabalzi F., 2004. Technological innovation among buffalo breeders of southern Lazio, Italy. *Agricoltura Mediterranea*. Vol. 134, 58-67.
- De Rosa M., Di Francia, 2006. Personal communication.
- Di Cristofaro E., several years. Procedura per la preparazione, caricamento e reporting dell'inventario nazionale delle emissioni del settore Agricoltura. Internal report ISPRA. Rome, Italy.
- EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook 2023. Technical guidance to prepare national emission inventories. EEA report 06/2023.
- ENEA, 1994. Personal communication, expert in agriculture sector. Ente nazionale per l'energia, l'ambiente e le nuove tecnologie (ENEA), Andrea Sonnino.
- ENEA, 2006. Valutazione della possibilità di sostituzione dell'urea con altri fertilizzanti azotati. Final report. Rome, Italy.
- ENAMA, 2011. "Biomasse ed Energia - Censimento impianti, biocarburanti di seconda generazione e casi studio".
- ENR, 2011. Personal communication with Ente Nazionale Risi (ENR), Enrico Losi. Information available on rice surface by variety and time of cultivation.
- ENR, 2013. XLV Relazione annuale Anno 2012. Il risicoltore. Ente Nazionale Risi.

ENR, 2014 [a]. Personal communication with Ente Nazionale Risi (ENR), Elena Noja. Information available on the length of the vegetation period for some varieties of rice.

ENR, 2014 [b]. XLVI Relazione annuale Anno 2013. Il risicoltore. Ente Nazionale Risi.

ENR, several years [a]. Personal communication with Ente Nazionale Risi (ENR), Dr. Romani. Information on agronomic management of rice cultivation.

ENR, several years [b]. Data available online on rice surface by variety and production. <http://www.enterisi.it/servizi/Menu/dinamica.aspx?idSezione=17505&idArea=17548&idCat=17552&ID=17552&TipoElemento=categoria>.

ENSE, 1999. Caratterizzazione morfo-fisiologica delle varietà di riso iscritte al catalogo italiano dal 1992 al 1998. Quaderno numero 47 a cura di L. Tamborini. Ente Nazionale delle Sementi Elette – Milano.

ENSE, 2004. Caratterizzazione morfo-fisiologica delle varietà di riso iscritte al catalogo italiano dal 1999 al 2004. Quaderno numero 48 a cura di L. Tamborini e G. Polenghi. Ente Nazionale delle Sementi Elette – Milano.

EPIC, 2015. Environmental Policy Integrated Climate Model. User's Manual Version 0810 September 2015.

ESDAC, 2010. Available Thematic Data Layers for Commission Decision of [11 June 2010] on guidelines for the calculation of land carbon stocks for the purpose of Annex V to Directive 2009/28/EC. <https://esdac.jrc.ec.europa.eu/content/support-renewable-energy-directive#tabs-0-description=0>.

EUROSTAT, 2007[a]. Farm structure in Italy – 2005. Statistics in Focus Agriculture and Fisheries 22/2007 Product KS-SF-07-022 European Communities.

EUROSTAT, 2007[b]. Agriculture. Main statistics 2005-2006. Product Ks-ED-07-002-En-C. European Communities.

EUROSTAT, 2012. Agriculture. Main statistics 2010-2011. Product KS-FK-12-001-EN-C. European Communities.

FAO, several years. FAOSTAT, the FAO Statistical Database, <http://www.fao.org/faostat/en/#data>.

Ferrero A., Nguyen N.V., 2004. Constraints and opportunities for the sustainable development of rice-based production systems in Europe. In proceedings: FAO Rice Conference, 12-13 February 2004, FAO, Rome, Italy.

Gazzetta Ufficiale della Repubblica Italiana (G.U.), 2006. Criteri e norme tecniche generali per la disciplina regionale dell'utilizzazione agronomica degli effluenti di allevamento e di acque reflue di cui all'articolo 38 del decreto legislativo 11 maggio 1999 N. 152. G.U. n. 109 del 12/05/06 - Suppl. Ordinario n.120. Ministero delle Politiche Agricole e Forestali. Italy. <http://www.gazzettaufficiale.it/>.

Gazzetta Ufficiale della Repubblica Italiana (G.U.), 2016[a]. Ministero delle Politiche Agricole Alimentari e Forestali - Decreto 25 Febbraio 2016 - Criteri e norme tecniche generali per la disciplina regionale dell'utilizzazione agronomica degli effluenti di allevamento e delle acque reflue, nonché per la produzione ed utilizzazione agronomica del digestato (G.U. n. 90 del 18 aprile 2016).

Gazzetta Ufficiale della Repubblica Italiana (G.U.), 2016[b]. Attuazione della legge 3 maggio n. 79 in materia di ratifica ed esecuzione dell'Emendamento di Doha al Protocollo di Kyoto (G.U. n. 298 del 22 dicembre 2016).

Gislon G., Colombini S., Borreani G., Crovetto G. M., Sandrucci A., Galassi G., Tabacco E., Rapetti L., 2020. Milk production, methane emissions, nitrogen, and energy balance of cows fed diets based on different forage systems. J. Dairy Sci. 103:8048–8061 <https://doi.org/10.3168/jds.2019-18134>.

-
- Greco M., Martino L., 2001. The agricultural statistical system in Italy. In: Conference on Agricultural and Environmental Application, Rome 4-8 June. Italy 46-461pp.
- Holzapfel-Pschorn A., Seiler W., 1986. Methane emission during a cultivation period from an Italian Rice Paddy. *Journal of Geophysical Research* Vol. 91 N° D11 11,803-11,814.
- Husted S., 1993. An open chamber technique for determination of methane emission from stored livestock manure. *Atmospheric Environment* 11 (27).
- Husted S., 1994. Seasonal variation in methane emissions from stored slurry and solid manures, *J. Env. Qual.* 23, pp. 585-592.
- Infascelli F., 2003. Nuove acquisizioni sulla nutrizione e sull'alimentazione della bufala. In: *Il Congresso Nazionale sull'Allevamento del Bufalo Monterotondo - Roma*, pp. 1-18.
- Internship Mounérat N., 2024. Verification and analysis of data used to calculate the nitrogen content of crop residues. Mounérat Nathan. June-August 2024.
- IPCC, 1997. Revised 1996 IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Guidelines and Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.
- IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.
- IPCC 2014, 2013 Revised Supplementary Methods and Good Practice Guidance Arising from the Kyoto Protocol, Hiraishi, T., Tanabe, K., Srivastava, N., Baasansuren, J., Fukuda, M. and Troxler, T.G. (eds) Published: IPCC, Switzerland.
- IPCC, 2019. 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories <https://www.ipcc-nggip.iges.or.jp/public/2019rf/index.html>.
- ISPRA, 2020. Database SCIA - National System for the collection, processing and dissemination of climatological data of environmental interest - Spatialised monthly average temperature data of the national territory for the periods 1961-1990, 1971-2000, 1981-2010. http://www.scia.isprambiente.it/wwwrootscia/scia_eng.html.
- ISPRA, 2021. Database della disaggregazione a livello provinciale dell'Inventario nazionale delle emissioni:1990-1995-2000-2005-2010-2015-2019. Istituto Superiore per la Protezione e la Ricerca Ambientale, ISPRA. <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.
- ISPRA, several years [a]. Quality Assurance/Quality Control plan for the Italian Inventory.
- ISPRA, several years [b]. Serie storiche delle emissioni nazionali di inquinanti atmosferici, Rete del Sistema Informativo Nazionale Ambientale - SINANET. Istituto Superiore per la Protezione e la Ricerca Ambientale. <http://emissioni.sina.isprambiente.it/serie-storiche-emissioni/>.
- ISTAT, 1991. Caratteristiche strutturali delle aziende agricole, fascicoli provinciali, 4° Censimento generale dell'Agricoltura (20 ottobre 1990-22 febbraio 1991), Roma – Italia.
- ISTAT, 2003. 5° Censimento Generale dell'Agricoltura. Caratteristiche strutturali delle aziende agricole. Fascicolo Nazionale: dati regionali, provinciali e comunali. Istituto Nazionale di Statistica, Roma – Italia.
- ISTAT, 2004. Personal communication, expert in agriculture statistics- fertilizers from the National Institute of Statistics (ISTAT), Mario Adua.

ISTAT, 2006[a]. Struttura e produzioni delle aziende agricole Anno 2005. Statistiche in breve (27 dicembre 2006). Statistiche Servizio Agricoltura – Allevamenti e pesca. Istituto Nazionale di Statistica, Roma – Italia.

ISTAT, 2006[b]. Personal communication, expert in agriculture statistics from the National Institute of Statistics (ISTAT), Giampaola Bellini.

ISTAT, 2007[a]. Farm and structure survey from 2005. Information on the number of animals at a provincial level. Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, 2007[b]. Annuario Statistico Italiano 2007- Capitolo 13 Agricoltura. Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, 2007[c]. Personal communication with N. Mattaliano. E-mail request for elaboration Farm and structure survey 2003 data on burning residues -cereals. Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, 2007[d]. Indagine sulla struttura e produzione delle aziende agricole. Anno 2005. Prodotto DCSSD1.1.1. Rapporto di qualità su SPA 2005. Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, 2008[a]. Struttura e produzioni delle aziende agricole. Anno 2007 (03 Dicembre 2008). Istituto Nazionale di Statistica, Roma – Italia.

ISTAT, 2008[b]. Indagine sulla struttura e produzione delle aziende agricole. Anno 2007. Rapporto sulla Qualità. Istituto Nazionale di Statistica, Roma - Italia.

ISTAT, 2010. Istruzioni per la rilevazione. 6° Censimento Generale dell'Agricoltura. Istituto Nazionale di Statistica, Roma - Italia.

ISTAT, 2012. 6° Censimento Generale dell'Agricoltura. Istituto Nazionale di Statistica, Roma - Italia. <http://dati-censimentoagricoltura.istat.it/>.

ISTAT, 2013. La valutazione della qualità. Atti del 6° Censimento Generale dell'Agricoltura. Istituto Nazionale di Statistica, Roma – Italia. <http://www.istat.it/it/archivio/112514>.

ISTAT, 2015. Indagine sulla struttura e produzione delle aziende agricole. Anno 2013. Istituto Nazionale di Statistica, Roma - Italia.

ISTAT, 2018. Indagine sulla struttura e produzione delle aziende agricole. Anno 2016. Istituto Nazionale di Statistica, Roma - Italia.

ISTAT, several years[a]. Statistiche dell'agricoltura, zootecnia e mezzi di produzione – Annuari (1990-1993), Istituto Nazionale di Statistica, Roma – Italia.

ISTAT, several years[b]. Statistiche dell'agricoltura – Annuari (1994-2000), Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, several years[c]. Struttura e produzioni delle aziende agricole – Informazione (1995- 1999), Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, several years[d]. Statistiche sulla pesca e zootecnia – Informazione (1998-2001), Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, several years[e]. Statistiche sulla pesca, caccia e zootecnia – Informazione (1996-1997), Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, several years[f]. Annuario Statistico Italiano - Annuario (1990; 1993-1994; 1997-2003), Istituto Nazionale di Statistica, Roma –Italia.

ISTAT, several years[g]. Dati annuali sulla consistenza del bestiame. Istituto Nazionale di Statistica, Roma – Italia. <http://dati.istat.it/>.

-
- ISTAT, several years[h]. Dati annuali e mensili sul settore lattiero caseario. Istituto Nazionale di Statistica, Roma – Italia. <http://dati.istat.it/>.
- ISTAT, several years[i]. Dati congiunturali sui mezzi di produzione. Istituto Nazionale di Statistica, Roma – Italia. <http://dati.istat.it/>.
- ISTAT, several years[j]. Dati congiunturali sulle coltivazioni. Istituto Nazionale di Statistica, Roma –Italia. <http://dati.istat.it/>.
- ISTAT, several years[k]. Personal communication with D. Ciaccia: e-mail request of rabbit production data. Istituto Nazionale di Statistica, Roma – Italia.
- ISTAT, several years[l]. Serie storiche - Agricoltura, zootecnia e pesca <http://seriestoriche.istat.it/>.
- Kruger M., Frenzel P., Kemnitz D., Conrad R., 2005. Activity, structure and dynamics of the methanogenic archaeal community in a flooded Italian rice field. *FEMS Microbiology Ecology* 51: 323–331.
- LAORE, 2014. Agenzia regionale per lo sviluppo in agricoltura. Opuscolo n. 3. Note tecniche sull'alimentazione degli ovini e dei caprini. LAORE Sardegna http://www.sardegnaagricoltura.it/documenti/14_43_20140205090638.pdf.
- Leip A., Bocchi S., 2007. Contribution of rice production to greenhouse gas emissions in Europe. In: *Proceeding of the Fourth Temperate Rice Conference*. Ed. S.Bocchi, A. Ferrero, A. Porro. 25-28 June Novara –Italy.
- Leip A., Russo S., Smith K.A., Conen F., Bidoglio G., 2002. Rice cultivation by direct drilling and delayed flooding reduces methane emissions. In: van Ham et al. (eds): *Non-CO₂ Greenhouse Gases (NCGG-3): Scientific understanding, control options and policy aspects*. p. 457-458.
- Lupotto E., Greppi D., Cavigliolo S., 2005. Personal communication, group of experts in rice paddy cultivation and agronomic practices from the C.R.A. – Experimental Institute of Cereal Research – Rice Research Section of Vercelli (Consiglio per la Ricerca e sperimentazione in Agricoltura, Istituto sperimentale per la Cerealicoltura, Sezione specializzata per la Riscoltura) Italia.
- Mannini P., 2004. Risparmio idrico/metodi e sistemi irrigui. La sommersione. In: *Supplementi di Agricoltura* 18. Le buone pratiche agricole per risparmiare acqua. Assessorato Agricoltura, Ambiente e Sviluppo Sostenibile, Regione Emilia-Romagna, pp.154-157. <http://agricoltura.regione.emilia-romagna.it/>.
- Marik T., Fischer H., Conen F., Smith K., 2002. Seasonal variations in stable carbon and hydrogen isotope ratios in methane from rice fields. *Global Biogeochemical Cycles*, vol. 16, N°4.
- MASE, 2022. Eighth National Communication under the UN Framework Convention on Climate Change Italy December 2022 <https://unfccc.int/documents/624766>.
- Masucci F., Di Francia A., Giofrè F., Zullo A., Proto V., 1999. Prediction of digestibility in buffalo. In: *XIII ASPA Congress, Piacenza (Italy)* 21-24 June 345-347.
- Masucci F., Di Francia A., Proto V., 1997. In vivo digestibility, rate of particulate passage and dry matter rumen degradability in buffaloes and sheep. In: *V World Buffalo Congress, Caserta (Italy)* 13-16 October, 296-301.
- MATTM, several years. Personal communication with Marco Porrega: e-mails request for sewage sludge applied to agricultural soils in Italy. Ministero dell'Ambiente e della Tutela del Territorio e del Mare, Roma –Italia.
- Miniotti E. F., Romani M., 2023. Personal communication of 10/3/2023 on description of cultivation techniques of experimental fields.

-
- Molle G., Decandia M., Cabiddu A., Landau S. Y., Cannas A., 2008. An update on the nutrition of dairy sheep grazing Mediterranean pastures. *Small Ruminant Research*, 77(2-3), 93-112.
- Molle G., Cannas A., 2015. Tecniche di alimentazione della pecora Sarda: stato dell'arte e prospettive.
- Mordenti A., Pacchioli M.T., Della Casa G., 1997. Production and nutrition techniques in the control of meat quality in heavy pigs. XXXII International Symposium on Animal Production: Advances in Technology, Accuracy and Management Milano, 29th September –1st October 1997. pag 81.
- Motola V., Colonna N., Alfano V., Gaeta M., Sasso S., De Luca V., De Angelis C., Soda A., Braccio G., 2009. Censimento potenziale energetico biomasse, metodo indagine, atlante Biomasse su WEB-GIS. *Ric. Sist. Elettr.*, 167, 141.
- NRC, 2001. Nutrient Requirements of dairy cattle Ninth edition, Nat. Acad. Press, Washington, D.C. USA.
- OSSLATTE, 2001. Annuario del latte, Edizione 2001. Capitolo 3: La produzione di latte secondo l'ISTAT e l'AIA, Osservatorio sul mercato dei prodotti lattiero-caseari del latte.
- OSSLATTE/ISMEA, 2003. Il mercato del latte, rapporto 2003. Capitolo 3: La struttura degli allevamenti e la produzione di latte secondo l'ISTAT. Osservatorio sul mercato dei prodotti lattiero-caseari del latte e l'Istituto di Servizi per il Mercato Agricolo ed Alimentare.
- Perelli M., 2007. Prezzi dei prodotti agricoli e fertilizzazione. *Fertilizzanti Maggio 2007*. Anno IX N3. 10-13pp.
- Peyron M., Bertora C., Pelissetti S., Said-Pullicino D., Celi L., Miniotti E., Romani M., Sacco D., 2016. Greenhouse gas emissions as affected by different water management practices in temperate rice paddies. *Agriculture, Ecosystems & Environment*, 232, 17-28.
- PROINCARNE, 2005. Personal communication, expert in goat and sheep breeding. Associazione Produttori Carni Bovine dell'Emilia-Romagna, Stefano Ronchi.
- Regione Emilia-Romagna, 2004. L. R. 28/98 – P.S.A. 2001 - N. PROG. 3 TAB. B3 - Bilancio dell'azoto nelle specie di interesse zootecnico, Relazione finale, a cura di C.R.P.A., September 2004, Reggio Emilia, Italy.
- Regione Emilia-Romagna, 2005. Disciplinari di produzione integrata 2005 Norme tecniche di coltura - Tecnica agronomica - Colture erbacee – RISO. Direzione Agricoltura, Regione Emilia-Romagna.
- Rivieccio R., 2019. Tesi Dottorato "Soil database of Italy at 1:250,000 scale and thematic applications for assessing environmental services" di Rosa Rivieccio, Tutor Prof. Marco Marchetti, Co-Tutor Dott. Rosario Napoli - Scienze, tecnologie e biotecnologie per la sostenibilità - XXXI Ciclo, Ecologia forestale e tecnologie ambientali. Corso congiunto di Università degli Studi della Tuscia e Università degli Studi del Molise. <http://hdl.handle.net/2067/49539>. Dati di riferimento utilizzati: SOIL DATABASE 250 -Banca dati nazionale dei suoli in scala 1:250.000, Responsabile dott. Rosario Napoli <https://www.crea.gov.it/web/agricoltura-e-ambiente/-/soil-database-250-banca-dati-suoli>.
- Romani M., 2023. Personal communication of 06/15/2023 on description of cultivation techniques of experimental fields.
- Roy R., Detlef Kluber H., Conrad R., 1997. Early initiation of methane production in anoxic rice soil despite the presence of oxidants. *FEMS Microbiology Ecology* 24:311-320.
- Russo S., 1994. Semina interrata con sommersione ritardata: un'alternativa all'impianto della risaia tradizionale. *L'informatore Agrario* 12/94 p 39-46.
- Safley L.M., Casada M.E., Woodbury J., Roos K.F., 1992. Global methane emissions from livestock and poultry manure. USEPA, Washington D.C., EPA/400/191/048.

-
- Said-Pullicino D., 2023[a]. Personal communication of 06/15/2023 on description of cultivation techniques of experimental fields.
- Said-Pullicino D., 2023[b]. Personal communication of 06/8/2023 on description of cultivation techniques of experimental fields.
- Schütz H., Holzapfel-Pschorn A., Conrad R., Rennenberg H., Seiler W., 1989 [a]. A 3-year continuous record on the influence of daytime, season and fertilizer treatment on methane emission rates from an Italian rice padd., *Journal of Geophysical Research* 94, D13, pp. 16405-16415.
- Schütz H., Seiler W., Conrad R., 1989 [b]. Processes involved in formation and emission of methane in rice paddies. *Biogeochemistry*, 7, pp. 33-53.
- Spanu A., 2006. Personal communication, expert in rice cultivation from Università degli Studi di Sassari, Sardegna – Italy.
- Spanu A., Murtas A., Ledda L., Ballone F., 2004. Confronto tra varietà di riso sottoposte a irrigazione turnata. *L'informatore Agrario* 18/2004 p 61-62.
- Spanu A., Pruneddu G., 1996. The influence of irrigation volumes on sprinkler-irrigated rice (*Oryza sativa*) production. *Agricoltura Mediterranea*, Vol 126, 377-382.
- Steed Jr. J., Hashimoto A.G., 1995. Methane emissions from typical manure management systems, *Bioresource Technology* 50 pp. 123-130.
- TERNA, several years. National production data from biogas. <https://www.terna.it/it/sistema-elettrico/statistiche/pubblicazioni-statistiche>.
- Tinarelli A., 1973. *La coltivazione del riso* Editorial Edagricole, First edition p. 425.
- Tinarelli A., 1986. *Il riso*. Editorail Edagricole, Second edition p. 426.
- Tinarelli A., 2005. Personal communication, Italian expert in rice cultivation – Antonio Tinarelli, participated in the working group with the Experimental Institute of Cereal Research – Rice Research Section of Vercelli, Italia.
- Tossato S., Regis F., 2002. Collana monografica di manuali naturalistico-agronomici, con riferimento alle principali colture geneticamente modificate. Volume 6. *Il Riso*. Agenzia Regionale per la Protezione Ambientale Piemonte (ARPA Piemonte), Piemonte, Italy.
- UNAITALIA, several years. Poultry production information. Unione nazionale filiere agroalimentari delle carni e delle uova. <http://www.unaitalia.com/>.
- UNFCCC, several years. Report of the individual review of the greenhouse gas inventories of Italy (FCCC/ARR/year/ITA) <https://unfccc.int/process-and-meetings/transparency-and-reporting/reporting-and-review-under-the-convention/greenhouse-gas-inventories-annex-i-parties/inventory-review-reports-2020>.
- UNICALCE, 2016. Personal communication, expert of the lime production sector. Associazione Produttori Calce, Sergio Peruta.
- Vitali A., Moretti B., Bertora C., Miniotti E. F., Tenni D., Romani M., Facchi A., Martin M., Fogliatto S., Vidotto F., Celi L., Said-Pullicino D., 2024. The environmental and agronomic benefits and trade-offs linked with the adoption alternate wetting and drying in temperate rice paddies. *Field Crops Research*, 317, 109550.
- Wassmann R., 2005. Personal communication, expert in methane from rice paddies (Forschungszentrum Karlsruhe IMK-IFU, Garmisch-Partenkirchen, Germany). E-mail communication received on 16/08/2005.
- Weber S., Lueders T., Friedrich M.W., Conrad R., 2001. Methanogenic populations involved in the degradation of rice straw in anoxic paddy soil. *FEMS Microbiology Ecology* 38:11-20.

- Xiccato G., Schiavon S., Gallo L., Bailoni L., Bittante G., 2005. Nitrogen excretion in dairy cow, beef and veal cattle, pig, and rabbit farms in Northern Italy. *Italian Journal of Animal Science*. vol. 4n (suppl. 3), 103-111.
- Yan X., Yagi K., Akiyama H., Akimoto H., 2005. Statistical analysis of the major variables controlling methane emission from rice fields. *Global Change Biology* (2005) 11, 1131–1141.
- Zavattaro L., Romani M., Sacco D., Bassanino M., Grignani C., 2004. Fertilization management of paddy fields in Piedmont (NW Italy) and its effects on the soil and water quality. In proceedings: Challenges and opportunities for sustainable rice-based production systems. Torino, Italy 13-15 September 2004.
- Zicarelli L., 2001. Evoluzione dell'allevamento bufalino in Italia. In Proc. I Congresso Nazionale sull'Allevamento del Bufalo Eboli, Salerno, Italy, pp. 1-19.

9.5 LAND USE, LAND USE CHANGE AND FORESTRY

- Alberti G., Peressotti A., Piussi P., Zerbi G., 2008. Forest ecosystem carbon accumulation during a secondary succession in the Eastern Prealps of Italy, *Forestry: An International Journal of Forest Research*, Volume 81, Issue 1, Pages 1–11, <https://doi.org/10.1093/forestry/cpm026>
- ARPA Lombardia - Regione Lombardia, 2011 [a]. INEMAR, Inventario emissioni in atmosfera. Emissioni in Lombardia nel 2008 - revisione pubblica.
- ARPA Lombardia - Regione Lombardia, 2011 [b] – Personal Communication by Federico Antognazza.
- Batjes, N., 1996. Total carbon and nitrogen in the soils of the world. *European Journal of Soil Science*, 47: 151–163.
- Benedetti A., Pompili L., Nisini L., 2004. Ruolo attivo dell'agricoltura nei processi di mitigazione del cambiamento climatico globale. Rapporto del progetto Climagri-Cambiamenti climatici e agricoltura, – CRA- Istituto Sperimentale per la Nutrizione delle Piante.
- Bovio G., 2007. Method for forest fire damage level assessment based on detectable effects. In 'Evaluation of Forest Fire Damages in Italy'. Eds Ciancio O., Corona P., Marinelli M., Pettenella D., Accademia Italiana di Scienze Forestali: Florence, Italy, pp. 55–60.
- Carbognin, L., Gambolati, G., Putti, M., Rizzetto, F., Teatini, P., Tosi, L. (2006). Soil contamination and land subsidence raise concern in the Venice watershed, Italy. *WIT Transactions on Ecology and the Environment*, 99.
- Ceccanti B., Doni S., Macci C., Cercignani G., Masciandaro G., 2008. Characterization of stable humic-enzyme complexes of different soil ecosystems through analytical isoelectric focussing technique (IEF), *Soil Biology & Biochemistry* 40 (2008) 2174–2177.
- Chirici G., Giannetti F., Travaglini D., Nocentini S., Francini S., D'Amico G., Calvo E., Fasolini D., Broll M., Maistrelli F., Tonner J., Pietrogiovanna M., Oberlechner K., Andriolo A., Comino R., Faidiga A., Pasutto I., Carraro G., Zen S., Contarin F., Alfonsi L., Wolynski A., Zanin M., Gagliano C., Tonolli S., Zoanetti R., Tonetti R., Cavalli R., Lingua E., Pirotti F., Grigolato S., Bellingeri D., Zini E., Gianelle D., Dalponte M., Pompei E., Stefani A., Motta R., Morresi D., Garbarino M., Alberti G., Valdevit F., Tomelleri E., Torresani M., Tonon G., Marchi M., Corona P., Marchetti M. (2019). Stima dei danni della tempesta "Vaia" alle foreste in Italia. *Forest@* 16: 3-9. – doi: 10.3832/efor3070-016 [online 2019-02-15]
- Ciccolini, V., Giannini, V., Bosco, S., Pellegrino, E., Pistocchi, C., Sabbatini, T., Rossetto, R., Silvestri, N., Bonari, E. (2013). Restoration of a mediterranean drained peatland: the case study of the Massaciuccoli lake basin (Tuscany, IT). In Extended abstract) in International Workshop AWARE Approaches in Wetland Restoration (pp. 21-23).

CRA-MPF, several years. National Forestry Inventory (INFC2005, INFC2015).

CRPA, 1997. Piani Regionali di Risanamento e tutela della qualità dell'aria. Quadro delle azioni degli enti locali per il settore zootecnico delle aree padane. Relazione di dettaglio sulla metodologia adottata per la quantificazione delle emissioni di protossido di azoto. Settembre 1997.

CRPA, 2009. Progetto Salvaguardia e valorizzazione del prato stabile irriguo in area Parmigiano-Reggiano attraverso l'ottimizzazione della risorsa idrica e azotata, Personal communication.

Del Gardo I., Six J., Peressotti A., Cotrufo M.F., 2003. Assessing the impact of land-use change on soil C sequestration in agricultural soils by means of organic matter fractionation and stable C isotopes. *Global Change Biology* (2003) 9, 1204–1213.

Di Cosmo L., Gasparini P., Paletto A., Nocetti M., 2013. Deadwood basic density values for national-level carbon stock estimates in Italy. *Forest Ecology and Management* 295 (2013) 51–58.

EMEP/EEA, 2009. Air pollutant emission inventory guidebook 2009. EEA Technical report n. 9/2009.

ERSAF, 2008. Stock di carbonio nei suoli regionali. Progetto Kyoto-Ricerca sui cambiamenti climatici e il controllo dei gas serra in Lombardia - GS3.

FAO, 2016. FAOSTAT database. URL: <http://faostat3.fao.org/home/E> (last access 09/03/2016). Food and Agriculture Organization of the United Nations.

Federici S, Vitullo M, Tulipano S, De Lauretis R, Seufert G, 2008. An approach to estimate carbon stocks change in forest carbon pools under the UNFCCC: the Italian case. *iForest* 1: 86-95 URL: <http://www.sisef.it/forest@/show.php?id=466>.

Fornasiero, A., Gambolati, G., Putti, M., Teatini, P., Ferraris, S., Pitacco, A., Rizzetto, F., Tosi, L., Bonardi, M., Gatti, P. (2002). Subsidence due to peat soil loss in the Zennare basin (Italy): Design and set-up of the field experiment. *Scientific Research and Safeguarding of Venice*. Istituto Veneto di Scienze Lettere ed Arti, Venice, Italy.

Francaaviglia R., Aromolo R., Benedetti A., Beni C., Biondi F.A., Dell'Abate M.T., Figliolia A., Mecella G., Pompili L., 2006. Qualità funzionali alla conservazione della fertilità integrale dei suoli. Rapporto del Progetto Conservazione e valorizzazione della risorsa suolo: definizione delle qualità del suolo ai fini della gestione agricola e forestale ecocompatibile – CRA- Istituto Sperimentale per la Nutrizione delle Piante.

Gambolati, G., Putti, M., Teatini, P., Bonardi, M., Camporese, M., Ferraris, S., Storti, G. G., Nicoletti, V., Rizzetto, F., Saladin, P., Silvestri, S., Tosi, L. (2005). Subsidence due to peatland oxidation in the Venice Lagoon catchment. In *Scientific Research and Safeguarding of Venice*. Co. Ri. La. Research Program 2001-2003, Volume III, 2003 Results. CORILA. Consorzio per la Gestione del Centro di Coordinamento delle Ricerche Inerenti il Sistema Lagunare di Venezia. Stampa "Multigraf" Spinea, Venezia 2005.

Gambolati, G., Putti, M., Teatini, P., Stori, G. G. (2003). Subsidence due to peat oxidation and its impact on drainage infrastructures in a farmland catchment south of the Venice Lagoon. *Materials and Geoenvironment*, 50, 125-128.

Gardi C., Brenna S., Solaro S., Piazzì M., Petrella F., 2007. The carbon sequestration potential of soils: some data from northern Italian regions" *Italian Journal of Agronomy* 2:163-170 <http://www.agronomy.it/index.php/agro/article/view/ija.2007.143/140>.

Giannini, V., Peruzzi, E., Masciandaro, G., Doni, S., Macci, C., Bonari, E., Silvestri, N. (2020). Comparison among different rewetting strategies of degraded agricultural peaty soils: Short-term effects on chemical properties and ecoenzymatic activities. *Agronomy*, 10(8), 1084. Adams, 1973. "The effect of organic matter on the bulk and true densities of some uncultivated podzolic soil." *J. Soil Sci.* 24:10-17.

Giannini, V., Silvestri, N., Dragoni, F., Pistocchi, C., Sabbatini, T., Bonari, E. (2017). Growth and nutrient uptake of perennial crops in a paludicultural approach in a drained Mediterranean peatland. *Ecological engineering*, 103, 478-487.

IPCC 2014, 2013 Revised Supplementary Methods and Good Practice Guidance Arising from the Kyoto Protocol, Hiraishi, T., Krug, T., Tanabe, K., Srivastava, N., Baasansuren, J., Fukuda, M. and Troxler, T.G. (eds) Published: IPCC, Switzerland.

IPCC 2019. 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories <https://www.ipcc-nggip.iges.or.jp/public/2019rf/index.html>.

IPCC, 2003. Good Practice Guidance for Land Use, Land-Use Change and Forestry. IPCC Technical Support Unit, Kanagawa, Japan.

IPCC, 2006. Guidelines for National Greenhouse Gas Inventories. IPCC Technical Support Unit, Kanagawa, Japan.

IPLA 2007, Realizzazione della parte piemontese della Carta dei Suoli nazionale a scala 1:250.000, Personal communication.

ISTAT, 2018. Indagine sulla struttura e produzione delle aziende agricole. Anno 2016. Istituto Nazionale di Statistica, Roma - Italia.

ISTAT, 2024. Censimento Agricoltura 2020. Istituto Nazionale di Statistica, Roma – Italia. <https://www.istat.it/notizia/censimento-agricoltura-2020-online-i-principali-dati/>.

ISTAT, several years [a]. Statistiche forestali. Istituto Nazionale di statistica, Roma.

ISTAT, several years [b]. Statistiche dell'agricoltura. Istituto Nazionale di statistica, Roma.

ISTAT, several years [c]. Annuario Statistico Italiano. Istituto Nazionale di statistica, Roma.

La Mantia T, Oddo G, Rühl J, Furnari G, Scalenghe R, 2007. Variation of soil carbon stocks during the renaturation of old fields: the case study of the Pantelleria Island, Italy. *Forest@* 4: 102-109. <http://www.sisef.it/forest@/show.php?id=433>.

Lagomarsino A., Moscatelli M.C., Di Tizio A., Mancinelli R., Grego S., Marinari S., 2009. Soil biochemical indicators as a tool to assess the short-term impact of agricultural management on changes in organic C in a Mediterranean environment. *Ecological indicators* 9 (2009) 518–527.

Lugato E., Berti A., 2008. Potential carbon sequestration in a cultivated soil under different climate change scenarios: A modelling approach for evaluating promising management practices in north-east Italy. *Agriculture, Ecosystems and Environment* 128 (2008) 97–103.

MAF/ISAFA, 1988. Inventario Forestale Nazionale. Sintesi metodologica e risultati. Ministero dell'Agricoltura e delle foreste. Istituto Sperimentale per l'asestamento forestale e per l'Alpicoltura, Trento.

MAMB, 1992. Inventario delle zone umide del territorio italiano (a cura di G. De Maria, Servizio Conservazione Natura, Ministero dell'ambiente e del territorio).

Martiniello P., 2007. Biochemical parameters in a Mediterranean soil as effected by wheat–forage rotation and irrigation. *Europ. J. Agronomy* 26 (2007) 198–208.

Masciandaro G., Ceccanti B., 1999. Assessing soil quality in different agro-ecosystems through biochemical and chemico-structural properties of humic substances. *Soil & Tillage Research* 51 (1999) 129-137.

-
- Monaco Stefano, Hatch D. J., Sacco D., Bertora C., Grignania C., 2008. Changes in chemical and biochemical soil properties induced by 11-yr repeated additions of different organic materials in maize-based forage systems. *Soil Biology & Biochemistry* 40 (2008) 608–615.
- Novara A., Gristina L., La Mantia T., Rühl J., 2013. Carbon dynamics of soil organic matter in bulk soil and aggregate fraction during secondary succession in a Mediterranean environment, *Geoderma*, Volumes 193–194, Pages 213–221, ISSN 0016-7061. <https://doi.org/10.1016/j.geoderma.2012.08.036>.
- Pellis G., Chiti T., Rey A., Curiel Yuste J., Trotta C., Papale D., 2019. The ecosystem carbon sink implications of mountain forest expansion into abandoned grazing land: The role of subsoil and climatic factors, *Science of The Total Environment*, Volume 672, Pages 106–120, ISSN 0048-9697, <https://doi.org/10.1016/j.scitotenv.2019.03.329>.
- Perucci P., Monaci E., Onofri A., Dischetti C., Casacci C., 2008. Changes in physico-chemical and biochemical parameters of soil following addition of wood ash: A field experiment. *Europ. J. Agronomy* 28 (2008) 155–161.
- Puglisi E., Fragoulis G., Del Re A.A.M., Spaccini R., Piccolo A., Gigliotti G., Said-Pullicino D., Trevisan M., 2008. Carbon deposition in soil rhizosphere following amendments with compost and its soluble fractions, as evaluated by combined soil–plant rhizobox and reporter gene systems. *Chemosphere* 73 (2008) 1292–1299.
- Rawls W.J., Brakensiek, D.L. 1985. Prediction of soil water properties for hydrologic modelling, in *Proceedings of Symposium on Watershed Management*, ASCE, pp. 293–299.
- Scarascia Mugnozza G., Bauer G., Persson H., Matteucci G., Masci A., 2000. Tree biomass, growth and nutrient pools. In: Schulze E.-D. (edit.) *Carbon and Nitrogen Cycling in European forest Ecosystems*, Ecological Studies 142, Springer Verlag, Heidelberg. Pp. 49–62. ISBN 3-540-67239-7.
- Somogyi Z., Teobaldelli M., Federici S., Matteucci G., Pagliari V., Grassi G., Seufert G., 2008. Allometric biomass and carbon factors database. *iForest* 1: 107–113. <http://www.sisef.it/iforest/contents/?id=ifor0463-0010107>.
- Tabacchi G., De Natale F., Di Cosmo L., Floris A., Gagliano C., Gasparini P., Genchi L., Scrinzi G., Tosi V., 2007. Le stime di superficie 2005 – Parte 1. *Inventario Nazionale delle Foreste e dei Serbatoi Forestali di Carbonio*. MiPAF - Corpo Forestale dello Stato - Ispettorato Generale, CRA - ISAFa, TN.: 1–413, vers. 2.
- Tabacchi G., De Natale F., Gasparini P., 2010. Coerenza ed entità delle statistiche forestali - Stime degli assorbimenti netti di carbonio nelle foreste italiane, *Sherwood* n.165/2010.
- Tabacchi, G., Di Cosmo, L., Gasparini, P., 2011. Aboveground tree volume and phytomass prediction equations for forest species in Italy. *Eur. J. Forest Res.* 130 (6), 911–934.
- Triberti L., Nastri A., Giordani G., Comellini F., Baldoni G., Toderi G., 2008. Can mineral and organic fertilization help sequester carbon dioxide in cropland? *Europ. J. Agronomy* 29 (2008) 13–20.
- Viaroli P., Gardi C., 2004. Censimento e caratterizzazione pedologica e vegetazionale dei "Prati Stabili" presenti nel Parco Regionale Fluviale del Taro. *Relazione tecnica* - Università degli Studi di Parma - Dipartimento di Scienze Ambientali.
- Xiloyannis C., 2007. La valutazione del contenuto e composizione del carbonio organico del suolo di sistemi agricoli. *Relazione tecnica* - Università degli Studi della Basilicata - Dipartimento di Scienze dei sistemi colturali, forestali e dell'ambiente.

9.6 WASTE

Acaia et al., 2004. Emissioni atmosferiche da discariche di rifiuti in Lombardia: stato attuale e scenari tecnologici di riduzione. RS – Rifiuti Solidi vol. XVIII n. 2, pp. 93-112.

AMA-Comune di Roma, 1996. Nuovo impianto per l'incenerimento dei rifiuti ospedalieri. Rapporto AMA.

Andreottola G., Cossu R., 1988. Modello matematico di produzione del biogas in uno scarico controllato. RS – Rifiuti Solidi vol. II n. 6, pp. 473-483.

ANPA, 1998. Il sistema ANPA di contabilità dei rifiuti, prime elaborazioni dei dati. Agenzia Nazionale per la Protezione dell'Ambiente.

ANPA-FLORYS, 2000. Industria conciaria, Studio di settore. Agenzia Nazionale per la Protezione dell'Ambiente.

ANPA-FLORYS, 2001. Industria della carta e cartone, Studio di settore. Agenzia Nazionale per la Protezione dell'Ambiente.

ANPA-ONR, 1999 [a]. Primo Rapporto sui rifiuti speciali. Agenzia Nazionale per la Protezione dell'Ambiente.

ANPA-ONR, 1999 [b]. Secondo Rapporto sui Rifiuti Urbani e sugli Imballaggi e rifiuti di imballaggio. Agenzia Nazionale per la Protezione dell'Ambiente.

ANPA-ONR, 2001. I rifiuti del comparto agro-alimentare, Studio di settore. Agenzia Nazionale per la Protezione dell'Ambiente. Rapporto n. 11/2001.

APAT, 2002. Annuario dei dati ambientali. Agenzia per la Protezione dell'Ambiente e per i servizi Tecnici. Rapporto n. 7/2002.

Asja, 2003. Dichiarazione Ambientale 2003. Asja Ambiente Italia S.p.A., 2003.

Assobirra, several years. Rapporti Annuali e Dati Statistici. Also available on the website <http://www.assobirra.it>.

Assocarta, several years. Rapporto Ambientale dell'industria cartaria italiana. Also available on the website <http://www.assocarta.it>.

AUSITRA-Assoambiente, 1995. Impianti di trattamento dei rifiuti solidi urbani e assimilabili. Indagine a cura di Merzagora W., Ferrari S.P.

BLUE BOOK, several years. I dati sul Servizio Idrico Integrato in Italia. Utilitatis, Anea.

Borgioli E., 1981. Nutrizione e alimentazione degli animali domestici. Ed Agricole, p. 464.

CESTAAT, 1988. Impieghi dei sottoprodotti agricoli ed agroindustriali, Vol. 1. Centro Studi sull'Agricoltura, l'Ambiente e il Territorio, edizione fuori commercio, p. 311.

CNR, 1980. Indagine sui Rifiuti Solidi Urbani in Italia. Consiglio Nazionale delle Ricerche, Progetto Finalizzato Energetica.

Colombari et al., 1998. Le emissioni di metano dalle discariche di rifiuti in Italia: stima e scenari futuri. ENEA RT/AMB/98/30.

Colombo, 2001. Nuovo Colombo, Manuale dell'Ingegnere, Vol. 3, 83^{ma} edizione. Hoepli editore.

COOU, several years. Consorzio Olii Usati, also available on the web-site <http://www.coou.it>.

COVIRI, several years. Relazione annuale al parlamento sullo stato dei servizi idrici. Autorità di vigilanza sulle risorse idriche e sui rifiuti.

-
- CREA, 2017. Fornitura dati meteo-climatici georeferenziati nell'ambito della collaborazione CREA-AA/ISPRA. CREA - Consiglio per la Ricerca in Agricoltura e l'Analisi dell'Economia Agraria Centro di ricerca Agricoltura e Ambiente (CREA-AA), delivery data mail 19/10/2017.
- De Poli F., Pasqualini S., 1991. Landfill gas: the Italian situation. ENEA, atti del convegno Sardinia 91, Third International Landfill Symposium.
- De Stefanis P. et al., 1998. Gestione dei rifiuti ad effetto serra. ENEA-CNR, atti della Conferenza Nazionale Energia e Ambiente, Rome 25-18 November 1998.
- De Stefanis P., 1999. Personal communication.
- De Stefanis P., 2002. Metodologia di stima delle emissioni di gas serra dalla combustione di rifiuti. RS Rifiuti Solidi vol.XVI n. 3 maggio - giugno 2002.
- De Stefanis P., 2012. Personal communication (mail 16 November 2012).
- Decree of President of the Republic 10 September 1982, n.915. Attuazione delle direttive 75/442/CEE relativa ai rifiuti e 76/403/CEE relativa ai rifiuti tossici e nocivi. G.U. 15 dicembre 1982, n. 343, S.O.
- EC, 1975. Council Directive 1975/442/EC. Council Directive 75/442/EC of 15 July 1975 on waste framework. Official Journal of the European Communities 25 July 1975.
- EC, 1976. Council Directive 1976/403/EC. Council Directive 76/403/EC of 6 April 1976 on treatment and disposal of PCBs and PCTs. Official Journal of the European Communities 26 April 1976.
- EC, 1978. Council Directive 1978/319/EC. Council Directive 78/319/EC of 20 March 1978 on toxic and dangerous waste. Official Journal of the European Communities 31 March 1978.
- EC, 1986. Council Directive 86/278/EC. Council Directive 86/278/EC of 12 June 1986 on the protection of the environment, and in particular of the soil, when sewage sludge is used in agriculture. Official Journal of the European Communities 4 July 1986.
- EC, 1999. Council Directive 1999/31/EC. Council Directive 99/31/EC of 26 April 1999 on the landfill of waste. Official Journal of the European Communities 16 July 1999.
- EMEP/CORINAIR, 2007. Atmospheric Emission Inventory Guidebook. Technical report No 16/2007.
- EMEP/EEA, 2009. Air Pollutant Emission Inventory Guidebook. Technical report No 9/2009.
- EMEP/EEA, 2016. Air Pollutant Emission Inventory Guidebook. Technical report No 21/2016.
- EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook. Technical report No 6/2023.
- ENEA-federAmbiente, 2012. Rapporto sul recupero energetico da rifiuti urbani in Italia. 3° ed.
- ENI S.p.A., 2001. Rapporto Salute Sicurezza Ambiente.
- EU, 2016. 2016 comprehensive review of national greenhouse gas inventory data pursuant to Article 19(1) of Regulation (EU) No 525/2013. Final review report. Italy. 28 August 2016.
- FAO, several years. Food balance, available on the website <http://faostat.fao.org> (last access 26/11/2015).
- Favoino E., Cortellini L., 2001. Composting and biological treatment in southern European countries: an overview. Conference Proceedings Soil and Biowaste in Southern Europe. Rome 18-19 January, 2001.
- Favoino E., Girò F., 2001. An assessment of effective, optimised schemes for source separation of organic waste in Mediterranean districts. Conference Proceedings Soil and Biowaste in Southern Europe. Rome 18-19 January, 2001.
- FEDERAMBIENTE, 1992. Analisi dei principali sistemi di smaltimento dei rifiuti solidi urbani.

FEDERAMBIENTE, 1998. Impianti di smaltimento: analisi sui termocombustori RSU – prima edizione. Indagine a cura di Motawi A..

FEDERAMBIENTE, 2001. Impianti di smaltimento: analisi sui termoutilizzatori RU. Indagine a cura di Morabito L., GEA n. 5/2001.

FEDERCHIMICA, several years. Rapporto Responsible Care. Federazione Nazionale dell'Industria Chimica.

Ferrari G., 1996. I rifiuti città per città. GEA, July 1996.

Finn L., Spencer R., 1997. Managing biofilters for consistent odor and VOC treatment. Biocycle, January 1997 Vol. 38 Iss.1.

Fondazione per lo sviluppo sostenibile e FISE UNIRE, 2016. L'Italia del riciclo, 2016. http://www.fondazionevilupposostenibile.org/wp-content/uploads/dlm_uploads/2016/12/rapporto_Italia_del_Riciclo_2016.pdf.

Gaudio et al., 1993. Emissioni in atmosfera dalle discariche di rifiuti in Italia. RS, Rifiuti Solidi vol. VII n. 5, Sept.-Oct. 1993.

Hogg D., 2001. Biological treatment of waste: a solution for tomorrow. ISWA Beacon Conference.

Internship Mounérat N., 2024. Verification and analysis of data used to calculate the nitrogen content of crop residues. Mounérat Nathan. June-August 2024.

IPCC, 1995. IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.

IPCC, 2000. Good Practice Guidance and Uncertainty Management in National Greenhouse Gas Inventories. IPCC National Greenhouse Gas Inventories Programme, Technical Support Unit, Hayama, Kanagawa, Japan.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

IRSA-CNR, 1998. Personal Communication.

ISPRA, several years. Rapporto Rifiuti. Istituto Superiore per la Protezione e la Ricerca Ambientale.

ISPRA, 2010. Personal Communication. Waste Cadastre database, year 2007.

ISPRA, 2017. Update of CH₄ emission factor from composting. Technical note n.1/2017.

ISPRA, 2018. Update of CH₄ emission from landfills. Technical note n.1/2018.

ISTAT, 1984. Statistiche ambientali 1984. Istituto nazionale di statistica.

ISTAT, 1987. Approvvigionamento idrico, fognature e impianti di depurazione in Italia – anno 1987. Collana d'informazione n. 20, ed. 1991.

ISTAT, 1991. Statistiche ambientali 1991. Istituto nazionale di statistica.

ISTAT, 1993. Statistiche ambientali 1993. Istituto nazionale di statistica.

ISTAT, 1998 [a]. Il processo di depurazione e la qualità delle acque reflue urbane. Indagine sugli impianti di depurazione delle acque reflue urbane, anno 1993. Istituto nazionale di statistica.

ISTAT, 1998 [b]. Caratteristiche strutturali degli impianti di depurazione delle acque reflue urbane. Indagine sugli impianti di depurazione delle acque reflue urbane, anno 1993. Istituto nazionale di statistica.

ISTAT, 2017. Forme, livelli e dinamiche dell'urbanizzazione in Italia.

ISTAT, several years [a]. Annuario Statistico. Istituto Nazionale di Statistica.

ISTAT, several years [b]. Bollettino mensile di statistica. Istituto Nazionale di Statistica.

ISTAT, several years [c]. Banche dati ISTAT, <http://www.istat.it/it/prodotti/banche-dati>.

ISTAT, several years [d]. Sistema di Indagini sulle Acque, SIA. Istituto nazionale di statistica, also available at website <http://www.istat.it>.

ISTAT, several years [e]. Censimento delle acque per uso civile. Istituto nazionale di statistica, also available at website <http://www.istat.it>.

Law 22 maggio 2015, n. 68 Disposizioni in materia di delitti contro l'ambiente. (G.U. 28 maggio 2015, n. 122)

Law Decree 30 December 2008, n.208. Misure straordinarie in materia di risposte idriche e protezione dell'ambiente. G.U. 31 dicembre 2008, n. 304, S.O.

Legislative Decree 27 January 1992 n. 99 Attuazione della direttiva 86/278/CEE concernente la protezione dell'ambiente, in particolare del suolo, nell'utilizzazione dei fanghi di depurazione in agricoltura. G.U.15 febbraio 1992 n. 38, S.O.

Legislative Decree 11 May 1999, n. 152. Disposizioni sulla tutela delle acque dall'inquinamento e recepimento della direttiva 91/271/CEE concernente il trattamento delle acque reflue urbane e della direttiva 91/676/CEE relativa alla protezione delle acque dall'inquinamento provocato dai nitrati provenienti da fonti agricole. G.U. 29 maggio 1999, n. 124, S.O.

Legislative Decree 13 January 2003 n. 36. Attuazione della direttiva 1999/31/EC relativa alle discariche di rifiuti. G.U. 12 marzo 2003, n. 59 – S.O. 40/L.

Legislative Decree 5 February 1997, n. 22. Attuazione delle direttive 91/156/CEE sui rifiuti 91/698/CEE sui rifiuti pericolosi e 94/62/CEE sugli imballaggi e sui rifiuti di imballaggio. G.U. 15 febbraio 1997, n. 38, S.O.

Masotti L., 1996. Depurazione delle acque. Edizioni Calderoni.

MASE, several years [a]. RSA - Rapporto sullo stato dell'ambiente 1989, 1992, 1997, 2001. Ministero dell'Ambiente e della Tutela del Territorio e del Mare.

MASE, several years [b]. Personal communication with Marco Porrega: E-mail request for sewage sludge applied to agricultural soils in Italy. *Ministero dell'Ambiente e della Tutela del Territorio e del Mare*, Roma –Italia.

Metcalf and Eddy, 1991. Wastewater engineering: treatment, disposal and reuse. Mc Graw Hill, third edition.

Ministerial Decree 12 July 1990. Linee Guida per il contenimento delle emissioni inquinanti degli impianti industriali e la fissazione dei valori minimi di emissione. G.U. 30 luglio 1990, n. 176.

Ministerial Decree 19 November 1997, n. 503. Regolamento recante norme per l'attuazione delle Direttive 89/369/CEE e 89/429/CEE concernenti la prevenzione dell'inquinamento atmosferico provocato dagli impianti di incenerimento dei rifiuti urbani e la disciplina delle emissioni e delle condizioni di combustione degli impianti di incenerimento di rifiuti urbani, di rifiuti speciali non pericolosi, nonché di taluni rifiuti sanitari. G.U. 29 gennaio 1998, n. 23.

Motola V., Colonna N., Alfano V., Gaeta M., Sasso S., De Luca V., De Angelis C., Soda A., Braccio G., 2009. Censimento potenziale energetico biomasse, metodo indagine, atlante Biomasse su WEB-GIS. Ric. Sist. Elettr, 167, 141.

-
- Morselli L., 1998. L'incenerimento dei rifiuti, ricognizione sulla realtà regionale. Università degli Studi di Bologna, Dipartimento di chimica industriale e dei materiali e Regione Emilia Romagna, Assessorato Territorio, Programmazione e Ambiente.
- Muntoni A., Poletti A., 2002. Modelli di produzione del biogas - limiti di applicazione e sensibilità. Conference proceedings, Università degli Studi di Roma La Sapienza "Gestione del biogas da discarica: controllo, recupero e monitoraggio. Rome, December 2002.
- Provincia di Roma, 2008. Documento di indirizzo per la riduzione della produzione di rifiuti urbani e l'implementazione delle raccolte differenziate nel territorio della provincia di Roma. Dipartimento Ambiente della Provincia di Roma, 12 febbraio 2008.
- Regione Calabria, 2002. Piano regionale di gestione rifiuti. Supplemento straordinario al Bollettino Ufficiale Regione Calabria 30 novembre 2002, n. 22.
- Regione Calabria, 2016. Piano Regionale Gestione Rifiuti. Parte 1 – Quadro conoscitivo.
- Regione Campania, 2016. Aggiornamento del Piano Regionale per la Gestione dei Rifiuti Urbani della Regione Campania. Dicembre 2016.
- Regione Emilia Romagna, 2009. La gestione dei rifiuti in Emilia Romagna. Regione Emilia Romagna – ARPA Emilia Romagna, Report 2009.
- Regione Emilia Romagna, 2016. Piano Regionale di Gestione dei Rifiuti. Quadro conoscitivo. Aggiornamento dei dati.
- Regione Lazio, 2020. Deliberazione del Consiglio Regionale 5 agosto 2020, n. 4. Piano regionale di gestione dei rifiuti della regione Lazio.
- Regione Piemonte, 2007. L'evoluzione merceologica dei Rifiuti Urbani: la storia e le prospettive. Recycling Prix proceedings. Turin, October 2007.
- Regione Piemonte, 2016. Deliberazione del Consiglio regionale 19 aprile 2016, n. 140 – 14161. Piano regionale di gestione dei rifiuti urbani e dei fanghi di depurazione.
- Regione Sardegna, 2016. Piano regionale di gestione dei rifiuti sezione rifiuti urbani – aggiornamento.
- Regione Sicilia, 2004. Programma regionale per la riduzione dei rifiuti biodegradabili da avviare in discarica. Ordinanza 25 marzo 2004, n. 323 del Commissario delegato per l'emergenza rifiuti e la tutela delle acque in Sicilia.
- Regione Toscana, 2014. PRB - Parte Prima – Sezione Conoscitivo-Programmatica - Allegato di Piano 1.
- Regione Umbria, 2007. Programma regionale per la riduzione dei rifiuti biodegradabili da avviare in discarica. Bollettino Ufficiale Regione Umbria 31 gennaio 2007, n. 5.
- Regione Veneto, 2006. Programma regionale per la riduzione dei rifiuti biodegradabili da avviare in discarica. Bollettino Ufficiale Regione Veneto 21 luglio 2006, n. 65.
- SEFIT, 2015. Emissioni inquinanti in atmosfera per i crematori italiani. Indagine conoscitiva ed elaborazione dati. Novembre 2015.
- SEFIT, 2019. Emissioni inquinanti in atmosfera per i crematori italiani. Indagine conoscitiva ed elaborazione dati.
- SEFIT, several years. Personal Communication with Daniele Fogli: E-mail request for activity data regarding cremation of corpses in Italy.
- Solini, 2010. Emissioni di gas serra dallo scarico e trattamento di acque reflue. PhD thesis.

Tecneco, 1972. Indagine Nazionale sullo smaltimento dei Rifiuti Solidi Urbani. Dispense 1995 Prof. Liuzzo, Università degli Studi di Roma "La Sapienza".

TERNA, several years. Dati statistici sull'energia elettrica in Italia. Rete Elettrica Nazionale.

UNIC, several years. Rapporto Ambientale. Unione Nazionale Industria Conciaria.

UNEM, several years. Statistiche economiche, energetiche e petrolifere. Unione Energia per la Mobilità.

US EPA, 1990. Air emissions Species Manual, vol. I: Volatile Organic Compound Species Profiles, Second Edition. EPA-450/2-90-001a (United States Environmental Protection Agency – Office of Air Quality Planning and Standards, Research Triangle Park, NC 27711), January 1990.

9.7 ANNEX 1

IPCC, 2000. Good Practice Guidance and Uncertainty Management in National Greenhouse Gas Inventories. IPCC National Greenhouse Gas Inventories Programme, Technical Support Unit, Hayama, Kanagawa, Japan.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

9.8 ANNEX 2

ENEL, several years. Dati statistici sull'energia elettrica in Italia. ENEL.

ENI, several years. La congiuntura economica ed energetica. ENI.

TERNA, several years. Dati statistici sull'energia elettrica in Italia. Rete Elettrica Nazionale.

UNAPACE, several years. Data from the association of industrial electricity producers. <http://www.assoelettrica.it/>.

9.9 ANNEX 3

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

9.10 ANNEX 4

ENEA/MAP/APAT, 2004. Energy data harmonization for CO₂ emission calculations: the Italian case. Rome 23/02/04. EUROSTAT file n. 200245501004.

ENEL, several years. Dati statistici sull'energia elettrica in Italia. ENEL.

MASE, several years. Bilancio Energetico Nazionale (BEN). Ministero dell'Ambiente e della Sicurezza Energetica, <https://sisen.mase.gov.it/dgsaie/bilancio-energetico-nazionale>.

9.11 ANNEX 5

MASE, several years. Bilancio Energetico Nazionale (BEN). Ministero dell'Ambiente e della Sicurezza Energetica. <https://sisen.mase.gov.it/dgsaie/bilancio-energetico-nazionale>.

EUROSTAT, 2023.

https://ec.europa.eu/eurostat/databrowser/view/nrg_bal_c/default/table?lang=en&category=nrg.nrg_quant.nrg_bal

9.12 ANNEX 6

APAT, 2003. Analisi dei fattori di emissione di CO₂ dal settore dei trasporti. Ilacqua M., Contaldi M., Rapporti n° 28/2003.

EMISIA SA, 2012. COPERT 4 v 10.0, Computer programme to calculate emissions from road transport, November 2012. <http://www.emisia.com/copert/>.

EMEP/CORINAIR, 2007. Atmospheric Emission Inventory Guidebook. Technical report No 16/2007.

Innovhub, several years. Report on the physico-chemical characterization of fossil fuels used in Italy. Fuel Experimental Station.

IPCC, 1997. Revised 1996 IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Guidelines and Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

MASE, several years [a]. Bilancio Energetico Nazionale (BEN). Ministero dell'Ambiente e della Sicurezza Energetica <https://sisen.mase.gov.it/dgsaie/bilancio-energetico-nazionale>.

MASE, several years [b]. Bollettino Petrolifero Trimestrale (BPT). Ministero dell'Ambiente e della Sicurezza Energetica. <https://sisen.mase.gov.it/dgsaie/bollettino-petrolifero>.

Snam Rete Gas, several years. Bilancio di sostenibilità.

TERNA, several years. Dati statistici sull'energia elettrica in Italia. Rete Elettrica Nazionale.

9.13 ANNEX 7

ANABORAPI, 2022. Associazione degli Allevatori della Razza Bovina Piemontese. Provincia di Torino e APA Torino. <https://anaborapi.it/>.

Bittante G., Gallo L., Schiavon S., Contiero B., Fracasso A., 2004. Bilancio dell'azoto negli allevamenti di vacche da latte e vitelloni. In (Xiccato et al., 2004) Bilancio dell'azoto in allevamenti di bovini, suini e conigli – Progetto interregionale - Legge 23/12/1999 n. 499, art. 2 - report finale, Regione Veneto.

Borgioli E., 1981. Nutrizione e alimentazione degli animali domestici. Edagricole, p. 464.

CESTAAT, 1988. Impieghi dei sottoprodotti agricoli ed agroindustriali, Vol. 1. Centro Studi sull'Agricoltura, l'Ambiente e il Territorio, p. 311.

Cevolani D. et al, 2021. "Alimenti per la vacca da latte e il bovino da carne", pp 461-472. Edagricole, Milano, 2021.

Cevolani D. et al, 2022. "Alimenti per la vacca da latte e il bovino da carne", pp 453-466. Edagricole, Milano, 2022.

Cozzi G., 2007. Present situation and future challenges of beef cattle production in Italy and the role of research. Italian Journal of Animal Science, 6, (suppl 1), 389-396.

-
- CRPA, 1997[a]. Piani Regionali di Risanamento e tutela della qualità dell'aria. Quadro delle azioni degli enti locali per il settore zootecnico delle aree padane. Allegato 2. Relazione di dettaglio sulla metodologia adottata per la quantificazione delle emissioni di metano. Febbraio 1997.
- CRPA, 1997[b]. Piani Regionali di Risanamento e tutela della qualità dell'aria. Quadro delle azioni degli enti locali per il settore zootecnico delle aree padane. Relazione di dettaglio sulla metodologia adottata per la quantificazione delle emissioni di protossido di azoto. Settembre 1997.
- CRPA, 2006[a]. Progetto MeditAIRaneo: settore Agricoltura. Relazione finale. Technical report on the framework of the MeditAIRaneo project for the Agriculture sector, Reggio Emilia – Italia.
- CRPA, 2008[a]. Le scelte politiche energetico-ambientali lanciano il biogas. L'Informatore Agrario 3/2008, p.28-32.
- CRPA, 2008[b]. "Biogas: l'analisi di fattibilità tecnico-economica". Opuscolo CRPA n. 4/2008.
- CRPA, 2011[a]. "Il biogas accelera la corsa verso gli obiettivi 2020". Supplemento a L'Informatore Agrario n. 26/2011.
- CRPA, 2011[b]. "Carne bovina: l'impatto della Pac dopo il 2013", analisi del CRPA realizzata su incarico di INTERCARNEPRO, 2011 - <https://agrireregionieuropa.univpm.it/it/content/article/31/27/effetti-della-riforma-pac-sugli-allevamenti-di-carne-bovina-italia>.
- CRPA, 2012. "Bovini da latte e biogas – Linee guida per la costruzione e la gestione degli impianti".
- CRPA, 2013. "Biogas, il settore è strutturato e continua a crescere". Supplemento a L'Informatore Agrario n. 11/2013.
- CRPA, 2016. Personal communication - experts Nicola Labartino and Laura Valli from the Research Centre on Animal Production (expert consultation on N excretion and national production systems). Reggio Emilia, Italy.
- CRPA, 2018. Studio per la valutazione degli effetti sulle emissioni delle trasformazioni in corso nel settore degli allevamenti. Report. Reggio Emilia – Italy.
- CRPA/AIEL, 2008. Energia dal biogas prodotto da effluenti zootecnici, biomasse dedicate e di scarto. Ed. Associazione Italiana Energie Ambientali (AIEL).
- CRPA/CNR, 1992. Indagine sugli scarti organici in Emilia-Romagna.
- EEA, 2025. Final Review Report - Italy. 2025 Comprehensive Review of National Greenhouse Gas Inventory Data pursuant to Article 38(1a) of Regulation (EU) No 2018/1999 and Article 4(3) of Regulation (EU) 2018/842.
- Ellis J. L., Kebreab E., Odongo N. E., McBride B. W., Okine E. K., France J., 2007. Prediction of Methane Production from Dairy and Beef Cattle. Article in Journal of Dairy Science - August 2007.
- EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook 2023. Technical guidance to prepare national emission inventories. EEA report 06/2023.
- ENAMA, 2011. "Biomasse ed Energia - Censimento impianti, biocarburanti di seconda generazione e casi studio".
- ENEA, 1994. Personal communication, expert in agriculture sector. Ente nazionale per l'energia, l'ambiente e le nuove tecnologie (ENEA), Andrea Sonnino.
- Escobar-Bahamondes P., Oba M., Beauchemin K. A., 2016. Universally applicable methane prediction equations for beef cattle fed high-or low-forage diets. Canadian Journal of Animal Science, 97(1), 83-94.

Fabbri C., Shams-Eddin S., Bondi F., Piccinini S., 2011. "Efficienza e problematiche di un impianto a digestione anaerobica a colture dedicate". IA – Ingegneria Ambientale, Vol. XL n.1° gennaio-Febbraio 2011.

Gong Y., Bellingeri A., Fumagalli F., Sechi G. S., Atzori A. S., Masoero F., Gallo A., Cabrera V. E., 2025. A mixed integer linear programming framework for mitigating enteric methane emissions on dairy farms through optimized crop and diet planning. *Journal of Cleaner Production*, 145636.

Gratton C., Strauser J., Jordan N., Jackson R. D., 2024. Agroecological innovation to scale livestock agriculture for positive economic, environmental, and social outcomes. *Environ. Res.: Food Syst.* 1 (2024) 013001 <https://doi.org/10.1088/2976-601X/ad382f>.

Grossi S., Massa V., Giorgino A., Rossi L., Dell'Anno M., Pinotti L., Avidano F., Compiani R., Sgoifo Rossi C. A., 2022. "Feeding Bakery Former Foodstuffs and Wheat Distiller's as Partial Replacement for Corn and Soybean Enhances the Environmental Sustainability and Circularity of Beef Cattle Farming." *Sustainability*.

IPCC, 1997. Revised 1996 IPCC Guidelines for National Greenhouse Gas Emission Inventories. Three volumes: Reference Manual, Reporting Manual, Reporting Guidelines and Workbook. IPCC/OECD/IEA. IPCC WG1 Technical Support Unit, Hadley Centre, Meteorological Centre, Meteorological Office, Bracknell, UK.

IPCC, 2006. 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Prepared by the National Greenhouse Gas Inventories Programme, Eggleston H.S., Buendia L., Miwa K., Ngara T. and Tanabe K. (eds). Published: IGES, Japan.

ISMEA, 2022. Bovino da carne. ISMEA, Febbraio 2022.

MASE, several years. Personal communication with Marco Porrega: e-mails request for sewage sludge applied to agricultural soils in Italy. Ministero dell'Ambiente e della Tutela del Territorio e del Mare, Roma –Italia.

Mazzenga A., Brscic M., Cozzi G., 2007. The use of corn silage in diets for beef cattle of different genotype. *Italian Journal of Animal Science*, 6 (suppl. 1), 321-323.

Motola V., Colonna N., Alfano V., Gaeta M., Sasso S., De Luca V., De Angelis C., Soda A., Braccio G., 2009. Censimento potenziale energetico biomasse, metodo indagine, atlante Biomasse su WEB-GIS. *Ric. Sist. Elettr.* 167, 141.

Niu M., Kebreab E., Hristov A.N., Oh J., Arndt C., Bannink A., Bayat A.R., et al., 2018. Prediction of enteric methane production, yield, and intensity in dairy cattle using an intercontinental database. *Global change biology* 1-22.

Pacchioli M.T., Bortolazzo E., Franzoni A., Carteri F., Balestra R., Di Pasquale F., 2023. Alimentare "precisamente" il bovino da carne. *Tecnica bovini. Allevatori Top*, n° 03 | marzo 2023.

Regione Veneto, 2008. Allegato A del Decreto della Direzione Agroambiente e Servizi per l'Agricoltura n. 308 del 7.8.2008. Dipartimento di Scienze Animali, Università degli Studi di Padova - Relazione sui modelli di bilancio dell'azoto e del fosforo proposti nell'allegato D del DGR del Veneto n. 2439 del 7 Agosto 2007.

UBA, 2014. National Inventory Report for the German Greenhouse Gas Inventory 1990 – 2012.

Xiccato G., Bailoni L., Bittante G., Gallo L., Gottardo F. Mantovani R., Schiavon S., 2004. "Bilancio dell'azoto in allevamenti di bovini, suini e conigli" Progetto interregionale - Legge 23/12/1999 n. 499, art. 2 - report finale, Regione Veneto, Italia.

Xiccato G., Schiavon S., Gallo L., Bailoni L., Bittante G., 2005. Nitrogen excretion in dairy cow, beef and veal cattle, pig, and rabbit farms in Northern Italy. *Italian Journal of Animal Science*. vol. 4n (suppl. 3), 103-111.

9.14 ANNEX 11

APAT - ARPA Lombardia, 2007. Stima dei consumi di legna da ardere per riscaldamento ed uso domestico in Italia, Rapporto Finale.

Corona P, Giuliarelli D, Lamonaca A, Mattioli W, Tonti D, Chirici G, Marchetti M, 2007. Confronto sperimentale tra superfici a ceduo tagliate a raso osservate mediante immagini satellitari ad alta risoluzione e tagliate riscontrate amministrativamente. *Forest@* 4 (3): 324-332. URL: <http://www.sisef.it/forest@/show.php?id=468>.

Di Cosmo L., Gasparini P., Paletto A., Nocetti M., 2013. Deadwood basic density values for national-level carbon stock estimates in Italy. *Forest Ecology and Management* 295 (2013) 51–58.

Federici S, Vitullo M, Tulipano S, De Lauretis R, Seufert G, 2008. An approach to estimate carbon stocks change in forest carbon pools under the UNFCCC: the Italian case. *iForest* 1: 86-95 URL: <http://www.sisef.it/forest@/show.php?id=466>.

Giordano G., 1980. Tecnologia del legno. Hoepli. Milano.

ISAFA, 2004. Riselvtalia Project, Personal communication.

MAF/ISAFA, 1988. Inventario Forestale Nazionale. Sintesi metodologica e risultati. Ministero dell'Agricoltura e delle foreste. Istituto Sperimentale per l'assestamento forestale e per l'Alpicoltura, Trento.

Tabacchi G., De Natale F., Gasperini P., 2010. Coerenza ed entità delle statistiche forestali - Stime degli assorbimenti netti di carbonio nelle foreste italiane, *Sherwood* n.165/2010.

UNECE – FAO, Timber Committee, 2008 - Italian statement on potential wood supply, communication by national correspondent, March 2008.

9.15 ANNEX 12

Bovio G., 2007. Method for forest fire damage level assessment based on detectable effects. In 'Evaluation of Forest Fire Damages in Italy'. Eds Ciancio O., Corona P., Marinelli M., Pettenella D., Accademia Italiana di Scienze Forestali: Florence, Italy, pp. 55–60.

EMEP/EEA, 2023. Air Pollutant Emission Inventory Guidebook. Technical guidance to prepare national emission inventories. EEA Report 06/2023. ISBN: 978-92-9480-598.

IPCC, 2006. Guidelines for National Greenhouse Gas Inventories. IPCC Technical Support Unit, Kanagawa, Japan.

ISTAT, several years [a]. Statistiche forestali. Istituto Nazionale di statistica, Roma.

ANNEX 1: KEY CATEGORIES AND UNCERTAINTY

A1.1 Introduction

The 2006 IPCC Guidelines (IPCC, 2006) recommend as good practice the identification of *key categories* in national GHG inventories. A *key category* is defined as an emission source that has a significant influence on a country's GHG inventory in terms either of the absolute/relative level of emissions or the trend in emissions, or both. Two different approaches are reported in the guidelines according to whether or not a country has performed an uncertainty analysis of the inventory: Approach 1 and Approach 2.

When using Approach 1, key categories are identified by means of a pre-determined cumulative emissions threshold, usually fixed at 95% of the total. If an uncertainty analysis is carried out at category level for the inventory, Approach 2 can be used to identify key categories. Approach 2 is a more detailed analysis that builds on Approach 1; in fact, the results of Approach 1 are multiplied by the relative uncertainty of each source/sink category. Key categories are those that represent 90% of the uncertainty contribution. So the factors which make a source or a sink a key category have a high contribution to the total, a high contribution to the trend and a high uncertainty. If both the approaches are applied, it is good practice to use the results of the Approach 2 analysis.

For the Italian inventory, a key category analysis has been carried out according to both the methods, excluding and including the LULUCF sector. National emissions have been disaggregated, as far as possible, into the categories proposed in the IPCC guidelines; other categories have been added to reflect specific national circumstances. Both level and trend analysis have been applied. For the base year, the level assessment has been carried out.

Summary of the results of the key category analysis, for the base year and the last reported year, is reported in Tables 1.3– 1.6 of chapter 1. The tables indicate whether a key category derives from the level assessment or the trend assessment, according to Approach 1, Approach 2 or both.

For the base year, 27 categories were individuated according to Approach 1, whereas 31 categories were carried out by Approach 2. Including the LULUCF sector in the analysis, 35 categories were selected according to Approach 1 and 42 with Approach 2.

For the year 2024, 25 categories were individuated by Approach 1 accounting for 95% of the total emissions, without LULUCF; for the trend 27 key categories were selected. Repeating the key category analysis for the full inventory, including the LULUCF sector, 35 categories were individuated accounting for 95% of the total emissions and removals in 2024, and 36 key categories in trend assessment.

The application of Approach 2 to the 2024 emission levels gives as a result 29 key categories accounting for the 90% of the total levels with uncertainty, when applying the trend analysis the number of the key categories is equal to 36. The application of Approach 2 including the LULUCF categories results in 32 key categories, for the year 2024, accounting for 90% of the total levels with uncertainty; for the trend analysis including LULUCF categories, the results were 37 key categories.

A1.2 Approach 1 key category assessment

As described in the 2006 IPCC Guidelines (IPCC, 2006), Approach 1 for identifying key categories assesses the impact of various categories on the level and on the trend of the national emission inventory. Both level and trend assessments should be applied to an emission GHG inventory.

As regards the level assessment, the contribution of each source or sink category to the total national inventory level is calculated as follows:

$$\text{Category Level Assessment} = \frac{|\text{Source or Sink Category Estimate}|}{\text{Total Contribution}}$$

$$L_{x,t} = \frac{|E_{x,t}|}{\sum_y |E_{y,t}|}$$

where

$L_{x,t}$ = level assessment for source or sink x in year t ;

$|E_{x,t}|$ = absolute value of emission and removal estimate of source or sink category x in year t ;

$\sum_y |E_{y,t}|$ = total contribution, which is the sum of the absolute values of emissions and removals in year t .

The contribution of all categories (including the LULUCF sector) is entered as absolute values.

Therefore, key categories are those which, when summed in descending order of magnitude, add up to over 95% of the total emissions.

As far as the trend assessment is concerned, the contribution of each source and sink category's trend can be assessed by the following equation:

Category Trend Assessment = Category Level Assessment * | Category Trend - Total Trend |

$$T_{x,t} = |E_{x,0}| / \sum_y |E_{y,0}| \cdot \left| \left[(E_{x,t} - E_{x,0}) / |E_{x,0}| \right] - \left[(E_t - E_0) / \sum_y |E_{y,0}| \right] \right|$$

where

$T_{x,t}$ = trend assessment, contribution of the category trend to the overall inventory trend;

$|E_{x,0}|$ = absolute value of emissions and removals of category x in the base year (year 0);

$\sum_y |E_{y,0}|$ = total contribution, sum of the absolute values of emissions and removals in year 0;

$E_{x,t}$ and $E_{x,0}$ = real values of estimates of category x in years t and 0, respectively;

E_t and $E_0 = \sum_y E_{y,t}$ and $\sum_y E_{y,0}$ = total inventory estimates in years t and 0, respectively.

The source or sink category trend is the change in the category emissions over time, computed by subtracting the base year estimate for a generic category from the latest inventory year estimate and dividing by the absolute value of the latest inventory year estimate; the total trend is the change in the total inventory emissions over time, computed by subtracting the base year estimate for the total inventory from the current year estimate and dividing by the current year estimate.

In circumstances where the base year emissions for a given category are zero, the expression is reformulated to avoid zero in the denominator:

$$T_{x,t} = |E_{x,t}| / |E_{x,0}|$$

As differences in trend are more significant to the overall inventory level for larger categories, the results of the trend difference are multiplied by the results of the level assessment to provide appropriate weighting.

Thus, key categories are those for which the category trend diverges significantly from the total trend, weighted by the emission level of the category.

Both level and trend assessments have been carried out for the Italian GHG inventory. For the base year, a level assessment is computed.

The results of Approach 1 are shown in Table A1.1 and Table A1.2, level and trend assessments without LULUCF categories. Results of the key category analysis with the LULUCF are reported in Table A1.3 and Table A1.4.

Table A1.1 Results of the key category analysis without LULUCF. Approach 1 Level assessment, year 2024

CATEGORIES	2024 <i>kt CO₂ eq</i>	Level assessment	Cumulative Percentage
Transport - CO2 Road transportation	104,025	0.286	0.29
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	47,800	0.132	0.42
Energy industries - CO2 gaseous fuels	43,455	0.120	0.54
Manufacturing industries and construction - CO2 gaseous fuels	30,122	0.083	0.62
Solid waste disposal - CH4	15,419	0.042	0.66
Energy industries - CO2 liquid fuels	14,986	0.041	0.70
Enteric Fermentation- CH4	13,488	0.037	0.74
Other sectors - CO2 commercial, residential, agriculture liquid fuels	10,757	0.030	0.77
Manufacturing industries and construction - CO2 liquid fuels	10,266	0.028	0.80
Mineral industry- CO2 Cement production	6,762	0.019	0.82
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	5,613	0.015	0.83
Transport - CO2 Waterborne navigation	5,012	0.014	0.85
Energy industries - CO2 solid fuels	4,951	0.014	0.86
Manufacturing industries and construction - CO2 solid fuels	4,338	0.012	0.87
Direct N2O Emissions from Managed soils	4,203	0.012	0.88
Manure Management - CH4	4,098	0.011	0.89
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	3,921	0.011	0.91
Wastewater treatment and discharge - CH4	2,651	0.007	0.91
Transport - CO2 Civil Aviation	2,419	0.007	0.92
Fugitive - CH4 Oil and natural gas - Natural gas	2,167	0.006	0.93
Indirect N2O Emissions from Managed soils	2,114	0.006	0.93
Other sectors - CH4 commercial, residential, agriculture biomass	1,903	0.005	0.94
Rice cultivations - CH4	1,793	0.005	0.94
Mineral industry- CO2 Lime production	1,580	0.004	0.946
Manure Management - N2O	1,376	0.004	0.9497
Fugitive - CO2 Oil and natural gas - Oil	1,289	0.004	0.953
Wastewater treatment and discharge - N2O	1,238	0.003	0.96

Table A1.2 Results of the key category analysis without LULUCF. Approach 1 Trend assessment

CATEGORIES	Contribution to trend (%)	Cumulative Percentage
Energy industries - CO2 liquid fuels	0.161	0.16
Transport - CO2 Road transportation	0.153	0.31
Energy industries - CO2 gaseous fuels	0.122	0.44
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.087	0.52
Energy industries - CO2 solid fuels	0.085	0.61
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.062	0.67
Manufacturing industries and construction - CO2 solid fuels	0.053	0.72
Manufacturing industries and construction - CO2 liquid fuels	0.049	0.77
Manufacturing industries and construction - CO2 gaseous fuels	0.029	0.80
Solid waste disposal - CH4	0.023	0.82
Product uses as substitutes for ozone depleting substances - HFCs		
Refrigeration and Air conditioning	0.022	0.85
Mineral industry- CO2 Cement production	0.017	0.86
Fugitive - CH4 Oil and natural gas - Natural gas	0.017	0.88
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	0.014	0.89
Chemical industry- N2O Adipic acid production	0.011	0.90
Enteric Fermentation- CH4	0.006	0.91
Transport - CO2 Civil Aviation	0.005	0.91
Mineral industry- CO2 Other processes uses of carbonates	0.005	0.92
Metal industry- PFCs Aluminium production	0.005	0.92
Chemical industry- N2O Nitric acid production	0.005	0.93
Transport - CO2 Waterborne navigation	0.005	0.93
Other sectors - CH4 commercial, residential, agriculture biomass	0.004	0.94
Metal industry- CO2 Iron and steel production	0.004	0.94
Chemical industry- CO2 Ammonia production	0.004	0.94
Other sectors - CO2 commercial, residential, agriculture solid fuels	0.002	0.95
Direct N2O Emissions from Managed soils	0.002	0.9497
Transport - CH4 Road transportation	0.002	0.952
Manufacturing industries and construction - CO2 other fuels	0.002	0.9538

Table A1.3 Results of the key category analysis with LULUCF. Approach 1 Level assessment, year 2024

CATEGORIES	2024 kt CO ₂ eq	Level assessment	Cumulative Percentage
Transport - CO2 Road transportation	104,025	0.238	0.24
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	47,800	0.109	0.35
Energy industries - CO2 gaseous fuels	43,455	0.099	0.45
Forest Land remaining Forest Land - Living biomass -CO2	-41,680	0.095	0.54
Manufacturing industries and construction - CO2 gaseous fuels	30,122	0.069	0.61
Solid waste disposal - CH4	15,419	0.035	0.65
Energy industries - CO2 liquid fuels	14,986	0.034	0.68
Enteric Fermentation- CH4	13,488	0.031	0.71
Land Converted to Forest Land -Living biomass - CO2	-12,699	0.029	0.74
Other sectors - CO2 commercial, residential, agriculture liquid fuels	10,757	0.025	0.77
Manufacturing industries and construction - CO2 liquid fuels	10,266	0.023	0.79
Mineral industry- CO2 Cement production	6,762	0.015	0.80
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	5,613	0.013	0.82
Transport - CO2 Waterborne navigation	5,012	0.011	0.83
Energy industries - CO2 solid fuels	4,951	0.011	0.84
Manufacturing industries and construction - CO2 solid fuels	4,338	0.010	0.85

Direct N2O Emissions from Managed soils	4,203	0.010	0.86
Manure Management - CH4	4,098	0.009	0.87
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	3,921	0.009	0.88
Land Converted to Grassland - mineral soils- CO2	-3,630	0.008	0.89
Wastewater treatment and discharge - CH4	2,651	0.006	0.89
Grassland Remaining Grassland - living biomass - CO2	-2,639	0.006	0.90
Transport - CO2 Civil Aviation	2,419	0.006	0.90
Cropland Remaining Cropland - mineral soils - CO2	-2,198	0.005	0.91
Fugitive - CH4 Oil and natural gas - Natural gas	2,167	0.005	0.91
Indirect N2O Emissions from Managed soils	2,114	0.005	0.92
Harvest Wood Products - CO2	-2,002	0.005	0.92
Other sectors - CH4 commercial, residential, agriculture biomass	1,903	0.004	0.93
Rice cultivations - CH4	1,793	0.004	0.93
Land Converted to Forest Land - soils -CO2	-1,656	0.004	0.94
Mineral industry- CO2 Lime production	1,580	0.004	0.94
Land Converted to Forest Land - DOM (deadwood+litter) CO2	-1,440	0.003	0.943
Manure Management - N2O	1,376	0.003	0.946
Fugitive - CO2 Oil and natural gas - Oil	1,289	0.003	0.949
Wastewater treatment and discharge - N2O	1,238	0.003	0.9515
Metal industry- CO2 Iron and steel production	1,232	0.003	0.9543

Table A1.4 Results of the key category analysis with LULUCF. Approach 1 Trend assessment

CATEGORIES	% Contribution to trend	Cumulative Percentage
Transport - CO2 Road transportation	0.162	0.16
Energy industries - CO2 gaseous fuels	0.109	0.27
Energy industries - CO2 liquid fuels	0.107	0.38
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.086	0.46
Forest Land remaining Forest Land - Living biomass -CO2	0.072	0.54
Energy industries - CO2 solid fuels	0.058	0.59
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.039	0.63
Manufacturing industries and construction - CO2 gaseous fuels	0.036	0.67
Manufacturing industries and construction - CO2 solid fuels	0.035	0.70
Land Converted to Forest Land -Living biomass - CO2	0.030	0.73
Manufacturing industries and construction - CO2 liquid fuels	0.030	0.76
Solid waste disposal - CH4	0.024	0.79
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	0.020	0.81
Grassland Remaining Grassland - living biomass -CO2	0.019	0.83
Forest Land remaining Forest Land - DOM (deadwood+litter) - CO2	0.015	0.84
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	0.012	0.85
Enteric Fermentation- CH4	0.011	0.86
Fugitive - CH4 Oil and natural gas - Natural gas	0.011	0.87
Mineral industry- CO2 Cement production	0.008	0.88
Chemical industry- N2O Adipic acid production	0.008	0.89
Land Converted to Grassland - mineral soils- CO2	0.007	0.90
Transport - CO2 Waterborne navigation	0.006	0.90
Transport - CO2 Civil Aviation	0.005	0.91
Harvest Wood Products - CO2	0.005	0.91
Land Converted to Forest Land - soils -CO2	0.004	0.92

CATEGORIES	% Contribution to trend	Cumulative Percentage
Other sectors - CH4 commercial, residential, agriculture biomass	0.004	0.92
Direct N2O Emissions from Managed soils	0.004	0.93
Cropland Remaining Cropland - mineral soils - CO2	0.004	0.93
Metal industry- PFCs Aluminium production	0.003	0.93
Chemical industry- N2O Nitric acid production	0.003	0.94
Mineral industry- CO2 Other processes uses of carbonates	0.003	0.94
Manure Management - CH4	0.003	0.94
Chemical industry- CO2 Ammonia production	0.002	0.94
Grassland Remaining Grassland - mineral soils-CO2	0.002	0.95
Land Converted to Settlements - CO2	0.002	0.948
Metal industry- CO2 Iron and steel production	0.002	0.9503
Wastewater treatment and discharge - N2O	0.002	0.952

The application of Approach 1, excluding LULUCF categories, gives as a result 26 key categories accounting for the 95% of the total levels; when applying the trend analysis, excluding LULUCF categories, the number of key categories is equal to 27 (Tables A1.1, A1.2). The Approach 1 level assessment repeated for the full inventory, including the LULUCF, results in 35 key categories (sources and sinks), and 36 key categories outcome from the trend analysis (Tables A1.3, A1.4).

For the year 1990, the results are reported in the following tables, including and excluding LULUCF.

Table A1.5 Results of the key category analysis without LULUCF. Approach 1 Level assessment, 1990

CATEGORIES	1990 kt CO ₂ eq	Level assessment	Cumulative Percentage
Transport - CO2 Road transportation	92,332	0.18	0.18
Energy industries - CO2 liquid fuels	81,197	0.16	0.33
Energy industries - CO2 solid fuels	38,647	0.07	0.41
Other sectors - CO2 commercial, residential, agriculture liquid fuels	38,274	0.07	0.48
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	36,338	0.07	0.55
Manufacturing industries and construction - CO2 liquid fuels	32,806	0.06	0.61
Manufacturing industries and construction - CO2 gaseous fuels	32,234	0.06	0.68
Manufacturing industries and construction - CO2 solid fuels	25,732	0.05	0.73
Enteric Fermentation- CH4	17,174	0.03	0.76
Energy industries - CO2 gaseous fuels	16,954	0.03	0.79
Mineral industry- CO2 Cement production	15,846	0.03	0.82
Solid waste disposal - CH4	13,671	0.03	0.85
Fugitive - CH4 Oil and natural gas - Natural gas	9,225	0.02	0.87
Transport - CO2 Waterborne navigation	5,470	0.01	0.88
Manure Management - CH4	5,308	0.01	0.89
Direct N2O Emissions from Managed soils	5,146	0.01	0.90
Chemical industry- N2O Adipic acid production	3,914	0.01	0.90
Wastewater treatment and discharge - CH4	3,584	0.01	0.91
Metal industry- CO2 Iron and steel production	3,124	0.01	0.92
Indirect N2O Emissions from Managed soils	2,710	0.01	0.92
Mineral industry- CO2 Other processes uses of carbonates	2,544	0.00	0.93
Fugitive - CO2 Oil and natural gas - Oil	2,402	0.00	0.93
Manure Management - N2O	2,314	0.00	0.94
Rice cultivations - CH4	2,102	0.00	0.94

CATEGORIES	1990	Level assessment	Cumulative Percentage
Chemical industry- CO2 Ammonia production	1,892	0.00	0.94
Mineral industry- CO2 Lime production	1,877	0.00	0.947
Chemical industry- N2O Nitric acid production	1,783	0.00	0.95001
Metal industry- PFCs Aluminium production	1,778	0.00	0.953

Table A1.6 Results of the key category analysis with LULUCF. Approach 1 Level assessment, 1990

CATEGORIES	1990 kt CO ₂ eq	Level assessment	Cumulative Percentage
Transport - CO2 Road transportation	92,332	0.17	0.17
Energy industries - CO2 liquid fuels	81,197	0.15	0.31
Energy industries - CO2 solid fuels	38,647	0.07	0.38
Other sectors - CO2 commercial, residential, agriculture liquid fuels	38,274	0.07	0.45
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	36,338	0.07	0.52
Manufacturing industries and construction - CO2 liquid fuels	32,806	0.06	0.58
Manufacturing industries and construction - CO2 gaseous fuels	32,234	0.06	0.64
Manufacturing industries and construction - CO2 solid fuels	25,732	0.05	0.68
Enteric Fermentation- CH4	17,174	0.03	0.71
Energy industries - CO2 gaseous fuels	16,954	0.03	0.74
Mineral industry- CO2 Cement production	15,846	0.03	0.77
Forest Land remaining Forest Land - Living biomass -CO2	-13,919	0.03	0.80
Solid waste disposal - CH4	13,671	0.02	0.82
Fugitive - CH4 Oil and natural gas - Natural gas	9,225	0.02	0.84
Transport - CO2 Waterborne navigation	5,470	0.01	0.85
Grassland Remaining Grassland - living biomass -CO2	5,376	0.01	0.86
Manure Management - CH4	5,308	0.01	0.87
Direct N2O Emissions from Managed soils	5,146	0.01	0.88
Chemical industry- N2O Adipic acid production	3,914	0.01	0.88
Wastewater treatment and discharge - CH4	3,584	0.01	0.89
Forest Land remaining Forest Land - DOM (deadwood+litter) - CO2	-3,476	0.01	0.90
Metal industry- CO2 Iron and steel production	3,124	0.01	0.90
Indirect N2O Emissions from Managed soils	2,710	0.00	0.91
Mineral industry- CO2 Other processes uses of carbonates	2,544	0.00	0.91
Land Converted to Forest Land -Living biomass - CO2	-2,525	0.00	0.92
Fugitive - CO2 Oil and natural gas - Oil	2,402	0.00	0.92
Manure Management - N2O	2,314	0.00	0.93
Rice cultivations - CH4	2,102	0.00	0.93
Chemical industry- CO2 Ammonia production	1,892	0.00	0.93
Mineral industry- CO2 Lime production	1,877	0.00	0.94
Chemical industry- N2O Nitric acid production	1,783	0.00	0.94
Metal industry- PFCs Aluminium production	1,778	0.00	0.94
Transport - CO2 Civil Aviation	1,493	0.00	0.95
Indirect CO2	1,391	0.00	0.948
Cropland Remaining Cropland - Living biomass - CO2	1,200	0.00	0.9501
Land Converted to Grassland - mineral soils - CO2	-1,124	0.00	0.95211

The application of Approach 1 for the year 1990, excluding LULUCF categories, gives as a result 27 key categories accounting for 95% of the total levels; when applying the assessment, including the LULUCF, the number of key categories increases to 35 (Tables A1.5, A1.6).

A1.3 Uncertainty assessment (IPCC Approach 1)

Approach 2 for the identification of key categories implies the assessment of the uncertainty analysis to an emission inventory. As already mentioned, the IPCC Approach 1 has been applied to the Italian GHG inventory to estimate uncertainties for 1990 and the last submitted year. In this section, detailed results are reported for 2024. The uncertainty analysis has also been implemented both excluding and including the LULUCF sector in the national totals.

Results are reported in Table A1.7, for the year 2024, excluding the LULUCF sector and in Table A1.8 figures of inventory total uncertainty, including the LULUCF sector, are shown.

Details on the method used for LULUCF are described in chapter 6.

Table A1.7 Results of the uncertainty analysis excluding LULUCF (Approach 1). Year 2024

IPCC category	Gas	Emissions		Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Energy industries - CO2 liquid fuels	CO2	81,197	14,986	3%	3%	0.042	0.000	0.080	0.029	0.002	0.001	0.0000072
Energy industries - CO2 solid fuels	CO2	38,647	4,951	3%	3%	0.042	0.000	0.042	0.010	0.001	0.000	0.0000018
Energy industries - CO2 gaseous fuels	CO2	16,954	43,455	3%	3%	0.042	0.000	0.061	0.083	0.002	0.004	0.0000159
Energy industries - CO2 other fuels	CO2	143	111	3%	3%	0.042	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - N2O liquid fuels	N2O	256	112	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - N2O solid fuels	N2O	145	19	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - N2O gaseous fuels	N2O	8	22	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - N2O other fuels	N2O	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - N2O biomass	N2O	15	80	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - CH4 liquid fuels	CH4	82	11	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - CH4 solid fuels	CH4	147	8	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - CH4 gaseous fuels	CH4	13	30	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - CH4 other fuels	CH4	0	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Energy industries - CH4 biomass	CH4	58	72	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - CO2 liquid fuels	CO2	32,806	10,266	3%	3%	0.042	0.000	0.024	0.020	0.001	0.001	0.0000012
Manufacturing industries and construction - CO2 solid fuels	CO2	25,732	4,338	3%	3%	0.042	0.000	0.026	0.008	0.001	0.000	0.0000007
Manufacturing industries and construction - CO2 gaseous fuels	CO2	32,234	30,122	3%	3%	0.042	0.000	0.015	0.058	0.000	0.002	0.0000062
Manufacturing industries and construction - CO2 other fuels	CO2	0	525	3%	3%	0.042	0.000	0.001	0.001	0.000	0.000	0.0000000
Manufacturing industries and construction - N2O liquid fuels	N2O	823	367	3%	50%	0.501	0.000	0.000	0.001	0.000	0.000	0.0000000
Manufacturing industries and construction - N2O solid fuels	N2O	216	25	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - N2O gaseous fuels	N2O	146	139	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - N2O other fuels	N2O	0	26	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - N2O biomass	N2O	6	64	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - CH4 liquid fuels	CH4	47	22	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000

IPCC category	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
	Gas	1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Manufacturing industries and construction - CH4 solid fuels	CH4	120	28	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - CH4 gaseous fuels	CH4	16	14	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - CH4 other fuels	CH4	0	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Manufacturing industries and construction - CH4 biomass	CH4	4	222	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.0000001
Transport - CO2 Road transportation	CO2	92,332	104,025	3%	3%	0.042	0.000	0.076	0.200	0.002	0.008	0.0000770
Transport - N2O Road transportation	N2O	746	830	3%	40%	0.401	0.000	0.001	0.002	0.000	0.000	0.0000001
Transport - CH4 Road transportation	CH4	969	150	3%	40%	0.401	0.000	0.001	0.000	0.000	0.000	0.0000002
Transport - CO2 Waterborne navigation	CO2	5,470	5,012	3%	3%	0.042	0.000	0.002	0.010	0.000	0.000	0.0000002
Transport - N2O Waterborne navigation	N2O	34	33	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CH4 Waterborne navigation	CH4	39	18	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CO2 Civil Aviation	CO2	1,493	2,419	3%	3%	0.042	0.000	0.003	0.005	0.000	0.000	0.0000000
Transport - N2O Civil Aviation	N2O	11	16	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CH4 Civil Aviation	CH4	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CO2 Railways	CO2	613	18	3%	5%	0.058	0.000	0.001	0.000	0.000	0.000	0.0000000
Transport - N2O Railways	N2O	64	2	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CH4 Railways	CH4	1	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CO2 Other transportation - pipelines	CO2	411	748	3%	3%	0.042	0.000	0.001	0.001	0.000	0.000	0.0000000
Transport - N2O Other transportation - pipelines	N2O	6	10	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Transport - CH4 Other transportation - pipelines	CH4	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - CO2 commercial, residential, agriculture liquid fuels	CO2	38,274	10,757	3%	3%	0.042	0.000	0.031	0.021	0.001	0.001	0.0000016
Other sectors - CO2 commercial, residential, agriculture solid fuels	CO2	899	0	3%	3%	0.042	0.000	0.001	0.000	0.000	0.000	0.0000000
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	CO2	36,338	47,800	3%	3%	0.042	0.000	0.043	0.092	0.001	0.004	0.0000168
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	CO2	530	3,921	3%	3%	0.042	0.000	0.007	0.008	0.000	0.000	0.0000001
Other sectors - N2O commercial, residential, agriculture liquid fuels	N2O	885	524	3%	50%	0.501	0.000	0.000	0.001	0.000	0.000	0.0000000
Other sectors - N2O commercial, residential, agriculture solid fuels	N2O	4	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - N2O commercial, residential, agriculture gaseous fuels	N2O	173	214	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000

IPCC category	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
	Gas	1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Other sectors - N2O commercial, residential, agriculture other fossil fuels	N2O	13	139	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - N2O commercial, residential, agriculture biomass	N2O	473	824	3%	50%	0.501	0.000	0.001	0.002	0.000	0.000	0.0000002
Other sectors - CH4 commercial, residential, agriculture liquid fuels	CH4	105	13	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - CH4 commercial, residential, agriculture solid fuels	CH4	11	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - CH4 commercial, residential, agriculture gaseous fuels	CH4	46	57	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - CH4 commercial, residential, agriculture other fossil fuels	CH4	1	9	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other sectors - CH4 commercial, residential, agriculture biomass	CH4	1,116	1,903	3%	50%	0.501	0.000	0.002	0.004	0.001	0.000	0.0000012
Other non specified - CO2 military mobile - liquid fuels	CO2	1,071	605	3%	5%	0.058	0.000	0.000	0.001	0.000	0.000	0.0000000
Other non specified - N2O military mobile - liquid fuels	N2O	60	10	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Other non specified - CH4 military mobile - liquid fuels	CH4	5	2	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CO2 Solid fuels	CO2	0	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CH4 Solid fuels	CH4	148	25	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CO2 Oil and natural gas - Oil	CO2	2,402	1,289	3%	10%	0.104	0.000	0.001	0.002	0.000	0.000	0.0000000
Fugitive - CH4 Oil and natural gas - Oil	CH4	347	58	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - N2O Oil and natural gas - Oil	N2O	0	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CO2 Oil and natural gas - Natural gas	CO2	9	3	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CH4 Oil and natural gas - Natural gas	CH4	9,225	2,167	3%	50%	0.501	0.000	0.008	0.004	0.004	0.000	0.0000169
Fugitive - CO2 Oil and natural gas - venting and flaring	CO2	956	240	50%	10%	0.510	0.000	0.001	0.000	0.000	0.000	0.0000001
Fugitive - N2O Oil and natural gas - venting and flaring	N2O	1	0	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CH4 Oil and natural gas - venting and flaring	CH4	232	66	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.0000000
Fugitive - CO2 Oil and natural gas - Other - flaring in refineries	CO2	681	141	50%	10%	0.510	0.000	0.001	0.000	0.000	0.000	0.0000000
Fugitive - N2O Oil and natural gas - Other - flaring in refineries	N2O	10	6	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.0000000

IPCC category	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
	Gas	1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	CH4	226	455	50%	50%	0.707	0.000	0.001	0.001	0.000	0.001	0.0000005
Mineral industry- CO2 Cement production	CO2	15,846	6,762	3%	10%	0.104	0.000	0.008	0.013	0.001	0.001	0.0000010
Mineral industry- CO2 Lime production	CO2	1,877	1,580	3%	10%	0.104	0.000	0.001	0.003	0.000	0.000	0.0000000
Mineral industry- CO2 Glass production	CO2	453	534	3%	10%	0.104	0.000	0.000	0.001	0.000	0.000	0.0000000
Mineral industry- CO2 Other processes uses of carbonates	CO2	2,544	526	3%	10%	0.104	0.000	0.002	0.001	0.000	0.000	0.0000001
Chemical industry- CO2 Ammonia production	CO2	1,892	390	3%	10%	0.104	0.000	0.002	0.001	0.000	0.000	0.0000000
Chemical industry- N2O Nitric acid production	N2O	1,783	21	3%	10%	0.104	0.000	0.002	0.000	0.000	0.000	0.0000001
Chemical industry - CO2 Adipic acid production	CO2	1	2	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry- N2O Adipic acid production	N2O	3,914	6	3%	10%	0.104	0.000	0.005	0.000	0.001	0.000	0.0000003
Chemical industry- Caprolactam, Glyoxal and Glyoxylic Acid production -N2O	N2O	10	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry- CO2 Carbide production	CO2	26	2	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry- CO2 Titanium dioxide production	CO2	0	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry- CO2 Soda ash production	CO2	183	215	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry - CO2 Petrochemical and carbon black production	CO2	422	536	3%	10%	0.104	0.000	0.000	0.001	0.000	0.000	0.0000000
Chemical industry - CH4 Petrochemical and carbon black production	CH4	69	3	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Chemical industry- HFCs Fluorochemical production	HFCs	372	1	5%	50%	0.502	0.000	0.000	0.000	0.000	0.000	0.0000001
Chemical industry- PFCs Fluorochemical production	PFCs	837	177	5%	50%	0.502	0.000	0.001	0.000	0.000	0.000	0.0000002
Chemical industry- SF6 Fluorochemical production	SF6	118	0	5%	50%	0.502	0.000	0.000	0.000	0.000	0.000	0.0000000
Metal industry- CO2 Iron and steel production	CO2	3,124	1,232	3%	10%	0.104	0.000	0.002	0.002	0.000	0.000	0.0000000
Metal industry- CH4 Iron and steel production	CH4	76	28	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Metal industry- CO2 Ferroalloys production	CO2	395	0	3%	10%	0.104	0.000	0.001	0.000	0.000	0.000	0.0000000
Metal industry- CO2 Aluminium production	CO2	359	0	3%	20%	0.202	0.000	0.000	0.000	0.000	0.000	0.0000000
Metal industry- PFCs Aluminium production	PFCs	1,778	0	3%	20%	0.202	0.000	0.002	0.000	0.000	0.000	0.0000002
Metal industry- HFCs Magnesium production	HFCs	0	4	3%	20%	0.202	0.000	0.000	0.000	0.000	0.000	0.0000000
Metal industry- CO2 Zinc production	CO2	500	152	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.0000000
Non-Energy products from Fuels and Solvent Use - CO2	CO2	370	313	30%	50%	0.583	0.000	0.000	0.001	0.000	0.000	0.0000001
Electronics Industry - HFCs	HFCs	0	38	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000

IPCC category	Gas	Emissions			Uncertainty			Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Contribution to variance	Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Electronics Industry - PFCs	PFCs	0	88	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000
Electronics Industry - SF6	SF6	0	81	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000
Electronics Industry - NF3	NF3	0	26	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000
Electronics Industry - N2O	N2O	0	3	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	HFCs	0	5,613	30%	50%	0.583	0.000	0.011	0.011	0.005	0.005	0.0000500
Product uses as substitutes for ozone depleting substances - PFCs Refrigeration and Air conditioning	PFCs	0	14	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.0000000
Product uses as substitutes for ozone depleting substances - HFCs Foam blowing agents	HFCs	0	341	30%	50%	0.583	0.000	0.001	0.001	0.000	0.000	0.0000002
Product uses as substitutes for ozone depleting substances - HFCs Fire protection	HFCs	0	517	30%	50%	0.583	0.000	0.001	0.001	0.000	0.000	0.0000004
Product uses as substitutes for ozone depleting substances - HFCs Aerosols	HFCs	0	189	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.0000001
Other Product Manufacture and Use - SF6	SF6	303	247	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.0000000
Other Product Manufacture and Use - N2O	N2O	694	466	5%	10%	0.112	0.000	0.000	0.001	0.000	0.000	0.0000000
Enteric Fermentation- CH4	CH4	17,174	13,488	3%	20%	0.202	0.000	0.003	0.026	0.001	0.001	0.0000015
Manure Management - CH4	CH4	5,308	4,098	5%	20%	0.206	0.000	0.001	0.008	0.000	0.001	0.0000003
Manure Management - N2O	N2O	2,314	1,376	5%	20%	0.206	0.000	0.000	0.003	0.000	0.000	0.0000000
Field burning of agricultural residues - CH4	CH4	15	10	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.0000000
Field burning of agricultural residues - N2O	N2O	4	3	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.0000000
Liming and other carbon containing fertilisers - CO2	CO2	45	18	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.0000000
Urea application - CO2	CO2	465	420	10%	20%	0.224	0.000	0.000	0.001	0.000	0.000	0.0000000
Direct N2O Emissions from Managed soils	N2O	5,146	4,203	20%	50%	0.539	0.000	0.001	0.008	0.001	0.002	0.0000056
Indirect N2O Emissions from Managed soils	N2O	2,710	2,114	20%	50%	0.539	0.000	0.000	0.004	0.000	0.001	0.0000014
Indirect N2O Emissions from Manure Management	N2O	762	487	5%	50%	0.502	0.000	0.000	0.001	0.000	0.000	0.0000000
Rice cultivations - CH4	CH4	2,102	1,793	5%	10%	0.112	0.000	0.001	0.003	0.000	0.000	0.0000001
Solid waste disposal - CH4	CH4	13,671	15,419	10%	20%	0.224	0.000	0.011	0.030	0.002	0.004	0.0000226
Biological treatment of Solid waste - CH4	CH4	5	114	20%	100%	1.020	0.000	0.000	0.000	0.000	0.000	0.0000000
Biological treatment of Solid waste - N2O	N2O	18	390	20%	100%	1.020	0.000	0.001	0.001	0.001	0.000	0.0000006
Incineration and open burning of waste - CO2	CO2	512	76	10%	20%	0.224	0.000	0.001	0.000	0.000	0.000	0.0000000
Incineration and open burning of waste - CH4	CH4	53	67	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.0000000
Incineration and open burning of waste - N2O	N2O	33	20	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.0000000
Wastewater treatment and discharge - CH4	CH4	3,584	2,651	20%	100%	1.020	0.000	0.000	0.005	0.000	0.001	0.0000022

IPCC category	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
	Gas	1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Wastewater treatment and discharge - N2O	N2O	1,120	1,238	20%	100%	1.020	0.000	0.001	0.002	0.001	0.001	0.0000012
Indirect CO2	Indirect CO2	1,391	871	30%	50%	0.583	0.000	0.000	0.002	0.000	0.001	0.00000005
TOTAL		520,626	363,490				0.001					0.0002
						Percentage uncertainty in total inventory	2.5%				Trend uncertainty	1.6%

Table A1.8 Results of the uncertainty analysis including LULUCF (Approach 1). Year 2024

IPCC category	Gas	Emissions			Uncertainty			Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Contribution to variance	Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Energy industries - CO2 liquid fuels	CO2	81,197	16,705	3%	3%	0.042	0.000	0.067	0.032	0.002	0.001	0.000
Energy industries - CO2 solid fuels	CO2	38,647	14,033	3%	3%	0.042	0.000	0.020	0.027	0.001	0.001	0.000
Energy industries - CO2 gaseous fuels	CO2	16,954	44,283	3%	3%	0.042	0.000	0.064	0.085	0.002	0.004	0.000
Energy industries - CO2 other fuels	CO2	143	106	3%	3%	0.042	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - N2O liquid fuels	N2O	256	122	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - N2O solid fuels	N2O	145	56	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - N2O gaseous fuels	N2O	8	22	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - N2O other fuels	N2O	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - N2O biomass	N2O	15	69	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - CH4 liquid fuels	CH4	82	11	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - CH4 solid fuels	CH4	147	12	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - CH4 gaseous fuels	CH4	13	31	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - CH4 other fuels	CH4	0	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Energy industries - CH4 biomass	CH4	58	64	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - CO2 liquid fuels	CO2	32,806	12,770	3%	3%	0.042	0.000	0.016	0.025	0.000	0.001	0.000
Manufacturing industries and construction - CO2 solid fuels	CO2	25,732	5,896	3%	3%	0.042	0.000	0.020	0.011	0.001	0.000	0.000
Manufacturing industries and construction - CO2 gaseous fuels	CO2	32,234	30,409	3%	3%	0.042	0.000	0.019	0.059	0.001	0.002	0.000
Manufacturing industries and construction - CO2 other fuels	CO2	0	459	3%	3%	0.042	0.000	0.001	0.001	0.000	0.000	0.000
Manufacturing industries and construction - N2O liquid fuels	N2O	823	404	3%	50%	0.501	0.000	0.000	0.001	0.000	0.000	0.000
Manufacturing industries and construction - N2O solid fuels	N2O	216	29	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - N2O gaseous fuels	N2O	146	142	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - N2O other fuels	N2O	0	22	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - N2O biomass	N2O	6	63	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - CH4 liquid fuels	CH4	47	26	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000

IPCC category	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
	Gas	1990	2024	AD	EF	Combined		Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Manufacturing industries and construction - CH4 solid fuels	CH4	120	34	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - CH4 gaseous fuels	CH4	16	14	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - CH4 other fuels	CH4	0	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Manufacturing industries and construction - CH4 biomass	CH4	4	220	20%	50%	0.539	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CO2 Road transportation	CO2	92,332	99,907	3%	3%	0.042	0.000	0.079	0.192	0.002	0.008	0.000
Transport - N2O Road transportation	N2O	746	818	3%	40%	0.401	0.000	0.001	0.002	0.000	0.000	0.000
Transport - CH4 Road transportation	CH4	969	150	3%	40%	0.401	0.000	0.001	0.000	0.000	0.000	0.000
Transport - CO2 Waterborne navigation	CO2	5,470	4,694	3%	3%	0.042	0.000	0.002	0.009	0.000	0.000	0.000
Transport - N2O Waterborne navigation	N2O	34	31	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CH4 Waterborne navigation	CH4	39	16	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CO2 Civil Aviation	CO2	1,493	2,359	3%	3%	0.042	0.000	0.003	0.005	0.000	0.000	0.000
Transport - N2O Civil Aviation	N2O	11	18	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CH4 Civil Aviation	CH4	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CO2 Railways	CO2	613	37	3%	5%	0.058	0.000	0.001	0.000	0.000	0.000	0.000
Transport - N2O Railways	N2O	64	4	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CH4 Railways	CH4	1	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CO2 Other transportation - pipelines	CO2	411	946	3%	3%	0.042	0.000	0.001	0.002	0.000	0.000	0.000
Transport - N2O Other transportation - pipelines	N2O	6	13	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Transport - CH4 Other transportation - pipelines	CH4	1	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - CO2 commercial, residential, agriculture liquid fuels	CO2	38,274	12,062	3%	3%	0.042	0.000	0.024	0.023	0.001	0.001	0.000
Other sectors - CO2 commercial, residential, agriculture solid fuels	CO2	899	0	3%	3%	0.042	0.000	0.001	0.000	0.000	0.000	0.000
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	CO2	36,338	46,610	3%	3%	0.042	0.000	0.045	0.090	0.001	0.004	0.000
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	CO2	530	5,774	3%	3%	0.042	0.000	0.010	0.011	0.000	0.000	0.000
Other sectors - N2O commercial, residential, agriculture liquid fuels	N2O	885	609	3%	50%	0.501	0.000	0.000	0.001	0.000	0.000	0.000
Other sectors - N2O commercial, residential, agriculture solid fuels	N2O	4	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - N2O commercial, residential, agriculture gaseous fuels	N2O	173	209	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000

IPCC category	Gas	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Type A		Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions	
Other sectors - N2O commercial, residential, agriculture other fossil fuels	N2O	13	140	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - N2O commercial, residential, agriculture biomass	N2O	473	1,025	3%	50%	0.501	0.000	0.001	0.002	0.001	0.000	0.000	0.000
Other sectors - CH4 commercial, residential, agriculture liquid fuels	CH4	105	16	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - CH4 commercial, residential, agriculture solid fuels	CH4	11	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - CH4 commercial, residential, agriculture gaseous fuels	CH4	46	55	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - CH4 commercial, residential, agriculture other fossil fuels	CH4	1	9	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other sectors - CH4 commercial, residential, agriculture biomass	CH4	1,116	2,394	3%	50%	0.501	0.000	0.003	0.005	0.002	0.000	0.000	0.000
Other non specified - CO2 military mobile - liquid fuels	CO2	1,071	364	3%	5%	0.058	0.000	0.001	0.001	0.000	0.000	0.000	0.000
Other non specified - N2O military mobile - liquid fuels	N2O	60	7	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other non specified - CH4 military mobile - liquid fuels	CH4	5	1	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CO2 Solid fuels	CO2	0	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CH4 Solid fuels	CH4	148	29	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CO2 Oil and natural gas - Oil	CO2	2,402	1,207	3%	10%	0.104	0.000	0.001	0.002	0.000	0.000	0.000	0.000
Fugitive - CH4 Oil and natural gas - Oil	CH4	347	69	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - N2O Oil and natural gas - Oil	N2O	0	0	3%	50%	0.501	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CO2 Oil and natural gas - Natural gas	CO2	9	3	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CH4 Oil and natural gas - Natural gas	CH4	9,225	2,169	3%	50%	0.501	0.000	0.007	0.004	0.004	0.000	0.000	0.000
Fugitive - CO2 Oil and natural gas - venting and flaring	CO2	956	311	50%	10%	0.510	0.000	0.001	0.001	0.000	0.000	0.000	0.000
Fugitive - N2O Oil and natural gas - venting and flaring	N2O	1	1	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CH4 Oil and natural gas - venting and flaring	CH4	199	50	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - CO2 Oil and natural gas - Other - flaring in refineries	CO2	681	219	50%	10%	0.510	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Fugitive - N2O Oil and natural gas - Other - flaring in refineries	N2O	10	7	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.000	0.000

IPCC category	Gas	Emissions			Uncertainty			Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Contribution to variance	Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	CH4	226	465	50%	50%	0.707	0.000	0.001	0.001	0.000	0.001	0.000
Mineral industry- CO2 Cement production	CO2	15,846	6,746	3%	10%	0.104	0.000	0.006	0.013	0.001	0.001	0.000
Mineral industry- CO2 Lime production	CO2	1,877	1,785	3%	10%	0.104	0.000	0.001	0.003	0.000	0.000	0.000
Mineral industry- CO2 Glass production	CO2	453	579	3%	10%	0.104	0.000	0.001	0.001	0.000	0.000	0.000
Mineral industry- CO2 Other processes uses of carbonates	CO2	2,544	534	3%	10%	0.104	0.000	0.002	0.001	0.000	0.000	0.000
Chemical industry- CO2 Ammonia production	CO2	1,892	386	3%	10%	0.104	0.000	0.002	0.001	0.000	0.000	0.000
Chemical industry- N2O Nitric acid production	N2O	1,783	25	3%	10%	0.104	0.000	0.002	0.000	0.000	0.000	0.000
Chemical industry - CO2 Adipic acid production	CO2	1	3	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- N2O Adipic acid production	N2O	3,914	22	3%	10%	0.104	0.000	0.005	0.000	0.000	0.000	0.000
Chemical industry- Caprolactam, Glyoxal and Glyoxylic Acid production -N2O	N2O	10	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- CO2 Carbide production	CO2	26	2	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- CO2 Titanium dioxide production	CO2	0	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- CO2 Soda ash production	CO2	183	229	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry - CO2 Petrochemical and carbon black production	CO2	422	529	3%	10%	0.104	0.000	0.001	0.001	0.000	0.000	0.000
Chemical industry - N2O Petrochemical and carbon black production	N2O	69	3	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- HFCs Fluorochemical production	HFCs	372	1	5%	50%	0.502	0.000	0.000	0.000	0.000	0.000	0.000
Chemical industry- PFCs Fluorochemical production	PFCs	837	173	5%	50%	0.502	0.000	0.001	0.000	0.000	0.000	0.000
Chemical industry- SF6 Fluorochemical production	SF6	118	0	5%	50%	0.502	0.000	0.000	0.000	0.000	0.000	0.000
Metal industry- CO2 Iron and steel production	CO2	3,124	1,324	3%	10%	0.104	0.000	0.001	0.003	0.000	0.000	0.000
Metal industry- CH4 Iron and steel production	CH4	76	33	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Metal industry- CO2 Ferroalloys production	CO2	395	0	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Metal industry- CO2 Aluminium production	CO2	359	0	3%	20%	0.202	0.000	0.000	0.000	0.000	0.000	0.000
Metal industry- PFCs Aluminium production	PFCs	1,778	0	3%	20%	0.202	0.000	0.002	0.000	0.000	0.000	0.000
Metal industry- HFCs Magnesium production	HFCs	0	4	3%	20%	0.202	0.000	0.000	0.000	0.000	0.000	0.000
Metal industry- CO2 Zinc production	CO2	500	161	3%	10%	0.104	0.000	0.000	0.000	0.000	0.000	0.000
Non-Energy products from Fuels and Solvent Use - CO2	CO2	370	313	30%	50%	0.583	0.000	0.000	0.001	0.000	0.000	0.000
Electronics Industry - HFCs	HFCs	0	36	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000
Electronics Industry - PFCs	PFCs	0	105	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000
Electronics Industry - SF6	SF6	0	48	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000
Electronics Industry - NF3	NF3	0	20	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000

IPCC category	Gas	Emissions			Uncertainty			Contribution to variance	Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Type A		Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions	
Electronics Industry - N2O	N2O	0	3	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	HFCs	0	5,613	30%	50%	0.583	0.000	0.011	0.011	0.006	0.005	0.000	0.000
Product uses as substitutes for ozone depleting substances - PFCs Refrigeration and Air conditioning	PFCs	0	14	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Product uses as substitutes for ozone depleting substances - HFCs Foam blowing agents	HFCs	0	341	30%	50%	0.583	0.000	0.001	0.001	0.000	0.000	0.000	0.000
Product uses as substitutes for ozone depleting substances - HFCs Fire protection	HFCs	0	517	30%	50%	0.583	0.000	0.001	0.001	0.001	0.000	0.000	0.000
Product uses as substitutes for ozone depleting substances - HFCs Aerosols	HFCs	0	189	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other Product Manufacture and Use - SF6	SF6	303	247	5%	20%	0.206	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Other Product Manufacture and Use - N2O	N2O	694	466	5%	10%	0.112	0.000	0.000	0.001	0.000	0.000	0.000	0.000
Enteric Fermentation- CH4	CH4	17,174	13,488	3%	20%	0.202	0.000	0.007	0.027	0.001	0.001	0.000	0.000
Manure Management - CH4	CH4	5,308	4,098	5%	20%	0.206	0.000	0.002	0.008	0.000	0.001	0.000	0.000
Manure Management - N2O	N2O	2,314	1,376	5%	20%	0.206	0.000	0.000	0.003	0.000	0.000	0.000	0.000
Field burning of agricultural residues - CH4	CH4	15	10	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Field burning of agricultural residues - N2O	N2O	4	3	30%	50%	0.583	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Liming - CO2	CO2	45	18	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Urea application - CO2	CO2	465	420	10%	20%	0.224	0.000	0.000	0.001	0.000	0.000	0.000	0.000
Direct N2O Emissions from Managed soils	N2O	5,146	4,203	20%	50%	0.539	0.000	0.002	0.008	0.001	0.002	0.000	0.000
Indirect N2O Emissions from Managed soils	N2O	2,710	2,114	20%	50%	0.539	0.000	0.001	0.004	0.001	0.001	0.000	0.000
Indirect N2O Emissions from Manure Management	N2O	762	487	5%	50%	0.502	0.000	0.000	0.001	0.000	0.000	0.000	0.000
Rice cultivations - CH4	CH4	2,102	1,793	5%	10%	0.112	0.000	0.001	0.004	0.000	0.000	0.000	0.000
Solid waste disposal - CH4	CH4	13,671	15,419	10%	20%	0.224	0.000	0.014	0.030	0.003	0.004	0.000	0.000
Biological treatment of Solid waste - CH4	CH4	5	114	20%	100%	1.020	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Biological treatment of Solid waste - N2O	N2O	18	390	20%	100%	1.020	0.000	0.001	0.001	0.001	0.000	0.000	0.000
Incineration and open burning of waste - CO2	CO2	512	76	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Incineration and open burning of waste - CH4	CH4	53	67	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Incineration and open burning of waste - N2O	N2O	33	20	10%	20%	0.224	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Wastewater treatment and discharge - CH4	CH4	3,584	2,651	20%	100%	1.020	0.000	0.001	0.005	0.001	0.001	0.000	0.000
Wastewater treatment and discharge - N2O	N2O	1,120	1,238	20%	100%	1.020	0.000	0.001	0.002	0.001	0.001	0.000	0.000
Forest Land remaining Forest Land - Living biomass - CO2	CO2	-13,919	-41,680	19%	31%	0.363	0.003	0.066	0.082	0.020	0.023	0.001	0.001
Forest Land remaining Forest Land - DOM (deadwood+litter) - CO2	CO2	-3,476	-413	17%	26%	0.307	0.000	0.003	0.001	0.001	0.000	0.000	0.000

IPCC category	Gas	Emissions			Uncertainty			Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Contribution to variance	Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Forest Land remaining Forest Land - soils -CO2	CO2	0	0				0.000	0.000	0.000	0.000	0.000	0.000
Forest Land remaining Forest Land - CH4	CH4	309	69	5%	70%	0.702	0.000	0.000	0.000	0.000	0.000	0.000
Forest Land remaining Forest Land - N2O	N2O	162	36	5%	70%	0.702	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Forest Land -Living biomass - CO2	CO2	-2,525	-12,699	19%	31%	0.363	0.000	0.022	0.025	0.007	0.007	0.000
Land Converted to Forest Land - DOM (deadwood+litter) CO2	CO2	-668	-1,440	17%	26%	0.307	0.000	0.002	0.003	0.001	0.001	0.000
Land Converted to Forest Land - soils -CO2	CO2	-217	-1,656	20%	46%	0.500	0.000	0.003	0.003	0.001	0.001	0.000
Land Converted to Forest Land - CH4	CH4	31	20	5%	70%	0.702	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Forest Land - N2O	N2O	16	10	5%	70%	0.702	0.000	0.000	0.000	0.000	0.000	0.000
Cropland Remaining Cropland - Living biomass - CO2	CO2	1,200	828	5%	11%	0.120	0.000	0.000	0.002	0.000	0.000	0.000
Cropland Remaining Cropland - mineral soils - CO2	CO2	-795	-2,198	5%	30%	0.304	0.000	0.003	0.004	0.001	0.000	0.000
Cropland Remaining Cropland - organic soils - CO2	CO2	712	699	20%	90%	0.922	0.000	0.001	0.001	0.000	0.000	0.000
Cropland Remaining Cropland - CH4	CH4	98	96	20%	70%	0.728	0.000	0.000	0.000	0.000	0.000	0.000
Cropland Remaining Cropland - N2O	N2O	2	1	20%	70%	0.728	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Cropland - living biomass - CO2	CO2	0	0	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Cropland -mineral soils CO2	CO2	749	749	50%	26%	0.562	0.000	0.001	0.001	0.000	0.001	0.000
Land Converted to Cropland - soils CO2	CO2	0	0	50%	75%	0.901	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Cropland - N2O	N2O	69	69	50%	70%	0.860	0.000	0.000	0.000	0.000	0.000	0.000
Grassland Remaining Grassland - living biomass -CO2	CO2	5,376	-2,639	19%	31%	0.363	0.000	0.011	0.005	0.004	0.001	0.000
Grassland Remaining Grassland - DOM (deadwood+litter) CO2	CO2	-114	-330	17%	26%	0.307	0.000	0.001	0.001	0.000	0.000	0.000
Grassland Remaining Grassland - mineral soils-CO2	CO2	160	772	5%	30%	0.304	0.000	0.001	0.002	0.000	0.000	0.000
Grassland Remaining Grassland - organic soils-CO2	CO2	27	25	20%	90%	0.922	0.000	0.000	0.000	0.000	0.000	0.000
Grassland Remaining Grassland - CH4	CH4	389	85	15%	70%	0.716	0.000	0.000	0.000	0.000	0.000	0.000
Grassland Remaining Grassland - N2O	N2O	213	101	15%	70%	0.716	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Grassland - living biomass -CO2	CO2	0	-45	50%	50%	0.707	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Grassland - DOM (deadwood+litter) - CO2	CO2	0	0	50%	26%	0.562	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Grassland - mineral soils- CO2	CO2	-1,124	-3,630	50%	75%	0.901	0.000	0.006	0.007	0.004	0.005	0.000
Land Converted to Wetland - CO2	CO2	0	0	75%	75%	1.061	0.000	0.000	0.000	0.000	0.000	0.000
Land Converted to Settlements - CO2	CO2	738	1,049	75%	75%	1.061	0.000	0.001	0.002	0.001	0.002	0.000
Land Converted to Settlements - N2O	N2O	28	55	75%	75%	1.061	0.000	0.000	0.000	0.000	0.000	0.000
Harvest Wood Products - CO2	CO2	-389	-2,002	25%	50%	0.559	0.000	0.003	0.004	0.002	0.001	0.000
Indirect N2O from Managed soils - LULUCF	N2O	0	0	75%	75%	1.061	0.000	0.000	0.000	0.000	0.000	0.000

IPCC category	Gas	Emissions			Uncertainty			Sensitivity		Uncertainty in trend		
		1990	2024	AD	EF	Combined	Contribution to variance	Type A	Type B	introduced by EF uncertainty	introduced by AD uncertainty	in total national emissions
Indirect CO2	Indirect CO2	1,391	871	30%	50%	0.583	0.000	0.000	0.002	0.000	0.001	0.000
TOTAL		507,677	299,422				0.004					0.001
						Percentage uncertainty in total inventory	6.2%				Trend uncertainty	3.7%

Emission sources of the Italian inventory are disaggregated into a detailed level, 130 categories, according to the IPCC list in the guidelines and considering national circumstances and importance. Considering also the LULUCF sector, sources and sinks of the Italian inventory are disaggregated into 163 categories. Uncertainties are therefore estimated for these categories. To estimate uncertainty for both activity data and emission factors, information provided in the IPCC Guidelines, as well as expert judgement have been used; standard deviations have also been considered whenever measurements were available.

The assumptions on which uncertainty estimations are based are documented for each category. Figures to draw up uncertainty are checked with the relevant analyst experts and literature references and they are consistent with the IPCC Good Practice Guidance and the 2006 IPCC Guidelines (IPCC, 2000; IPCC, 2006).

The general approach for quantifying a level of uncertainty to activity data and emission factors is to set values within a range low, medium and high according to the confidence the expert relies on the value. For instance, a low value (e.g. 3-5%) has been attributed to activity data derived from the energy balance and statistical yearbooks, medium-high values within a range of 20-50% for all the data which are not directly or only partially derived from census or sample surveys or data which are simple estimations. For emission factors, the uncertainties set are usually higher than those for activity data; figures suggested by the IPCC good practice guidance and guidelines (IPCC, 2000; IPCC, 2006) are used when the emission factor is a default value or when appropriate, low values are attributed to measured data whereas the uncertainty values are high in all other cases.

For 1990, the uncertainty estimated by Approach 1 is equal to 2.1%; if considering the LULUCF sector the overall uncertainty increases to 2.4%.

In 2024, the results of Approach 1 suggest an uncertainty of 2.5% in the combined GWP total emissions. The analysis also estimates an uncertainty of 1.5% in the trend.

Including the LULUCF sector in the total uncertainty assessment, Approach 1 shows an uncertainty of 6.2% in the combined GWP total emissions for the year 2024, whereas the uncertainty in the trend is equal to 3.7%. Results are shown in Table A1.8

Further investigation is needed to better quantify the uncertainty values for some specific source, nevertheless it should be noted that a conservative approach has been followed.

A1.4 Approach 2 key category assessment

Approach 2 can be used to identify key categories when an uncertainty analysis has been carried out on the inventory. It is helpful in prioritizing activities to improve inventory quality and to reduce overall uncertainty. Under Approach 2, the source or sink category uncertainties are incorporated by weighting the Approach 1 level and trend assessment results with the source category's relative uncertainty.

Therefore, the following equations:

Level Assessment, with Uncertainty = Approach 1 Level Assessment · Relative Category Uncertainty

Trend Assessment, with Uncertainty = Approach 1 Trend Assessment · Relative Category Uncertainty

Approach 2 has been applied both to the year 1990 and the last year of the submission.

The results of the Approach 2 key category analysis, without LULUCF categories, are provided in Table A1.9, for 2024, while in Table A1.11 results, including LULUCF categories, are shown. For 1990, results of the analysis excluding and including LULUCF categories are reported in Table A1.13 and Table A1.14. The results of the trend analysis are reported in Table A1.10 and in Table A1.12, excluding LULUCF and including LULUCF, respectively.

The application of Approach 2 to the year 1990 gives as a result 31 key categories accounting for 90% of the total uncertainty levels. Including the LULUCF categories, 42 key categories accounted for 90% of the total uncertainty levels.

For the year 2024, 29 key categories accounting for 90% of the total uncertainty levels were identified; when applying the trend analysis, the key categories increased to 36.

The application of Approach 2 to the inventory, including the LULUCF categories, results in 32 key categories which account for 90% of the total uncertainty levels; for the trend analysis, with LULUCF, the number of key categories is 37.

Table A1.9 Results of the key category analysis without LULUCF. Approach 2 Level assessment, year 2024

CATEGORIES	Share	Uncertainty	L*U	Level assessment with uncertainty	Cumulative Percentage
Transport - CO2 Road transportation	0.29	0.0424	0.0121	0.1141	0.11
Solid waste disposal - CH4	0.04	0.2236	0.0095	0.0892	0.20
Product uses as substitutes for ozone depleting substances - HFCs					
Refrigeration and Air conditioning	0.02	0.5831	0.0090	0.0847	0.29
Enteric Fermentation- CH4	0.04	0.2022	0.0075	0.0705	0.36
Wastewater treatment and discharge - CH4	0.01	1.0198	0.0074	0.0699	0.43
Direct N2O Emissions from Managed soils	0.01	0.5385	0.0062	0.0585	0.49
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.13	0.0424	0.0056	0.0525	0.54
Energy industries - CO2 gaseous fuels	0.12	0.0424	0.0051	0.0477	0.59
Manufacturing industries and construction - CO2 gaseous fuels	0.08	0.0424	0.0035	0.0331	0.62
Wastewater treatment and discharge - N2O	0.00	1.0198	0.0035	0.0327	0.65
Indirect N2O Emissions from Managed soils	0.01	0.5385	0.0031	0.0294	0.68
Fugitive - CH4 Oil and natural gas - Natural gas	0.01	0.5009	0.0030	0.0281	0.71
Other sectors - CH4 commercial, residential, agriculture biomass	0.01	0.5009	0.0026	0.0247	0.73
Manure Management - CH4	0.01	0.2062	0.0023	0.0218	0.76
Mineral industry- CO2 Cement production	0.02	0.1044	0.0019	0.0183	0.78
Energy industries - CO2 liquid fuels	0.04	0.0424	0.0017	0.0164	0.79
Indirect CO2	0.00	0.5831	0.0014	0.0131	0.80
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.03	0.0424	0.0013	0.0118	0.82
Manufacturing industries and construction - CO2 liquid fuels	0.03	0.0424	0.0012	0.0113	0.83
Other sectors - N2O commercial, residential, agriculture biomass	0.00	0.5009	0.0011	0.0107	0.84
Biological treatment of Solid waste - N2O	0.00	1.0198	0.0011	0.0103	0.85
Transport - N2O Road transportation	0.00	0.4011	0.0009	0.0086	0.86
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	0.00	0.7071	0.0009	0.0083	0.87
Product uses as substitutes for ozone depleting substances - HFCs					
Fire protection	0.00	0.5831	0.0008	0.0078	0.87
Manure Management - N2O	0.00	0.2062	0.0008	0.0073	0.88
Other sectors - N2O commercial, residential, agriculture liquid fuels	0.00	0.5009	0.0007	0.0068	0.89
Indirect N2O Emissions from Manure Management	0.00	0.5025	0.0007	0.0063	0.89
Transport - CO2 Waterborne navigation	0.01	0.0424	0.0006	0.0055	0.899
Energy industries - CO2 solid fuels	0.01	0.0424	0.0006	0.0054	0.905
Rice cultivations - CH4	0.00	0.1118	0.0006	0.0052	0.91

Table A1.10 Results of the key category analysis without LULUCF. Approach 2 Trend assessment

CATEGORIES	Trend assessment with uncertainty	Uncertainty	T*U	Relative trend assessment with uncertainty	Cumulative Percentage
Product uses as substitutes for ozone depleting substances	0.01	0.5831	0.0063	0.138	0.14
- HFCs Refrigeration and Air conditioning					
Fugitive - CH4 Oil and natural gas - Natural gas	0.01	0.5009	0.0041	0.091	0.23
Energy industries - CO2 liquid fuels	0.08	0.0424	0.0034	0.075	0.30
Transport - CO2 Road transportation	0.08	0.0424	0.0032	0.071	0.37
Energy industries - CO2 gaseous fuels	0.06	0.0424	0.0026	0.057	0.43
Solid waste disposal - CH4	0.01	0.2236	0.0025	0.056	0.49
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.04	0.0424	0.0018	0.040	0.53
Energy industries - CO2 solid fuels	0.04	0.0424	0.0018	0.040	0.57
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.03	0.0424	0.0013	0.029	0.60
Manufacturing industries and construction - CO2 solid fuels	0.03	0.0424	0.0011	0.024	0.62
Other sectors - CH4 commercial, residential, agriculture biomass	0.00	0.5009	0.0011	0.024	0.64
Manufacturing industries and construction - CO2 liquid fuels	0.02	0.0424	0.0010	0.023	0.67
Wastewater treatment and discharge - N2O	0.00	1.0198	0.0009	0.020	0.69
Mineral industry- CO2 Cement production	0.01	0.1044	0.0009	0.019	0.70
Biological treatment of Solid waste - N2O	0.00	1.0198	0.0007	0.016	0.72
Direct N2O Emissions from Managed soils	0.00	0.5385	0.0006	0.014	0.74
Manufacturing industries and construction - CO2 gaseous fuels	0.01	0.0424	0.0006	0.014	0.75
Enteric Fermentation- CH4	0.00	0.2022	0.0006	0.013	0.76
Product uses as substitutes for ozone depleting substances	0.00	0.5831	0.0006	0.013	0.77
- HFCs Fire protection					
Chemical industry- N2O Adipic acid production	0.01	0.1044	0.0005	0.012	0.79
Metal industry- PFCs Aluminium production	0.00	0.2022	0.0005	0.011	0.80
Other sectors - N2O commercial, residential, agriculture biomass	0.00	0.5009	0.0005	0.010	0.81
Fugitive - CO2 Oil and natural gas - venting and flaring	0.00	0.5099	0.0004	0.009	0.82
Transport - CH4 Road transportation	0.00	0.4011	0.0004	0.009	0.83
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	0.00	0.7071	0.0004	0.009	0.83
Chemical industry- PFCs Fluorochemical production	0.00	0.5025	0.0004	0.009	0.84
Product uses as substitutes for ozone depleting substances	0.00	0.5831	0.0004	0.008	0.85
- HFCs Foam blowing agents					
Fugitive - CO2 Oil and natural gas - Other - flaring in refineries	0.00	0.5099	0.0003	0.007	0.86
Wastewater treatment and discharge - CH4	0.00	1.0198	0.0003	0.006	0.87
Other sectors - CO2 commercial, residential, agriculture other fossil fuels	0.01	0.0424	0.0003	0.006	0.87
Mineral industry- CO2 Other processes uses of carbonates	0.00	0.1044	0.0003	0.006	0.88
Chemical industry- HFCs Fluorochemical production	0.00	0.5025	0.0003	0.006	0.882
Chemical industry- N2O Nitric acid production	0.00	0.1044	0.0002	0.005	0.888
Transport - N2O Road transportation	0.00	0.4011	0.0002	0.005	0.89
Indirect N2O Emissions from Managed soils	0.00	0.5385	0.0002	0.005	0.898
Manufacturing industries and construction - CH4 biomass	0.00	0.5385	0.0002	0.005	0.903
Biological treatment of Solid waste - CH4	0.00	1.0198	0.0002	0.005	0.91

Table A1.11 Results of the key category analysis with LULUCF. Approach 2 Level assessment, year 2024

CATEGORIES	Share	Uncertainty	L*U	Level assessment with uncertainty	Cumulative Percentage
Forest Land remaining Forest Land - Living biomass -CO2	0.10	0.3631	0.0346	0.2196	0.22
Land Converted to Forest Land -Living biomass - CO2	0.03	0.3631	0.0106	0.0669	0.29
Transport - CO2 Road transportation	0.24	0.0424	0.0101	0.0640	0.35
Solid waste disposal - CH4	0.04	0.2236	0.0079	0.0500	0.40
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	0.01	0.5831	0.0075	0.0475	0.45
Land Converted to Grassland - mineral soils- CO2	0.01	0.9014	0.0075	0.0475	0.50
Enteric Fermentation- CH4	0.03	0.2022	0.0062	0.0396	0.54
Wastewater treatment and discharge - CH4	0.01	1.0198	0.0062	0.0392	0.57
Direct N2O Emissions from Managed soils	0.01	0.5385	0.0052	0.0328	0.61
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.11	0.0424	0.0046	0.0294	0.64
Energy industries - CO2 gaseous fuels	0.10	0.0424	0.0042	0.0268	0.66
Manufacturing industries and construction - CO2 gaseous fuels	0.07	0.0424	0.0029	0.0185	0.68
Wastewater treatment and discharge - N2O	0.00	1.0198	0.0029	0.0183	0.70
Indirect N2O Emissions from Managed soils	0.00	0.5385	0.0026	0.0165	0.72
Harvest Wood Products - CO2	0.00	0.5590	0.0026	0.0162	0.73
Land Converted to Settlements - CO2	0.00	1.0607	0.0025	0.0161	0.75
Fugitive - CH4 Oil and natural gas - Natural gas	0.00	0.5009	0.0025	0.0158	0.76
Grassland Remaining Grassland - living biomass -CO2	0.01	0.3631	0.0022	0.0139	0.78
Other sectors - CH4 commercial, residential, agriculture biomass	0.00	0.5009	0.0022	0.0138	0.79
Manure Management - CH4	0.01	0.2062	0.0019	0.0123	0.80
Land Converted to Forest Land - soils -CO2	0.00	0.5000	0.0019	0.0120	0.82
Mineral industry- CO2 Cement production	0.02	0.1044	0.0016	0.0102	0.83
Cropland Remaining Cropland - mineral soils - CO2	0.01	0.3041	0.0015	0.0097	0.84
Cropland Remaining Cropland - organic soils - CO2	0.00	0.9220	0.0015	0.0093	0.85
Energy industries - CO2 liquid fuels	0.03	0.0424	0.0015	0.0092	0.86
Indirect CO2	0.00	0.5831	0.0012	0.0074	0.86
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.02	0.0424	0.0010	0.0066	0.87
Land Converted to Forest Land - DOM (deadwood+litter) CO2	0.00	0.3073	0.0010	0.0064	0.88
Manufacturing industries and construction - CO2 liquid fuels	0.02	0.0424	0.0010	0.0063	0.88
Land Converted to Cropland -mineral soils CO2	0.00	0.5617	0.0010	0.0061	0.89
Other sectors - N2O commercial, residential, agriculture biomass	0.00	0.5009	0.0009	0.0060	0.89
Biological treatment of Solid waste - N2O	0.00	1.0198	0.0009	0.0058	0.90001
Transport - N2O Road transportation	0.00	0.4011	0.0008	0.0048	0.90
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	0.00	0.7071	0.0007	0.0047	0.91

Table A1.12 Results of the key category analysis with LULUCF. Approach 2 Trend assessment

CATEGORIES	Trend assessment	Uncertainty	T*U	Relative trend assessment with uncertainty	Cumulative Percentage
Forest Land remaining Forest Land - Living biomass -CO2	0.04	0.3631	0.0145	0.18	0.18
Product uses as substitutes for ozone depleting substances - HFCs Refrigeration and Air conditioning	0.01	0.5831	0.0064	0.08	0.26
Land Converted to Forest Land -Living biomass - CO2	0.02	0.3631	0.0060	0.07	0.33
Grassland Remaining Grassland - living biomass -CO2	0.01	0.3631	0.0038	0.05	0.38
Transport - CO2 Road transportation	0.09	0.0424	0.0038	0.05	0.43
Land Converted to Grassland - mineral soils- CO2	0.00	0.9014	0.0033	0.04	0.47
Solid waste disposal - CH4	0.01	0.2236	0.0030	0.04	0.50
Fugitive - CH4 Oil and natural gas - Natural gas	0.01	0.5009	0.0030	0.04	0.54
Energy industries - CO2 gaseous fuels	0.06	0.0424	0.0026	0.03	0.57
Energy industries - CO2 liquid fuels	0.06	0.0424	0.0025	0.03	0.60
Forest Land remaining Forest Land - DOM (deadwood+litter) - CO2	0.01	0.3073	0.0025	0.03	0.63
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.05	0.0424	0.0020	0.02	0.66
Harvest Wood Products - CO2	0.00	0.5590	0.0015	0.02	0.68
Energy industries - CO2 solid fuels	0.03	0.0424	0.0014	0.02	0.69
Enteric Fermentation- CH4	0.01	0.2022	0.0012	0.02	0.71
Land Converted to Forest Land - soils -CO2	0.00	0.5000	0.0012	0.02	0.72
Land Converted to Settlements - CO2	0.00	1.0607	0.0012	0.01	0.74
Direct N2O Emissions from Managed soils	0.00	0.5385	0.0011	0.01	0.75
Other sectors - CH4 commercial, residential, agriculture biomass	0.00	0.5009	0.0011	0.01	0.77
Wastewater treatment and discharge - N2O	0.00	1.0198	0.0011	0.01	0.78
Wastewater treatment and discharge - CH4	0.00	1.0198	0.0010	0.01	0.79
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.02	0.0424	0.0009	0.01	0.80
Manufacturing industries and construction - CO2 gaseous fuels	0.02	0.0424	0.0009	0.01	0.81
Manufacturing industries and construction - CO2 solid fuels	0.02	0.0424	0.0008	0.01	0.82
Biological treatment of Solid waste - N2O	0.00	1.0198	0.0007	0.01	0.83
Manufacturing industries and construction - CO2 liquid fuels	0.02	0.0424	0.0007	0.01	0.84
Product uses as substitutes for ozone depleting substances - HFCs Fire protection	0.00	0.5831	0.0006	0.01	0.85
Cropland Remaining Cropland - mineral soils - CO2	0.00	0.3041	0.0006	0.01	0.85
Indirect N2O Emissions from Managed soils	0.00	0.5385	0.0005	0.01	0.86
Other sectors - N2O commercial, residential, agriculture biomass	0.00	0.5009	0.0005	0.01	0.87
Mineral industry- CO2 Cement production	0.00	0.1044	0.0005	0.01	0.87
Cropland Remaining Cropland - organic soils - CO2	0.00	0.9220	0.0005	0.01	0.88
Chemical industry- N2O Adipic acid production	0.00	0.1044	0.0004	0.01	0.88
Fugitive - CH4 Oil and natural gas - Other - flaring in refineries	0.00	0.7071	0.0004	0.01	0.89
Product uses as substitutes for ozone depleting substances - HFCs Foam blowing agents	0.00	0.5831	0.0004	0.00	0.89
Metal industry- PFCs Aluminium production	0.00	0.2022	0.0004	0.00	0.899
Grassland Remaining Grassland - mineral soils-CO2	0.00	0.3041	0.0004	0.00	0.903
Manure Management - CH4	0.00	0.2062	0.0004	0.00	0.91
Land Converted to Cropland -mineral soils CO2	0.00	0.5617	0.0003	0.00	0.91

Table A1.13 Results of the key category analysis without LULUCF. Approach 2 Level assessment, 1990

CATEGORIES	Share	Uncertainty	L*U	Level assessment with uncertainty	Cumulative Percentage
Fugitive - CH4 Oil and natural gas - Natural gas	0.02	0.5009	0.0089	0.0915	0.09
Transport - CO2 Road transportation	0.18	0.0424	0.0075	0.0775	0.17
Wastewater treatment and discharge - CH4	0.01	1.0198	0.0070	0.0723	0.24
Enteric Fermentation- CH4	0.03	0.2022	0.0067	0.0687	0.31
Energy industries - CO2 liquid fuels	0.16	0.0424	0.0066	0.0682	0.38
Solid waste disposal - CH4	0.03	0.2236	0.0059	0.0605	0.44
Direct N2O Emissions from Managed soils	0.01	0.5385	0.0053	0.0549	0.49
Mineral industry- CO2 Cement production	0.03	0.1044	0.0032	0.0327	0.53
Energy industries - CO2 solid fuels	0.07	0.0424	0.0031	0.0325	0.56
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.07	0.0424	0.0031	0.0321	0.59
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.07	0.0424	0.0030	0.0305	0.62
Indirect N2O Emissions from Managed soils	0.01	0.5385	0.0028	0.0289	0.65
Manufacturing industries and construction - CO2 liquid fuels	0.06	0.0424	0.0027	0.0275	0.68
Manufacturing industries and construction - CO2 gaseous fuels	0.06	0.0424	0.0026	0.0271	0.70
Wastewater treatment and discharge - N2O	0.00	1.0198	0.0022	0.0226	0.73
Manure Management - CH4	0.01	0.2062	0.0021	0.0217	0.75
Manufacturing industries and construction - CO2 solid fuels	0.05	0.0424	0.0021	0.0216	0.77
Indirect CO2	0.00	0.5831	0.0016	0.0161	0.79
Energy industries - CO2 gaseous fuels	0.03	0.0424	0.0014	0.0142	0.80
Other sectors - CH4 commercial, residential, agriculture biomass	0.00	0.5009	0.0011	0.0111	0.81
Fugitive - CO2 Oil and natural gas - venting and flaring	0.00	0.5099	0.0009	0.0096	0.82
Manure Management - N2O	0.00	0.2062	0.0009	0.0094	0.83
Other sectors - N2O commercial, residential, agriculture liquid fuels	0.00	0.5009	0.0009	0.0088	0.84
Chemical industry- PFCs Fluorochemical production	0.00	0.5025	0.0008	0.0083	0.85
Manufacturing industries and construction - N2O liquid fuels	0.00	0.5009	0.0008	0.0082	0.86
Chemical industry- N2O Adipic acid production	0.01	0.1044	0.0008	0.0081	0.86
Transport - CH4 Road transportation	0.00	0.4011	0.0007	0.0077	0.87
Indirect N2O Emissions from Manure Management	0.00	0.5025	0.0007	0.0076	0.88
Metal industry- PFCs Aluminium production	0.00	0.2022	0.0007	0.0071	0.89
Fugitive - CO2 Oil and natural gas - Other - flaring in refineries	0.00	0.5099	0.0007	0.0069	0.89
Metal industry- CO2 Iron and steel production	0.01	0.1044	0.0006	0.0065	0.9003
Transport - N2O Road transportation	0.00	0.4011	0.0006	0.0059	0.91

Table A1.14 Results of the key category analysis with LULUCF. Approach 2 Level assessment, 1990

CATEGORIES	Share	Uncertainty	L*U	Level assessment with uncertainty	Cumulative Percentage
Forest Land remaining Forest Land - Living biomass - CO2	0.0252	0.3631	0.0091	0.0785	0.08
Fugitive - CH4 Oil and natural gas - Natural gas	0.0167	0.5009	0.0083	0.0718	0.15
Transport - CO2 Road transportation	0.1668	0.0424	0.0071	0.0609	0.21
Wastewater treatment and discharge - CH4	0.0065	1.0198	0.0066	0.0568	0.27
Enteric Fermentation- CH4	0.0310	0.2022	0.0063	0.0540	0.32
Energy industries - CO2 liquid fuels	0.1467	0.0424	0.0062	0.0535	0.38
Solid waste disposal - CH4	0.0247	0.2236	0.0055	0.0475	0.42
Direct N2O Emissions from Managed soils	0.0093	0.5385	0.0050	0.0431	0.47
Grassland Remaining Grassland - living biomass - CO2	0.0097	0.3631	0.0035	0.0303	0.50
Mineral industry- CO2 Cement production	0.0286	0.1044	0.0030	0.0257	0.52
Energy industries - CO2 solid fuels	0.0698	0.0424	0.0030	0.0255	0.55
Other sectors - CO2 commercial, residential, agriculture liquid fuels	0.0692	0.0424	0.0029	0.0252	0.57
Other sectors - CO2 commercial, residential, agriculture gaseous fuels	0.0657	0.0424	0.0028	0.0240	0.60
Indirect N2O Emissions from Managed soils	0.0049	0.5385	0.0026	0.0227	0.62
Manufacturing industries and construction - CO2 liquid fuels	0.0593	0.0424	0.0025	0.0216	0.64
Manufacturing industries and construction - CO2 gaseous fuels	0.0582	0.0424	0.0025	0.0212	0.66
Wastewater treatment and discharge - N2O	0.0020	1.0198	0.0021	0.0177	0.68
Manure Management - CH4	0.0096	0.2062	0.0020	0.0170	0.70
Manufacturing industries and construction - CO2 solid fuels	0.0465	0.0424	0.0020	0.0170	0.71
Forest Land remaining Forest Land - DOM (deadwood+litter) - CO2	0.0063	0.3073	0.0019	0.0166	0.73
Land Converted to Grassland - mineral soils- CO2	0.0020	0.9014	0.0018	0.0157	0.75
Land Converted to Forest Land -Living biomass - CO2	0.0046	0.3631	0.0017	0.0142	0.76
Indirect CO2	0.0025	0.5831	0.0015	0.0126	0.77
Land Converted to Settlements - CO2	0.0013	1.0607	0.0014	0.0122	0.79
Energy industries - CO2 gaseous fuels	0.0306	0.0424	0.0013	0.0112	0.80
Cropland Remaining Cropland - organic soils - CO2	0.0013	0.9220	0.0012	0.0102	0.81
Other sectors - CH4 commercial, residential, agriculture biomass	0.0020	0.5009	0.0010	0.0087	0.82
Fugitive - CO2 Oil and natural gas - venting and flaring	0.0017	0.5099	0.0009	0.0076	0.82
Manure Management - N2O	0.0042	0.2062	0.0009	0.0074	0.83
Other sectors - N2O commercial, residential, agriculture liquid fuels	0.0016	0.5009	0.0008	0.0069	0.84
Land Converted to Cropland -mineral soils CO2	0.0014	0.5617	0.0008	0.0065	0.84
Chemical industry- PFCs Fluorochemical production	0.0015	0.5025	0.0008	0.0065	0.85
Manufacturing industries and construction - N2O liquid fuels	0.0015	0.5009	0.0007	0.0064	0.86
Chemical industry- N2O Adipic acid production	0.0071	0.1044	0.0007	0.0063	0.86
Transport - CH4 Road transportation	0.0018	0.4011	0.0007	0.0060	0.87
Indirect N2O Emissions from Manure Management	0.0014	0.5025	0.0007	0.0059	0.87
Metal industry- PFCs Aluminium production	0.0032	0.2022	0.0006	0.0056	0.88
Fugitive - CO2 Oil and natural gas - Other - flaring in refineries	0.0012	0.5099	0.0006	0.0054	0.89
Metal industry- CO2 Iron and steel production	0.0056	0.1044	0.0006	0.0051	0.89
Transport - N2O Road transportation	0.0013	0.4011	0.0005	0.0046	0.8956
Grassland Remaining Grassland - CH4	0.0007	0.7159	0.0005	0.0043	0.8999
Mineral industry- CO2 Other processes uses of carbonates	0.0046	0.1044	0.0005	0.0041	0.904
Fugitive - CO2 Oil and natural gas - Oil	0.0043	0.1044	0.0005	0.0039	0.91

ANNEX 2: ENERGY CONSUMPTION FOR POWER GENERATION

A2.1 Source category description

The main source of data on fuel consumption for electricity production is the annual report "Statistical data on electricity in Italy - Production" ("Dati statistici sull'energia elettrica in Italia - Produzione"), edited from 1999 by the Italian Independent System Operator (TERNA, several years), a public company that runs the high voltage transmission grid. For the period 1990-1998 the same data was published by ENEL (ENEL, several years), former monopolist of electricity distribution. The time series has been available since 1963. In these publications, consumptions of all power plants are reported, either public or privately owned.

Detailed data are collected at plant level. They include electricity production and estimation of physical quantities of fuels and the related energy content. The Terna Statistical Office, a member of the National Statistical System, is legally responsible for preparing the official statistics of the electricity sector and for managing the survey in its various phases, starting from data acquisition, control and correction of inconsistent data, processing and final publication. As regards production, the report indicates hydroelectric, thermoelectric and renewable energy production, broken down by plant type and region. In Table A2.1 the time series of fuel consumptions for power sector production is reported.

Table A2.1 Time series of power sector production by fuel, Gg or Mm³

	1990	1995	2000	2005	2010	2015	2020	2022	2023	2024
national coal	58	-	Solids 9,633	Solids 16,253	Solids 14,998	Solids 16,245	Solids 5,274	Solids 8,936	Solids 5,128	Solids 1,533
imported coal	10,724	8,216								
lignite	1,501	380								
Natural gas, Mm ³	9,731	11,277	22,334	30,544	29,630	20,365	24,689	25,502	21,514	21,377
BOF (steel converter) gas, Mm ³	509	633	Coal Gases 8,690	Coal Gases 12,104	Coal Gases 8,822	Coal Gases 3,658	Coal Gases 2,527	Coal Gases 2,791	Coal Gases 1,719	Coal Gases 1,211
Blast furnace gas, Mm ³	6,804	6,428								
Coke gas, Mm ³	693	540								
Light distillate	5	6	Oil products 19,352	Oil products 7,941	Oil products 2,152	Oil products 1,133	Oil products 549	Oil products 945	Oil products 669	Oil products 415
Diesel oil	303	184								
Heavy fuel oil	21,798	25,355								
Refinery gas	211	378								
Petroleum coke	186	189								
Gases from chemical processes	444	803	Others	Others	Others	Others	Others	Others	Others	Others
Other fuels	344	697	5,153	Mm ³ = 978	Mm ³ = 1,501	Mm ³ = 3,509	Mm ³ = 3,478	Mm ³ = 3,337	Mm ³ = 3,166	Mm ³ = 3,167
				Gg= 15,460	Gg= 18,160	Gg= 16,257	Gg= 15,884	Gg= 17,324	Gg= 15,625	Gg= 15,940
Tar	2	-	-							
Heat recovered from Pyrite	146	3	-							

Source: TERNA, several years

Figures reported in the table show that natural gas has substituted oil products, from 1990 to 2024, becoming the main fuel for electricity production while coal consumption, decreased until 2020, seems

to show an upward trend in the last two years but it was only a temporary phase, since 2023 the phase-out process of coal has resumed normally.

For the purpose of calculating GHG emissions, a detailed list of 25 fuels was delivered to ISPRA by TERNA for the years from 2000 to 2007. From 2008 the list of the fuels used to estimate emissions was expanded by TERNA, up to 40 different types in 2012. The list includes different varieties of renewable sources according to their composition and origin, useful to estimate the percentage of renewable sources for electricity generation and to comply with national regulations of waste derived fuels. These figures include also the amount of fuels used to cogenerate heat and electricity in some power plants.

The detailed information is confidential and only the elaboration applied to calculate emissions at an aggregated level is reported in Table A2.2. The consumption of municipal solid waste (MSW) / industrial wastes is separated from the biomass consumption, and reported under other fuels, since the use of this fuel for electricity generation is expanding and emission factors are different.

Terna is responsible for compiling the IEA-EUROSTAT-UNECE questionnaire on electricity and heat that is transmitted by MASE, together with other questionnaires on other energy vectors, to EUROSTAT which produces the national energy balances for the member countries of the European Union. In the past, also the association of the industrial electricity producers (UNAPACE, several years) up to the year 1998, and ENI, the former national oil company up to the year 2000, published production data with the associated fuel consumptions (ENI, several years).

A2.2 Methodological issues

The inventory estimates are based directly on the data provided by Terna rather than on the energy balances produced by Eurostat based on the same data since they are available earlier and therefore allow compliance with deadlines. Furthermore, the questionnaire is more detailed and has more information than the Eurostat energy balances and, finally, Eurostat uses conversion factors (e.g. lower calorific values) standardized at European level while on the other hand, where possible, national values are reported. This last circumstance may be the basis of differences between the national data and the Eurostat data.

Table A2.2 shows all energy and emissions summarized by fuel and split into two main categories of producers: public services and industrial producers for the year 2024, according to the reporting in the CRT. Since 1998, expansion of industrial cogeneration of electricity and splitting of national monopoly has transformed many industrial producers into "independent producers", regularly supplying the national grid. So, part of the energy/emissions of the industrial producers are added to Table 1.A.1.a of the CRT, according to the best information available, including those available at plant level from the EU ETS scheme.

Table A2.2 Power sector, Energy/CO₂ emissions in CRT format, year 2024

	TJ	CO ₂ , Gg
Public Electricity and Heat Production - Table 1.A.1a		
Liquid fuels	8,475	660
Solid fuels	38,157	3,519
Natural gas	667,790	39,459
Refinery gases		
Coal gases		
Biomass	88,314	7,783
Other fuels (incl.waste)		
Total	802,736	43,638
Industrial producers and auto-producers - Tables 1.A.1b, 1.A.1c and 1.A.2		
Liquid fuels	22,138	1,680
Solid fuels	0	0
Natural gas	214,535	12,677
Refinery gases	26,102	1,464
Other refinery products	42,329	4,154

	TJ	CO ₂ , Gg
Coal gases	8,753	1,364
Biomass	104,033	9,168
Other fuels (incl.waste)	44,750	3,988
Total	462,640	25,326
General total	1,265,376	68,964

Source: ISPRA elaborations

Currently, a review process of the national energy balance is underway with Eurostat and involves the various interested parties (TERNA, GSE, MASE). In the previous submission, National Energy Balance experts implemented methodological changes for 2022 and subsequently applied these changes to 2021 to make it consistent. ISPRA is following this process closely to know the details and optimize the estimates. It will probably take a few years to also reconstruct the historical series of fuels according to the new definitions. In this submission shift of other oil products from energy to no-energy consumptions thanks to a discussion with Federchimica (national association of chemical industries) for the years from 2021 to 2024 and the introduction of data concerning hydrogen production, at the moment, only for 2024.

A2.3 Uncertainty and time-series consistency

The combined uncertainty in CO₂ emissions from electricity production is estimated to be about 4.2% in annual emissions; a higher uncertainty, equal to 50.1%, is calculated for CH₄ and N₂O emissions on account of the uncertainty levels attributed to the related emission factors.

In Table A2.3, the time series of the total CO₂ emissions from electricity generation activities is reported, including total electricity produced and specific indicators of CO₂ emissions for the total energy production and for the thermoelectric production respectively, expressed in grams of CO₂ per kWh. The emission factors are reported excluding the electricity produced from pumped storage units using water that has previously been pumped uphill, as requested by Directive 2009/28/EC of the European Parliament and of the Council promoting the electricity renewable sources.

The time series clearly shows that although the specific carbon content of the kWh generated in Italy has constantly improved over the years, total emissions have raised till 2006 due to the even bigger increase of electricity production. The decreasing trend starting from 2007 results from an increase in energy production from renewable sources, combined with a further reduction in the use of oil products for electricity production.

Table A2.3 Time series of CO₂ emissions from electricity production

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Total electricity produced (gross), TWh	216.6	241.5	276.6	303.7	302.1	283.0	280.5	289.1	284.0	264.7	271
Total CO ₂ emitted, Mt	126.4	133.4	139.7	144.7	121.7	94.5	73.5	77.9	86.7	67.5	56.4
g CO ₂ /kwh (gross thermo-electric production)	709	680	634	572	526	492	405	411	435	415	371
G CO ₂ /kwh of total gross production*	593	562	518	488	407	336	264	272	307	256	209

* excluding electricity production from pumped storage units using water that has previously been pumped uphill

Source: ISPRA elaborations

The trend of CO₂ emissions for thermoelectric production is the result of an increase of natural gas share due to the entry into service of more efficient combined cycle plants. The downward trend takes also into account the general increase in efficiency of the power plants.

A2.4 Source-specific QA/QC and verification

Basic activity data to estimate emissions from all operators are annually collected and reported by the national grid administrator (TERNA, several years). Other data are collected directly from operators for plants bigger than 20 MWt, with a yearly survey since 2005 and communicated at international level in the framework of the EU ETS scheme. Activity data and other parameters, as net calorific values, are compared every year at an aggregate level, by fuel; differences and problems have been identified, analysed in detail and solved with sectoral experts.

A2.5 Source-specific recalculations

Recalculations occurred in the last three years as a consequence of an ETS power plant that has become part of a refinery plant as a hydrogen production unit and has therefore been excluded from 1A1a.

A2.6 Source-specific planned improvements

As reported above, Italy, in agreement with Eurostat, is updating some methodologies relating to the national energy balance and therefore the plan for improving the estimates is strictly linked to the application of these methodologies.

ANNEX 3: ESTIMATION OF CARBON CONTENT OF COALS USED IN INDUSTRY

Care should be exercised to avoid double counting of carbon dioxide (CO₂) emissions in both IPPU and Energy Sector, or, in omitting CO₂ emissions since CO₂ emissions resulting from carbon's role as process reactant and as a heat source to drive the chemical reactions involved in the metallurgical processes are closely related in many cases. Any methodology considering CO₂ capture should consider that CO₂ emissions captured in the process may be both combustion and process related. In cases where combustion and process emissions are to be reported separately, e.g., for iron and steel production, inventory compilers should ensure that the same quantities of CO₂ are not double counted.

Iron and steel integrated production has only taken place in two sites in Italy since the year 2005, with integrated steel plants, coke ovens and electricity self-production and just in one site since 2015. Only pig iron has been produced also in one additional location up to 2020. This has allowed for careful check of the processes involved and the emissions estimates at site level and, with reference to other countries, may or may not have exacerbated the unbalances in carbon emissions due to the use of standard emission factor developed for other industrial sites.

In estimating emissions from this source category: coke production (Energy) and iron and steel production (IPPU), there is a risk of double counting or omission in either the Industrial Processes or the Energy Sector. According to the 2006 Guidelines, since the primary use of carbon sources (predominantly coke, but also coal, oil, natural gas, limestone, etc.) is to produce pig iron, the CO₂ and CH₄ emissions from iron and steel production including sinter production are considered industrial process emissions and should be reported as such. The CO₂ and CH₄ emissions from coke production (both fuel consumption and conversion losses) are categorized as energy production and should be reported as such. However, for integrated production and iron and steel with onsite coke production, there may be flows of by-products (e.g., coke oven gas, blast furnace gas, coke oven by-products) between the coke production facility and the iron and steel production facility, creating potential double counting issues. Carbon consumed in the form of coke oven gas at an iron and steelmaking facility and the resulting CO₂ and CH₄ emissions would be categorized as IPPU emissions and reported as such. Carbon consumed in the form of blast furnace gas at an onsite coke production facility and the resulting CO₂ and CH₄ emissions would be categorized as Energy emissions and should be reported as such. Tracking of such carbon flows will require good knowledge of the inventory in that source category. Because of the dominant role of coke, it is important to consider the existence of coke making at a facility and define the boundary limits of carbon balance at an iron and steelmaking facility to ensure that CO₂ emissions are not double counted. CO₂ and CH₄ emissions associated with onsite and offsite coke making are to be reported under the Energy Sector.

Consistent with the IPCC good practice guidance, Italy provides the energy and carbon balance in the iron and steel category. However, CO₂ emissions due to the consumption of coke, coal and other reducing agents used in the iron and steel industry have been accounted for as fuel consumption and reported under the energy sector when the IPCC good practice guidance shows a preference for including these emissions under the industrial processes sector rather than the energy sector.

But it is necessary to consider that carbon serves a dual purpose in the iron making process, primarily as a reducing agent to convert iron oxides to iron, but also as an energy source to provide heat when carbon and oxygen react exothermically.

The choice between several reducing agents is not determined by costs alone. Apart from being a reducing agent, coke also serves as a carrier of the bulk column in the blast furnace. Without this carrying capacity, blast furnace operation would not be possible (coke is highly porous).

The coke primarily serves as a reducing agent, but also as a fuel and it is not possible to distinguish between the two functions of the material.

A balance is made between the coal used for coke production and the quantities of derived fuels used in various sectors. The iron and steel sector gets the resulting quantities of energy and carbon after subtraction of what is used for electricity generation, non-energy purposes and other industrial sectors.

To avoid double counting a specific methodology has been developed: it balances energy and carbon content of coking coals used by steelworks, industry, for non-energy purposes and coal gasses used for electricity generation.

The balance is made between the coal used for coke production and the quantities of derived fuels used in various sectors. The iron and steel sector gets the resulting quantities of energy and carbon after subtraction of what is used for electricity generation, non-energy purposes and other industrial sectors. According to the 2006 IPCC Guidelines (IPCC, 2006), the use of reductants is also included in this balance because no sufficient information to detail emissions between the energy and industrial processes sectors is available. The carbon balance methodology does not imply separate off input between the energy and industrial sectors but ensures no double counting occurs.

Table A3.1 summarizes the quantities of coal and coal by-products used by the energy system in the year 2024; all the data mentioned are those provided by the Ministry of Environment to the Joint Questionnaire IEA/OECD/EUROSTAT for the same year.

In Table A3.1 the quantities of coke, coke gas and blast furnace gas used by the different sectors are detailed as well as the quantities of the same energy carriers that are self-used, used to produce coke or wasted. Inputs are indicated in the blue cells while outputs are reported in the orange ones.

Table A3.1 Energy balance, 2024, TJ

	TJ input	TJ output	
steam coal	48,537	199	clinker/industry
		40,637	thermoelectric power plants
		7,701	blast furnace
anthracite	4,275	4,275	steel plants
sub bituminous and lignite	15	15	clinker/industry
coking coal	47,532	0	coking coal consumption
		0	Non-energy use in other sectors
Coke import/export/stock change	-4,202		
coke		0	other industry and domestic
		0	ferroalloys
		0	blast furnace consumption
coke oven gas		9,157	coke oven gas in coke oven and blast furnace
		3,712	coke oven gas reheating
		3,531	coke oven gas thermoelectric
blast furnace gas		3,941	BF gas in coke oven
		0	BF gas thermoelectric
		4,812	BF gas reheating
BOF gas			coal gasses in thermoelectric + reheating
			carbon stored in products
tot	96,157	77,980	Input – output= 18,077 TJ → 23.3%

In Table A3.2, the same energy data of Table A3.1 evaluated for their carbon content are reported, according to the emission factors reported in Table 3.12 of the NIR.

The balance is the resulting quantity of emissions after subtraction of carbon emissions estimated for coke ovens, electricity production, other coal uses and non-energy uses.

The low implied emission factors in CRT and annual variations in the average CO₂ emission factor for solid fuel are due to the fact that both activity data and emissions reported under this category include the results of the carbon balance.

All main installations of the iron and steel sector are included in EU ETS, but not all sources of emission. Only part of the processes of integrated steel making is subject to EU ETS, in particular the manufacturing process after the production of row steel was excluded up to 2007 and only the lamination processes have been included from 2008 onwards. Additional information from the operators on fuel consumptions and average emission factors is used to verify our calculation and CO₂ emissions at plant level and to calculate average CO₂ emission factors for coal and derived gases from 2005; obviously from the 2015


submission emission factors have been updated on the basis of 2006 IPCC Guidelines, see Annex 6 for further details.

Table A3.2 Carbon balance, 2024, Gg CO₂

	input	output	
steam coal	4,476,406	18,360	clinker/industry
		3,747,797	thermoelectric power plants
		710,249	blast furnace
anthracite	431,792	431,792	steel plants
sub bituminous and lignite	1,553	1,553	clinker/industry
coking coal	4,443,779	0	coking coal consumption
		0	Non-energy use in other sectors
coke import/export/stock change	-442,476		
coke		0	other industry and domestic
		0	ferroalloys
		2,270,371	blast furnace consumption
coke oven gas		596,162	coke oven gas in coke oven and blast furnace
		158,391	coke oven gas reheating
		176,776	coke oven gas thermoelectric
blast furnace gas		0	BF gas in coke oven
		1,187,178	BF gas thermoelectric
		0	BF gas reheating
BOF gas		25	coal gasses in thermoelectric + reheating
		6,197	carbon stored in products
		79,330	Coal and tar export
tot	8,911,054	9,213,127	Input-output=-302 Gg CO₂ unbalance -3.28%

In 2024 the unbalance in terms of CO₂ is equal to -302 Gg; this amount has been subtracted from the total to avoid double counting of carbon. The flowchart of carbon - cycle for the year 2024 is reported below. CO₂ emissions from primary input fuels and from final fuel consumptions are compared. Emissions related to fuel input data are enhanced in light-blue whereas emissions estimated from final fuel consumptions are highlighted in orange. Emissions from the use of coke in blast furnaces result from differences between emissions from final consumption of coke and the value of the carbon balance for 2024. The amount of carbon stored in produced steel was estimated and subtracted from the balance to avoid the subsequent overestimation of CO₂. The amount of coke used for ferroalloys production has also been subtracted to avoid a double counting of emissions already estimated and reported in the industrial processes sector.

CO₂ emission calculation (Gg) Year 2024



ANNEX 4: CO₂ REFERENCE APPROACH

A4.1 Introduction

The IPCC Reference Approach is a 'top down' inventory based on data on production, imports, exports and stock changes of crude oils, feedstock, natural gas and solid fuels. Estimates are made of the carbon stored in manufactured products, the carbon consumed as international bunker fuels and the emissions from biomass combustion.

It is good practice to apply both a sectoral approach and the reference approach to estimate a country's CO₂ emissions from fuel combustion and to compare the results of these two independent estimates. Significant differences may indicate possible problems with the activity data, net calorific values, carbon content, excluded carbon calculation, etc. The Reference Approach is designed to calculate the emissions of CO₂ from fuel combustion, starting from high level energy supply data. The assumption is that carbon is conserved so that, for example, carbon in crude oil is equal to the total carbon content of all the derived products. The Reference Approach does not distinguish between different source categories within the energy sector and only estimates total CO₂ emissions from Source category 1A, Fuel Combustion. Emissions derive both from combustion in the energy sector, where the fuel is used as a heat source in refining or producing power, and from combustion in final consumption of the fuel or its secondary products.

For reference approach, as for the inventory, data submitted by the Ministry of Environment to the Joint Questionnaire IEA/OECD/EUROSTAT have been used for solid fuels, natural gas, liquid fuels and the update is ongoing for other fuels.

Starting from those data and using the emission factors reported in chapter 3, Table 3.12, it is possible to estimate the total carbon entering the national energy system.

The carbon stored in products is estimated according to the procedure illustrated in paragraph 3.9 and directly subtracted to the emission balance.

With reference to table 1.A(b) of the CRT, activity data are those indicated in Annex 5. The following data are reported and used for the *Reference Approach*:

1. all liquid fuels as available in the Joint Questionnaire IEA/ EUROSTAT/UNECE;
2. all coal data as available in the Joint Questionnaire IEA/ EUROSTAT/UNECE;
3. natural gas data as available in the Joint Questionnaire IEA/ EUROSTAT/UNECE;
4. waste production data;
5. biomass fuel data as available in the Joint Questionnaire IEA/ EUROSTAT/UNECE.

The following additional information is needed to complete table 1.A(b) of CRT and it is found in other sources:

- 1) Orimulsion, this fuel is mixed up with imported fuel oil (on the base of the energy content), the quantities used for electricity generation are reported by ENEL (ENEL, several years), the former electricity monopoly, presently the only user of this fuel, in their environmental report. This fuel is not used any more since 2004.
- 2) No energy products from refineries. Data on those materials are mixed up in the no energy use by the joint questionnaire, while detailed data are available in BPT (MASE, several years). The quantities of those materials are quite relevant for the no energy use of oil.

A4.2 Comparison of the sectoral approach with the reference approach

The detailed inventory contains sources not accounted for in the IPCC Reference Approach, as offshore flaring and well testing and non-fuel industrial processes and so gives a higher estimate of CO₂ emissions from 1A categories.

First of all, the IPCC Reference total CO₂ can be compared with the CRT Table 1A total. Results show the IPCC Reference totals are between –0.83 and –4.83 percent with respect to the comparable ‘bottom up’ totals and against last year’s range (between –1.30 and –5.40) demonstrating that the ongoing work on the energy balance is bringing good results also in this comparison. Italy believes that, by continuing this work, it will return well within the acceptable range (<-3%) in the coming years.

Differences are observed both for energy and emissions. Quality control activities have been done and a detailed explanation of them will require specific meetings and additional verification activities with the energy experts responsible for the official communication of the energy statistics to make the transition to the new data format for the whole time series.

As above mentioned, sectoral approach considers sources not considered in the Reference approach, so negative differences occur between CO₂ emissions from reference approach and the sectoral one. The highest difference is observed for 1999.

Differences between emissions estimated by the reference and sectoral approach are reported in Table A4.1.

Table A4.1 Reference and sectoral approach CO₂ emission estimates 1990-2024 (Mt) and percentage differences

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Sectoral approach	405.1	417.5	440.8	470.4	410.8	342.2	285.1	317.1	321.6	294.4	284.1
Reference approach	396.4	407.1	423.0	457.5	399.6	330.1	282.7	303.7	308.5	284.4	271.8
Δ %	-2.16	-2.50	-4.04	-2.73	-2.72	-3.53	-0.83	-4.23	-4.07	-3.37	-4.30

There are a number of reasons why the totals differ, and these arise from differences in the methodologies and the statistics used.

Explanations for the discrepancies:

1. The IPCC Reference Approach is based on statistics of production, imports, exports and stock changes of fuels whilst the ‘bottom-up’ approach uses fuel consumption data. The two sets of statistics can be related using mass balances (MASE, several years), but these show that some fuel is unaccounted for. This fuel is reported under ‘statistical differences’ which consist of measurement errors and losses. A significant proportion of the discrepancy between the IPCC Reference approach and the ‘bottom up’ approach arises from these statistical differences particularly with liquid fuels.
2. In the power sector, in the detailed approach, statistics from producers are used, whereas for the reference approach the IEA/EUROSTAT/UNECE questionnaires data are used. The two data sets are not connected; in the questionnaires sections used, only the row data of imports-exports are contained.
3. The ‘bottom up’ approach only includes emissions from the no energy use of fuel where they can be specifically identified and estimated such as with fertilizer production and iron and steel production. The IPCC Reference approach implicitly treats the non-energy use of fuel as if it were combustion. A correction is then applied by deducting an estimate of carbon stored from non-energy fuel use. The result is that the IPCC Reference approach is based on a higher estimate of non-energy use emissions than the ‘bottom-up’ approach.
4. The IPCC Reference Approach uses data on primary fuels such as crude oil and natural gas liquids which are then corrected for imports, exports and stock changes of secondary fuels. Thus, the estimates obtained will be highly dependent on the default carbon contents used for the primary fuels.
5. Finally, the revision and update of Energy Balance data in the last year, as already mentioned in the NID, led to large statistical differences in liquid fuels. In the previous submission (2025), the exercise was carried out to consider the comparison between the reference and sectoral approaches also considering the statistical differences reported in the energy balance for liquids. If statistical differences

would be added to apparent consumptions difference between Reference and Sectoral approach are reduced. As statistical differences represent the difference between apparent consumptions (only based on production, import, export and stock change) and the observed amount, consequently differences between reference and sectoral approach are high in 2022 and 2023. Statistical differences for liquid fuels in 2022 and 2023 are particularly high (in 2023 the total liquid statistical difference is equal to 110,000 TJ and 184,000 TJ in 2022). These differences are officially reported in the Eurostat Energy Balance. This issue of high statistical differences is under discussion between our national energy balance experts and Eurostat and other international bodies.

A4.3 Comparison of the sectoral approach with the reference approach and international statistics

A verification of national energy balance and CO₂ emissions with data communicated to the joint EUROSTAT/IEA/UNECE questionnaire was carried out in 2004 and results are reported in the document "Energy data harmonization for CO₂ emission calculations: the Italian case" (ENEA/MAP/APAT, 2004).

From 2004 some improvements were implemented both in the national and international statistics also through the revision of the questionnaire but differences in apparent consumptions still occur.

Comparing the apparent consumption reported in GHG inventory in 1A(b) with the apparent consumption using data reported pursuant to Regulation (EC) No 1099/2008 (EUROSTAT data) differences are low since the inventory now uses almost entirely the data from the JOINT Questionnaires IEA/OECD/EUROSTAT which were then used in turn to produce the Eurostat energy balance sheet. The differences are -0.1% for liquid fuels, 0% for solids and gases, -3.0% for waste resulting in a overall difference equal to -0.1%.

ANNEX 5: NATIONAL ENERGY BALANCE, YEAR 2024

Currently, a review process of the national energy balance is underway with Eurostat and involves the various interested parties (TERNA, GSE, MASE) in Italy.

In 2024-2025 submission, some recalculations occurred as reported in the previous NIDs. In a first step, the National Energy Balance experts implemented methodological changes for 2022 and subsequently applied these changes to 2021 to make it consistent. ISPRA is following this process closely to know the details and optimize the estimates. This change in methodology has caused a break in the series for some fuels and it is necessary further work to improve the time series consistency, and it will probably take a few years to also reconstruct the historical series of fuels according to the new definitions. In this submission shift of other oil products from energy to no-energy consumptions thanks to a discussion with Federchimica (national association of chemical industries) for the years since 2021 to 2024 and the introduction of data concerning hydrogen production, at the moment, only for 2024.

The official national energy balance (BEN) from the year 1998 to 2020 is available, in Italian, on the website of the Italian Ministry of the Environment (MASE, several years): <https://sisen.mase.gov.it/dgsaie/bilancio-energetico-nazionale>. At the same web address data communicated by Italy to the Joint Questionnaire OECD/IEA/EUROSTAT are available in the format revisited by EUROSTAT. Some differences between data communicated to the international organizations and EUROSTAT publication have been observed and are under investigation; they should mainly due to the use of default instead of country specific energy conversion factors and different classification criteria of fuels.

The energy balances of the entire times series are reported on the Eurostat website: [\[nrg_bal_c\] Complete energy balances](#)

From 2016, data submitted by the Ministry of Environment to the Joint Questionnaire IEA/OECD/EUROSTAT have been used for solid, liquid and gaseous fuel consumptions (EUROSTAT, 2026). The entire time series was not reconstructed and data from national energy balance (BEN) have been also used for the inventory. In fact, some inconsistencies were found in data communicated to Eurostat and referring to the ninety years, especially in the sectoral distribution of fuels; in these cases, the information already available in the national energy balances has been maintained because considered more reliable and consistent in the time series.

ANNEX 6: NATIONAL EMISSION FACTORS

Monitoring the carbon content of the fuels used nationally is an ongoing activity at ISPRA. The purpose is to analyse regularly the chemical composition of the used fuel or relevant commercial statistics to estimate the carbon content / emission factor (EF) of the fuels. For each primary fuel (natural gas, oil, coal) a specific procedure has been established.

Starting from 2021 submission the updated atomic weights of Carbon and Oxygen (NIST Chemistry WebBook, SRD 69 - National Institute of Standard and Technology, USA) have been used since 2005 (National Institute of Standard and Technology, USA) to convert carbon content to CO₂ content and viceversa.

A6.1 Natural gas

The national market is characterized by the commercialization of gases with different chemical composition in variable quantities from one year to the other. Since 1990 natural gas has been produced in Italy and imported by pipelines from Russia, Algeria and the Netherlands. Moreover, an NGL facility is importing gas from Algeria and Libya. From 2003-2004 onwards Norway and Libya have also been added to the supply list, through new pipeline connections, and from 2008 a new NGL facility has entered service, using mainly liquefied gas from Oman. There are also sizeable underground storage facilities and additional pipelines/NGL facilities are planned.

The estimation of an average EF for natural gas is the only way to calculate total emissions from this source in Italy, because the origin of the gas used by final consumers cannot be tracked through the national statistics and it is subject to variations during the year, according to supply. Only the main industrial installations perform routine checks to estimate the average chemical composition / energy content of natural gas used.

Another task connected to the use of natural gases of different origins and composition is linked to the estimation of an average content of methane to estimate fugitive emissions of this gas from the transmission / distribution network. Since the beginning of the inventory estimations, the average EF of the used gas in Italy has been estimated by the inventory team and it changes every year.

From 2008 in the energy balance, BEN 2008, (MASE, several years [a]) some modifications have occurred; a new average lower heat value has been derived from Eurostat methodology. This new conversion factor did imply a methodological revision to estimate the average national EF. Additionally, the IPCC 2006 guidelines, see table A6.1, contain important information to consider: the recognition of a certain variability of the EF for this source; the estimation of a lower and upper bound for the EFs; the link between energy content and EF; the statement that, by converting to energy units all EFs, their variability can be reduced. Moreover, default oxidation factor is estimated to be equal to 1 (full oxidation) (IPCC, 2006).

The natural gases transmitted by the grid operator are regularly analyzed at import gates, for budgetary reasons. Energy content for cubic meters, percentage of methane and other substances are calculated. For example, methane content can change considerably: national produced gas sold to the grid is almost 99% methane (% moles), the one coming from Algeria has less than 85% of methane and significant quantities of propane-butane. Also, carbon content changes significantly.

Natural gas properties are more stable referring to the country of origin, with small variations in chemical composition from year to year. Speciation of gas from each import manifold is regularly published by national transmission grid operator (Snam Rete Gas, several years). Other information is also available from the main final users (TERNA, several years).

So, for each year, the average methane and carbon content of the natural gas used in Italy are estimated, using international trade statistical data, and a national emission factor is estimated.

The list of factors for the years of interest is reported in Table A6.1.

As shown in the table, the ranges of national EFs are within the lower and upper threshold of the IPCC 2006 guidelines.

With regard the oxidation factors, increasing values have been used from 0.995 in 1990 to 1.000 in 2005 according to the improvement of combustion efficiency in the nineties.

Table A6.1 Natural gas carbon emission factors

	t CO ₂ / TJ (stechiometric)	t CO ₂ / TJ	t CO ₂ / 10 ³ std cubic mt	t CO ₂ / toe
Natural gas (dry) IPCC '96	55.820	55.820	1.928	2.337
Natural gas, IPCC '06 average	56.100	56.100	1.932	2.349
lower	54.300			
upper	58.300			
National Emission Factors				
Natural gas, 1990	56.103	55.822	1.935	2.337
Natural gas, 1995	56.236	55.955	1.947	2.343
Natural gas, 2000	56.415	56.258	1.955	2.355
Natural gas, 2001	56.337	56.212	1.946	2.353
Natural gas, 2002	56.914	56.819	1.985	2.379
Natural gas, 2003	56.483	56.420	1.974	2.362
Natural gas, 2004	56.450	56.418	1.973	2.362
Natural gas, 2005	56.475	56.475	1.978	2.365
Natural gas, 2006	56.553	56.553	1.979	2.368
Natural gas, 2007	56.444	56.444	1.976	2.363
Natural gas, 2008, with 8190 lhv	57.732	57.732	1.980	2.417
Natural gas, 2009, with 8190 lhv	57.914	57.914	1.986	2.425
Natural gas, 2010, with 8190 lhv	57.945	57.945	1.987	2.426
Natural gas, 2011, with 8190 lhv	57.427	57.427	1.969	2.404
Natural gas, 2012, with 8190 lhv	57.702	57.702	1.979	2.416
Natural gas, 2013, with 8190 lhv	57.447	57.447	1.970	2.405
Natural gas, 2014, with 8190 lhv	57.473	57.473	1.971	2.406
Natural gas, 2015, with 8190 lhv	57.633	57.633	1.976	2.413
Natural gas, 2016, with 8190 lhv	58.140	58.140	1.994	2.434
Natural gas, 2017, with 8190 lhv	58.000	58.000	1.989	2.428
Natural gas, 2018, with 8190 lhv	57.846	57.846	1.984	2.422
Natural gas, 2019, with 8190 lhv	57.746	57.746	1.980	2.418
Natural gas, 2020, with 8190 lhv	57.910	57.910	1.986	2.425
Natural gas, 2021, with 8190 lhv	58.504	58.504	2.006	2.449
Natural gas, 2022, with 8190 lhv	58.918	58.918	2.020	2.467
Natural gas, 2023, with 8190 lhv	59.205	59.205	2.030	2.479
Natural gas, 2024, with 8190 lhv	59.089	59.089	2.026	2.474

Source: ISPRA elaborations

The methodology used to estimate the EF is based on the available data. Each year the quantities of natural gas imported or produced in Italy are published on the web by the MASE <https://sisen.mase.gov.it/dgsaie/bilancio-gas-naturale>. Those data are produced by the national grid operator and are concerned on all imported gas by point of entrance in the country and all natural gas produced. To compare quantities of different gases, the physical quantities of imported/produced gas are normalized to a higher heat value (hhv) equal to 9100 kcal/m³ and standard conditions. Other data input used in the estimation are the average chemical composition and the hhv of the gas at each import "gate" and for the national production. Those data are published by Snam in its yearly "Bilancio di Sostenibilità" (Snam Rete Gas, several years) and with them it is possible to estimate the average carbon content of the fuel. Those data refer to the physical quantities of imported / produced gas.

So, the total quantities of imported gas (normalized at the hhv of 9100) published by MASE are transformed back to the physical quantities of actually imported gas using the hhv ratio and then average carbon content of the total gas imported or produced in Italy can be estimated. Data are then referred to the normalized quantities of gas used in national statistics.

Data on final consumption of gas refers to the lower heat value (lhv). In particular, the electricity production companies regularly estimate the actual lhv of the gas they are using and this figure is published yearly by TERNA. Operator's data are used to verify the calculation results.

As mentioned above, in BEN 2008 the average lhv has been changed from 8250 kcal/m³ (historical value) to 8190 kcal/m³, to harmonize national data with Eurostat methodology. Eurostat considers the lhv as being 10% less than hhv, regardless of the actual value. This change influences the EF if it is referred to the energy content (lhv) of the fuel, but it has no influence if the EF is referred to cubic meters.

A6.2 Diesel oil, petrol and LPG

ISPRA set periodical investigations on the carbon content of the main transportation fuels sold in Italy, petrol, diesel and LPG, with the aim of testing the average fuels. The goal of this work is the verification of CO₂ emission factors of Italian energy system, with a particular focus on the transportation sector. The results of analysis of fuel samples performed by "Stazione Sperimentale Combustibili" (APAT, 2003; Innovhub, several years) were compared with emission factors used in Reference Approach of the Intergovernmental Panel for Climate Change (IPCC, 1997; IPCC, 2006). These two methodologies are widely used to prepare data at the international level but, when applied to the Italian data set produce results with significant differences, around 2- 4%. The reason has been traced back to the emission factors that are referred to the energy content of the fuel for IPCC.

The results of the study link the chemical composition to the lhv for a series of fuels representative of the national production, allowing for more precise evaluations of the emission factors.

IPCC 1996 emission factors for diesel fuels and IPCC-Europe for LPG are almost identical to the experimental results (less than 1% difference), and it has been decided to use IPCC emission factors for the period 1990-1999 and the measured EF from the year 2000 onwards. The figures from the last surveys have been used for the years 2017-2020.

Concerning petrol, instead, IPCC 1996 emission factor is quite low, and it must be updated, the reason may be linked to the extensive use of additives in recent years to reach a high octane number after the lead has been phased out. For 2000 and the following years the experimental factor are used, for the period 1990-1999 it has been decided to use an interpolate factor between IPCC emission factors and the measured value, using the lhv as the link between the national products and the international database.

The list of emission factors used is reported in Table A6.2.

Table A6.2 Fuels, national production, carbon emission factors

	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Petrol, IPCC / OECD	68.559	3.071	2.870
Petrol, IPCC Europe	72.270	3.148	3.026
Petrol (Italian National Energy Balance), interpolated emission factor 1990-1999	71.034	3.123	2.974
Petrol, experimental averages 2000-2011	71.864	3.143	3.009
Petrol, experimental averages 2012-2016	73.338	3.140	3.071
Petrol, experimental averages 2017-2020	73.081	3.152	3.060
Gas oil, IPCC / OECD	73.274	3.175	3.068
Gas oil, IPCC Europe	73.260	3.108	3.067
Gas oil, 1990 – 1999	73.274	3.129	3.068
Gas oil, engines, experimental averages 2000-2011	73.892	3.171	3.094
Gas oil, engines, experimental averages 2012-2016	73.648	3.151	3.084
Gas oil, engines, experimental averages 2017-2020	73.510	3.150	3.078
Gas oil, heating, experimental averages 2000-2011	74.438	3.175	3.117
Gas oil, heating, experimental averages 2012-2016	73.578	3.155	3.081
Gas oil, heating, experimental averages 2017-2020	73.927	3.169	3.095
LPG, IPCC / OECD	62.392	2.952	2.612
LPG, IPCC / Europe	64.350	3.000	2.694
LPG, 1990 – 1999	62.392	2.873	2.612
LPG, experimental averages 2000-2016	65.592	3.026	2.746
LPG, experimental averages 2017-2020	65.984	3.026	2.763
Biodiesel, experimental averages 2017-2020	74.938	2.803	3.137

Source: ISPRA elaborations

A6.3 Fuel oil

The main information available nationally of fuel oil EF is a sizable difference in carbon content between high sulphur and light sulphur brands. The data were elaborated from literature and from an extensive series of samples (more than 400) analysed by ENEL and made available to ISPRA. Carbon content varies to a certain extent also between the medium sulphur content and the very low sulphur products, but the main discrepancies refer to the high sulphur type. According to the available statistical data, it was possible to trace back to the year 1990 the produced and imported quantities of fuel oil divided between high and low sulphur products and to estimate the average carbon emission factor for the years of interest, see Table A6.3 for details.

Table A6.3 Fuel oil, average of national and imported products, carbon emission factors

	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Fuel oil , IPCC, 1996	77.400	76.626	3.154	3.208
Fuel oil , IPCC, 2006 average	77.400	77.400	3.127	3.241
lower	75.500			
upper	78.800			
National emission factors				
Fuel oil, average 1990	77.339	76.565	3.113	3.206
Fuel oil, average 1995	77.425	76.650	3.129	3.209
Fuel oil, average 2000	76.665	76.239	3.140	3.192
Fuel oil, average 2001	76.655	76.315	3.141	3.195
Fuel oil, average 2002	76.709	76.454	3.148	3.201
Fuel oil, average 2003	76.921	76.750	3.158	3.213
Fuel oil, average 2004	76.939	76.853	3.162	3.218
Fuel oil, average 2005	75.877	75.877	3.144	3.177
Fuel oil, average 2006	75.955	75.955	3.144	3.180
Fuel oil, average 2007	76.328	76.328	3.147	3.196
Fuel oil, average 2008	76.682	76.682	3.145	3.211
Fuel oil, average 2009	76.635	76.635	3.145	3.209
Fuel oil, average 2010	76.865	76.865	3.145	3.218
Fuel oil, average 2011	77.063	77.063	3.147	3.226
Fuel oil, average 2012	76.507	76.507	3.145	3.203
Fuel oil, average 2013	76.695	76.695	3.145	3.211
Fuel oil, average 2014	76.698	76.698	3.145	3.211
Fuel oil, average 2015	76.606	76.606	3.144	3.207
Fuel oil, average 2016	76.606	76.606	3.144	3.207
Fuel oil, average 2017	76.690	76.690	3.144	3.211
Fuel oil, average 2018	76.692	76.692	3.144	3.211
Fuel oil, average 2019	76.594	76.594	3.143	3.207
Fuel oil, average 2020	76.497	76.497	3.143	3.203
Fuel oil, average 2021	76.501	76.501	3.143	3.203
Fuel oil, average 2022	76.609	76.609	3.144	3.207
Fuel oil, average 2023	76.427	76.427	3.136	3.200
Fuel oil, average 2024	76.475	76.475	3.143	3.202

Source: ISPRA elaborations

Data for all years are within IPCC 2006 ranges, but it can be noticed that they are on the lower side from year 2000 onwards. The change from an average to a low EF is due to the harmful emissions limits and fuel regulations introduced in Italy between 1990 and 2000. Most of the fuel used from 2000 onwards is not heavy, high sulphur, fuel oil but light type, low sulphur. With regard the oxidation factors, increasing values have been used from 0.99 in 1990 to 1.00 in 2005 according to the improvement of combustion efficiency in the nineties.

A6.4 Coal

Italy has only negligible national production of coal; most part is imported from various countries and there are differences in carbon content of coal mined in different parts of the world. The variations in carbon content can be linked to the hydrogen content and to the LHV of the coal.

An additional national circumstance refers to the absence of long-term import contracts. The quantities shipped by the main exporters change considerably from year to year. Detailed data are available in BPT (MASE, several years [b]) supplied by the Ministry of Environment and reported for the submission year in Table A6.4.

Table A6.4 – Coal imported by country in 2024 (Mg)

Country	Coaking coal	Coke	Anthracite	Steam coal	Total Coal	Petroleum coke
BELGIUM			7,711		7,711	
CZECHIA		8,622			8,622	
GERMANY			110		110	
ITALY		5,310			5,310	
HUNGARY		6,765			6,765	
POLAND	4,747	644			5,391	
SLOVENIA					0	48
SPAIN					0	28,314
TOTAL EU	4,747	21,341	7,821	0	33,909	28,362
AUSTRALIA	157,138			260,664	417,802	
BOSNIA-ERZEGOVINA		1,398			1,398	
CHINA			14,885		14,885	
COLOMBIA				359,912	359,912	
INDIA			2,721		2,721	
INDONESIA		50,994		380,650	431,643	
KAZAKISTAN				294,827	294,827	
KIRGHIZISTAN			7,202		7,202	
SOUTH AFRICA			27,110	358,560	385,670	
TAGIKISTAN				8,563	8,563	
U.S.A.	1,447,373	34,684			1,482,057	784,649
UCRAINA	122,220				122,220	
VENEZUELA				59,038	59,038	
TOTAL NON EU	1,726,731	87,075	51,918	1,722,215	3,587,939	784,649
TOTAL	1,731,478	108,416	59,739	1,722,215	3,621,848	813,011

Source: MASE, several years [b]

Therefore, an attempt was made to find out a methodology allowing for a more precise estimation of the carbon content of this fuel. It is possible, using literature data for the coals and detailed statistical records of international trade, to find out the weighted average of carbon content and of the LHV of the fuel imported to Italy each year. The still unresolved problem is how to properly link statistical data, referred to the coal "as it is" without specifying moisture and ash content of the product, to the literature data, referring to sample coals.

The intention is to improve the quality of the collected statistical data including moisture content of coals; currently this obstacle has been overcome with the following procedure:

- using an ample set of experimental data on coals imported in a couple of years on an extensive series of samples, more than 200, analysed by ENEL (the main electricity producing company in Italy) it was possible to correlate "as it is" LHV and carbon content to the average properties of the coals imported in the same period of time and calculated from literature data (EMEP/CORINAIR, 2007);
- for each inventory year, it was possible to calculate the weighted average of LHV and carbon content of imported coals using available literature data;
- using this calculated data and the correlation found out, the estimate of carbon content of the average "as it is" coal reported in the statistics was possible.

Using this methodology and the available statistical data, it was possible to trace back to the year 1990 the average LHV of the imported coal and estimate average carbon EF for each year, see Table A6.4 for detailed data. The results do not show impressive changes yearly; anyway, a noticeable difference in the emission factor is highlighted in the table. In Table A6.5 updated coal EFs are reported. National emission factors result in the range given by the lower and upper values for "other bituminous coal" in the IPCC 2006 Guidelines (IPCC, 2006).

With the aim of improving the estimation of the coal CO₂ emission factors an in-depth analysis of data reported in the framework of the European emissions trading scheme has been carried out. In consideration that these data referring to emission factors and activity data are validated and the amount

of fuel reported accounts for more than 90% of the national coal fuel consumption, the average coal CO₂ emission factors, resulting from ETS data, have been applied from 2005.

With regard the oxidation factors, increasing values have been used from 0.98 in 1990 to 1.00 in 2005 according to the improvement of combustion efficiency in the nineties.

Table A6.5 – Coal, average carbon emission factors

	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Other bituminous coal, IPCC 1996	94.600	92.708	2.427	3.881
Other Bituminous coal, IPCC 2006, av	94.600	94.600	2.441	3.961
lower	89.500			
upper	99.700			
National emission factors				
Steam coal, 1990	96.512	94.582	2.502	3.960
Steam coal, 1995	95.926	94.007	2.519	3.936
Steam coal, 2000	93.312	92.276	2.427	3.863
Steam coal, 2001	95.304	94.457	2.463	3.955
Steam coal, 2002	94.727	94.096	2.457	3.940
Steam coal, 2003	95.385	94.961	2.476	3.976
Steam coal, 2004	95.382	95.170	2.476	3.985
Steam coal, 2005	94.305	94.305	2.399	3.948
Steam coal, 2006	93.741	93.741	2.346	3.925
Steam coal, 2007	94.078	94.078	2.324	3.939
Steam coal, 2008	93.451	93.451	2.287	3.913
Steam coal, 2009	93.847	93.847	2.325	3.929
Steam coal, 2010	93.697	93.697	2.317	3.923
Steam coal, 2011	93.365	93.365	2.318	3.909
Steam coal, 2012	93.667	93.667	2.346	3.922
Steam coal, 2013	93.645	93.645	2.331	3.921
Steam coal, 2014	94.029	94.029	2.339	3.937
Steam coal, 2015	94.619	94.619	2.335	3.962
Steam coal, 2016	95.092	95.092	2.350	3.981
Steam coal, 2017	93.886	93.886	2.361	3.931
Steam coal, 2018	94.340	94.340	2.345	3.950
Steam coal, 2019	95.278	95.278	2.375	3.989
Steam coal, 2020	94.013	94.013	2.356	3.936
Steam coal, 2021	93.078	93.078	2.334	3.897
Steam coal, 2022	93.233	93.233	2.310	3.903
Steam coal, 2023	93.395	93.395	2.302	3.910
Steam coal, 2024	92.227	92.227	2.318	3.861

Source: ISPRA elaborations

A6.5 Other fuels

Country specific emission factors have been calculated for other fuels and included in the inventory on account of the analysis of data reported by plants in the framework of the European emissions trading scheme. In consideration that these data referring to emission factors and activity data are validated and the amount of fuels reported accounts for more than 90% of the national consumption, the average CO₂ emission factors have been applied since 2005.

In the following, values of CO₂ emission factors are specified for the different fuels. From 2005, figures result from a weighted average of ETS data; before that period, emission factors derive from literature data or other national data collection.

Oxidation factors have been considered equal to 1 for all the fuels (IPCC, 2006) with exception of residual gases of chemical processes where the oxidation factors resulting from ETS data have been used.

Table A6.6 – Refinery gas, average carbon emission factors

<i>Refinery gas</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Refinery gas, 1990-2004	57.600	57.600	2.851	2.412
Refinery gas, 2005	58.320	58.320	2.756	2.442
Refinery gas, 2006	57.369	57.369	2.644	2.402
Refinery gas, 2007	57.110	57.110	2.645	2.391
Refinery gas, 2008	58.137	58.137	2.686	2.434
Refinery gas, 2009	57.477	57.477	2.673	2.406
Refinery gas, 2010	56.750	56.750	2.652	2.376
Refinery gas, 2011	57.291	57.291	2.689	2.399
Refinery gas, 2012	57.269	57.269	2.701	2.398
Refinery gas, 2013	57.447	57.447	2.649	2.405
Refinery gas, 2014	57.095	57.095	2.634	2.390
Refinery gas, 2015	56.865	56.865	2.653	2.381
Refinery gas, 2016	58.210	58.210	2.652	2.437
Refinery gas, 2017	58.110	58.110	2.644	2.433
Refinery gas, 2018	58.307	58.307	2.657	2.441
Refinery gas, 2019	56.465	56.465	2.660	2.364
Refinery gas, 2020	56.146	56.146	2.639	2.351
Refinery gas, 2021	56.014	56.014	2.649	2.345
Refinery gas, 2022	56.531	56.531	2.665	2.367
Refinery gas, 2023	56.497	56.497	2.666	2.365
Refinery gas, 2024	56.070	56.070	2.651	2.348

Source: ISPRA elaborations

Table A6.7 – Coke oven gas, average carbon emission factors

<i>Coke oven gas</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / 10 ³ std cubic mt	t CO ₂ / toe
Coke oven gas, 1990-2004	42.111	42.111	0.807	1.763
Coke oven gas, 2005	42.128	42.128	0.754	1.764
Coke oven gas, 2006	42.678	42.678	0.743	1.787
Coke oven gas, 2007	42.416	42.416	0.714	1.776
Coke oven gas, 2008	42.250	42.250	0.733	1.769
Coke oven gas, 2009	42.980	42.980	0.748	1.799
Coke oven gas, 2010	42.816	42.816	0.735	1.793
Coke oven gas, 2011	43.328	43.328	0.746	1.814
Coke oven gas, 2012	44.046	44.046	0.773	1.844
Coke oven gas, 2013	42.861	42.861	0.760	1.794
Coke oven gas, 2014	43.767	43.767	0.775	1.832
Coke oven gas, 2015	43.314	43.314	0.751	1.813
Coke oven gas, 2016	43.700	43.700	0.758	1.830
Coke oven gas, 2017	43.877	43.877	0.758	1.837
Coke oven gas, 2018	44.008	44.008	0.763	1.843
Coke oven gas, 2019	44.820	44.820	0.792	1.877
Coke oven gas, 2020	45.854	45.854	0.844	1.920
Coke oven gas, 2021	45.490	45.490	0.830	1.905
Coke oven gas, 2022	44.925	44.925	0.805	1.881
Coke oven gas, 2023	44.857	44.857	0.756	1.878
Coke oven gas, 2024	44.857	44.857	0.748	1.878

Source: ISPRA elaborations

Table A6.8 – Blast furnace gas, average carbon emission factors

<i>Blast furnace gas</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / 10 ³ std cubic mt	t CO ₂ / toe
Blast furnace gas, 1990-2004	270.575	270.575	0.954	11.328
Blast furnace gas, 2005	263.653	263.653	0.870	11.039
Blast furnace gas, 2006	255.948	255.948	0.849	10.716
Blast furnace gas, 2007	261.469	261.469	0.835	10.947
Blast furnace gas, 2008	256.133	256.133	0.838	10.724

<i>Blast furnace gas</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / 10 ³ std cubic mt	t CO ₂ / toe
Blast furnace gas, 2009	259.560	259.560	0.834	10.867
Blast furnace gas, 2010	257.390	257.390	0.863	10.776
Blast furnace gas, 2011	255.351	255.351	0.877	10.691
Blast furnace gas, 2012	252.808	252.808	0.885	10.585
Blast furnace gas, 2013	251.428	251.428	0.929	10.527
Blast furnace gas, 2014	245.964	245.964	0.958	10.298
Blast furnace gas, 2015	250.072	250.072	0.931	10.470
Blast furnace gas, 2016	247.893	247.893	0.952	10.379
Blast furnace gas, 2017	249.927	249.927	0.877	10.464
Blast furnace gas, 2018	250.282	250.282	0.862	10.479
Blast furnace gas, 2019	249.335	249.335	0.877	10.439
Blast furnace gas, 2020	251.043	251.043	0.883	10.511
Blast furnace gas, 2021	247.920	247.920	0.918	10.380
Blast furnace gas, 2022	250.750	250.750	0.911	10.498
Blast furnace gas, 2023	254.347	254.347	0.897	10.649
Blast furnace gas, 2024	246.717	246.717	0.908	10.330

Source: ISPRA elaborations

Table A6.9 – Oxygen furnace gas, average carbon emission factors

<i>Oxygen furnace gas</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / 10 ³ std cubic mt	t CO ₂ / toe
Oxygen furnace gas, 1990-2004	195.086	195.086	1.504	8.168
Oxygen furnace gas, 2005	197.579	197.579	1.437	8.272
Oxygen furnace gas, 2006	202.372	202.372	1.390	8.473
Oxygen furnace gas, 2007	195.871	195.871	1.320	8.201
Oxygen furnace gas, 2008	196.465	196.465	1.277	8.226
Oxygen furnace gas, 2009	196.970	196.970	1.253	8.247
Oxygen furnace gas, 2010	197.029	197.029	1.216	8.249
Oxygen furnace gas, 2011	198.482	198.482	1.160	8.310
Oxygen furnace gas, 2012	198.199	198.199	1.226	8.298
Oxygen furnace gas, 2013	185.522	185.522	1.068	7.767
Oxygen furnace gas, 2014	200.970	200.970	1.335	8.414
Oxygen furnace gas, 2015	201.532	201.532	1.351	8.438
Oxygen furnace gas, 2016	203.868	203.868	1.309	8.536
Oxygen furnace gas, 2017	199.257	199.257	1.305	8.343
Oxygen furnace gas, 2018	192.862	192.862	1.353	8.075
Oxygen furnace gas, 2019	194.622	194.622	1.387	8.148
Oxygen furnace gas, 2020	195.877	195.877	1.387	8.148
Oxygen furnace gas, 2021	192.710	192.710	1.397	8.068
Oxygen furnace gas, 2022	191.486	191.486	1.414	8.017
Oxygen furnace gas, 2023	199.069	199.069	1.354	8.335
Oxygen furnace gas, 2024	199.535	199.535	1.283	8.354

Source: ISPRA elaborations

Table A6.10 – Heavy residual fuels, average carbon emission factors

<i>Heavy residual fuels</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Heavy residual fuels, 1999-2006	81.817	81.817	3.213	3.426
Heavy residual fuels, 2007	81.823	81.823	3.214	3.426
Heavy residual fuels, 2008	80.350	80.350	3.156	3.364
Heavy residual fuels, 2009	79.612	79.612	3.125	3.333
Heavy residual fuels, 2010	78.940	78.940	3.104	3.305
Heavy residual fuels, 2011	79.160	79.160	3.091	3.314
Heavy residual fuels, 2012	79.359	79.359	3.098	3.323
Heavy residual fuels, 2013	80.598	80.598	3.139	3.374
Heavy residual fuels, 2014	80.355	80.355	3.129	3.364
Heavy residual fuels, 2015	79.609	79.609	3.100	3.333
Heavy residual fuels, 2016	79.553	79.553	3.098	3.331
Heavy residual fuels, 2017	79.920	79.920	3.112	3.346

<i>Heavy residual fuels</i>	t CO ₂ / TJ (stechiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Heavy residual fuels, 2018	79.572	79.572	3.099	3.332
Heavy residual fuels, 2019	79.625	79.625	3.101	3.334
Heavy residual fuels, 2020	80.211	80.211	3.124	3.358
Heavy residual fuels, 2021	79.606	79.606	3.100	3.333
Heavy residual fuels, 2022	80.480	80.480	3.134	3.370
Heavy residual fuels, 2023	80.611	80.611	3.139	3.375
Heavy residual fuels, 2024	81.026	81.026	3.155	3.392

Source: ISPRA elaborations

Table A6.11 – Synthesis gas, average carbon emission factors

<i>Synthesis gas</i>	t CO ₂ / TJ (stechiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Synthesis gas, 1999-2005	98.103	98.103	0.906	4.107
Synthesis gas, 2006	98.566	98.566	0.982	4.127
Synthesis gas, 2007	98.321	98.321	0.830	4.117
Synthesis gas, 2008	98.860	98.860	0.886	4.139
Synthesis gas, 2009	105.956	105.956	0.956	4.436
Synthesis gas, 2010	110.487	110.487	0.910	4.626
Synthesis gas, 2011	109.188	109.188	0.915	4.571
Synthesis gas, 2012	106.913	106.913	0.881	4.476
Synthesis gas, 2013	100.817	100.817	0.895	4.221
Synthesis gas, 2014	100.596	100.596	0.898	4.212
Synthesis gas, 2015	100.732	100.732	0.930	4.217
Synthesis gas, 2016	103.993	103.993	0.929	4.354
Synthesis gas, 2017	103.043	103.043	0.983	4.314
Synthesis gas, 2018	109.145	109.145	1.009	4.570
Synthesis gas, 2019	104.034	104.034	0.948	4.356
Synthesis gas, 2020	102.912	102.912	0.870	4.309
Synthesis gas, 2021	97.899	97.899	1.196	4.099
Synthesis gas, 2022	99.071	99.071	0.926	4.148
Synthesis gas, 2023	97.875	97.875	0.864	4.098
Synthesis gas, 2024	98.130	98.130	0.953	4.108

Source: ISPRA elaborations

Table A6.12 – Residual gas of chemical processes, average carbon emission factors

<i>Residual gas of chemical processes</i>	t CO ₂ / TJ (stechiometric)	Oxidation factor	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Residuals gas of chem. processes, 1990-2007	51.500	0.995	51.243	2.365	2.145
Residuals gas of chem. processes, 2008	51.308	0.995	51.052	2.505	2.137
Residuals gas of chem. processes, 2009	50.588	0.995	50.342	2.502	2.108
Residuals gas of chem. processes, 2010	50.323	0.996	50.112	2.295	2.098
Residuals gas of chem. processes, 2011	50.568	0.995	50.335	2.516	2.107
Residuals gas of chem. processes, 2012	51.179	0.995	50.947	2.229	2.133
Residuals gas of chem. processes, 2013	47.484	1.000	47.484	2.071	1.988
Residuals gas of chem. processes, 2014	42.912	1.000	42.912	2.273	1.797
Residuals gas of chem. processes, 2015	47.830	1.000	47.830	2.163	2.003
Residuals gas of chem. processes, 2016	47.362	1.000	47.362	2.284	1.983
Residuals gas of chem. processes, 2017	47.525	1.000	47.525	2.256	1.990
Residuals gas of chem. processes, 2018	47.205	1.000	47.205	2.271	1.976
Residuals gas of chem. processes, 2019	52.375	1.000	52.375	2.216	2.193
Residuals gas of chem. processes, 2020	48.229	1.000	48.229	2.189	2.019
Residuals gas of chem. processes, 2021	47.589	1.000	47.589	2.204	1.992
Residuals gas of chem. processes, 2022	48.935	1.000	48.935	2.216	2.049
Residuals gas of chem. processes, 2023	49.736	1.000	49.736	2.226	2.082
Residuals gas of chem. processes, 2024	50.150	1.000	50.150	2.202	2.100

Source: ISPRA elaborations

Table A6.13 – Petroleum coke for no refinery plants, average carbon emission factors

<i>Petroleum coke</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Petroleum coke, 1990-2004	97.500	97.500	3.169	4.082
Petroleum coke, 2005	92.957	92.957	3.097	3.892
Petroleum coke, 2006	93.295	93.295	3.125	3.906
Petroleum coke, 2007	93.427	93.427	3.193	3.912
Petroleum coke, 2008	93.525	93.525	3.203	3.916
Petroleum coke, 2009	94.106	94.106	3.227	3.940
Petroleum coke, 2010	93.679	93.679	3.160	3.922
Petroleum coke, 2011	93.715	93.715	3.219	3.924
Petroleum coke, 2012	93.303	93.303	3.207	3.906
Petroleum coke, 2013	93.178	93.178	3.128	3.901
Petroleum coke, 2014	93.513	93.513	3.122	3.915
Petroleum coke, 2015	93.771	93.771	3.132	3.926
Petroleum coke, 2016	93.459	93.459	3.121	3.913
Petroleum coke, 2017	93.465	93.465	3.129	3.913
Petroleum coke, 2018	93.680	93.680	3.122	3.922
Petroleum coke, 2019	93.498	93.498	3.117	3.915
Petroleum coke, 2020	93.368	93.368	3.126	3.909
Petroleum coke, 2021	93.331	93.331	3.126	3.908
Petroleum coke, 2022	92.968	92.968	3.120	3.892
Petroleum coke, 2023	93.965	93.965	3.135	3.934
Petroleum coke, 2024	93.880	93.880	3.129	3.931

Source: ISPRA elaborations

Table A6.14 – Petroleum coke for refinery plants, average carbon emission factors

<i>Petroleum coke</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Petroleum coke, 2010	100.684	100.684	3.428	4.215
Petroleum coke, 2011	99.331	99.331	3.413	4.159
Petroleum coke, 2012	100.081	100.081	3.435	4.190
Petroleum coke, 2013	99.336	99.336	3.415	4.159
Petroleum coke, 2014	95.879	95.879	3.400	4.014
Petroleum coke, 2015	96.778	96.778	3.432	4.052
Petroleum coke, 2016	101.995	101.995	3.416	4.270
Petroleum coke, 2017	96.734	96.734	3.430	4.050
Petroleum coke, 2018	97.295	97.295	3.422	4.074
Petroleum coke, 2019	96.929	96.929	3.437	4.058
Petroleum coke, 2020	97.082	97.082	3.442	4.065
Petroleum coke, 2021	96.536	96.536	3.423	4.042
Petroleum coke, 2022	96.855	96.855	3.435	4.055
Petroleum coke, 2023	95.672	95.672	3.393	4.006
Petroleum coke, 2024	95.308	95.308	3.380	3.990

Source: ISPRA elaborations

Table A6.15 –Coke, average carbon emission factors

<i>Coke</i>	t CO ₂ / TJ (stoichiometric)	t CO ₂ / TJ	t CO ₂ / t	t CO ₂ / toe
Coke, 1990-2004	110.368	108.161	3.170	4.528
Coke, 2005	110.916	110.916	3.246	4.644
Coke, 2006	111.049	111.049	3.181	4.649
Coke, 2007	111.814	111.814	3.191	4.681
Coke, 2008	111.649	111.649	3.187	4.675
Coke, 2009	111.303	111.303	3.161	4.660
Coke, 2010	109.079	109.079	3.125	4.567
Coke, 2011	110.380	110.380	3.188	4.621
Coke, 2012	112.969	112.969	3.309	4.730
Coke, 2013	111.113	111.113	3.172	4.652
Coke, 2014	109.195	109.195	3.198	4.572
Coke, 2015	109.728	109.728	3.206	4.594
Coke, 2016	109.533	109.533	3.217	4.586

Coke	t CO₂ / TJ (stechiometric)	t CO₂ / TJ	t CO₂ / t	t CO₂ / toe
Coke, 2017	108.755	108.755	3.237	4.553
Coke, 2018	108.864	108.864	3.218	4.558
Coke, 2019	108.590	108.590	3.169	4.546
Coke, 2020	107.468	107.468	3.181	4.499
Coke, 2021	108.466	108.466	3.154	4.541
Coke, 2022	108.216	108.216	3.189	4.531
Coke, 2023	111.311	111.311	3.200	4.660
Coke, 2024	105.305	105.305	3.085	4.409

Source: ISPRA elaborations

Table A6.16 –Coking coal, average carbon emission factors

Coking coal	t CO₂ / TJ (stechiometric)	t CO₂ / TJ	t CO₂ / t	t CO₂ / toe
Coking coal, 1990-2004	94.600	94.600	2.668	3.961
Coking coal, 2005	92.466	92.466	2.971	3.871
Coking coal, 2006	94.058	94.058	2.968	3.938
Coking coal, 2007	94.479	94.479	2.971	3.956
Coking coal, 2008	94.869	94.869	2.961	3.972
Coking coal, 2009	94.718	94.718	2.970	3.966
Coking coal, 2010	94.627	94.627	3.007	3.962
Coking coal, 2011	95.459	95.459	2.999	3.997
Coking coal, 2012	95.380	95.380	3.014	3.993
Coking coal, 2013	94.381	94.381	2.982	3.952
Coking coal, 2014	93.983	93.983	2.991	3.935
Coking coal, 2015	94.457	94.457	2.995	3.955
Coking coal, 2016	94.171	94.171	2.967	3.943
Coking coal, 2017	94.004	94.004	2.967	3.936
Coking coal, 2018	95.361	95.361	2.974	3.993
Coking coal, 2019	94.676	94.676	2.948	3.964
Coking coal, 2020	94.947	94.947	2.966	3.975
Coking coal, 2021	94.757	94.757	2.938	3.967
Coking coal, 2022	94.447	94.447	2.953	3.954
Coking coal, 2023	91.519	91.519	2.938	3.832
Coking coal, 2024	93.490	93.490	2.906	3.914

Source: ISPRA elaborations

Table A6.17 –Anthracite, average carbon emission factors

Anthracite	t CO₂ / TJ (stechiometric)	t CO₂ / TJ	t CO₂ / t	t CO₂ / toe
Anthracite, 1990-2004	98.300	98.300	2.625	4.116
Anthracite, 2005	93.035	93.035	2.856	3.895
Anthracite, 2006	95.127	95.127	2.817	3.983
Anthracite, 2007	97.722	97.722	2.796	4.091
Anthracite, 2008	97.183	97.183	2.764	4.069
Anthracite, 2009	98.335	98.335	2.861	4.117
Anthracite, 2010	97.416	97.416	2.844	4.079
Anthracite, 2011	99.465	99.465	2.911	4.164
Anthracite, 2012	98.717	98.717	2.870	4.133
Anthracite, 2013	98.348	98.348	2.886	4.118
Anthracite, 2014	97.960	97.960	2.877	4.101
Anthracite, 2015	101.373	101.373	2.906	4.244
Anthracite, 2016	101.630	101.630	2.924	4.255
Anthracite, 2017	103.107	103.107	3.027	4.317
Anthracite, 2018	100.405	100.405	3.005	4.204
Anthracite, 2019	105.114	105.114	3.033	4.401
Anthracite, 2020	104.757	104.757	2.964	4.386
Anthracite, 2021	104.131	104.131	3.021	4.360
Anthracite, 2022	104.643	104.643	3.044	4.381
Anthracite, 2023	101.334	101.334	2.974	4.243
Anthracite, 2024				

Source: ISPRA elaborations

Table A6.18 –Industrial waste (fossil), average carbon emission factors

Industrial waste	t CO₂ / TJ (stoichiometric)	t CO₂ / TJ	t CO₂ / t	t CO₂ / toe
Industrial waste, 2005-2012	79.968	79.968	1.924	3.348
Industrial waste, 2013	79.076	79.076	1.853	3.311
Industrial waste, 2014	81.851	81.851	1.931	3.427
Industrial waste, 2015	78.976	78.976	1.988	3.307
Industrial waste, 2016	78.592	78.592	2.019	3.291
Industrial waste, 2017	82.164	82.164	2.090	3.440
Industrial waste, 2018	80.019	80.019	2.034	3.350
Industrial waste, 2019	81.243	81.243	2.093	3.401
Industrial waste, 2020	79.915	79.915	2.070	3.346
Industrial waste, 2021	81.473	81.473	2.027	3.411
Industrial waste, 2022	81.504	81.504	2.054	3.412
Industrial waste, 2023	81.721	81.721	2.014	3.421
Industrial waste, 2024	79.529	79.529	2.005	3.330

Source: ISPRA elaborations

ANNEX 7: AGRICULTURE SECTOR

Additional information used for estimating categories 3A, 3B and 3D from the agriculture sector is reported in this section.

A7.1 Enteric fermentation (3A)

The time series of parameters used for estimating the Dairy Cattle EF using the Tier 2 approach, are reported in Table A.7.1. Information on the equations used for estimating the different net energy (NE_m, NE_g, etc.) is described in the 2019 IPCC Guidelines (IPCC, 2019).

Table A.7.1 Parameters used for the Tier 2 approach - dairy cattle

	NE _m (MJ/day)	NE _a (MJ/day)	NE _g (MJ/day)	NE _i (MJ/day)	NE _w (MJ/day)	NE _p (MJ/day)	REM	REG	DE (%)	GE (MJ/day)	Y _m (%)
1990	46.95	0.40	0.97	33.52	0.00	4.57	0.514	0.308	65.00	260.66	6.50
1995	46.95	0.40	0.97	43.38	0.00	4.45	0.514	0.308	65.00	289.83	6.50
2000	46.95	0.40	0.97	44.31	0.00	4.35	0.514	0.308	65.00	292.33	6.50
2005	46.95	0.40	0.97	50.84	0.00	4.27	0.519	0.316	66.45	301.97	6.18
2010	46.95	0.44	0.97	55.54	0.00	4.23	0.522	0.322	67.68	307.60	6.08
2015	46.95	0.49	0.97	56.89	0.00	4.18	0.522	0.321	67.51	312.51	6.09
2020	46.95	0.54	0.97	71.74	0.00	4.30	0.525	0.327	68.77	346.17	5.98
2021	46.95	0.54	0.97	74.94	0.00	4.34	0.526	0.328	68.90	354.22	5.97
2022	46.95	0.54	0.97	74.98	0.00	4.34	0.525	0.327	68.67	355.92	5.99
2023	46.95	0.54	0.97	77.11	0.00	4.33	0.526	0.328	68.92	360.00	5.97
2024	46.95	0.54	0.97	81.05	0.00	4.32	0.526	0.328	68.95	370.65	5.97

Source: ISPRA elaborations.

For non-dairy cattle, data on nitrogen excreted are derived by the Nitrogen Balance Inter-regional Project that involved Emilia Romagna, Lombardy, Piedmont and Veneto regions, where animal breeding is concentrated and for that they have been assumed representative of the national level.

The project was aimed at developing models to calculate the nitrogen balance for different types of breeding, including cattle. The following information was collected: the movement of the heads and feed at farm level, animal nutrition plans, feed consumption per animal category and bred, management techniques, reproductive phase and the productive results, mortality, age, weight at different growth and fattening phases, number and type of stable places in the herd, the type of simple feed or compound feed used, the estimated nitrogen content, the composition of the feed ration, average levels daily consumption per animal category and stage of breeding cycle (Xiccato et al., 2004).

The survey data related to replacement heifers and other non-dairy cattle are described below.

Replacement heifers

Breeding performance

In Table A.7.2 the national average values of the main characteristics of the replacement heifers breeding are reported. Friesian, Brown and Red-spotted livestock breeds have been considered.

The national value is the average of the results of the survey carried out in Veneto, Emilia Romagna, Lombardy and Piedmont which monitors the feed consumption, the composition of the rations and the numeric movements and weight of livestock in the period between 2002 and 2003. For Veneto, specifically, data from 89 representative farms, for a total of 8,466 heads, were collected (Regione Veneto, 2008; Bittante et al., 2004).

Table A.7.2 Main characteristics of the replacement heifers breeding

Type of feed over the years	Unit of measure	Average value	Sd (2)
Age at weaning	day	85	23
Age at first calving	month	28.5	
Live weight at birth	kg/head	39	
Average live weight at weaning	kg/head	101	19
Average live weight at first calving	kg/head	540	
Feed ration distribution			
Traditional	%	25	
Unifed	%	38	
Mixed	%	37	
Intake of dry matter from weaning at first calving	kg/head/period	6473	1459
Daily dry matter intake	kg/d	8.24	1.89
Average crude protein ration (Nx6,25)	kg/kg	0.121	0.018
Nitrogen balance			
N consumed from birth to weaning	kg/head/period	5.3	2.7
N consumed from weaning to calving	kg/head/period	123.9	29.7
N retention in products from birth to calving	kg/head/period	14.41	
N excreted from birth to calving	kg/head/period	114.8	29.6
N annually excreted	kg/head/year	48.3 (1)	12.5

(1) the value was divided by the average weight and used to calculate the annual average nitrogen excretion for females from breeding between 1 and 2 years and more than 2 years (reported in CRPA, 2006[a]); (2) Standard deviation.

Feed consumption and composition of rations

Average value of dry matter intake from weaning at first calving is 6473 kg/head/period (8.24 kg of dry matter intake per day).

Animals receive rations based, even in summer, on hay fodder, corn silage and fibrous products with minimal additions of feed concentrates.

The protein content of these rations is on average 12% of dry matter intake. The use of fresh grass is generally avoided, the best fodder is normally reserved for dairy cows and the inferior fodder for the replacement heifers.

Digestibility

The feed ration is rich in fiber (as described above) and therefore less digestible than the ration of fattening animals. Methane conversion factors were estimated with the formula proposed by Ellis (Ellis et al, 2007) based on daily DMI and forages proportion (FP) in the diet (see section below CH₄ conversion factors for non-dairy cattle category).

Other cattle

Breeding performance

A revision of the feeding plan, diets and slaughtering categories were made on the basis of updated literature and research results. The review also takes in account the development that beef cattle breeding has undergone since the early 2000s, when alongside the breeding of animals of specialized breeds (mainly imported calves), the practice of using dairy females fertilized with beef bull semen to obtain cross-breeds for slaughter was widely introduced. Based on the information gathered by CRPA in the bibliography and field experiences, the dry matter intake values were updated. In addition, the Ym values in use were recalculated with the Ellis formula based on the updated results of the composition of the diets.

In Italy there are different types of beef cattle breeding, which can be traced back to 3 main cases (CRPA, 2011[b]):

- farms oriented to the fattening phase only, widespread in regions of the Po Valley. This production model mainly uses calves over 6 months old, whose final growing-fattening phase is carried out in confinement farms ("ristallo"). This type of breeding in the northern Italian plain guarantees the largest physical flow of product to the beef supply chain in Italy;
- farms with suckler cows that wean calves that are then fattened. Placed mainly in the regions of Central-Southern Italy and in Piedmont. Cows are from specialized breeds for the production of meat,

mostly of national origin (Marchigiana, Chianina, Romagnola, Piemontese), French breeds like Limousine and double purpose breeds;

- extensive breeding with national rustic breeds, followed in southern Italy and islands, generally located in the internal hilly and mountainous areas; these farms are now marginal in terms of meat quantity, but provide niche products.

The concentration of other cattle is in the northern area of Italy, and more specifically in Piedmont (21%) Veneto (19%), and Lombardy (14%) more than half of the beef cattle of the national herd (ISMEA, 2022). Today less than 10% of the animals in the meat supply chain belong to local meat breeds, and 26% of the herd is made up of crossbreeds. Meat supply is mainly represented by cattle between 1 and 2 years of age (57%), "late-career" cattle over two years of age account for about 20% of the national supply, and cattle slaughtered before one year of age are 23% (ISMEA, 2022).

Feed consumption and composition of rations

Since the beginning of the sixties, the intensive farming under confinement, the most prevalent in the Po valley, has been closely linked to the development of the cultivation of maize, as the main energy source, and the availability of flour from imported soybean, as a protein source (Regione Veneto, 2008). In the same years, in agricultural areas in Northern Italy a substantial abandonment of the cattle from traditional meat, based on a wide use of permanent and/or temporary fodder was recorded. This process has developed because of the development of the product ensiling technique obtained by chopping of the whole plant, harvested in the milky-wax ripeness phase of kernels (corn silage). The use of corn silage increases by about 50% the amount of energy per hectare, reducing, consequently, the cost of the unit forage (Regione Veneto, 2008). The use of corn silage and concentrated feed, suitably integrated, in diets for cattle, increases the speed of growth of animals, improving the energy efficiency of the ration, reducing the duration of the production cycle and raising the yields of slaughter and the qualitative level of carcasses and meat (Regione Veneto, 2008).

A recent manual on ruminant feeding in Italy (Cevolani D. *et al*, 2021; 2022) provides useful information on the diet of beef cattle.

Table A.7.3 Examples of rationing for growth/fattening beef cattle with corn silage and without (dry matter)

Ration feed	Growing kg/head/day	Fattening kg/head/day	Growing kg/head/day	Fattening kg/head/day
Corn silage	7	9	0	0
Straw	0.5	0.5	1	1
Corn flour	3.5	5	5	6.2
Soibean meal	1	0.8	0.8	0.8
Sugar beet pulp, dehydrated	1	0.7	1.5	1.5
Sunflower meal	0.5	0.5	0.5	0.5
Oils/fats	0.2	0.3	0.2	0.3
Supplement	0.2	0.2	0.2	0.2
Forages total	7.5	9.5	1	1
Concentrate total	6.4	7.5	8.2	9.5
DMI intake	13.9	17	9.2	10.5
% Forages	53.96	55.88	10.87	9.52
% Concentrate	46.04	44.12	89.13	90.48

Source: Cevolani D. *et al*, 2022.

Table A.7.4 Examples of rationing for suckler cow and beef cattle (dry matter)

Ration feed	Gestation kg/head/day	Lactation kg/head/day	Growing kg/head/day	Fattening kg/head/day
Pastures	25	25	0	0
Hay	3.5	3.5	1.5	1.0
Straw	2.5	1.5	0.5	0.5
Concentrate	1.0	5.0	4.0	7.0
Corn silage	0	0	6.0	8.0
Forages total	31	30	8	9.5
Concentrate total	1	5	4	7
DMI intake	32	35	12	16.5

Ration feed	Gestation kg/head/day	Lactation kg/head/day	Growing kg/head/day	Fattening kg/head/day
% Forages	96.88	85.71	66.67	57.58
% Concentrate	3.13	14.29	33.33	42.42

Source: Cevolani D. et al, 2021.

Those data are in line with the survey conducted on 135 farms in Veneto, Lombardy and Piedmont on the average type of the feed composition and crude protein content of rations for Charolais cattle (Cozzi, 2007 – see Table A.7.5). Despite some differences between farms located in different regions it is observed that in all cases corn silage, corn mash and cereals are the main constituents of rations. The use of dried beet pulp, in the Veneto region, was significant. In Veneto and Lombardy, the fiber forages are represented almost exclusively by straw, while in Piedmont these are partially or totally replaced by permanent meadow hay. The supplement of protein is generally based on soybean flour. The protein content is in all cases around 14% of dry matter, a content slightly lower than that found by Xiccato et al., (Xiccato et al., 2005) on 40 farms in Veneto (14.4% + 0.9%) and slightly higher than that found by Mazzenga et al., (Mazzenga et al., 2007) on 406 farms in the Po valley (13% + 1.1%).

Table A.7.5 Feed and chemical composition of total mixed rations for Charolais cattle in different regions (dry matter)

Ration feed	Veneto	Lombardy	Piedmont
Farms, n.	101	23	11
Feed ration, kg			
Silage corn	2.99	3.46	2.12
Mash corn	0.52	0.91	1.76
Cereals, flour and grains	0.86	0.58	0.67
Dried beet pulp	0.39	0.21	0.18
Fodder long fiber	0.61	0.61	0.87
Protein supplements, vitamins and minerals	2.00	2.26	2.09
Molasses and vegetable fats	0.09	0.09	0.17
Chemical composition:			
Dry matter %	55.2	52.6	62.3
Crude protein %	14.0	13.9	14.0
Total forages	4.50	5.19	4.92
Total concentrates	2.95	2.93	2.93
Total feed	7.45	8.11	7.86
% of concentrates	40	36	37
% of forages	60	64	63

Source: Cozzi, 2007.

Taking into consideration also values of DMI reported by Grossi (Grossi et al, 2022) and by the Association of Piemontese breeders (ANABORAPI, 2022), and also some direct experience on field, value of DMI reference consumption is evaluated by CRPA (see section CH₄ conversion factors for non-dairy cattle category).

In general, dry matter consumption is reported in the bibliography by weight classes, but within weight classes females are rarely distinguished from males.

Digestibility

As mentioned above, the rations consist mainly of silage and cereals and for fattening animals the ration has been assumed more digestible.

This assumption is supported by a recent survey on dry matter (DM) total tract apparent digestibility in beef cattle (Pacchioli et al, 2023), carried out on Charolais male in growing and finishing periods feed with wheat silage and corn mash as fodder bases. DM total tract apparent digestibility values were 77.64% and 74.12% at growing and fattening, respectively.

CH₄ conversion factors for non-dairy cattle category

The country specific Y_m values for non-dairy cattle, for the different subcategories, have been calculating with the linear equation proposed by Ellis (Ellis et al, 2007) based on daily DMI and forages proportion in the diet, considering the national weight and DMI values and assuming percentages of forages between 30% and 65%.

Ellis' equation was chosen by Italy, in agreement with the CRPA's experts. The choice was justified because the equation is based on feed composition, DMI and % forage parameters, values available at country-specific level for each non-dairy cattle subcategory.

The model was also confirmed for calculating Y_m values because it is mentioned in the 2019 IPCC guidelines. Ellis linear equation returns Y_m values in the range of 4.2-4.7, and these values are consistent with the type of diets used in Italy for non-dairy cattle.

In Italy, beef cattle farming includes imported specialized breeds, mostly French ones, undergoing a 3–5 month finishing period; native breeds (e.g., Chianina, Marchigiana, Romagnola, Piemontese) fattened after weaning; and dairy breeds or dairy-beef crosses. During the finishing phase, all are raised in confined systems.

Data on the type of forages and feed used in the Italian farms are reported below:

- In the project on beef supply chain sustainability through optimized animal feeding and precision agriculture and livestock practices (<https://www.innovarurale.it/it/pei-agri/gruppi-operativi/bancadati-go-pei/sostenibilita-della-filiera-carne-mediante>), conducted from 2021 to 2023, the digestibility of diets from beef farm representative of the majority of beef cattle raised in Italy has been assessed (Pacchioli M.T. et al, 2023). The data presented are derived from a research project conducted on commercial herds where the ration in use was the actual feeding (and not changed) and which served to develop a method for evaluating ration digestibility under on-farm conditions.

- Diets are based on forages, generally silages of maize and/or winter cereals, complemented by grains and/or compound feeds and supplements. The silage portion of the ration ranges from 30% to 65% of the dry matter. It should be noted that although maize silage is classified as forage, it contributes high levels of starch (average 32.95% of dry matter; min 19.63%, max 42.28%, SD 4.11 – source: CRPA Lab, average of 795 samples from 2021 to 2024). Due to the widespread presence of starch (from both forage and concentrates), silage-based diets used in most Italian beef systems have high apparent digestibility, exceeding 75% for dry matter.

Livestock production systems are reported in Gratton et al. (2024), cattle farming systems can be classified into two types: feedlot-based livestock and livestock in grassland-finished systems.

Feedlot-based livestock involves keeping animals in confined environments where they are provided with feed and shelter. Feed is stored and distributed by operators who also manage livestock manure; forage is grown from annual crops such as corn using high-input technologies and management.

Livestock in grazing systems utilize various sources of forage. Pastures are managed using a rotating system of portions of land to improve forage production and quality.

The Italian livestock systems is largely represented by the first type, where animals are housed in barn and fed high-quality fodder produced on the farm itself, supplemented with grains/complete feed.

About the validation of the model developed by Ellis et al. 2007, the CRPA contacted other international researchers and experts who confirmed the predictive validity of Ellis' models for calculating Y_m values for different categories of cattle.

In 2024 a research group worked on a mixed integer linear programming (MILP) model that simultaneously optimizes crop planning and dairy cow diet formulation: between different purposes (costs, efficiency, etc.) also the reduction of methane emission has been considered. The methane emission values used as a reference in MILP development were calculated using an empirical linear equation from Ellis et al., 2007, Table 5 (equation [8c]) (see, Gong et al., 2025). It was selected among various models evaluated by authors for estimating enteric methane emissions for dairy farms because it

combines the predictive accuracy of Ym with the ease of obtaining the required parameters, metabolic energy (ME, MJ/day per head) and NDF (kg/day per head) at farm level.

Still on the validity of the model developed by Ellis et al. in 2007, the article by Escobar-Bahamondes et al. (2016) states that the use of specific equations for the proportion of forage in the diet reduced the uncertainty in estimating CH₄ emissions from beef cattle compared to the IPCC Tier 2 methodology.

The work of Ellis et al. 2007 is also a reference for the IPCC 2019 Refinement. It is based on the results of 29 published studies, which have scientific value beyond the number of animals considered because statistical models are applied to ensure the validity of the results obtained.

Beyond the number of animals considered in the 30 studies from which the value reported in the 2019 IPCCs was derived, 17 studies are based on data from Canada and the US, 2 Australia, 2 Brazil, 9 EU (UK 1, France 2, Switzerland 1, Ireland 5). These are certainly countries that have different types of breeding (breeds raised and type of ration) than those in Italy. Therefore, the IPCC default value is largely derived from US and Canadian data, countries where growth regulators such as monensin are used, affecting the default value of the IPCC Guidelines.

In any case, the Ellis et al 2007 formula, although based on data from the U.S. and Canadian countries, as moreover the 2019 IPCC Ym values, is to be considered valid, as it is able to account for changes in diets: in fact, it leads to Ym values superimposable to those proposed by IPCC 2019 when the amount of forage in the ration is close to 75%, as well as for the feedlot with % forage in the diet of 10%.

In reference to the study by Niu et al. (2018), cited to demonstrate the difference between EU and US cattle during the 2025 ESR review process (EEA, 2025), it should be noted that the study refers to dairy cows and not beef cattle, and that the mean Ym values of EU and US are similar and both have high variability, which prevents one result from being significantly different from the other (EU range 3.6-9.8 and US range 2.7-8.4). The standard deviation of US is greater than that of EU, although US has lower minimum and maximum. Moreover, the two ranges of variation overlap in the range (3.6, 8.4), which is a large percentage of the range of variation in both cases. In essence, there is absolutely no evidence to determine which between US and EU is higher.

Moreover, as reported by the performance indicators in Niu et al. 2018 paper, particularly for models based on DMI or DMI+NDF, which are the most important variables for estimating CH₄ (as reported by the authors), models based on the intercontinental, EU and US databases do not offer such different performance for EU and US.

The data contained in the NorFor database were cited during the ESR 2025 review process (EEA, 2025) to assert that the data provided by Italy are not significantly different from other European data sets, such as the multinational NorFor database (<https://www.norfor.info/services/norfor-feed-table/>).

For this reason, the reviewer considered that the Italian data cannot be considered an argument in favor of significantly different feeding strategies that result in a low Ym for Italy.

The NorFor database is well known in Italy, and the data reported refer not only to Scandinavian fodder but also to fodder from other countries, as well as from literature. For this reason, the data reported in the NorFor database are not very different from the Italian data. However, it should be noted that forages grown in northern Europe is unlikely to reach the starch levels found in maize silage and wheat silage in Italy.

In any case, the data contained in the NorFor database relates to the nutritional composition of single row materials, forages and grains. In this issue raised by the reviewer, the topic concerns the composition of the ration, which, as explained in various passages. Italian rations for cattle contain a lot of starch from various raw materials, including those other than fodder.

The wide range from which the average value in the 2019 IPCC guidelines was derived (Ym values ranging from 3.2% to 8.85%, and that the values are derived from studies that do not represent Southern Europe) indicates that that figure has very wide variability and cannot be considered as a more accurate value for calculating emission estimates than values by animal subcategory calculated with country-specific diet values.

The most Italian beef systems have high digestibility and therefore, the beef systems cannot be associated with the default IPCC Ym values of 6.5 or 6.3%, but are more comparable to feedlot systems, which are associated with much lower Ym values (3.0% in table 10.12 of 2006 IPCC Guidelines). The default IPCC Ym value of 6.5 refer to low-quality feed, associated with the categories Other Cattle and Buffaloes that are primarily fed low quality crop residues and by-products, which is not the type of feed used in Italian farms.

In the 2019 IPCC Guidelines (Chapter 10 of Volume 4, Table 10.12), the non-dairy cattle category, fed with rations of >75% high quality forage and/or mixed rations, forage of between 15 and 75% the total ration mixed with grain, and/or silage, is too broad to be represented by a single Ym value (6.3%). Considering the diverse composition of diets in the non-dairy cattle category, it is known that digestible energy varies between 62% and 71%. However, a single Ym value of 6.3% and a fixed methane emission rate of 21 g CH₄/kg DMI are applied. Feeding systems that use cereal silage and diets high in starch are not well represented by this description, which brings together diets that are different in terms of nutritional value and digestibility.

The levels of DM intake and % forage have a significant impact on the Ym and it is necessary to take this into account and use a model that reflects the contribution of the variation in these parameters.

Considering the rations shown in Table 10.12 (IPCC 2019, Chapter 10 of Volume 4), the CRPA calculated the following percentages of starch content:

-100% grains = 47-49% starch;

-90% grains + 10% forages = 46-47% starch.

The starch percentage is equal to that found in the rations most commonly used in Italian livestock farms, as shown in Table A.7.6.

Italian diets are based on forages, generally silages of maize and/or winter cereals, complemented by grains and/or compound feeds and supplements. The silage portion of the ration ranges from 30% to 65% of the dry matter. It should be noted that although maize silage is classified as forage, it contributes high levels of starch (average 32.95% of dry matter; min 19.63%, max 42.28%, SD 4.11 – source: CRPA Lab, average of 795 samples from 2021 to 2024). Due to the widespread presence of starch (from both forage and concentrates), silage-based diets used in most Italian beef systems have high apparent digestibility, exceeding 75% for dry matter.

Thus, the italian diets do not use a 90% grain ratio, but the diets contain whole-plant cereal silage with a high starch percentage, to which high amounts of concentrates are added, in a 50 to 70% concentrate/forage ratio. The rations have high digestibility and therefore cannot be associated with high Ym values.

The CRPA conducted a survey of 32 cattle farms associated with Asporcarne (Piedmont) and Unicarve (Veneto) as part of a LIFE Carbon Farming project (LIFE20 CCM/FR/001663) to identify beef cattle feeding systems in Italy. The results are shown in Table A.7.6.

The feeding system used for most non-dairy cattle in Italy is based on silage.

Table A.7.6 Beef cattle feeding systems in Italy (dry matter)

Ration feed	WITHOUT silage	WITH silage
	DM	DM
Whole plant silage kg/d		2.79
corn		
winter cereals		
Fiber source kg/d	2.59	1.68
hay		
straw		
sugar beet pulp, dehydrates		
Feed kg/d	5.7	6.22
complete feed		
ear or grain corn silage		

Ration feed		WITHOUT silage	WITH silage
		DM	DM
RATION			
DM	Kg/d	8.29	10.69
starch	(%DM)	32.75	48.53
aNDFom	(%DM)	45.59	20.87
concentrates	(%DM)	67.77	58.18
Forages	(%DM)	31.23	41.82

Source: CRPA.

The diets identified in the survey were divided into those using silage-preserved forages (2/3) or dry fodder only (1/3). Both types of diet are rich in complete feed and starch. Starch reaches a very high percentage in diets with corn silage, a forage rich in starch unlike autumn-winter cereal forages and dry forages.

Table A.7.7 shows the average nutritional composition of the forages and feed included in the diets.

Table A.7.7 Composition of forages and feeds included in the diet (dry matter)

	DM	Ash	CP	Starch	aNDFom	ADF	uNDF	Source
Whole plant silage - corn	33.25	4.69	7.78	32.95	39.97	25.57	22.3	CRPA, 787 samples
Whole plant silage – winter cereals	31.20	8.3	9	7.6	55.6	36.3	18	CRPA, 230 samples
Hay – mix gram+leg	87.00	9.65	11.35	1.70	55.61	40.01	22.03	CRPA, 728 samples
Straw	91.00	6.70	4.20	0.00	77.50	50.00		Feedipedia
Sugar beet pulp, dehydrates	88.80	7.10	8.90	0.90	47.10	23.80		Feedipedia
Complete feed	87.00	7.01	17.82	68.97	11.49			Labels from producers
Ear or grain corn silage	58.80	2	7.8	57.8	18.5	9.3	3.9	CRPA, 205 samples

Source: CRPA.

With reference to the default IPCC Ym values, the IPCC guidelines state that country-specific exceptions to these general rules should be considered on the basis of detailed data provided by national livestock experts.

Considering information provided by CRPA and reported in Feed consumption and composition of rations section in terms of typical diets used in Italy and dry matter consumption of beef cattle types grown, the following parameters are adopted by CRPA for non-dairy cattle subcategories.

For cattle less than one year, DMI is estimated at 4.9 kg/head/day;

Males from 1 to 2 years: DMI is considered at 2.0% by weight for breeding males and 1.7% for slaughter;

Females 1 to 2 years: DMI is considered at 3.0% by weight for breeding females and 2.0% for slaughter;

Males > 2 years: DMI is considered at 2.0% by weight for all;

Females > 2 years: DMI is considered at 2.5 % by weight for breeding females and at 1.7% for slaughter;

for other cows, DMI is 2.0 % by weight.

The country specific Ym values, for the different subcategories, have been calculated (see Table A.7.8) with the formula proposed by Ellis (Ellis et al, 2007) based on daily DMI and forages proportion (FP) in the diet, considering the national weight and DMI values and assuming percentages of forages between 30% and 65%, (see previous section). Cattle < 1 year (reported in Table A.7.8) in Italy is baby beef: the average weight is 236 kg and daily consumption is in average 7.5 kg (5 kg of concentrates and 2.5 kg of silage and dry forage); dry matter intake is about 5 kg (equal to 2.1% live weight) and the percentage of forages is only about 30%.

Table A.7.8 Estimation of Ym values by non-dairy cattle subcategories

Livestock categories		Average live weight	Dry matter intake (DMI)	DMI (DMI= weight *DMI %)	DMI MJ/day	forages on dry matter %	CH ₄ - Ellis et al 2007 formula MJ/day	Methane conversion factors - Ym %
			% with respect to weight	kg/head/day				
< 1 year	others	236	2.1	4.85 (1)	89.4	30%	3.7	4.16%
1-2 years Male	breeding animal	557	2	11.14	205.5	65%	9.7	4.72%
	slaughter animal	557	1.7	9.47	174.7	55%	8.1	4.62%
1-2 years Female	breeding animal	405	3	12.15	224.2	65%	10.4	4.63%
	slaughter animal	444	2	8.88	163.8	55%	7.7	4.68%
> 2 years Male		700	2	14.00	258.3	55%	11.2	4.32%
> 2 years Female	breeding heifers	540	2.5	13.50	249.1	65%	11.3	4.54%
	heifers for slaughter	540	1.7	9.18	169.4	55%	7.9	4.65%
	other cows	557	2	11.14	205.5	55%	9.2	4.48%

(1) for this subcategory the previous value (CRPA, 1997[a]) very similar to the current one (4.96) has not been changed.

In 2026, a project will be launched with the CRPA, which will last about a year and will include various activities related to livestock farming. In particular, based on numerous studies and data collected, and through an analysis of existing literature and the most recent experimental contributions carried out in Italy on beef cattle, data relating to rations used, estimates of GE, DE and Ym parameters for cattle by subcategory, ration protein and corresponding nitrogen excretion will be verified and updated. The data estimated in the inventory will be verified at the same time and updated if necessary.

A7.2 Manure management (3B)

In this section the country-specific methodology for estimating the amount of manure sent to the bio-digesters and the amount of methane produced, to be subtracted from the total amount of methane deriving from manure management, is explained.

The inventory of methane emissions from manure management is based on a country specific methodology which also considers the share of manure sent to bio-digesters annually to recover power and heat.

In Italy the number of bio-digesters has been increasing for the last years in a significant way. Anaerobic digestion of animal manure allows for the recovery of energy and heat and for reducing methane emissions to air.

1) The anaerobic bio-digesters in Italy and relevant assumptions

The information available concerning heat and power production from biogas at anaerobic digesters fed with animal manure and agriculture residues (energy crops, agro-industrial by-products) is supplied by TERNA, MASE and CRPA.

TERNA, the Italian electricity transmission grid operator, reports annually the production of energy from traditional sources and from renewable. As for energy from biogas production in anaerobic digesters TERNA accounts for the number of digesters connected to the national grid and reports the power capacity, the energy production, combined heat and energy production and provides the figures separately for two categories:

- Bio-digesters receiving animal manure
- Bio-digesters receiving agriculture residues

The information is collected electronically and submitted by bio-digesters operators. TERNA's data about installed power, energy production, biogas used for energy production are then available for the inventory purposes (see data from renewable sources in sections "power plants" and "production" at <https://www.terna.it/it/sistema-elettrico/statistiche/pubblicazioni-statistiche>).

The Ministry of the Environment (MASE) prepares annually the National Energy Balance which is available on the Eurostat website (https://ec.europa.eu/eurostat/databrowser/view/nrg_bal_c/default/table?lang=en&category=nrg.nrg_quant.nrg_quanta.nrg_bal). Data on gas supply from 2017 from renewable sources (biomethane) are considered in the energy balance. The GSE (Energy services provider) provides annual biomethane production data broken down according to the organic matrices used for production.

CRPA is the Research Centre on Animal Production, among other activities it has been studying the implementation of anaerobic digestion in the agricultural sector of our country, and it has been carrying out surveys to build a picture of the anaerobic digestion plants in the livestock and agro-industrial sector in Italy. In the surveys total number of Italian anaerobic systems is considered, so the plants not connected to the national energy grid are included too. CRPA archive includes also information about the feed (plants working with animal manure, energy crops and agro-industrial by-products). Information about technologies and changes in technologies along the inventory time series is also available for inventory purposes.

Comparing the number of plants using manure in the CRPA surveys and those to TERNA, there is evidence that many operators using manure together with crops as a feed to digesters report their information to TERNA under the most general category agriculture residues.

Based on official data by TERNA and on information collected by CRPA (CRPA, 2013; CRPA, 2011[a]; ENAMA, 2011; CRPA, 2008[a]) the inventory team provides with the following picture concerning bio-digesters in Italy:

- As for technology, up to 2005 anaerobic digestion of animal manure was implemented at about less than 100 plants. In the '90s a typical reactor was a coverage storage structure where manure was stored and anaerobic digestion could occur, the output of the process being biogas mainly burned to recover heat for the livestock facility. In the following years, due to an increasing interest in anaerobic digestion and thanks to incentives to the sector, the implementation of multiple substrates (biomass) co-digestion at the same digester can be observed. Consequently, the type of process reactor has been changing too, with CSTR (completely stirred tank reactor) reactors becoming the largest share out of the total number of digesters.
- The number of installations has been significantly increasing for the last years (following table), thus affecting also the amount of CH₄ emissions released to the atmosphere, that's why the GHG emissions inventory should take into account also this practice.

In Table A.7.7 a summary of the information provided by TERNA and the estimated data for biogas production is supplied.

Table A.7.7 Anaerobic digesters in Italy

N° of plants and productions	Anaerobic digesters		Energy production			Biogas production
	Total n.	Animal manure n.	Total GWh	Animal manure GWh	Agricultural residues GWh	Total Mm ³
1990	0	0	0.0	0.0	-	-
1995	5	4	10.7	8.1	2.6	Not available
2000	10	5	8.8	4.9	3.9	Not available
2005	24	14	142.4	25.7	117	Not available
2010	176	95	611.2	221.0	390.2	839
2015	1,466	493	6,557.4	1,067.2	5,490	3,194
2020	1,734	656	6,892.3	1,293.7	5,599	3,581
2021	1,793	688	6,941.6	1,296.9	5,645	4,084
2022	1,850	719	6,739.3	1,277.0	5,462	4,066
2023	1,914	750	6,420.1	1,226.4	5,194	3,900

N° of plants and productions	Anaerobic digesters		Energy production			Biogas production
	Total	Animal manure	Total	Animal manure	Agricultural residues	Total
	n.	n.	GWh	GWh	GWh	Mm³
2024	1,987	774	6,463.6	1,205.7	5,257.9	3,951

Source: TERNA and estimated data for biogas production.

Official information about biogas/biomethane used and energy production at bio-digesters, provided by TERNA and reported in the National Energy Balance (as described above), and information about feed of the bio-digesters, provided by CRPA, allow for estimating the amount of slurry and manure fed annually to the Italian bio-digesters.

The biogas average yield and the chemical characteristics of substrates fed to digesters are described in Table A.7.8 supplied by CRPA (CRPA, 2012).

Table A.7.8 Average yields and average chemical characteristics of some substrates used for biogas production

Tabella 8 - Rese medie e caratteristiche chimiche medie di alcuni substrati utilizzabili per la produzione di biogas

Matrice	Solidi volatili (kg/t)	Biogas (m³/kg SV)	CH ₄ (%)	NTK (% ST)	Matrice	Solidi volatili (kg/t)	Biogas (m³/kg SV)	CH ₄ (%)	NTK (% ST)
Liquami zootecnici									
Liquame suino	30	0,50	67	8	Liquame bovino	82	0,35	55	4,7
Solido separato bovino	200	0,4	55	2,5	Letame bovino	210	0,40	55	2,7
Prodotti vegetali									
Insilato di sorgo zuccherino	282	0,6	53	1,8	Insilato di grano	289	0,60	53	1,7
Insilato di erba	248	0,56	52	2,7	Insilato di mais	310	0,65	53	1,4
Scarti agro-industriali animali									
Siero di latte	55	0,75	60	2,3	Sangue bovino	101	0,65	65	11,4
Contenuti ruminali bovini	176	0,75	53	2,6	Fanghi di macelli suini	160	0,35	60	3
Fango di flottazione avicolo	85	0,35	60	14,7	Fanghi di macelli bovini	122	0,35	60	4,8
Scarti agro-industriali vegetali									
Scarti di lavorazione del mais dolce	154	0,48	55	2,2	Bucchette e semi di pomodori	291	0,35	55	3,1
Scarti di leguminose	169	0,6	60	4,9	Scarti di lavorazione della patata	230	0,60	53	1,5

Dati CRPA

As for the types of feed treated in bio-digesters there has been a significant shift from single substrate feed to multiple substrates feed during the last years (CRPA, 2013; CRPA, 2011[a]); the share of bio-digesters treating animal manure only has been decreasing while the share of plants operating co-digestion of multiple substrates feed has been increasing.

Table A.7.9 Bio-digesters (%) by type of feed sent to anaerobic digesters over the years

Type of feed over the years	2007	2010	2011	2012
animal manure only (%)	56	36	29	18
animal manure+energy crops+ agricultural residues (%)	38	55	58	62
energy crops only (%)	6	9	13	20

Source: CRPA.

Because of multiple substrates fed to bio-digesters, the following average characteristics of the feed, as supplied by CRPA, are considered for the Italian bio-digesters to calculate the total amount of feed from animal manure anaerobic digestion (CRPA, 2018).

Table A.7.10 Type of feed sent to anaerobic digesters

Type of feed	Units	animal manure	energy crops	agro-industrial by-products
Animal manure only	% in the feed	100	0	0
Animal manure + energy crops + agro-industrial by-products	% in the feed	28	52	20
Animal manure + energy crops	% in the feed	38	62	0
Animal manure + agro-industrial by-products	% in the feed	69	0	31
Energy crops + agro-industrial by-products	% in the feed	0	81	19

Source: CRPA.

Based on the information reported above and in consideration of the typical feed of the bio-digesters the average parameters for animal manure, energy crops and agro-industrial by-products are those reported in Table A.7.11. The biogas methane content is generally reported to range from 50% to 65%, for inventory purposes and according to CRPA methane content is assumed to be 55% (CRPA/AIEL, 2008; CRPA, 2008[b]). As regards the average volatile solids content, values for animal manure and agro-industrial by-products have been changed based on the recent study of CRPA (CRPA, 2018).

Table A.7.11 Average parameters by the type of feed sent to anaerobic digesters

Parameters	Units	animal manure	energy crops	agro-industrial by-products
Average biogas producing potential	m ³ biogas/kg VS	0.4	0.6	0.6
Average CH ₄ content	%	55	55	55
Average volatile solids content	VS kg/t feed	139	280	237

Source: CRPA.

Based on all this information, total biogas generated from the amount of slurry and manure fed to bio-digesters can be estimated assuring that for the inventory purposes it does not include biogas generated based on other carbon sources than animal manure.

2) Losses from bio-digesters

Based on the information collected about the Italian bio-digesters, losses of biogas/methane can be characterized as:

- Biogas losses from anaerobic digestion unit (biogas escaping from the digester)
- Biogas losses from digestate storage
- Biogas losses from the combustion unit in the power&heat production step

As for point 1) according to the available literature on Italian bio-digesters (Fabbri *et al.*, 2011) and to the NIR of other EU Country (UBA, 2014) and to the 2023 EMEP/EEA Guidebook (EMEP/EEA, 2023) (see chapter 5.B.2 Biological treatment of waste – anaerobic digestion at biogas facilities, paragraph 2.3), where manure is processed in bio-digesters with similar technology implemented, the average losses of biogas is reported to be about 1% of the total biogas produced.

As for point 2) according to the IPCC Guidelines this contribution to the emission is equal to zero when covered storage units are in place. Based on our information, digestate covered storage units are in places at the Italian bio-digesters.

As for point 3) emissions resulting from power&heat production step are not to be allocated under agriculture for the purposes of the GHG emissions inventory and are already estimated and allocated in the energy sector.

3) Methodology and parameters

Based on the information supplied by TERN, MASE and CRPA, a country specific methodology to estimate the *amount of animal manure treated in the bio-digesters* has been developed for the years 2007, 2010, 2011 and 2012 onwards. The amount of animal manure sent to anaerobic digesters is used to

estimate both the equivalent number of heads and their related *CH₄ emissions to be subtracted* from the total CH₄ emissions from manure management and *CH₄ emissions from losses of the digesters*.

N₂O emissions from manure management have been revised too because the emission factors (EFs) for animal manure sent to digesters are different from EFs for the other manure management systems (liquid system and solid storage).

In addition, for the reporting purposes the CH₄ producing potential (Bo), the percentages of nitrogen allocation (by climate region and manure management systems) and methane conversion factors (MCF) have been revised for the relevant animal categories.

Amount of animal manure treated in bio-digesters

Official data about power capacity of digesters (TERNA) have been disaggregated based on the *distribution of digesters' installed power by type of feed* (CRPA).

Based on the operating hours, calculated from TERNA data on total energy production divided by the total installed power at digesters, the *energy production by type of feed* has been calculated for the relevant years.

TERNA data are used also to calculate the average energy efficiency and the lower heating value (LHV) that applied to energy productions allow for deriving the *amount of biogas used to produce energy per type of feed*. To calculate this quantity, National Energy Balance data on the availability of biomethane fed into the grid are also considered (as described before).

Considering the percentage of biogas losses at digesters, equal to 1%, and the percentage of biogas flared at digesters, equal to 4%, it is possible to estimate the *biogas produced per type of feed* from biogas used. In 2017 submission, in response to the UNFCCC review process, the percentage of biogas flared has been estimated.

From biogas produced per type of feed it is possible to estimate the *total amount of feed* using the maximum biogas producing capacity (m³ biogas/kg VS – volatile solid) and the VS content in the feed (kg VS/t feed).

To estimate the *amount of animal manure sent to digesters*, multiple substrates in the feed have to be considered taking into account the shares of different substrates in the feeds.

CH₄ emissions to be subtracted

In order to take into account the practice of manure management in anaerobic bio-digesters, the equivalent, in terms of MMS (liquid and solid), CH₄ emissions should be calculated on the basis of the amount of manure treated in these plants considering the equivalent number of heads and then subtracted from the total CH₄ emissions from manure management. This is because the country specific methodology calculates the average EFs by livestock based on national and international literature which refer to the "conventional" MMS of liquid and solid manure.

Manure sent to digesters has been distributed according to the type of manure (liquid/slurry and solid) and the animal category using the distribution of the national inventory.

Based on the coefficients of the national inventory related to annual production of manure per head and animal category and type of manure, it is possible to estimate *the number of head equivalent* per animal category and type of manure.

Finally, *CH₄ emissions from manure* sent to digesters are calculated multiplying these equivalent heads by EFs of the inventory expressed in kg CH₄/head per year.

CH₄ emissions from losses of bio-digesters

Losses from digesters are equal to 1% of biogas produced. Considering that CH₄ content is equal to 55% of biogas the resulting amount of CH₄ is calculated and added to the total CH₄ emissions from manure management and distributed by animal category.

N₂O emissions

Based on Ministerial Decree of 2006 and 2016 on the use of zootechnical effluents containing data on livestock manure production by stable type, effluent type, and animal category and based on excreted nitrogen coefficients per animal category and type of manure, the nitrogen quantities in livestock manure sent to anaerobic digestion were estimated. The coefficients, expressed as g N/kg manure, were

calculated gross of losses. The resulting coefficients were then multiplied by the quantities of manure sent for anaerobic digestion.

Consequently, the amount of nitrogen stored in the other storage system has been estimated subtracting these N amounts from the relevant animal categories and their type of manure.

Emission factor of the 2006 IPCC Guidelines has been used to estimate the N₂O emissions from manure stored in digesters. The value is zero as reported in the 2006 IPCC Guidelines (IPCC, 2006).

MCF for anaerobic digester

The methane conversion factor has been calculated according to Formula 1 in Table 10.17 in the 2006 IPCC Guidelines:

$$MCF = \frac{[(CH_4 \text{ prod} - CH_4 \text{ used} - CH_4 \text{ flared} + (MCF_{\text{storage}} / 100 * Bo * VS_{\text{storage}} * 0.67)]}{(Bo * VS_{\text{storage}} * 0.67)} * 100$$

Where:

CH₄ prod = methane production in digester, (kg CH₄).

Note: When a gas tight coverage of the storage for digested manure is used, the gas production of the storage should be included.

CH₄ used = amount of methane gas used for energy, (kg CH₄)

CH₄ flared = amount of methane flared, (kg CH₄)

MCF_{storage} = MCF for CH₄ emitted during storage of digested manure (%)

VS_{storage} = amount of VS excreted that goes to storage prior to digestion (kg VS)

Note: When a gas tight storage is included: MCF_{storage} = 0; otherwise MCF_{storage} = MCF value for liquid storage.

The equation (CH₄ prod - CH₄ used - CH₄ flared) is equal to CH₄ emissions from losses of bio-digesters that is equal to 1% of biogas produced (as reported above): 1502 Mmc (millions of cubic meters of biogas produced from manure in 2024) * 0.01 * 0.55 (methane content is assumed to be 55%) = 8.26 Mmc CH₄. The amount of volatile solids (VS) has been calculated multiplying the amount of animal manure by different type of feed treated in bio-digesters to the average VS content by different type of feed (these values can be obtained from the values shown in Table A.7.11): 2373 kt (animal manure only) * 139 kg VS/t feed + 1035 kt (animal manure from the co-digestion of multiple substrates such as "animal manure + energy crops + agro-industrial by-products") * 232 kg VS/t feed + 4837 kt (animal manure from the co-digestion of multiple substrates such as "animal manure + energy crops") * 226 kg VS/t feed + 8505 kt (animal manure from the co-digestion of multiple substrates such as "animal manure + agro-industrial by-products") * 169 kg VS/t feed = 3106 kt VS. CH₄ producing capacity (Bo) is equal to 0.22 mc CH₄/kg VS. MCF = [8.26 Mmc CH₄ / (3106 kt VS * 0.22 mc CH₄/kg VS)] * 100 = 1.21%. In addition, digestate covered storage units are in places at the Italian bio-digesters so according to the Guidelines MCF_{storage} is equal to 0.

The figure 0.22 mc CH₄/kg VS used in the calculation is an average of the values related to pigs slurry, cattle slurry and solid manure, cattle separate solid manure. These values represent the maximum methanogen potential and have been measured in the laboratory trying to simulate in a controlled environment what happens in an anaerobic digester (as reported in CRPA, 2012). This value is different respect to the values in CRT table3.B(a)s1 that have been estimated with the equation 10.23 of the 2006 IPCC Guidelines. However, the measured and estimated data should be comparable.

More information on the estimate of weighted average values of MCF and Bo for animal manure digested in anaerobic digesters has been provided above, reporting a numerical example of how the MCF value is calculated including information on the data sources for the different parameters used.

The biogas flared at bio-digesters has been assumed equal to 4% of the total biogas produced (CRPA, 2016).

In the CRT table 3B(a), the nitrogen allocation and MCF supplied by climate region and manure management systems are reported.

The average CH₄ producing potential reported in Table 3B(a) of the CRT has been revised accordingly using the average MCF for all manure management systems and the 2006 IPCC Guidelines' Equation 10.23.

4) Time series of total manure sent to anaerobic digestion

The amount of animal manure treated in the bio-digesters has been developed for the years 2007, 2010, 2011 and 2012 onwards, as described in the previous paragraphs. To develop the complete time series, the following assumptions have been considered taking into account the information provided by TERNA:

- For the years 1990 no changes in the estimation occurred because digesters were not in place;
- For the years 1991-2000 the amount of animal manure treated in the bio-digesters has been estimated based on the energy production from anaerobic digestion of animal manure;
- For the years 2001-2006 the amount of animal manure treated in the bio-digesters has been estimated based on the biogas from animal manure used for energy production;
- For the years 2008 and 2009 the amount of animal manure treated in the bio-digesters has been estimated based on the total biogas used for energy production.

In Table A.7.12-14, reported in the NIR submitted in 2024 (National Inventory Report - Italian Greenhouse Gas Inventory 1990-2022), available at the link <https://emissioni.sina.isprambiente.it/inventario-nazionale/>, all data, parameters and equations used to estimate CH₄ emission from manure management for cattle and buffalo are reported. These data are: the average monthly temperature; storage temperatures and timescale for emptying manure storages; the amount of manure generated by each subcategory of cattle and buffalo (m³/head day⁻¹); the *methane emission rates* (g CH₄/m³ day⁻¹) calculated on the basis of the equations 5.1 and 5.2 reported in the paragraph 5.3.2; the specific conversion factors (g CH₄/kg VS); the content of VS in manure (g VS/head day⁻¹) produced by different subcategories of cattle (dairy and non-dairy cattle) and buffalo (cow buffaloes and other buffaloes); the slurry and solid manure EFs (kg CH₄/head year⁻¹) calculated with Equations 5.3 and 5.4 respectively; the total (slurry and solid manure) amount of VS handled in slurry/liquid and solid manure management systems for the entire reporting period; the total (slurry and solid manure) CH₄ emission factors.

A7.3 Agricultural soils (3D)

Sewage sludge applied to soils

In Table A.7.15 parameters used for estimating direct and indirect N₂O emissions from sewage sludge applied to soils are presented.

Table A.7.15 Time series of sewage sludge activity data

Year	Total amount sewage sludge for agriculture (t dry matter)	N content (%)	N sewage sludge (t)
1990	98,164	5.2	5,071
1995	157,512	5.2	8,137
2000	217,424	5.0	10,954
2005	215,742	4.1	8,874
2010	248,215	4.0	10,040
2015	222,225	3.7	8,303
2020	180,415	3.9	7,078
2021	171,710	3.9	6,745
2022	151,934	4.2	6,375
2023	137,776	4.1	5,639
2024	150,562	4.1	6,112

Source: ISPRA elaborations from MASE (MASE, several years).

Bedding material in the estimates for the category animal manure applied to soils

A description of the types of agricultural residues considered in the estimates of the animal manure applied to soils (3Da2a), crop residues (3Da4) and field burning of agricultural residues (3F) categories is reported.

First, the agricultural residues are distinguished between removable and fixed. The last term is used to differentiate them from removable residues (such as straw and cereal stalks and residues of woody crops), “fixed” (no- removable) residues refer to residues which remain on the ground after harvest. The fixed residues include the remaining cereal stalks and the residues of other crops (such as beans, tubers, forages, grass, vegetables, etc.). The distinction between fixed and removable residues is required in the UNECE/LRTAP Convention.

From the cultivation of the crop (e.g. wheat), the product (grain), the removable residue (straw and wheat stalks) and the fixed residue (portion of the wheat stalks that remains on the ground after harvest) are obtained. As regards the removable residues, it is assumed that a portion (10% of residues) is burnt (first is removed from the field and then burned in the open air) and the corresponding emissions are reported in the waste sector (5C open burning of agricultural waste). Another portion (90% of residues) is used for various purposes (feed, bedding, construction, etc.). As regards the fixed residues, it is assumed that a portion (10% of residues) is burnt (the combustion of the residues takes place in the field) and the corresponding emissions are reported in the agriculture sector in 3F field burning of agricultural residues category. Another portion (90% of residues) is returned to soils and the corresponding emissions are reported in crop residues category (3Da4).

Considering the example of wheat, the total amount of durum wheat residues is thus distributed (2024 data):

72% are the removable residues used for various purposes (feed, bedding, construction, etc.),

18% are the fixed residues returned to soils,

8% are the removable residues burnt (removed from the field and then burned in the open air),

2% are the fixed residues burnt (the combustion of the residues takes place in the field).

As regard the estimate of the amount of straw used as bedding and the nitrogen content (see Table A.7.16), the following data are used: the number of dairy cattle, non-dairy cattle and buffalo (excluding pigs for which assumes only the liquid storage); the average weight of the subcategories of cattle and buffalo categories; the types of housings in each subcategory; the amount of straw per day (per tons of live weight, per type of housing for cattle and buffalo subcategories); the nitrogen content in straw. Data on the amount of straw per day (per tons of live weight, per type of housing, for cattle and buffalo) are contained in the Ministerial Decree of 25 February 2016 on the use of zootechnical effluents, combined with the manure production coefficients used in the estimation of methane emissions from storage. As recommended during the 2019 UNFCCC review, data on the quantity of bedding material used in solid manure management system are provided for 1990: 1.90 kg dm (straw)/head/day for dairy cattle; 1.42 kg dm (straw)/head/day for fattening cattle; 1.56 kg dm (straw)/head/day for replacement cows; 2.31 kg dm (straw)/head/day for other non-dairy cattle; 2.61 kg dm (straw)/head/day for buffalo. Data for 2024 are: 1.11 kg dm (straw)/head/day for dairy cattle; 1.44 kg dm (straw)/head/day for fattening cattle; 1.49 kg dm (straw)/head/day for replacement cows; 2.19 kg dm (straw)/head/day for other non-dairy cattle; 2.44 kg dm (straw)/head/day for buffalo. The amount of nitrogen estimated from bedding materials was added to the nitrogen input from manure applied to soils (3Da2a category) to estimate N₂O emissions.

Table A.7.16 Time series of estimated annual straw consumption (dry matter) and N content

Year	Dairy cattle – straw consumed	Non-dairy cattle – straw consumed	Buffalo – straw consumed	Total straw consumed	N in organic bedding material (straw consumed)
t					
1990	1,828,772	2,690,058	90,119	4,608,949	23,567
1995	1,439,743	2,807,134	138,572	4,385,448	22,231
2000	1,429,510	2,665,661	175,378	4,270,548	21,623
2005	1,275,139	2,324,638	183,317	3,783,094	18,994
2010	1,029,172	2,024,662	326,327	3,380,161	16,878
2015	889,833	1,843,130	334,438	3,067,401	15,283
2020	717,026	1,951,527	359,099	3,027,652	15,210
2021	663,000	2,309,613	363,300	3,335,913	16,772
2022	651,494	2,268,159	365,427	3,285,080	16,448
2023	660,065	2,162,289	371,300	3,193,654	16,086

Year	Dairy cattle – straw consumed	Non-dairy cattle – straw consumed	Buffalo – straw consumed	Total straw consumed	N in organic bedding material (straw consumed)
2024	637,111	2,157,299	371,672	3,166,082	15,940

Crop residues (FCR)

In Tables A.7.17-20, residues production and parameters used for emission calculation of nitrogen input from crop residues (FCR) for each type of crop are shown. Cultivated surface and crops production data are shown in the tables A.7.17-18 in Annex 7, reported in the NIR submitted in 2024 (National Inventory Report - Italian Greenhouse Gas Inventory 1990-2022), available at the link <https://emissioni.sina.isprambiente.it/inventario-nazionale/>.

As recommended during the 2019 UNFCCC review, to enhance transparency on the total amount of crop residues generated and shares of the crop residue amounts used for different purposes (such as bedding material (3.D.a.2.a), left on fields (3.D.a.4), burnt on-site (3.F) and off-site (1.A, 5.C.2)), a flow-chart is reported in Figure A.7.1.

Table A.7.17 Parameters used for emission of nitrogen input from crop residues (FCR)

Crops	Residues/Crop product mass ratio ⁽¹⁾	Residues/Crop surface (t/ha) ⁽²⁾	Dry matter of residues (%) ⁽³⁾	Reincorporated fraction ⁽⁴⁾	Protein in dry matter ⁽⁵⁾	N content of above-ground residues ⁽⁵⁾	Ratio of below-ground residues to above-ground biomass (RBG-BIO) ⁽⁶⁾	N content of below-ground residues (NBG) ⁽⁶⁾	Dry matter fraction of harvested product (DRY) ⁽⁶⁾	Slope ⁽⁶⁾	Intercept ⁽⁶⁾
Wheat	0.238		85	0.91	0.03	0.0048	0.24	0.009	0.89		
Rice	0.222		75	0.6	0.045	0.0072	0.16	0.014	0.89		
Barley	0.237		85	0.91	0.04	0.0064	0.22	0.014	0.89		
Maize, stalks	0.126		40	1	0.045	0.0072	0.22	0.007	0.87		
Maize, cobs	0.020		50	1	0.035	0.0056	0.22	0.007	0.87		
Rye	0.315		85	0.91	0.04	0.0064	0.24	0.011	0.88		
Oats	0.242		85	0.91	0.04	0.0064	0.25	0.008	0.89		
Sorghum		1.824	85	0.91	0.045	0.0072	0.24	0.006	0.89		
Triticum	0.2		85	0.91	0.04	0.0064	0.25	0.008	0.88		
Potatoes	0.4		40	0.9	0.09	0.0144	0.20	0.014	0.22		
Sweet potatoes	0.4		40	0.9	0.09	0.0144	0.20	0.014	0.22		
Sugar beet	0.07		20	0.9	0.125	0.0200	0.20	0.014	0.16		
Sunflower	0.4		60	0.9	0.025	0.0040	0.24	0.006	0.94		
Cabbage	2.5		15	0.9	0.175	0.0280	0.20	0.014	0.07		
Artichoke	2.5		15	0.9	0.135	0.0216	0.20	0.014	0.08		
Asparagus		2.8	8	0.9	0.09375	0.0150	0.20	0.014	0.08		
Salad		3.4	4.5	0.9	0.09375	0.0150	0.20	0.014	0.06		
Spinach		3.4	8	0.9	0.09375	0.0150	0.20	0.014	0.08		
Tomato	0.3		15	0.9	0.08	0.0128	0.20	0.014	0.06		
Cauliflower		3.8	8	0.9	0.09375	0.0150	0.20	0.014	0.08		
Pumpkin and zucchini		9.5	4.5	0.9	0.09375	0.0150	0.20	0.014	0.08		
Cucumber		8.5	4.5	0.9	0.09375	0.0150	0.20	0.014	0.04		
Eggplant		9.5	8	0.9	0.09375	0.0150	0.20	0.014	0.08		
Pepper and chili		9.5	8	0.9	0.09375	0.0150	0.20	0.014	0.07		
Onion		0.7	8	0.9	0.09375	0.0150	0.20	0.014	0.09		
Garlic		0.7	30	0.9	0.09375	0.0150	0.20	0.014	0.09		
Bean,freshseed		17.7	20	0.9	0.125	0.0200	0.19	0.008	0.91		
Bean,dryseed		0.6699	85	0.9	0.1	0.0160	0.19	0.01	0.9		

Crops	Residues/Crop product mass ratio ⁽¹⁾	Residues/Crop surface (t/ha) ⁽²⁾	Dry matter of residues (%) ⁽³⁾	Reincorporated fraction ⁽⁴⁾	Protein in dry matter ⁽⁵⁾	N content of above-ground residues ⁽⁵⁾	Ratio of below-ground residues to above-ground biomass (RBG-BIO) ⁽⁶⁾	N content of below-ground residues (NBG) ⁽⁶⁾	Dry matter fraction of harvested product (DRY) ⁽⁶⁾	Slope ⁽⁶⁾	Intercept ⁽⁶⁾
Broadbean,freshseed		17.7	20	0.9	0.125	0.0200	0.19	0.008	0.91		
Broadbean,dryseed		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Pea,freshseed		17.7	20	0.9	0.125	0.0200	0.19	0.008	0.91		
Pea,dryseed		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Chickpea		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Lentil		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Tare		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Lupin		0.6699	85	0.9	0.1	0.0160	0.19	0.008	0.91		
Soyabean		2.6	47.5	0.9	0.075	0.0120	0.19	0.008	0.91		
Alfalfa			90	0.2	0.16875	0.0270	0.40	0.019	0.9		
Clovergrass			90	0.2	0.16875	0.0270	0.40	0.022	0.9		
Other temporary forages				0.2		0.0180	0.59	0.013	0.9		
Perennial grasses				0.2		0.0150	0.80	0.012	0.9	0.3	

(1) CESTAAT, 1988; Motola et al., 2009; ENEA, 1994. (2) CRPA/CNR, 1992; ENEA, 1994; Motola et al., 2009. (3) IPCC, 1997; CRPA/CNR, 1992; CESTAAT, 1988; Borgioli, 1981; CREA expert judgment. (4) Values are the complement of the fraction of fixed residues burned (CRPA, 1997 [b]). Values also include the non-combusted portion of burned grain residues, which have a combustion coefficient C of 90%, except for rice, which is 80%. (5) Nitrogen in dry matter is equal to raw protein in residues (dry matter fraction) (CESTAAT, 1988; Borgioli, 1981) divided by factor 6.25 (100 g of protein/16 g of nitrogen). (6) Table 11.2 of the 2006 IPCC Guidelines.

Table A.7.18 Above-ground residues production for the estimation of nitrogen from crop residues

t dry matter	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Wheat	1,188,909	1,165,094	1,089,081	1,488,981	1,385,103	1,495,233	1,325,250	1,439,379	1,304,202	1,360,429	1,226,001
Rice	162,144	165,932	156,473	230,742	262,154	250,744	254,927	249,203	212,017	230,961	241,245
Barley	289,425	235,802	214,465	238,349	190,353	192,545	219,860	213,645	226,644	233,594	179,721
Maize, stalks	304,923	439,618	527,261	528,289	428,137	356,476	341,216	305,394	235,937	268,663	248,161
Maize, cobs	58,639	84,542	101,396	104,279	84,959	70,739	67,711	60,602	46,819	53,313	49,245
Rye	3,094	2,942	1,531	1,954	3,732	3,532	3,075	2,917	3,057	2,955	3,151
Oats	44,387	44,822	47,292	84,198	59,419	53,759	49,922	48,018	49,834	46,393	42,503
Sorghum	14,798	21,511	21,188	51,281	73,517	82,751	96,498	68,467	65,744	74,934	78,930
Triticum	1,782	2,246	0	0	0	0	0	0	0	0	0
Potatoes	369,392	332,943	328,487	280,910	249,285	216,865	229,544	217,940	213,277	202,471	226,032
Sweet potatoes	1,808	2,284	2,319	3,240	1,389	1,208	989	943	1,280	1,137	896
Sugar beet	164,758	184,636	161,969	198,180	49,698	30,574	25,635	21,150	15,544	19,580	21,482
Sunflower	96,840	128,059	110,571	69,448	51,096	59,522	71,507	67,340	63,435	73,281	68,597
Cabbage	184,350	169,008	180,805	179,615	188,608	175,280	157,739	155,063	151,462	148,763	154,758
Artichoke	182,625	193,961	192,355	176,241	180,042	150,501	137,655	141,104	141,791	138,643	140,234
Asparagus	16,929	18,256	15,444	18,038	17,805	17,913	20,721	20,848	20,892	20,208	26,085
Salad	165,665	167,579	174,144	170,035	161,060	138,199	139,112	135,514	112,790	123,984	132,703
Spinach	25,748	27,061	23,774	25,049	21,781	21,966	20,879	20,685	18,938	19,458	19,128
Tomato	246,108	232,767	336,931	323,416	271,204	288,461	281,156	299,016	276,137	270,722	271,026
Cauliflower	73,739	91,166	94,343	68,970	67,895	59,371	58,930	57,486	55,966	55,921	57,167
Pumpkin and zucchini	125,904	128,155	138,898	158,987	164,863	176,831	191,430	189,521	180,960	179,798	200,305
Cucumber	37,171	32,419	17,405	19,813	18,865	17,600	17,825	17,098	16,828	17,748	20,630
Eggplant	100,453	98,173	117,371	115,602	102,751	96,404	90,330	90,926	91,157	92,403	95,309
Pepper and chili	141,208	124,441	137,648	130,975	112,871	109,454	95,065	91,869	89,234	89,004	87,888
Onion	12,217	11,008	10,193	8,597	8,822	8,314	8,971	8,760	8,843	8,758	8,971
Garlic	3,295	2,849	2,574	2,214	2,076	2,131	2,301	2,513	2,610	2,493	2,442
Bean, freshseed	103,000	84,758	83,004	81,936	67,354	60,388	63,420	65,057	55,748	59,148	59,645
Bean, dryseed	13,098	8,235	6,290	4,985	3,986	3,342	3,155	2,998	1,987	2,463	2,595
Broadbean, freshseed	58,637	50,197	42,473	33,573	30,044	28,016	26,097	25,877	25,530	24,858	22,879
Broadbean, dry seed	59,245	36,019	27,241	27,621	29,671	24,005	35,293	32,575	28,504	25,873	27,785
Pea, freshseed	99,800	76,400	40,366	41,193	30,766	52,887	57,186	55,683	58,154	53,688	53,566

t dry matter	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Pea, dryseed	5,766	3,772	2,561	6,340	6,658	6,367	11,824	10,119	9,129	8,567	8,156
Chickpea	2,633	1,721	2,275	2,993	3,879	6,359	10,579	10,031	8,011	8,101	8,623
Lentil	597	591	579	1,017	1,400	1,765	3,196	3,251	2,804	2,991	3,035
Vetch	3,284	3,719	3,872	4,067	4,305	4,439	4,457	4,457	4,457	4,457	4,457
Lupin	1,881	1,748	1,879	1,424	1,937	1,912	325	370	404	404	410
Soyabean	643,644	241,061	316,959	188,129	196,996	381,589	316,325	352,548	423,027	383,740	415,878
Alfalfa	7,854,693	7,270,964	6,697,965	6,766,190	5,723,391	4,503,712	5,562,434	4,807,243	4,058,449	4,530,250	4,982,746
Clovergrass	1,702,107	782,757	647,406	594,891	535,275	569,079	573,873	546,785	598,406	888,192	559,917
Other temporary forages	4,350,008	10,402,911	9,686,763	9,010,062	8,245,854	8,517,150	10,644,779	10,494,472	9,529,309	11,905,651	12,554,196
Total	18,914,700	23,072,128	21,763,551	21,441,821	19,038,998	18,237,380	21,221,192	20,336,867	18,409,317	21,634,004	22,306,499

Table A.7.19 Estimate of nitrogen from crop residues of perennial grasses ⁽¹⁾

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Surface (ha)	855,117	931,388	893,737	828,835	879,405	924,270	832,254	791,733	744,229	752,725	736,996
Production (t)	15,213,383	16,945,600	15,841,500	13,853,700	14,478,400	11,766,500	9,445,691	9,085,736	8,114,003	8,870,207	9,089,002
Crop (kg dm/ha) ⁽²⁾	16,012	16,375	15,953	15,043	14,817	11,458	10,215	10,328	9,812	10,606	11,099
AG _{DM} (t/ha) ⁽³⁾	4.80	4.91	4.79	4.51	4.45	3.44	3.06	3.10	2.94	3.18	3.33
R _{AG} (kg dm/ kg dm) ⁽⁴⁾	0.3	0.3	0.3	0.3	0.3	0.30	0.30	0.30	0.30	0.30	0.30
R _{BG} (kg dm/ kg dm) ⁽⁵⁾	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
F_{CR} of perennial grasses (t N) ⁽⁶⁾	46,498	51,793	48,418	42,342	44,252	35,963	28,870	27,770	24,800	27,111	27,780

(1) According to the equations 11.6 and 11.7 of the 2006 IPCC Guidelines. (2) Harvested annual dry matter yield - kg harvested fresh yield / ha * DRY (dry matter fraction). (3) Above-ground residue dry matter calculated as (Crop/1000)*slope+intercept. (4) Ratio of above-ground residues dry matter to harvested yield, calculated as AG_{DM}*1000/Crop. (5) Ratio of below-ground residues to harvested yield, calculated as R_{BG-BIO}*[(AG_{DM}*1000+Crop)/Crop]. (6) Calculated according to equation 11.6 assuming Frac_{Renew}=1/5 for below-ground residues, Area burnt=0, Frac_{Remove}=0.8.


Table A.7.20 Total nitrogen content in the above-ground and below-ground crop residues

Total nitrogen (t N)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Wheat	23,349	22,881	21,388	24,555	22,210	23,976	21,250	23,080	20,913	21,814	19,659
Rice	3,637	3,722	3,419	4,593	5,462	5,325	5,424	5,305	4,518	4,917	5,138
Barley	7,244	5,902	5,368	5,450	4,283	4,333	4,947	4,807	5,100	5,256	4,044
Maize, stalks	10,521	15,169	18,193	18,589	15,125	12,593	12,054	10,789	8,335	9,491	8,767

Total nitrogen (t N)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Maize, cobs	8,275	11,931	14,309	14,716	11,989	9,983	9,555	8,552	6,607	7,524	6,949
Rye	75	71	37	35	64	61	53	50	52	51	54
Oats	878	887	936	1,423	979	886	823	791	821	764	700
Sorghum	265	447	445	647	941	1,038	1,235	834	770	905	948
Triticum	32	41	0	0	0	0	0	0	0	0	0
Potatoes	7,244	6,529	6,442	5,509	4,888	4,253	4,501	4,274	4,182	3,970	4,432
Sweet potatoes	35	45	45	64	27	24	19	18	25	22	18
Sugar beet	8,699	9,749	8,552	10,464	2,624	1,614	1,354	1,117	821	1,034	1,134
Sunflower	1,034	1,368	1,181	742	546	636	764	719	677	783	733
Cabbage	5,258	4,821	5,157	5,123	5,380	4,999	4,499	4,423	4,320	4,243	4,414
Artichoke	4,171	4,430	4,393	4,025	4,112	3,437	3,144	3,222	3,238	3,166	3,203
Asparagus	282	305	259	304	300	302	348	350	352	341	439
Salad	2,852	2,884	3,001	2,941	2,792	2,395	2,424	2,361	1,971	2,165	2,312
Spinach	439	465	408	431	375	379	363	360	330	340	335
Tomato	4,443	4,202	6,083	5,839	4,896	5,208	5,076	5,398	4,985	4,887	4,893
Cauliflower	1,286	1,591	1,654	1,221	1,202	1,054	1,042	1,018	991	991	1,014
Pumpkin and zucchini	2,128	2,169	2,357	2,701	2,801	3,002	3,255	3,224	3,075	3,056	3,396
Cucumber	616	538	290	331	314	293	297	286	281	297	347
Eggplant	1,698	1,668	1,993	1,960	1,743	1,639	1,541	1,551	1,555	1,577	1,646
Pepper and chili	2,369	2,092	2,315	2,206	1,898	1,840	1,598	1,545	1,500	1,495	1,479
Onion	322	298	276	231	240	231	262	248	244	238	246
Garlic	64	55	50	44	41	42	45	49	51	48	48
Bean,freshseed	2,335	1,932	1,922	1,902	1,572	1,384	1,462	1,505	1,292	1,365	1,377
Bean,dryseed	275	175	137	114	88	75	74	70	46	58	61
Broadbean,freshseed	1,269	1,098	930	730	657	611	574	561	553	538	498
Broadbean,dryseed	1,102	710	533	560	617	492	728	663	577	533	583
Pea,freshseed	2,181	1,671	888	903	673	1,136	1,227	1,200	1,239	1,148	1,155
Pea,dryseed	139	87	58	149	149	138	273	230	208	192	181
Chickpea	48	32	42	56	74	124	214	202	162	162	173
Lentil	11	11	10	18	25	32	58	59	50	54	56
Vetch	59	68	71	76	80	83	84	84	84	84	84
Lupin	36	35	37	28	37	37	7	7	8	8	8
Soyabean	10,351	3,983	5,161	3,083	3,191	6,246	5,233	5,570	6,464	6,183	6,618
Alfalfa	108,801	100,715	92,778	93,723	79,279	62,384	77,049	66,589	56,217	59,385	64,885
Clovergrass	30,827	14,177	11,725	10,774	9,694	10,307	10,393	9,903	10,838	14,019	9,781

Total nitrogen (t N)	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Other temporary forages	114,450	280,990	262,407	251,611	216,412	238,580	296,329	290,312	257,721	298,519	308,217
Perennial grasses	46,498	51,793	48,418	42,342	44,252	35,963	28,870	27,770	24,800	27,111	27,780
Total	415,598	561,734	533,669	520,208	452,032	447,134	508,447	489,094	435,973	488,736	497,802

Figure A.7.1. Flow-chart on the amount of crop residues generated and shares of the crop residue amounts used for different purposes



Note: part of the 38,229,714 tons of total crop residues is used to feed the anaerobic digesters, but at the moment it is not possible to quantify their size; the quantity of stubble burning and open burning refers to the amount of dry residues burnt.

ANNEX 8: ADDITIONAL INFORMATION OF THE ANNUAL INVENTORY SUBMISSION

A8.1 Annual inventory submission

This appendix shows Tables 10s1 and 10s6 from the Common Reporting Tables, submitted in 2026, in which time series of emission estimates are reported in CO₂ eq.

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
kt CO ₂ eq										
Total (net emissions) ⁽⁴⁾	506,285.81	490,328.91	491,589.68	497,506.74	478,513.50	498,176.25	493,653.59	509,688.67	525,011.58	521,423.81
1. Energy	426,247.87	426,334.84	426,044.40	421,152.79	416,238.77	438,789.19	435,613.43	441,453.22	454,135.61	458,671.04
1.A. Fuel combustion	412,012.03	412,272.92	411,908.80	406,955.21	402,386.50	425,367.36	422,510.61	428,238.45	440,946.37	446,530.52
1.A.1. Energy industries	137,667.27	132,035.17	131,251.64	125,409.74	127,866.27	140,675.65	135,331.57	137,715.68	138,955.79	133,547.15
1.A.2. Manufacturing industries and construction	92,150.78	89,471.25	89,483.42	88,035.34	89,822.04	90,203.86	89,332.30	93,414.46	96,853.35	101,831.99
1.A.3. Transport	102,190.52	104,816.36	109,985.19	111,652.42	111,516.84	114,215.52	115,950.84	117,888.72	122,307.35	123,872.74
1.A.4. Other sectors	78,867.80	84,651.13	79,798.43	80,285.18	71,597.77	78,713.19	80,616.85	77,889.32	81,703.44	86,078.73
1.A.5. Other	1,135.66	1,299.00	1,390.11	1,572.53	1,583.59	1,559.13	1,279.05	1,330.27	1,126.45	1,199.91
1.B. Fugitive emissions from fuels	14,235.84	14,061.92	14,135.60	14,197.59	13,852.27	13,421.83	13,102.81	13,214.77	13,189.24	12,140.52
1.B.1. Solid fuels	148.33	131.11	145.54	97.32	91.19	83.17	78.12	78.65	74.33	71.29
1.B.2. Oil and natural gas and other emissions from energy production	14,087.51	13,930.81	13,990.07	14,100.26	13,761.08	13,338.66	13,024.69	13,136.13	13,114.91	12,069.22
1.C. CO ₂ Transport and storage	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
2. Industrial processes and product use	37,945.93	37,505.53	37,093.07	34,253.80	32,982.20	36,298.88	33,492.38	34,119.88	35,208.72	35,999.00
2.A. Mineral industry	20,720.45	20,682.33	21,476.60	19,076.44	18,591.19	20,239.69	18,575.37	18,844.17	19,106.28	19,903.26
2.B. Chemical industry	9,626.06	9,905.71	9,427.94	8,911.37	8,282.03	9,370.71	8,327.04	8,526.13	8,592.25	8,430.52
2.C. Metal industry	6,232.18	5,596.08	4,750.25	4,730.71	4,367.57	4,293.36	3,693.37	3,477.33	3,271.99	2,717.81
2.D. Non-energy products from fuels and solvent use	369.53	340.32	333.21	306.27	308.73	322.92	313.77	318.82	317.87	319.30
2.E. Electronic industry	NO	NO	NO	NO	NO	222.95	218.76	240.76	300.19	284.82
2.F. Product uses as substitutes for ODS	NA,NO	NA,NO	123.94	227.11	395.38	621.94	874.32	1,180.93	2,154.78	3,064.21
2.G. Other product manufacture and use	997.71	981.08	981.13	1,001.91	1,037.29	1,227.32	1,489.74	1,531.74	1,465.37	1,279.07
2.H. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
3. Agriculture	36,045.28	36,801.12	36,232.78	36,590.27	36,141.13	36,103.10	36,142.94	36,610.65	35,958.19	36,411.14
3.A. Enteric fermentation	17,174.50	17,460.56	16,887.43	16,698.22	16,783.38	16,796.48	17,011.19	16,925.28	16,819.07	17,054.74
3.B. Manure management	8,384.45	8,416.46	8,079.06	8,019.32	7,856.79	8,015.99	8,035.40	8,017.26	8,076.63	8,167.89
3.C. Rice cultivation	2,101.64	2,005.86	2,082.82	2,183.95	2,239.56	2,227.63	2,194.49	2,178.83	2,058.12	2,016.08
3.D. Agricultural soils	7,855.89	8,320.55	8,566.22	8,986.50	8,595.69	8,477.07	8,393.55	8,887.39	8,413.46	8,558.18
3.E. Prescribed burning of savannahs	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
3.F. Field burning of agricultural residues	18.93	20.47	19.98	19.13	19.23	18.46	19.50	17.84	20.16	19.71
3.G. Liming	1.36	1.36	1.37	1.38	1.38	1.39	1.38	1.39	1.37	2.01
3.H. Urea application	464.84	519.31	536.33	621.90	588.39	512.05	439.22	525.41	526.32	550.90
3.I. Other carbon-containing fertilizers	43.68	56.54	59.56	59.88	56.70	54.03	48.20	57.27	43.05	41.62
3.J. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4. Land use, land-use change and forestry ⁽⁴⁾	-12,949.09	-30,054.22	-27,952.39	-15,192.29	-28,261.14	-35,023.09	-34,345.06	-25,949.81	-23,447.30	-32,805.11
4.A. Forest land	-20,287.49	-32,391.13	-31,049.38	-20,703.89	-31,131.74	-34,275.67	-34,094.36	-26,561.15	-25,114.27	-30,625.56
4.B. Cropland	2,035.29	494.39	973.95	469.35	288.02	1,346.89	2,055.49	1,503.02	1,195.92	721.36
4.C. Grassland	4,926.41	1,428.98	1,399.91	4,663.93	1,915.21	-1,919.43	-2,326.40	-1,022.73	679.02	-2,826.00

4.D. Wetlands	NE,NO	4.98	4.98	4.98	4.98	4.98	8.16	8.16	8.16	8.16
4.E. Settlements	766.16	504.37	510.21	515.18	521.00	527.11	812.25	814.28	816.14	818.44
4.F. Other land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4.G. Harvested wood products	-389.46	-95.81	207.93	-141.84	141.38	-706.96	-800.22	-691.38	-1,032.28	-901.51
4.H. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5. Waste	18,995.82	19,741.65	20,171.82	20,702.16	21,412.54	22,008.17	22,749.91	23,454.73	23,156.37	23,147.74
5.A. Solid waste disposal	13,670.94	14,370.76	14,855.65	15,505.31	16,219.11	16,937.94	17,695.93	18,332.85	18,033.73	18,087.65
5.B. Biological treatment of solid waste	23.31	28.30	33.29	38.28	56.22	53.90	44.71	114.14	138.13	183.17
5.C. Incineration and open burning of waste	598.36	639.35	631.76	588.87	592.45	546.83	547.54	572.16	568.39	490.97
5.D. Wastewater treatment and discharge	4,703.21	4,703.24	4,651.12	4,569.70	4,544.77	4,469.50	4,461.73	4,435.59	4,416.11	4,385.95
5.E. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
6. Other (as specified in summary 1)	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Memo items: ⁽⁵⁾										
1.D.1. International bunkers	8,636.79	8,658.01	8,457.94	8,865.86	8,989.99	9,822.01	9,090.98	9,259.83	10,376.50	10,523.86
1.D.1.a. Aviation	4,317.33	5,164.15	5,106.96	5,264.45	5,438.99	5,845.16	6,200.25	6,273.71	6,821.79	7,538.87
1.D.1.b. Navigation	4,319.46	3,493.86	3,350.98	3,601.41	3,551.00	3,976.86	2,890.73	2,986.12	3,554.71	2,984.98
1.D.2. Multilateral operations	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
1.D.3. CO₂ emissions from biomass	13,971.14	16,302.70	15,256.93	15,594.08	16,025.34	16,652.91	16,666.22	17,937.59	18,212.63	19,730.37
1.D.4. CO₂ captured	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5.F.1. Long-term storage of C in waste disposal sites	5,888.68	6,295.55	7,547.88	7,851.36	8,571.78	8,457.94	8,167.02	8,026.84	8,056.66	8,006.36
Indirect N₂O	2,725.18	2,786.85	2,840.05	2,729.21	2,595.67	2,543.86	2,462.72	2,379.67	2,257.83	2,128.92

Indirect CO₂ ⁽⁶⁾	1,391.49	1,400.65	1,429.95	1,392.56	1,354.85	1,295.92	1,253.50	1,253.78	1,211.87	1,214.22

Total CO₂ equivalent emissions without LULUCF	519,234.90	520,383.13	519,542.07	512,699.03	506,774.65	533,199.34	527,998.65	535,638.48	548,458.88	554,228.91
Total CO₂ equivalent emissions with LULUCF	506,285.81	490,328.91	491,589.68	497,506.74	478,513.50	498,176.25	493,653.59	509,688.67	525,011.58	521,423.81
Total CO₂ equivalent emissions, including indirect CO₂, without LULUCF	520,626.39	521,783.78	520,972.02	514,091.59	508,129.50	534,495.26	529,252.15	536,892.26	549,670.75	555,443.13
Total CO₂ equivalent emissions, including indirect CO₂, with LULUCF	507,677.30	491,729.56	493,019.63	498,899.30	479,868.35	499,472.17	494,907.09	510,942.45	526,223.45	522,638.03

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009
kt CO ₂ eq										
Total (net emissions) ⁽⁴⁾	528,238.26	520,234.09	522,285.04	549,698.54	548,777.38	548,556.99	534,014.50	548,787.38	521,452.09	464,700.41
1. Energy	460,604.13	459,301.81	466,146.69	483,892.59	487,670.85	488,370.73	482,640.52	476,719.47	467,778.03	418,437.71
1.A. Fuel combustion	448,483.71	447,838.65	454,878.88	472,196.35	476,979.60	477,764.15	472,718.27	466,970.05	458,044.68	409,242.29
1.A.1. Energy industries	144,963.23	143,470.27	154,480.42	159,572.49	161,414.98	159,921.93	162,173.61	159,138.16	156,056.73	134,074.57
1.A.2. Manufacturing industries and construction	96,245.30	91,622.94	89,478.54	95,663.42	94,527.82	92,299.33	89,145.16	91,277.83	86,801.22	64,570.13
1.A.3. Transport	123,954.08	125,715.21	128,110.86	128,250.66	129,942.03	128,361.73	129,593.98	129,628.37	122,796.67	117,259.73
1.A.4. Other sectors	82,444.24	86,651.20	82,473.22	87,989.74	89,895.19	95,866.85	90,727.86	85,940.75	91,576.08	92,404.09
1.A.5. Other	876.86	379.03	335.84	720.03	1,199.59	1,314.31	1,077.66	984.93	813.98	933.77
1.B. Fugitive emissions from fuels	12,120.42	11,463.16	11,267.81	11,696.24	10,691.26	10,606.58	9,922.26	9,749.42	9,733.35	9,195.42
1.B.1. Solid fuels	108.73	121.46	120.06	150.43	94.83	100.84	73.77	127.39	108.12	66.46
1.B.2. Oil and natural gas and other emissions from energy production	12,011.70	11,341.70	11,147.75	11,545.81	10,596.42	10,505.74	9,848.49	9,622.04	9,625.23	9,128.96
1.C. CO ₂ Transport and storage	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
2. Industrial processes and product use	38,240.47	40,587.78	41,406.44	43,460.48	46,509.81	47,134.84	43,606.52	43,659.66	41,091.52	35,726.15
2.A. Mineral industry	20,749.02	21,531.35	21,554.56	22,429.73	23,186.82	23,304.75	23,361.75	23,781.94	21,498.18	17,249.99
2.B. Chemical industry	9,048.01	9,329.07	9,098.25	9,205.72	10,283.10	9,686.78	5,342.57	4,651.96	3,666.14	2,908.08
2.C. Metal industry	2,755.28	3,027.44	2,784.86	2,481.05	2,416.50	2,769.71	2,663.02	2,632.48	2,646.75	1,905.98
2.D. Non-energy products from fuels and solvent use	332.02	298.14	308.17	297.65	290.80	303.36	287.33	296.12	280.16	228.07
2.E. Electronic industry	374.50	311.14	337.08	351.30	324.73	302.58	224.62	179.53	189.13	155.34
2.F. Product uses as substitutes for ODS	3,714.27	4,908.94	6,214.25	7,577.54	8,847.84	9,639.05	10,553.08	11,066.06	11,719.47	12,237.08
2.G. Other product manufacture and use	1,267.37	1,181.68	1,109.27	1,117.48	1,160.02	1,128.61	1,174.14	1,051.57	1,091.68	1,041.60
2.H. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
3. Agriculture	35,280.44	34,801.64	34,379.05	34,364.80	33,592.41	33,039.12	32,310.75	32,987.07	32,189.63	31,531.01
3.A. Enteric fermentation	16,631.41	15,812.70	15,335.66	15,451.78	14,577.92	14,520.68	14,108.39	14,617.48	14,527.18	14,551.49
3.B. Manure management	7,913.87	8,283.39	8,062.77	8,060.22	7,829.14	7,832.40	7,728.61	7,879.45	7,765.03	7,704.16
3.C. Rice cultivation	1,855.18	1,897.03	1,999.25	2,066.29	2,167.38	2,078.33	2,068.26	2,099.47	2,066.88	2,186.34
3.D. Agricultural soils	8,290.61	8,202.47	8,350.77	8,152.00	8,365.18	8,022.42	7,794.18	7,779.45	7,257.62	6,651.73
3.E. Prescribed burning of savannahs	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
3.F. Field burning of agricultural residues	18.48	17.57	20.11	18.52	22.94	21.54	20.92	20.03	21.45	16.98
3.G. Liming	1.85	2.12	6.32	6.24	10.20	14.36	11.78	15.66	18.46	17.40
3.H. Urea application	525.37	539.23	560.22	564.97	576.04	506.92	539.36	536.96	498.22	371.58
3.I. Other carbon-containing fertilizers	43.67	47.13	43.95	44.77	43.59	42.47	39.27	38.58	34.78	31.33
3.J. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4. Land use, land-use change and forestry ⁽⁴⁾	-29,981.10	-39,990.24	-44,352.07	-36,578.56	-42,901.82	-44,057.07	-48,004.21	-27,629.16	-42,051.84	-43,582.49
4.A. Forest land	-29,897.45	-35,754.13	-39,316.48	-33,304.20	-37,754.27	-38,898.27	-41,761.66	-28,101.63	-36,897.60	-37,997.44
4.B. Cropland	936.90	-1,223.74	-630.88	-289.45	-610.70	-462.52	-1,057.83	-1,039.06	-422.36	-509.90
4.C. Grassland	-1,395.33	-3,622.35	-4,901.51	-3,396.09	-4,815.40	-5,572.24	-5,858.38	857.05	-5,386.48	-5,997.81
4.D. Wetlands	8.16	8.16	8.16	8.16	8.16	8.16	8.16	8.16	8.16	129.57

4.E. Settlements	820.64	825.29	830.21	834.70	839.52	1,370.86	1,380.98	1,385.05	1,394.14	1,111.66
4.F. Other land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4.G. Harvested wood products	-454.03	-223.47	-341.57	-431.70	-569.13	-503.08	-715.49	-738.73	-747.71	-318.57
4.H. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5. Waste	24,094.32	25,533.11	24,704.93	24,559.23	23,906.12	24,069.38	23,460.91	23,050.35	22,444.75	22,588.04
5.A. Solid waste disposal	19,263.51	20,659.32	19,845.23	19,642.68	18,975.38	19,042.68	18,400.86	18,036.26	17,509.11	17,637.28
5.B. Biological treatment of solid waste	232.37	301.35	370.33	407.69	401.80	455.64	484.36	497.18	485.32	494.74
5.C. Incineration and open burning of waste	287.20	308.90	263.14	288.43	291.71	330.97	345.63	314.08	310.85	348.46
5.D. Wastewater treatment and discharge	4,311.23	4,263.53	4,226.23	4,220.44	4,237.22	4,240.09	4,230.06	4,202.82	4,139.47	4,107.56
5.E. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
6. Other (as specified in summary 1)	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Memo items: ⁽⁵⁾										
1.D.1. International bunkers	11,910.96	12,487.98	12,149.32	14,185.15	14,628.49	15,260.08	16,516.82	17,448.99	17,621.70	15,298.73
1.D.1.a. Aviation	8,020.99	7,924.62	6,862.91	7,975.69	8,014.61	8,544.59	9,273.29	9,837.32	9,444.32	8,330.47
1.D.1.b. Navigation	3,889.97	4,563.36	5,286.41	6,209.46	6,613.88	6,715.49	7,243.53	7,611.67	8,177.38	6,968.26
1.D.2. Multilateral operations	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
1.D.3. CO₂ emissions from biomass	18,785.89	18,547.69	13,507.56	20,088.41	16,266.67	23,498.98	26,860.19	34,507.61	41,460.30	42,955.96
1.D.4. CO₂ captured	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5.F.1. Long-term storage of C in waste disposal sites	8,458.86	8,617.42	7,864.48	7,410.29	7,075.46	6,975.19	6,772.13	6,148.90	5,933.35	5,637.65
Indirect N₂O	2,031.29	1,973.55	1,893.58	1,883.39	1,825.09	1,751.79	1,657.78	1,586.21	1,414.67	1,293.39

Indirect CO₂ ⁽⁶⁾	1,173.22	1,165.55	1,160.58	1,155.33	1,149.94	1,154.92	1,169.99	1,153.54	1,103.51	1,040.96

Total CO₂ equivalent emissions without LULUCF	558,219.36	560,224.34	566,637.11	586,277.10	591,679.19	592,614.07	582,018.70	576,416.55	563,503.93	508,282.90
Total CO₂ equivalent emissions with LULUCF	528,238.26	520,234.09	522,285.04	549,698.54	548,777.38	548,556.99	534,014.50	548,787.38	521,452.09	464,700.41
Total CO₂ equivalent emissions, including indirect CO₂, without LULUCF	559,392.58	561,389.89	567,797.69	587,432.43	592,829.13	593,768.99	583,188.69	577,570.09	564,607.44	509,323.86
Total CO₂ equivalent emissions, including indirect CO₂, with LULUCF	529,411.48	521,399.64	523,445.62	550,853.87	549,927.32	549,711.91	535,184.49	549,940.92	522,555.60	465,741.37

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019
kt CO ₂ eq										
Total (net emissions) ⁽⁴⁾	471,602.55	465,468.07	454,011.84	404,222.74	382,107.15	390,254.85	386,048.67	393,567.52	370,378.40	359,803.81
1. Energy	428,784.52	416,455.03	399,448.54	366,757.47	346,253.97	358,353.71	354,503.30	349,143.90	344,572.72	334,389.55
1.A. Fuel combustion	419,121.92	406,627.61	389,820.15	357,192.70	337,175.37	349,698.13	346,628.54	341,266.70	337,124.95	327,430.33
1.A.1. Energy industries	137,478.23	133,372.65	128,318.61	109,142.51	100,504.03	106,063.99	104,690.95	104,819.87	95,838.74	91,704.52
1.A.2. Manufacturing industries and construction	70,047.62	70,899.32	66,492.07	56,756.91	52,576.55	55,569.10	54,346.83	53,110.92	54,213.39	49,957.88
1.A.3. Transport	115,900.11	114,893.08	107,510.13	104,412.93	109,255.76	106,679.18	105,586.99	101,504.92	105,098.60	106,292.67
1.A.4. Other sectors	95,007.61	86,920.13	87,138.77	86,258.54	74,242.18	80,917.69	81,478.20	81,498.84	81,626.64	79,013.39
1.A.5. Other	688.35	542.43	360.58	621.81	596.84	468.16	525.56	332.16	347.57	461.88
1.B. Fugitive emissions from fuels	9,662.59	9,827.42	9,628.38	9,564.77	9,078.61	8,655.58	7,874.77	7,877.20	7,447.77	6,959.22
1.B.1. Solid fuels	96.67	102.67	89.57	65.39	63.92	58.93	55.25	41.07	38.39	36.01
1.B.2. Oil and natural gas and other emissions from energy production	9,565.93	9,724.75	9,538.82	9,499.38	9,014.69	8,596.65	7,819.52	7,836.13	7,409.38	6,923.21
1.C. CO ₂ Transport and storage	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
2. Industrial processes and product use	36,578.82	36,321.81	33,190.73	31,666.41	31,277.63	28,803.45	28,199.85	27,683.46	28,239.06	26,894.38
2.A. Mineral industry	17,341.49	16,713.25	13,775.44	12,281.06	11,685.33	11,291.17	10,691.55	10,871.57	10,992.33	11,005.66
2.B. Chemical industry	3,088.68	2,913.55	2,724.16	2,919.58	2,742.21	2,747.29	2,876.24	2,633.22	3,042.31	2,207.26
2.C. Metal industry	2,002.95	2,202.24	2,023.29	1,736.01	1,679.84	1,615.04	1,768.44	1,729.48	1,734.72	1,649.86
2.D. Non-energy products from fuels and solvent use	270.32	262.56	228.37	237.63	274.34	275.38	299.75	301.67	312.05	305.34
2.E. Electronic industry	206.47	241.01	217.87	232.86	259.57	246.06	240.72	244.19	247.84	235.29
2.F. Product uses as substitutes for ODS	12,776.22	13,093.36	13,276.69	13,380.83	13,846.20	11,777.06	11,509.23	11,046.24	10,996.25	10,643.68
2.G. Other product manufacture and use	892.69	895.84	944.91	878.43	790.14	851.43	813.92	857.07	913.57	847.30
2.H. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
3. Agriculture	30,753.29	31,050.16	31,470.22	30,715.37	30,145.62	30,169.26	31,145.29	30,357.92	30,112.08	29,869.32
3.A. Enteric fermentation	14,125.30	14,121.69	14,176.30	14,344.37	14,199.33	14,309.95	14,631.44	14,731.89	14,647.13	14,626.29
3.B. Manure management	7,474.57	7,655.69	7,401.96	7,233.10	7,032.03	6,943.06	6,883.94	6,828.32	6,679.63	6,612.84
3.C. Rice cultivation	2,254.87	2,212.51	2,137.82	2,067.42	1,936.59	1,943.42	1,914.35	1,836.66	1,803.25	1,720.68
3.D. Agricultural soils	6,501.37	6,641.64	7,145.94	6,573.78	6,518.97	6,498.87	7,104.76	6,490.17	6,524.93	6,465.57
3.E. Prescribed burning of savannahs	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
3.F. Field burning of agricultural residues	16.12	14.83	16.09	15.39	15.07	15.66	16.80	14.84	14.77	14.36
3.G. Liming	18.31	25.42	15.88	14.12	11.97	13.50	11.95	17.47	15.45	16.24
3.H. Urea application	335.10	350.76	550.91	450.42	411.00	424.93	561.07	418.45	405.26	396.45
3.I. Other carbon-containing fertilizers	27.65	27.63	25.33	16.77	20.66	19.87	20.98	20.12	21.65	16.88
3.J. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4. Land use, land-use change and forestry ⁽⁴⁾	-47,001.69	-40,110.39	-31,960.47	-45,356.17	-45,799.71	-47,445.04	-47,851.16	-33,571.56	-52,490.16	-51,078.43
4.A. Forest land	-40,144.12	-36,930.95	-32,956.25	-40,713.93	-41,464.86	-42,172.09	-41,258.70	-31,095.68	-45,659.15	-42,959.98
4.B. Cropland	323.43	1,754.58	2,830.72	2,367.04	2,202.71	1,682.10	-149.39	-10.12	303.50	184.22
4.C. Grassland	-8,278.97	-6,297.28	-3,281.60	-8,524.75	-7,979.72	-8,304.96	-7,475.97	-3,555.64	-8,382.67	-7,843.06
4.D. Wetlands	129.57	129.57	129.57	129.57	129.57	129.57	31.61	31.61	31.61	31.61

4.E. Settlements	1,110.40	1,113.92	1,115.59	1,120.95	1,126.47	1,132.09	1,007.68	999.20	997.46	994.82
4.F. Other land	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
4.G. Harvested wood products	-141.99	119.77	201.50	264.95	186.12	88.25	-6.39	59.06	219.08	-1,486.05
4.H. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5. Waste	22,487.61	21,751.46	21,862.84	20,439.67	20,229.64	20,373.48	20,051.37	19,953.81	19,944.70	19,728.99
5.A. Solid waste disposal	17,428.78	16,748.75	16,852.78	15,487.87	15,428.65	15,665.79	15,283.45	15,236.26	15,220.45	15,016.38
5.B. Biological treatment of solid waste	577.33	588.36	587.48	614.89	665.53	598.76	609.15	600.09	591.00	582.38
5.C. Incineration and open burning of waste	269.66	264.00	282.92	289.72	195.97	184.74	190.44	171.61	169.53	170.67
5.D. Wastewater treatment and discharge	4,211.83	4,150.36	4,139.66	4,047.18	3,939.48	3,924.18	3,968.34	3,945.84	3,963.72	3,959.56
5.E. Other	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
6. Other (as specified in summary 1)	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Memo items: ⁽⁵⁾										
1.D.1. International bunkers	17,084.36	15,939.08	15,812.28	14,965.33	14,175.22	14,645.06	16,204.10	17,200.47	18,238.77	17,935.82
1.D.1.a. Aviation	8,874.06	9,274.17	8,987.49	8,931.34	9,084.56	9,634.62	10,362.25	11,232.38	12,040.28	12,480.91
1.D.1.b. Navigation	8,210.30	6,664.91	6,824.79	6,033.99	5,090.65	5,010.45	5,841.85	5,968.08	6,198.49	5,454.91
1.D.2. Multilateral operations	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
1.D.3. CO₂ emissions from biomass	42,802.17	37,113.25	43,445.90	46,879.82	43,806.28	46,428.95	45,870.24	48,199.71	46,730.15	47,353.32
1.D.4. CO₂ captured	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
5.F.1. Long-term storage of C in waste disposal sites	5,451.35	5,267.94	4,633.13	4,111.95	3,829.18	3,273.99	2,743.14	2,174.87	2,027.06	1,901.06
Indirect N₂O	1,279.81	1,204.78	1,145.43	1,037.76	1,013.28	958.50	930.47	915.68	874.00	847.07

Indirect CO₂ ⁽⁶⁾	976.49	1,002.35	950.62	931.85	867.09	815.43	766.31	821.57	847.73	866.81

Total CO₂ equivalent emissions without LULUCF	518,604.24	505,578.47	485,972.32	449,578.91	427,906.86	437,699.90	433,899.82	427,139.08	422,868.55	410,882.25
Total CO₂ equivalent emissions with LULUCF	471,602.55	465,468.07	454,011.84	404,222.74	382,107.15	390,254.85	386,048.67	393,567.52	370,378.40	359,803.81
Total CO₂ equivalent emissions, including indirect CO₂, without LULUCF	519,580.73	506,580.82	486,922.94	450,510.76	428,773.95	438,515.33	434,666.13	427,960.65	423,716.28	411,749.06
Total CO₂ equivalent emissions, including indirect CO₂, with LULUCF	472,579.04	466,470.42	454,962.46	405,154.59	382,974.24	391,070.28	386,814.98	394,389.09	371,226.13	360,670.62

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2020	2021	2022	2023	2024	Change from 1990 to latest reported year
	kt CO ₂ eq					%
Total (net emissions) ⁽⁴⁾	329,476.04	361,118.54	359,876.50	318,731.45	298,550.20	-41.03
1. Energy	298,120.19	330,181.48	333,376.56	305,141.17	294,525.73	-30.90
1.A. Fuel combustion	291,961.16	324,575.27	328,354.52	300,637.45	290,074.98	-29.60
1.A.1. Energy industries	81,645.99	85,869.84	94,526.80	75,206.04	63,856.85	-53.62
1.A.2. Manufacturing industries and construction	45,839.27	55,139.60	53,468.43	49,644.72	46,158.55	-49.91
1.A.3. Transport	86,521.26	102,861.33	108,934.86	108,905.47	113,281.84	10.85
1.A.4. Other sectors	77,316.80	80,383.83	70,903.06	66,510.01	66,160.47	-16.11
1.A.5. Other	637.85	320.66	521.37	371.21	617.27	-45.65
1.B. Fugitive emissions from fuels	6,159.03	5,606.21	5,022.04	4,503.73	4,450.74	-68.74
1.B.1. Solid fuels	28.78	27.90	29.73	28.70	24.59	-83.42
1.B.2. Oil and natural gas and other emissions from energy production	6,130.25	5,578.31	4,992.31	4,475.02	4,426.15	-68.58
1.C. CO ₂ Transport and storage	NO	NO	NO	NO	NO	–
2. Industrial processes and product use	23,736.00	24,712.36	22,830.23	21,692.46	20,106.86	-47.01
2.A. Mineral industry	9,862.18	11,149.69	10,154.97	9,757.15	9,402.43	-54.62
2.B. Chemical industry	1,843.99	1,752.54	1,434.46	1,373.01	1,351.89	-85.96
2.C. Metal industry	1,467.17	1,783.80	1,627.67	1,522.61	1,416.42	-77.27
2.D. Non-energy products from fuels and solvent use	269.10	304.55	287.17	306.95	312.88	-15.33
2.E. Electronic industry	207.35	223.19	247.70	209.32	236.03	–
2.F. Product uses as substitutes for ODS	9,418.50	8,810.97	8,284.56	7,733.05	6,673.85	–
2.G. Other product manufacture and use	667.72	687.60	793.70	790.36	713.36	-28.50
2.H. Other	NA	NA	NA	NA	NA	–
3. Agriculture	30,880.96	30,225.62	28,345.64	29,282.51	28,008.99	-22.29
3.A. Enteric fermentation	14,814.61	14,694.53	14,517.71	14,314.12	13,487.82	-21.47
3.B. Manure management	6,626.91	6,473.90	6,453.02	6,520.92	5,960.46	-28.91
3.C. Rice cultivation	1,696.22	1,677.37	1,547.03	1,510.03	1,793.22	-14.68
3.D. Agricultural soils	7,225.31	6,901.92	5,577.93	6,480.59	6,316.46	-19.60
3.E. Prescribed burning of savannahs	NO	NO	NO	NO	NO	–
3.F. Field burning of agricultural residues	14.42	15.05	13.93	14.57	12.99	-31.37
3.G. Liming	9.98	25.59	4.22	5.20	3.70	172.86
3.H. Urea application	471.95	413.50	218.28	424.39	420.05	-9.63
3.I. Other carbon-containing fertilizers	21.56	23.75	13.53	12.70	14.29	-67.28
3.J. Other	NO	NO	NO	NO	NO	–
4. Land use, land-use change and forestry ⁽⁴⁾	-43,781.76	-44,293.61	-44,784.21	-57,564.63	-64,068.12	394.77
4.A. Forest land	-39,951.41	-41,834.37	-43,600.61	-52,660.71	-57,753.57	184.68
4.B. Cropland	3,163.43	1,494.12	1,511.34	1,404.12	243.19	-88.05
4.C. Grassland	-7,217.12	-4,273.57	-3,282.38	-5,773.77	-5,659.66	-214.88
4.D. Wetlands	31.61	NE,NO	NE,NO	NE,NO	NE,NO	–

4.E. Settlements	991.15	1,107.65	1,103.47	1,102.62	1,103.46	44.03
4.F. Other land	NO	NO	NO	NO	NO	–
4.G. Harvested wood products	-799.43	-787.44	-516.03	-1,636.90	-2,001.54	413.93
4.H. Other	NO	NO	NO	NO	NO	–
5. Waste	20,520.65	20,292.70	20,108.28	20,179.94	19,976.74	5.16
5.A. Solid waste disposal	15,924.65	15,641.74	15,524.99	15,642.51	15,419.40	12.79
5.B. Biological treatment of solid waste	560.37	558.50	528.84	500.54	504.89	2,065.96
5.C. Incineration and open burning of waste	166.11	183.90	170.35	165.98	163.50	-72.67
5.D. Wastewater treatment and discharge	3,869.52	3,908.56	3,884.10	3,870.91	3,888.94	-17.31
5.E. Other	NO	NO	NO	NO	NO	–
6. Other (as specified in summary 1)	NA	NA	NA	NA	NA	–

Memo items: ⁽⁵⁾						
1.D.1. International bunkers	8,045.63	10,678.73	14,204.56	16,329.29	17,210.80	99.27
1.D.1.a. Aviation	3,812.71	4,992.74	9,169.91	11,676.24	12,958.92	200.16
1.D.1.b. Navigation	4,232.92	5,685.98	5,034.65	4,653.05	4,251.88	-1.56
1.D.2. Multilateral operations	NE	NE	NE	NE	NE	–
1.D.3. CO₂ emissions from biomass	46,835.17	49,362.55	43,950.61	39,946.71	38,829.57	177.93
1.D.4. CO₂ captured	NO	NO	NO	NO	NO	–
5.F.1. Long-term storage of C in waste disposal sites	1,835.41	1,702.39	1,644.30	1,513.87	1,345.78	-77.15
Indirect N₂O	754.48	791.08	790.05	733.05	708.69	-73.99

Indirect CO₂ ⁽⁶⁾	876.32	857.77	790.02	843.16	871.48	-37.37

Total CO₂ equivalent emissions without LULUCF	373,257.80	405,412.15	404,660.71	376,296.08	362,618.32	-30.16
Total CO₂ equivalent emissions with LULUCF	329,476.04	361,118.54	359,876.50	318,731.45	298,550.20	-41.03
Total CO₂ equivalent emissions, including indirect CO₂, without LULUCF	374,134.12	406,269.92	405,450.73	377,139.24	363,489.80	-30.18
Total CO₂ equivalent emissions, including indirect CO₂, with LULUCF	330,352.36	361,976.31	360,666.52	319,574.61	299,421.68	-41.02

GREENHOUSE GAS EMISSIONS AND REMOVALS	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
	kt CO ₂ eq									
CO ₂ emissions without net CO ₂ from LULUCF	438,208.03	437,741.83	437,936.51	430,267.77	424,506.71	448,595.81	442,842.92	448,570.96	460,824.37	465,507.84
CO ₂ emissions with net CO ₂ from LULUCF	423,941.09	406,975.86	409,203.62	413,731.72	395,333.13	413,046.35	407,960.04	421,742.27	436,330.72	432,077.79
CH ₄ emissions without CH ₄ from LULUCF	55,015.61	56,038.09	55,829.85	56,188.07	56,642.24	57,139.26	57,759.59	58,317.57	57,844.61	57,878.53
CH ₄ emissions with CH ₄ from LULUCF	55,842.88	56,466.68	56,294.86	57,013.58	57,175.84	57,410.63	58,046.53	58,836.19	58,481.10	58,246.21
N ₂ O emissions without N ₂ O from LULUCF	22,603.39	23,525.10	23,191.20	23,680.23	23,071.26	24,212.75	24,429.25	25,280.97	25,467.97	26,005.10
N ₂ O emissions with N ₂ O from LULUCF	23,093.96	23,808.26	23,506.69	24,198.48	23,450.09	24,467.76	24,680.13	25,641.24	25,877.83	26,262.36
HFCs	372.00	376.47	503.58	602.28	773.72	1,099.50	976.90	1,389.69	2,347.10	3,099.82
PFCs	2,614.99	2,257.62	1,635.01	1,502.75	1,278.23	1,350.88	1,119.28	1,163.24	1,209.13	1,210.12
Unspecified mix of HFCs and PFCs	NA,NO	NA,NO	NA,NO	NA,NO	NA,NO	24.43	24.43	24.43	24.43	24.43
SF ₆	420.89	444.02	445.91	457.93	502.49	700.13	784.51	837.53	707.45	476.39
NF ₃	NA,NO	NA,NO	NA,NO	NA,NO	NA,NO	76.57	61.78	54.09	33.83	26.69
Total (without LULUCF)	519,234.90	520,383.13	519,542.07	512,699.03	506,774.65	533,199.34	527,998.65	535,638.48	548,458.88	554,228.91
Total (with LULUCF)	506,285.81	490,328.91	491,589.68	497,506.74	478,513.50	498,176.25	493,653.59	509,688.67	525,011.58	521,423.81
Total (without LULUCF, with indirect)	520,626.39	521,783.78	520,972.02	514,091.59	508,129.50	534,495.26	529,252.15	536,892.26	549,670.75	555,443.13
Total (with LULUCF, with indirect)	507,677.30	491,729.56	493,019.63	498,899.30	479,868.35	499,472.17	494,907.09	510,942.45	526,223.45	522,638.03

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
	kt CO ₂ eq									
1. Energy	426,247.87	426,334.84	426,044.40	421,152.79	416,238.77	438,789.19	435,613.43	441,453.22	454,135.61	458,671.04
2. Industrial processes and product use	37,945.93	37,505.53	37,093.07	34,253.80	32,982.20	36,298.88	33,492.38	34,119.88	35,208.72	35,999.00
3. Agriculture	36,045.28	36,801.12	36,232.78	36,590.27	36,141.13	36,103.10	36,142.94	36,610.65	35,958.19	36,411.14
4. Land use, land-use change and forestry ⁽⁴⁾	-12,949.09	-30,054.22	-27,952.39	-15,192.29	-28,261.14	-35,023.09	-34,345.06	-25,949.81	-23,447.30	-32,805.11
5. Waste	18,995.82	19,741.65	20,171.82	20,702.16	21,412.54	22,008.17	22,749.91	23,454.73	23,156.37	23,147.74
6. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total (with LULUCF) ⁽⁸⁾	506,285.81	490,328.91	491,589.68	497,506.74	478,513.50	498,176.25	493,653.59	509,688.67	525,011.58	521,423.81

GREENHOUSE GAS EMISSIONS AND REMOVALS	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009
	kt CO2 eq									
CO ₂ emissions without net CO ₂ from LULUCF	469,598.27	469,679.26	477,136.32	495,093.78	500,687.24	501,365.47	496,074.61	489,793.65	478,131.96	424,032.06
CO ₂ emissions with net CO ₂ from LULUCF	438,806.23	429,074.29	432,352.12	457,804.86	457,273.60	456,834.83	447,649.22	460,775.44	435,443.77	379,724.39
CH ₄ emissions without CH ₄ from LULUCF	57,833.28	58,151.35	56,280.25	56,615.40	54,263.60	54,793.10	53,213.36	53,928.89	53,436.74	53,192.15
CH ₄ emissions with CH ₄ from LULUCF	58,331.05	58,518.92	56,526.56	57,042.92	54,559.32	55,061.89	53,447.47	54,797.98	53,811.57	53,625.29
N ₂ O emissions without N ₂ O from LULUCF	25,018.27	25,164.03	24,801.24	24,625.24	25,426.72	24,404.08	19,764.31	19,393.85	18,095.81	17,183.10
N ₂ O emissions with N ₂ O from LULUCF	25,331.44	25,411.18	24,987.05	24,908.07	25,642.82	24,608.85	19,951.38	19,913.81	18,357.34	17,475.13
HFCs	3,747.60	4,944.19	6,243.48	7,612.55	8,877.54	9,669.03	10,583.53	11,095.42	11,738.58	12,246.64
PFCs	1,363.28	1,370.91	1,361.50	1,712.93	1,770.46	1,759.44	1,749.68	1,703.21	1,547.39	1,099.48
Unspecified mix of HFCs and PFCs	24.43	24.43	24.43	24.43	24.43	24.43	24.43	24.43	24.43	24.43
SF ₆	620.97	877.38	761.83	564.94	600.36	565.14	586.59	465.53	510.23	487.09
NF ₃	13.26	12.79	28.06	27.84	28.86	33.38	22.20	11.57	18.79	17.97
Total (without LULUCF)	558,219.36	560,224.34	566,637.11	586,277.10	591,679.19	592,614.07	582,018.70	576,416.55	563,503.93	508,282.90
Total (with LULUCF)	528,238.26	520,234.09	522,285.04	549,698.54	548,777.38	548,556.99	534,014.50	548,787.38	521,452.09	464,700.41
Total (without LULUCF, with indirect)	559,392.58	561,389.89	567,797.69	587,432.43	592,829.13	593,768.99	583,188.69	577,570.09	564,607.44	509,323.86
Total (with LULUCF, with indirect)	529,411.48	521,399.64	523,445.62	550,853.87	549,927.32	549,711.91	535,184.49	549,940.92	522,555.60	465,741.37

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009
	kt CO2 eq									
1. Energy	460,604.13	459,301.81	466,146.69	483,892.59	487,670.85	488,370.73	482,640.52	476,719.47	467,778.03	418,437.71
2. Industrial processes and product use	38,240.47	40,587.78	41,406.44	43,460.48	46,509.81	47,134.84	43,606.52	43,659.66	41,091.52	35,726.15
3. Agriculture	35,280.44	34,801.64	34,379.05	34,364.80	33,592.41	33,039.12	32,310.75	32,987.07	32,189.63	31,531.01
4. Land use, land-use change and forestry ⁽⁴⁾	-29,981.10	-39,990.24	-44,352.07	-36,578.56	-42,901.82	-44,057.07	-48,004.21	-27,629.16	-42,051.84	-43,582.49
5. Waste	24,094.32	25,533.11	24,704.93	24,559.23	23,906.12	24,069.38	23,460.91	23,050.35	22,444.75	22,588.04
6. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total (with LULUCF) ⁽⁸⁾	528,238.26	520,234.09	522,285.04	549,698.54	548,777.38	548,556.99	534,014.50	548,787.38	521,452.09	464,700.41

GREENHOUSE GAS EMISSIONS AND REMOVALS	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019
	kt CO ₂ eq									
CO ₂ emissions without net CO ₂ from LULUCF	434,573.38	423,282.14	402,619.13	368,339.14	348,010.60	359,658.46	356,287.13	350,864.93	347,137.79	337,659.13
CO ₂ emissions with net CO ₂ from LULUCF	387,059.23	382,498.63	369,473.44	322,673.27	301,811.61	311,845.38	308,014.55	315,897.19	294,312.44	286,214.44
CH ₄ emissions without CH ₄ from LULUCF	52,783.55	51,316.65	51,855.64	50,251.00	49,100.37	49,088.73	48,509.23	48,445.68	47,638.45	46,344.93
CH ₄ emissions with CH ₄ from LULUCF	53,077.73	51,724.12	52,606.97	50,435.81	49,351.82	49,327.55	48,773.38	49,340.28	47,825.67	46,543.93
N ₂ O emissions without N ₂ O from LULUCF	16,631.41	15,861.43	16,346.74	15,568.48	15,093.19	15,090.80	15,645.84	15,097.60	15,070.05	14,827.61
N ₂ O emissions with N ₂ O from LULUCF	16,849.70	16,127.08	16,780.63	15,693.37	15,241.02	15,220.02	15,803.12	15,599.16	15,218.02	14,994.86
HFCs	12,789.72	13,108.90	13,288.51	13,394.95	13,853.13	11,785.78	11,516.15	11,050.53	10,996.88	10,639.46
PFCs	1,376.64	1,503.76	1,357.00	1,543.53	1,430.09	1,539.79	1,472.37	1,206.20	1,518.14	932.43
Unspecified mix of HFCs and PFCs	24.43	24.43	24.43	24.43	24.43	24.43	24.43	24.43	22.74	23.15
SF ₆	404.94	453.38	455.94	431.69	366.88	483.50	410.69	426.22	462.37	437.59
NF ₃	20.17	27.78	24.93	25.70	28.17	28.42	33.98	23.50	22.13	17.94
Total (without LULUCF)	518,604.24	505,578.47	485,972.32	449,578.91	427,906.86	437,699.90	433,899.82	427,139.08	422,868.55	410,882.25
Total (with LULUCF)	471,602.55	465,468.07	454,011.84	404,222.74	382,107.15	390,254.85	386,048.67	393,567.52	370,378.40	359,803.81
Total (without LULUCF, with indirect)	519,580.73	506,580.82	486,922.94	450,510.76	428,773.95	438,515.33	434,666.13	427,960.65	423,716.28	411,749.06
Total (with LULUCF, with indirect)	472,579.04	466,470.42	454,962.46	405,154.59	382,974.24	391,070.28	386,814.98	394,389.09	371,226.13	360,670.62

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019
	kt CO ₂ eq									
1. Energy	428,784.52	416,455.03	399,448.54	366,757.47	346,253.97	358,353.71	354,503.30	349,143.90	344,572.72	334,389.55
2. Industrial processes and product use	36,578.82	36,321.81	33,190.73	31,666.41	31,277.63	28,803.45	28,199.85	27,683.46	28,239.06	26,894.38
3. Agriculture	30,753.29	31,050.16	31,470.22	30,715.37	30,145.62	30,169.26	31,145.29	30,357.92	30,112.08	29,869.32
4. Land use, land-use change and forestry ⁽⁴⁾	-47,001.69	-40,110.39	-31,960.47	-45,356.17	-45,799.71	-47,445.04	-47,851.16	-33,571.56	-52,490.16	-51,078.43
5. Waste	22,487.61	21,751.46	21,862.84	20,439.67	20,229.64	20,373.48	20,051.37	19,953.81	19,944.70	19,728.99
6. Other	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total (with LULUCF) ⁽⁸⁾	471,602.55	465,468.07	454,011.84	404,222.74	382,107.15	390,254.85	386,048.67	393,567.52	370,378.40	359,803.81

GREENHOUSE GAS EMISSIONS AND REMOVALS	2020	2021	2022	2023	2024	Change from 1990 to latest reported year
	kt CO ₂ eq					(%)
CO ₂ emissions without net CO ₂ from LULUCF	300,706.13	334,094.68	336,796.28	309,321.19	298,490.11	-31.88
CO ₂ emissions with net CO ₂ from LULUCF	256,425.76	288,795.70	291,186.94	251,103.30	233,880.43	-44.83
CH ₄ emissions without CH ₄ from LULUCF	47,053.61	46,565.15	45,119.59	44,269.26	43,003.48	-21.83
CH ₄ emissions with CH ₄ from LULUCF	47,326.90	47,159.28	45,593.18	44,620.27	43,272.79	-22.51
N ₂ O emissions without N ₂ O from LULUCF	15,277.18	15,210.04	13,557.83	14,267.59	13,789.07	-39.00
N ₂ O emissions with N ₂ O from LULUCF	15,502.50	15,621.29	13,909.37	14,569.84	14,061.33	-39.11
HFCs	9,415.01	8,806.20	8,278.76	7,725.69	6,669.55	1,692.89
PFCs	515.55	413.14	462.02	297.21	279.70	-89.30
Unspecified mix of HFCs and PFCs	22.37	25.33	22.13	28.65	32.68	–
SF ₆	251.71	282.38	404.60	366.74	328.01	-22.07
NF ₃	16.24	15.23	19.50	19.74	25.71	–
Total (without LULUCF)	373,257.80	405,412.15	404,660.71	376,296.08	362,618.32	-30.16
Total (with LULUCF)	329,476.04	361,118.54	359,876.50	318,731.45	298,550.20	-41.03
Total (without LULUCF, with indirect)	374,134.12	406,269.92	405,450.73	377,139.24	363,489.80	-30.18
Total (with LULUCF, with indirect)	330,352.36	361,976.31	360,666.52	319,574.61	299,421.68	-41.02

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	2020	2021	2022	2023	2024	Change from 1990 to latest reported year
	kt CO ₂ eq					(%)
1. Energy	298,120.19	330,181.48	333,376.56	305,141.17	294,525.73	-30.90
2. Industrial processes and product use	23,736.00	24,712.36	22,830.23	21,692.46	20,106.86	-47.01
3. Agriculture	30,880.96	30,225.62	28,345.64	29,282.51	28,008.99	-22.29
4. Land use, land-use change and forestry ⁽⁴⁾	-43,781.76	-44,293.61	-44,784.21	-57,564.63	-64,068.12	394.77
5. Waste	20,520.65	20,292.70	20,108.28	20,179.94	19,976.74	5.16
6. Other	NA	NA	NA	NA	NA	–
Total (with LULUCF) ⁽⁸⁾	329,476.04	361,118.54	359,876.50	318,731.45	298,550.20	-41.03

ANNEX 9: OVERVIEW OF THE CURRENT SUBMISSION IMPROVEMENTS

A9.1 Results of the UNFCCC review process

The last inventory review was conducted in 2025 as part of the first BTR review process. At the moment the review report is still under finalization and will be published on <https://unfccc.int/first-biennial-transparency-reports>.

A9.2 Results of the latest EU-internal inventory review process

In 2025, an EU Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841 has been carried out, aimed to set out the annual emission allocations (AEAs) of Italy for the years from 2026 to 2030, as required by Article 4.3 of Regulation (EU) No 2018/842 (the 'Effort Sharing Regulation', ESR) and the annual limit values of Italy for the years from 2026 to 2030, as required by Article 4.4 of Regulation (EU) No 2018/841 (the 'LULUCF Regulation').

During the EU review process, several critical issues were identified, leading to revisions of the estimates in different sectors.

The technical correction applied by the EU Comprehensive review for methane emissions from 3A Enteric fermentation (3A1b Non-dairy cattle) subcategories has not been addressed, based on the rationale explained in Section 5.2

In the LULUCF sector, the estimate of carbon stock changes from dead organic matter and litter pools under forest land has been significantly modified, as documented in section 6.2. Revised estimates have been provided so for land converted to settlements: detailed information on the applied methodologies is included in section 6.6.

The EU review recommendations, technical corrections or revised estimates for the inventory sectors and categories are provided in the table below.

Member State:	ITALY			
Year of latest EU-internal inventory review:	2025			
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
2F3 Fire Protection, HFCs, 2021- 2023	For category 2F3 Fire Protection and HFC emissions, the TERT noted that per capita emissions were high compared to those of other Member States. In response to a question raised during the review, Italy acknowledged that the underlying information needs to be reassessed and provided a revised estimate for the entire time series. The TERT disagreed with the revised estimate provided by Italy. The TERT decided to calculate a technical correction for the years 2021-2023, which was accepted by Italy. The estimates demonstrate that the issue is above the threshold of significance. The TERT recommends that Italy continue the on-going investigations regarding emissions from this category and include revised estimates in its next submission.	Table 4 - ESR Final Review Report	Addressed	par. 4.7

3A Enteric Fermentation (3A1b Nondairy cattle), CH₄, 2021- 2023	For category 3A Enteric Fermentation and CH₄ from non-dairy cattle the TERT noted that in response to a question raised during the review, Italy explained that it is using a country-specific methodology based on national feeding data. According to the country-specific methodology, the average CH₄ loss (Y_m, CH₄ conversion factor) for non-dairy cattle is 3.99% (2023). The TERT notes that the value is significantly lower than the default value in the 2006 IPCC Guidelines Vol. 4, Ch.10, table 10.12 (6.5%) and in its 2019 Refinement (6.3%, table 10.12 (updated)) and therefore, the emissions are likely to be under-estimated. During the review, Italy provided additional information on the methodology, types of breed raised as well as description of rations, but did not give sufficient justification regarding the national conditions that would support the low Y_m value. Italy also did not provide a revised estimate. More specifically, in the 2025 submission, Italy used an equation from Ellis et al. (2007) to estimate the Y_m factor. The TERT notes that the equation used is based on data obtained from 1964 to 2004 from 83 American beef animals. On the contrary, the TERT notes that the Y_m value in the 2019 Refinement to the 2006 IPCC Guidelines is based on several thousand measurements. According to Niu et al. (2018), which is a key reference used in the 2019 Refinement, the Y_m of US cattle is on average nearly 20% lower than that of EU cattle. Therefore, the TERT considers that a model built on US data with a limited number of observations is likely to lead to under-estimation of emissions. In response to a question raised during the review, Italy explained that the use of “model 10b” (Ellis et al., 2007) was recommended by CRPA (Research Centre on Animal Production). Input to this model is Dry Matter Intake (DMI) and Forage Properties (FP). Italy also explained that the use of that formula allows Italy to use country-specific data, whereas this data could not be used if the default value in 2019 Refinement to the 2006 IPCC Guidelines was used. The TERT welcomes the intention of Italy to use country-specific data; however, the TERT considers that the available feeding data could also be used with other models. To further justify the low Y_m factor, Italy provided feeding data (digestibility etc.) during the review but did not provide feeding plans with very high amounts (80-90 %) of corn grain and the share of the national non-dairy cattle herd fed with these feeding plans. The TERT has the opinion that a high share of corn grain is a requisite for having a reduced production of CH₄ in the rumen compared to grass feeding. The TERT noted that the provided data is from a research project and does not represent actual feeding data. The TERT also noted that the data provided is not significantly different from other European datasets, see e.g. the multinational database NorFor (https://www.norfor.info/services/norfor-feed-table/) and can therefore not be seen as an argument for significantly different feeding strategies resulting in a low Y_m. Italy also	Table 4 - ESR Final Review Report	Not addressed. Detailed information will be provided in the NID, par. 5.2 in Non-dairy cattle and in par. 5.2.6 Source-specific planned improvements	par. 5.2

	argued that the data used to develop the Ym values presented in the 2006 IPCC Guidelines and its 2019 Refinement are from countries which have livestock production systems that differ significantly from those in Italy. The TERT is of the opinion that production systems in general have little or no effect on the CH₄ emission from enteric fermentation from the rumen as this is mainly a feeding issue. Furthermore, in its justification for a low Ym value Italy noted that literature for non-dairy cattle shows Ym values ranging from 3.2% to 8.85%, and that the values are derived from studies that do not represent Southern Europe, and that studies specific for Italy were not available. The TERT is of the opinion that a (relatively wide) range cannot be used as an argument for selecting a low Ym. Instead, the TERT considers that a proper statistical analysis is needed with relevant feeding data to develop a reliable mean value. Furthermore, Italy explained that most Italian beef systems have high digestibility and therefore, the beef systems cannot be associated with the default IPCC Ym values of 6.5 or 6.3%, but are more comparable to feedlot systems, which are associated with much lower Ym values (3.0% in table 10.12 of 2006 IPCC Guidelines). The TERT considers that the value of feedlot fed cattle refers to grain-fed feedlot cattle and that the value is measured under American conditions. Furthermore, the low Ym is applicable when the cattle is fed with >90 % grain. The TERT considers that Italy has not provided documentation that this would generally be the case for non-dairy cattle in Italy. The TERT assumes that it is not a common practice in Italy as grain feeding is costly in Europe compared to grass/silage feeding. Furthermore, Italy assumes that part of calf population < 1yr ("white meat calves") are solely fed on milk (Table 5.9 in the NID) and thus do not emit CH₄. The TERT considers that this is unlikely as the rumen in ruminants starts developing and emitting CH₄ after approximately 2-4 weeks and the calves would not develop normally with only milk. The TERT acknowledged the discussion and additional information provided by Italy during online in-country visit. The TERT also welcomed the intention of Italy to continue the research on beef production. However, based on the reasoning above, the TERT concluded that the country-specific Ym value of Italy is not sufficiently justified. In particular, Italy has not provided sufficient justification that Equation 10b in Ellis et al. (2007) is applicable for Italian feeding conditions for non-dairy cattle. This is because the dataset used by Ellis et al. (2007) to develop the model parameters in equation 10b, include raw data which are not applicable for Italian/European feeding conditions, such as feeding data with 90 % corn grain from American feed-lot systems which are not occurring in Europe and from trials where the ionophore growth promoter, monensin, is included in the feedstuff. Monensin is known to reduce the CH₄ emission from enteric fermentation and was banned in cattle feed in the European			

	Union by 1 January 2006. The TERT decided to calculate a technical correction for the years 2021, 2022 and 2023. The estimates demonstrate that the issue is above the threshold of significance. The technical correction was not accepted by Italy. The TERT recommends that Italy include a revised estimate in its next submission.			

Member State:	ITALY			
Year of latest EU-internal inventory review:		2025		
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
2F1 Refrigeration and Air Conditioning, HFCs, 2021- 2023	For 2F1 Refrigeration and Air Conditioning and other F-gas subcategories, the TERT noted that significant amounts of F-gases are reported in the section on recovery. Recovered gases are increasingly being reused in the same or other equipment because of increasing prices for fresh refrigerants. Not including reused HFCs in the top-down estimate of the refrigerant supply will likely result in a systematic under-estimation of emissions. The TERT also notes that the current estimate is in accordance with the 2006 IPCC Guidelines and that available data does not allow to include the impact of HFC reuse in the inventory. The TERT decided not to carry out a technical correction, because due to lack of data, a technical correction would not have improved accuracy of the estimates. Therefore, the TERT recommends that Italy collect data and information on F-gas reuse in different subcategories, include these in the emission estimates, and provides a description of the situation in their NID.	Table 4 - ESR Final Review Report	Addressed	par. 4.7

3 Agriculture, CH4, N2O, 1990-2023	For CH4 from 3A Enteric Fermentation (CRT Table3.A) and 3B Manure Management (CRT Table3.B(a)), for direct and indirect N2O from manure management (CRT Table3.B(b)) and for N2O from Urine and dung deposited by grazing animals and from Animal manure applied to soils and related Indirect N2O Emissions from managed soils (CRT Table3.D) for all years the TERT noted that there could be an under- or over-estimate of the emission. This under- or over-estimate occurs both for categories estimated using Tier 1 and those estimated using Tier 2 and is due to the estimation of AAP (Annual Average Population) based on NAPA (Number of Animals Produced Annually) according to Eq. 10.1 of the 2006 IPCC Guidelines, which directly impacts the estimated feed consumption and the related excretion of Volatile Solids (VS) and nitrogen from growing lambs and kids. In response to a question raised during the review, Italy explained that "for estimating emissions from livestock, the number of livestock measured by the annual surveys of the National Institute of Statistics (ISTAT), which surveys the number of livestock on farms as of December 1 each year, is used. The surveyed values are considered statistically an average value of the livestock raised during the year (of all animal subcategories), which can be equated with the number of stalls present on livestock farms, which is the activity data needed to estimate emissions" and that the statistics are "in accordance with EU Regulation 1165/2008, which establishes the rules for carrying out EU livestock statistics and sets December 1st as the data collection date for representing the number of livestock raised annually." The TERT agrees with this. However, the TERT notes that a key question is how the data from December 1st is converted to AAP and consequently to annual feed consumed in the inventory year and especially how the numbers are related to feed consumption used for replacement of the existing animal herd and the calculation of feed consumption for the lambs/kids during their life stage. This issue becomes important when animal numbers for short living animals like part of the sheep and goat herd are estimated by the national statistics by December 1st when a large proportion of the offspring has already been slaughtered. In its statement to conclusions presented by the TERT Italy provided additional explanation including on the maintenance and production energy requirements of primiparous. The TERT noted that the number of mature ewes in 2023 is reported as 5.87 million (NID table 5.12). With a pregnancy rate of 93% and an average birth rate of 1.27 (NID Table 5.13), approximately 7 million lambs should be born. The number of lambs included in the calculation for 2023 is 533,627 heads (NID table 5.12) which are in the calculation spreadsheet provided by Italy during the	Table 4 - ESR Final Review Report	Not addressed. Detailed information will be provided in the NID, par. 5.2 in Sheep and in par. 5.2.6 Source-specific planned improvements	par. 5.2

	review used as 'lamb years' (multiplication with 365 days feed consumption). The approximate average life-span of a lamb can then be calculated to be 28 days. In the provided spreadsheet the share of the CH₄ emission of growing lambs out of the total enteric fermentation CH₄ emission of sheep is only about 1.5%. Furthermore, the model used in Italy for mature ewes assumes energy consumption for maintenance, pregnancy, milk and wool but no growth. Assuming a life-span for adult ewes of five years there will be a need for 1.2 million lambs growing to maturity, which seems not to be included in the calculation. The TERT decided not to carry out a technical correction, because due to lack of data, a technical correction would not have improved accuracy of the estimates. The TERT recommends that Italy in its next submission provide detailed information on how feed eaten by the replacement and feed eaten by lambs and kids are included in the inventory and revise the estimates, if appropriate.			

Member State: ITALY				
Year of latest EU-internal inventory review:		2025		
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
3 Agriculture, N ₂ O, 1990- 2023	For categories 3B Manure Management and 3D1bi Animal Manure applied to Soils and gas N₂O for all years the TERT noted that there was an inconsistency between the amount of nitrogen excreted reported in CRT table 3.B(b) minus total N volatilized reported in the same table, and the amount reported in CRT table 3.D for Animal manure applied to soils. In response to a question raised during the review, Italy explained that the difference was due to excluding N₂ from the N volatilized. The TERT agreed with Italy that this is a reporting issue and does not constitute a potential over- or underestimate. Italy suggested in its response to continue reporting of N volatilized without N₂ and to add a note in the documentation box of the CRT table. Italy also explained that inclusion of nitrogen loss as N₂ in the CRT table 3.B(b) would not facilitate checking the consistency between CRT tables 3.B(b) and 3.D because the calculation also considers other factors, such as N lost as N₂O and N included in litter material. However, the TERT is of the view that Italy should include the amount of N₂ in the CRT table, as indicated the heading of the respective column in CRT table 3.B(b): "Total N volatilized as NH₃, NO_x and N₂". This will improve transparency and comparability and help checking the consistency between reported amounts in CRT categories 3B and 3D1bi. Therefore, the TERT recommends that Italy include loss of N₂ in CRT Table 3.B(b) in its next submission.	Table 4 - ESR Final Review Report	Addressed. The quantity of N₂ emissions have been included in the CRT table 3.B(b) and a note have been also included. This note explains that the quantities of N from animal manure considered available in Table3.B(b) and the amount of N from animal manure applied to soils reported in Table3.D are equal for the entire time series. To calculate the managed manure nitrogen available for application to managed soils, we deducted from the amount of N managed in MMS the amounts of N lost as NH₃, NO_x, N₂, N₂O and leaching, reported in Table Table3.B(b). In addition, the amount of N lost as NH₃ from the pre-storage manure at biogas facilities and storage	par. 5.3

Member State: ITALY				
Year of latest EU-internal inventory review:		2025		
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
			of digestate were deducted. Finally, the amount of N contained in the bedding materials was added. As regards N ₂ O indirect emissions, it should be noted that adding N ₂ to the 'Total N volatilised as NH ₃ , NO _x ' would result in an inconsistency in the estimate of indirect N ₂ O emissions. According to the 2006 and 2019 IPCC guidelines, indirect N ₂ O emissions from Manure Management are calculated from the N volatilisation in forms of NH ₃ and NO _x from manure management systems and N ₂ emissions are not considered.	

Member State:	ITALY			
Year of latest EU-internal inventory review:	2025			
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
5D Wastewater Treatment and Discharge, CH4, 1990-2023	The TERT noted with reference to 5D2 Industrial Wastewater, for CH4 and all years, that there is a lack of transparency regarding in-situ wastewater treatment technologies. The TERT noted that it is indicated in the NID (page 362) that "It is assumed that industrial wastewaters are treated 85% aerobically and 15% anaerobically (IRSA-CNR, 1998)" without any information of the type of anaerobic WWTP considered and the associated MCF. In response to a question raised during the review, Italy explained that the assumption on the split between aerobic and anaerobic treatment pathways refers to an expert judgement (IRSA-CNR, 1998) and that in absence of typology of anaerobic treatment it is assumed that MCF is equal to 1 which is supported by expert judgment. Italy also noted that this is a conservative approach. The TERT decided not to carry out a technical correction, because due to lack of data, a technical correction would not have improved accuracy of the estimates. The TERT recommends that Italy include the information provided to the TERT in the next NID and investigate further among industries with in-situ wastewater treatment plants to more accurately determine the actual split between aerobic and anaerobic treatment and revise the estimates, as appropriate.	Table 4 - ESR Final Review Report	Addressed	par. 7.5

4A1 Forest land remaining forest land, CO₂, 1990-2022	During the initial review in February 2025, Italy confirmed that the For-est model is used for estimation of CO₂ emissions from wildfires, assuming complete oxidation of the biomass, deadwood and litter pools. The TERT considered this assumption to be conservative, which may lead to an overestimate of losses from biomass, deadwood and litter pools for the forest category reported in Table CRT 4.A. Italy subsequently provided a revised estimate, using country-specific combustion factors. The TERT accepted the revised estimates of the country provided for biomass gains and losses, but could not accept the revised estimates for carbon stock changes in deadwood and litter pools, due to concerns with regards to the revised methodology applied to the deadwood and litter pools. The TERT then provided a technical correction (TC) for the litter and deadwood pools. Italy disagreed with the TC and provided a second revised estimate for deadwood by applying the stock change method using the NFI 2005 and NFI 2019 data. Italy estimated the deadwood carbon stock change by linear interpolation of the NFI data between 2005 and 2019 and by linear extrapolation of the data for the period 2020-2023, applying the same annual rate of deadwood carbon stock changes. In addition, Italy provided revised estimates for the litter pool for land converted to forest land, based on the country-specific data and the IPCC default method. The TERT accepted the revised estimates for litter carbon stock changes, but could not accept the revised estimate for deadwood, as the stock changes in the deadwood pool cannot remain constant over time due to significant fluctuations in the area of fires and annual variation in harvest levels. Following Italy's initial response to the TC, the TERT adjusted the deadwood mortality inputs in the technical correction model using a scaling factor. Italy disagreed with the second TC carried out by the TERT and therefore submitted a third revised estimate of the deadwood carbon pool using the modified TC method and national data including a) a country specific carbon fraction for deadwood, b) harvest volumes and deadwood harvest residue inputs, c) a specific mortality rate for biomass in Italian forests, and d) a revised deadwood decomposition constant (k), available data. These revisions better represent the ecological and climatic conditions characteristic of Italian forest ecosystems. The final deadwood model now also reflects the impacts of C inflows from harvest residues, mortality and fires on forest deadwood dynamics. The derived deadwood stock and stock changes are also consistent with the measured stock derived from the Italian NFI. The TERT accepts the revised estimates for deadwood carbon pool for the forest land category for the years 2016-2018 and 2021-2023, but recommends that Italy include the revised estimate for biomass, deadwood and litter for the entire time series in its next inventory submission	Table 3 - LULUCF Final Review Report	Addressed	par. 6.2.4; 6.2.7

Member State:	ITALY			
Year of latest EU-internal inventory review:		2025		
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
4E2 Land converted to settlements, CO ₂ , 1990-2022	For 4E2 Land converted to settlements and carbon stock change (CSC) in mineral soils, the TERT noted that the methodology used by Italy is not in line with the 2006 IPCC guidelines. As the values reported in Table 4.E.2 do not reflect the actual CSC in mineral soils, TERT requested Italy to provide a revised estimate following equation 2.25 (Vol. 2, IPCC, 2006), assuming a default time period for the transition between equilibrium SOC (i.e. 20 years). In response to a question raised during the review, Italy provided the revised estimate and explained that this estimate takes into account the 20-year transition period and assumes a SOC value for settlements equal to 80% of the previous land use category, in line with the 2006 IPCC guidelines (Vol. 4, Ch. 8) and updated SOC values for annual and woody crops and grasslands. In addition, the TERT noted that direct and indirect nitrous oxide (N ₂ O) emissions from nitrogen (N) mineralization/immobilization associated with loss/gain of soil organic matter also need to be revised accordingly. Italy provided revised estimates for CO ₂ and N ₂ O emissions for the years 2016, 2017, 2018, 2021, 2022 and 2023. The TERT agreed with the revised estimate provided by Italy. The TERT recommends that Italy include the revised estimate for the entire time series in its next submission.	Table 3 - LULUCF Final Review Report	Addressed	6.6.4; 6.6.7
4 Land use, land-use change and forestry, CH ₄ , CO ₂ , N ₂ O, 2001-2023	The TERT notes with reference to all LULUCF land categories (i.e. CRT 4.A to 4.F) that the requirement related to the use of Approach 3 for land use changes according to the Governance Regulation, Annex V, Part III is not fulfilled. In response to a question raised during the review, Italy explained that the country is in the process of implementing an Approach 3 land classification system to ensure compliance with the Governance and LULUCF Regulations. To ensure that the reporting of emissions and removals in the LULUCF sector is compliant with the requirements in the LULUCF regulation, the TERT recommends to use activity data that meets the requirements of Approach 3 according to the 2006 IPCC Guidelines (e.g. repeated sampling approach a spatially defined grid and/or repeated wall to wall mapping sufficiently comprehensive to detect land use changes) in future submission.	Table 3 - LULUCF Final Review Report	Addressing	chapter 6

Member State:	ITALY			
Year of latest EU-internal inventory review:		2025		
CRT category / issue	Review recommendation, technical correction or revised estimate	Review report / paragraph	MS response / status of implementation	Chapter/section in the NIR
4B1 Cropland remaining cropland, CO ₂ , 2016-2023	For category 4B1 Cropland remaining cropland and CO₂ emissions from cultivated organic soils for years 2016-2018 and 2023 the TERT noted that these emissions account for more than 25% of the total net emissions in the category cropland remaining cropland and are therefore considered a significant pool. The TERT notes with reference to the method used for estimating CO₂ emissions from cultivated organic soils in cropland remaining cropland (NID 2025 p. 302) that the minimum requirements according to the LULUCF regulation, Annex V, Part 3 are not fulfilled. For the period 2021-2025, Member States shall use at least Tier 1 methodologies in accordance with the 2006 IPCC guidelines for national GHG inventories, except for a carbon pool that accounts for at least 25 % of emissions or removals in a source or sink category which is prioritised within a Member State's national inventory system because its estimate has a significant influence on a country's total inventory of GHGs in terms of the absolute level of emissions and removals, the trend in emissions and removals, or the uncertainty in emissions and removals in the land use categories, in which case, at least Tier 2 methodologies in accordance with the 2006 IPCC guidelines for national GHG inventories shall be used. In response to a question raised during the review, Italy explained that CO₂ emissions from organic soils have been identified as a key category due to the very large uncertainty of the applied default emission factor and stated that Italy will apply methodology and EFs provided in the 2013 Wetland Supplement in the next submission. To ensure that the reporting of CO₂ emissions from cultivated organic soils in cropland remaining cropland is compliant with the requirements in the LULUCF regulation, the TERT recommends that Italy apply at least Tier 2 methodology in accordance with the 2006 IPCC Guidelines or 2013 Wetland Supplement in its next submission.	Table 3 - LULUCF Final Review Report	Addressed	par. 6.2.4

ANNEX 10: REPORTING UNDER EU REGULATION 2024/1281

A10.1 Consistency with ETS data

Reporting on consistency of reported emissions with data from the EU emissions trading system. Year 2024					
Total emissions (CO ₂ eq.)					
Category[1]		Greenhouse gas inventory emissions [kt CO ₂ eq][3]	Verified emissions under Directive 2003/87/EC [kt CO ₂ eq][3]	Ratio in % (Verified emissions/ inventory emissions)[3]	Comment[2]
Greenhouse gas emissions (for GHG inventory: total GHG emissions, including indirect CO ₂ emissions if reported, without LULUCF, and excluding emissions from domestic aviation; for Directive 2003/87/EC: GHG emissions from stationary installations under Article 2(1) of Directive 2003/87/EC)	Total GHG	361,071.17	101,392.57	28.08%	
CO ₂ emissions (for GHG inventory: total CO ₂ emissions, including indirect CO ₂ emissions if reported, without LULUCF, and excluding CO ₂ emissions from domestic aviation; for Directive 2003/87/EC: CO ₂ emissions from stationary installations under Article 2(1) of Directive 2003/87/EC)	Total CO ₂	296,071.49	101,364.32	34.24%	

CO ₂ emissions					
Category[1]		Greenhouse gas inventory emissions [kt CO ₂ eq][3]	Verified emissions under Directive 2003/87/EC [kt CO ₂ eq][3]	Ratio in % (Verified emissions/ inventory emissions)[3]	Comment[2]
1.A Fuel combustion activities, total	CO ₂	284,057.83	87,729.19		
1.A Fuel combustion activities, stationary combustion	CO ₂	171,231.67	87,729.19	51.23%	
1.A.1 Energy industries	CO ₂	63,503.10	62,059.54	97.73%	
1.A.1.a Public electricity and heat production	CO ₂	43,637.82	42,194.26	96.69%	
1.A.1.b Petroleum refining	CO ₂	17,182.24	17,182.24	100.00%	
1.A.1.c Manufacture of solid fuels and other energy industries	CO ₂	2,683.04	2,683.04	100.00%	
Iron and steel (for GHG inventory combined CRT categories 1.A.2.a+ 2.C.1 + 1.A.1.c and other relevant CRT categories that include emissions from iron and steel (e.g. 1A1a, 1B1) (4))	CO ₂	11,589.51	9,787.80	84.45%	
1.A.2. Manufacturing industries and construction	CO ₂	45,250.92	24,622.03	54.41%	
1.A.2.a Iron and steel	CO ₂	7,674.19	5,892.19	76.78%	
1.A.2.b Non-ferrous metals	CO ₂	1,033.37	408.71	39.55%	
1.A.2.c Chemicals	CO ₂	7,057.56	3,545.77	50.24%	

CO ₂ emissions					
Category[1]		Greenhouse gas inventory emissions [kt CO ₂ eq][3]	Verified emissions under Directive 2003/87/EC [kt CO ₂ eq][3]	Ratio in % (Verified emissions/ inventory emissions)[3]	Comment[2]
1.A.2.d Pulp, paper and print	CO ₂	3,794.36	3,256.72	85.83%	
1.A.2.e Food processing, beverages and tobacco	CO ₂	3,188.69	1,481.79	46.47%	
1.A.2.f Non-metallic minerals	CO ₂	10,387.33	8,151.18	78.47%	
1.A.2.g Other	CO ₂	12,115.42	1,885.67	15.56%	
1.A.3. Transport	CO ₂	112,221.30	620.58	0.55%	
1.A.3.e Other transportation (pipeline transport)	CO ₂	747.54	620.58	83.02%	
1.A.4 Other sectors	CO ₂	62,477.65	427.03	0.68%	
1.A.4.a Commercial / Institutional	CO ₂	19,342.23	427.03	2.21%	
1.A.4.c Agriculture/ Forestry / Fisheries	CO ₂	6,323.16	0	0.00%	
1.B Fugitive emissions from Fuels	CO ₂	1,672.84	1,538.10	91.95%	
1.C CO₂ Transport and storage	CO ₂				
1.C.1 Transport of CO ₂	CO ₂				
1.C.2 Injection and storage	CO ₂				
1.C.3 Other	CO ₂				
2.A Mineral products	CO ₂	9,402.43	9203.17	97.88%	
2.A.1 Cement Production	CO ₂	6762.25	6792.04	100.44%	
2.A.2 Lime production	CO ₂	1,580.39	1543.51	97.67%	
2.A.3 Glass production	CO ₂	534.25	534.25	100.00%	
2.A.4 Other process uses of carbonates	CO ₂	525.54	333.36	63.43%	
2.B Chemical industry	CO ₂	1,145.21	1,528.41	133.46%	Include also emissions from urea production
2.B.1 Ammonia production	CO ₂	390.35	760.25	194.76%	Include also emissions from urea production
2.B.3 Adipic acid production (CO ₂)	CO ₂	1.58	1.58	100.00%	
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	CO ₂				
2.B.5 Carbide production	CO ₂	2.46	0	0.00%	
2.B.6 Titanium dioxide production	CO ₂				
2.B.7 Soda ash production	CO ₂	214.55	230.22	107.30%	
2.B.8 Petrochemical and carbon black production	CO ₂	536.27	536.35	100.02%	
2.C Metal production	CO ₂	1384.52	1365.44	98.62%	
2.C.1 Iron and steel production	CO ₂	1232.28	1212.58	98.40%	
2.C.2 Ferroalloys production	CO ₂				
2.C.3 Aluminium production	CO ₂				
2.C.4 Magnesium production	CO ₂				
2.C.5 Lead production	CO ₂				
2.C.6 Zinc production	CO ₂	152.24	152.86	100.41%	
2.C.7 Other metal production	CO ₂				

N ₂ O emissions					
Category[1]	Gas	Greenhouse gas inventory emissions [kt CO ₂ eq][3]	Verified emissions under Directive 2003/87/EC [kt CO ₂ eq][3]	Ratio in % (Verified emissions/ inventory emissions)[3]	Comment[2]
2.B.2. Nitric acid production	N ₂ O	20.87	22.7	108.98%	
2.B.3. Adipic acid production	N ₂ O	5.51	5.5	100.00%	
2.B.4. Caprolactam, glyoxal and glyoxylic acid production	N ₂ O				

PFC emissions					
Category[1]	Gas	Greenhouse gas inventory emissions [kt CO ₂ eq][3]	Verified emissions under Directive 2003/87/EC [kt CO ₂ eq][3]	Ratio in % (Verified emissions/ inventory emissions)[3]	Comment[2]
2.C.3 Aluminium production	PFC				

[1] The allocation of verified emissions to disaggregated inventory categories at four digit level must be reported where such allocation of verified emissions is possible and emissions occur. The following notation keys should be used: NO = not occurring IE = included elsewhere C = confidential negligible = small amount of verified emissions may occur in respective CRF category, but amount is < 5% of the category

[2] The column comment should be used to give a brief summary of the checks performed and if a Member State wants to provide additional explanations with regard to the allocation reported. Member States should add a short explanation when using IE or other notation keys to ensure transparency.

[3] Data to be reported up to one decimal point for kt and % values

[4] To be filled on the basis of combined CRT categories pertaining to 'Iron and Steel', to be determined individually by each Member State; the stated formula is for illustration purposes only.

[5] In accordance with the scope set out in Article 2(1) of Directive 2003/87/EC of activities listed in Annex I to that Directive other than aviation activities, 'maritime transport' activities and activities only listed in that Annex for the purposes of Articles 14 and 15 of that Directive. CO₂ emissions from the use of any biomass in stationary installations under Directive 2003/87/EC are accounted for as zero for the purposes of this Annex.'

Notation: x = reporting year

A10.2 Consistency with energy statistics

Reporting on consistency with energy statistics. Year 2024

FUEL TYPES			Apparent consumption reported in GHG inventory (TJ) ⁽³⁾	Apparent consumption using data reported pursuant to Regulation (EC) No 1099/2008 (TJ) ⁽³⁾	Absolute difference ⁽¹⁾ (TJ) ⁽³⁾	Relative difference ⁽²⁾ % ⁽³⁾	Explanations for differences	
Liquid fossil	Primary fuels	Crude oil	2,506,743.0	2,506,376.6	366.4	0.0%		
		Orimulsion						
		Natural gas liquids	366.4	366.4	0.0	0.0%		
	Secondy fuels	Gasoline	-276,421.6	-276,664.3	242.7	-0.1%		
		Jet kerosene	-75,247.2	-76,554.0	1,306.9	-1.7%	different values for NCV	
		Other kerosene	-7,816.4	-7,793.9	-22.5	0.3%		
		Shale oil						
		Gas/diesel oil	-97,421.2	-96,433.3	-987.9	1.0%		
		Residual fuel oil	-168,243.9	-165,315.1	-2,928.8	1.7%	different values for NCV	
		Liquefied petroleum gases (LPG)	101,029.0	100,908.8	120.2	0.1%		
		Ethane						
		Naphta	-19,024.9	-19,224.7	199.8	-1.1%	different values for NCV	
		Bitumen	-43,969.6	-44,040.5	70.9	-0.2%		
		Lubricants	-2,654.3	-2,773.6	119.3	-4.5%	different values for NCV	
		Petroleum coke	28,961.4	29,169.4	-208.0	-0.7%		
		Referiny feedstocks	64,639.4	64,639.4	0.0	0.0%		
		Other oil	-8,409.7	-8,409.7	0.0	0.0%		
		Other liquid fossil						
		Liquid fossil totals		2,002,530.3	2,004,251.3	-1,721.0	-0.1%	
Solid fossil	Primary fuels	Anthracite	4,275.3	4,275.3	0.0	0.0%		
		Coking coal	46,932.3	46,932.3	0.0	0.0%		
		Other bituminous coal	50,102.5	50,102.5	0.0	0.0%		
		Sub-bituminous coal	0.0	0.0	0.0			
		Lignite	15.4	15.4	0.0	0.0%		
		Oil shale and tar sand	0.0	0.0	0.0			
	Secondary fuels	BKB and patent fuel	0.0	0.0	0.0			
		Coke oven/gas coke	-4,201.8	-4,201.8	0.0	0.0%		
		Coal tar	-956.9	-956.9	0.0	0.0%		
	Other solid fossil		0.0	0.0	0.0			
Solid fossil totals		96,166.7	96,166.7	0.0	0.0%			

Gaseous fossil	Natural gas (dry)	2,131,919.9	2,119,705.9	12,214.0	0.6%	
Other gaseous fossil		0.0	0.0	0.0		
Gaseous fossil totals		2,131,919.9	2,119,705.9	12,214.0	0.6%	
Waste (non-biomass fraction)		48,024.0	49,477.4	-1,453.3	-3.0%	different values for AD and NCV
Other fossil fuels		0.0		0.0		
Peat		0.0		0.0		
Total		4,278,640.9	4,269,601.2	9,039.7	0.2%	

(1) Apparent consumption reported in GHG inventory minus apparent consumption using data reported pursuant to Regulation (EC) No 1099/2008


(2) Absolute difference divided by apparent consumption reported in GHG inventory

(3) Data to be reported up to one decimal point for TJ and % values

ANNEX 11: FOR-EST MODEL

For-est is a book keeping model (Figure A11.1) that calculates annually the C stock of the aboveground biomass pool, as derived from the growing stock, by adding the annual net increment and subtracting annual losses associated with formal and informal⁵⁸ harvest (industrial roundwood and fuelwood), forest fires and other mortality, which includes all other disturbances⁵⁹ (i.e. drought, grazing, wind).

Figure A11.1 *For-est* model flow-chart



The model is applied to each of the 26⁶⁰ forest inventory typology, at regional/provincial scale (NUTS2 - 19 regions⁶¹ and 2 provinces), using as model input data for the forest area and initial growing stock of the first NFI (NFI1985), the forest area of the second and third NFIs (NFI2005, NFI2015), the preliminary results of the ongoing fourth NFI (NFI2025) and the Italian Forest Map (CFI2020), available through the National Information System for Forests and Forest Supply Chains (SINFor⁶²). An independent verification (Tabacchi et al., 2010) of the model results versus measured data was carried out in the year 2008 by comparison of the growing stock calculated by the model vs the data collected in the second national forest inventory⁶³, showing that the difference between the measured and modelled biomass C stocks is around -7%; which means that the model has underestimated by almost 0.3% net C stocks per year across the period 1985-2008.

Consistently, the time series of growing stock values in each forest inventory typology in each region/province is estimated applying the following steps:

⁵⁸ "Informal harvest" includes all harvest not captured by the official system of statistics either because occurring outside the chain of data collection, e.g. domestic fuelwood collection, or because may have occurred outside the planned harvest, e.g. small areas for which no harvesting plan is required and illegal harvest.

⁵⁹ Although natural mortality does not explicitly include losses caused by exceptional occurrences of those other disturbances, such exceptional losses are included in the national GHG inventory through the subsequent salvage logging of those lost biomass stocks.

⁶⁰ 4 different management system of practices (High stands, Coppices, Plantations, Protective) are combined with 22 forest types to classify 26 forest inventory typologies:

Stands: 1. norway spruce, 2. silver fir, 3. larches, 4. mountain pines, 5. mediterranean pines, 6. other conifers, 7. European beech, 8. turkey oak, 9. other oaks, 10. other broadleaves.

Coppices: 11. European beech, 12. sweet chestnut, 13. hornbeams, 14. other oaks, 15. turkey oak, 16. evergreen oaks, 17. other broadleaves, 18. conifers.

Plantations: 19. eucalyptus coppices, 20. other broadleaves coppices, 21. poplar stands, 22. other broadleaves stands, 23. conifers stands, 24. others.

Protective Forests: 25. rupicolous forest, 26. riparian forests

⁶¹ Abruzzo, Alto Adige/Sud Tirolo, Basilicata, Calabria, Campania, Emilia Romagna, Friuli Venezia Giulia, Lazio, Liguria, Lombardia, Marche, Molise, Piemonte, Puglia, Sardegna, Sicilia, Toscana, Trentino, Umbria, Valle d'Aosta, Veneto.

⁶² National Information System for Forests and Forest Supply Chains (SINFor): <https://sinfor.sian.it/>

⁶³ https://www.sian.it/inventarioforestale/jsp/risultati_introa.jsp?menu=3

- 1) deriving the initial growing stock volume for the year 1985 from the NFI data (MAF/ISAFA, 1988);
- 2) for each year, the current increment per hectare [$\text{m}^3 \text{ ha}^{-1} \text{ yr}^{-1}$] is computed with the forest inventory typology specific derivative Richards function, for each forest inventory typology using as independent variable x the per hectare growing stock.
- 3) for each year, the following losses are calculated:
 - a. harvest, statistical data collected from ISTAT on industrial roundwood production (all assigned to "*stands*" forests), fuelwood (all assigned to "*coppices*" forests) and wood outside forest (all assigned to "*plantations*" forests). From 2022 onwards, harvest data, by region, are available on the National Information System for Forests and Forest Supply Chains (SINFor⁶⁴). Aiming at considering the informal⁶⁵ harvest, the time series (1990-2021) has been recalculated, applying a correction factor, on regional basis, to the commercial harvested wood statistical data (Table A11.2). The correction factor⁶⁶, was inferred from the outcome of a 2005 NFI survey⁶⁷ (Table A11.1), carrying out a regional assessment of the harvested biomass. In each region/province, harvested quantities are assigned to each forest inventory typology in proportion to its total annual increment. The correction factors, at regional level, are reported in table A11.3.

Table A12.1 NFI survey - harvested volume

Region	Harvested volume	S.E.	Harvested volume	S.E.
	m^3	%	$\text{m}^3 \text{ ha}^{-1}$	%
Piemonte	1,360,223	31	1.6	30.9
Valle d'Aosta	-	-	-	-
Lombardia	1,039,728	52.7	1.7	52.7
Alto Adige (Bolzano)	862,811	62.4	2.6	62.4
Trentino	1,348,355	40.7	3.6	40.6
Veneto	475,573	40	1.2	39.9
Friuli - Venezia Giulia	462,541	67.3	1.4	67.3
Liguria	372,380	61.9	1.1	61.9
Emilia Romagna	362,005	62.2	0.6	62.2
Toscana	1,745,382	28.1	1.7	28
Umbria	1,294,494	43.6	3.5	43.6
Marche	418,031	74.9	1.4	74.9
Lazio	1,576,155	54.5	2.9	54.5
Abruzzo	388,752	51.8	1	51.7
Molise	200,825	54.5	1.5	54.4
Campania	915,244	59.6	2.4	59.6
Puglia	255,981	60.5	1.8	60.5
Basilicata	7,820	71.4	0	71.4
Calabria	624,762	53	1.3	53
Sicilia	23,477	58	0.1	57.9
Sardegna	62,323	53.3	0.1	53.2
Italia	13,796,864	12.9	1.6	12.9

⁶⁴ National Information System for Forests and Forest Supply Chains (SINFor): <https://sinfor.sian.it/#/carta>

⁶⁵ Data on biomass removed in commercial harvest have been judged underestimated, particularly fuelwood consumption (APAT - ARPA Lombardia, 2007, UNECE – FAO, Timber Committee, 2008, Corona et al., 2007).

⁶⁶ A correction factor for each Italian region (21) has been pointed out. The mean value is 1.57, obtained as ratio of data from official statistics and NFI survey data. The variance is equal to 0.82.

⁶⁷ NFI survey on harvested volume: <http://www.sian.it/inventarioforestale/caricaDocumento?idAlle=442>

Table A11.2 ISTAT data: harvested volume

Region	Harvested volume
	m^3
Piemonte	363,846
Valle d'Aosta	16,279
Lombardia	1,060,701
Alto Adige (Bolzano)	589,191
Trentino	484,906
Veneto	270,880
Friuli - Venezia Giulia	180,544
Liguria	96,515
Emilia Romagna	485,777
Toscana	1,477,135
Umbria	471,070
Marche	192,068
Lazio	875,408
Abruzzo	203,632
Molise	159,104
Campania	518,376
Puglia	101,776
Basilicata	299,019
Calabria	753,042
Sicilia	59,850
Sardegna	139,751
Italia	8,798,869

Table A11.3 Correction factors

Region	Correction factor
Piemonte	3.74
Valle d'Aosta	1.00
Lombardia	1.00
Alto Adige (Bolzano)	1.46
Trentino	2.78
Veneto	1.76
Friuli - Venezia Giulia	2.56
Liguria	3.86
Emilia Romagna	1.00
Toscana	1.18
Umbria	2.75
Marche	2.18
Lazio	1.80
Abruzzo	1.91
Molise	1.26
Campania	1.77
Puglia	2.52
Basilicata	1.00
Calabria	1.00
Sicilia	1.00
Sardegna	1.00
Italia	1.57

- b. fires, burnt area from Forest service statistics, assigned to forest inventory typologies proportionally to their area. The growing stock loss caused by forest fires is estimated based on the average growing stock per hectare. The methodology used for emission estimates due to forest fires is described in Annex 12.
- c. mortality, an average constant ratio of mortality to total growing stock (Federici et al, 2008) estimated by expert judgement for evergreen (1.16%) and deciduous (1.17%) forests;
- 4) for protective forest (i.e., rupicolous and riparian forests) only, an average constant ratio of 3% (expert judgement - Federici et al., 2008) of C stock losses associated with drain and grazing. Starting from 1986, for each year, the final growing stock per hectare [$m^3 ha^{-1}$] is computed adding to the final growing stock volume of the previous year the increment calculated for the current year and subtracting the losses occurred in the year as due to harvest, fires and mortality.

The procedure can be summarized as follows:

$$v_i = \frac{V_{i-1} + I_i - H_i - F_i - M_i - D_i}{A_i}$$

where:

$$I_i = f(v_{i-1}) \cdot A_{i-1};$$

v_i is the volume per hectare of growing stock for the current year;

V_{i-1} is the total previous year growing stock volume;

I_i is the total current increment of growing stock for the current year;

H_i is the total amount of harvested growing stock for the current year;

F_i is the total amount of burned growing stock for the current year;
 M_i is the annual rate of mortality;
 D is the annual rate of drain and grazing for the protective forest;
 A_i is the total area referred to a specific forest typology for the current year;
 v_{i-1} is the previous year growing stock volume per hectare;
 A_{i-1} is the total area referred to a specific forest typology for the previous year;
 f is the Richard function reported above.

The annual current increment is estimated through the use of a non-linear function, the Richards function, that has the growing stock as its independent variable. The Richards' 4 parameters allow the flexibility needed to represent the various potential growth rates, including the initial, nearly constant, rate. To calculate the 4 parameters for each forest inventory typology the Richards function has been fitted through the data of growing stock [$\text{m}^3 \text{ ha}^{-1}$] and increment [$\text{m}^3 \text{ ha}^{-1} \text{ yr}^{-1}$] obtained from the collection of Italian yield tables.

$$y = a \cdot \left[1 \pm e^{(\beta - kt)} \right]^{-\frac{1}{v}} \quad (\text{Richards function})$$

The per hectare growing stock (i.e. the biomass density of the stand) is the independent variable x , while the dependent variable y is the increment computed with the Richards function - first derivative.

$$\frac{dy}{dt} = \frac{k}{v} \cdot y \cdot \left[1 - \left(\frac{y}{a} \right)^v \right] + y_0 \quad (\text{Richards function - first derivative})$$

where the general constraint for the parameters are the following:



$$a, k > 0 \quad -1 \leq v \leq \infty \text{ and } v \neq 0$$

The constant y_0 is the growing stock volume at 1-year age.


The Richards function, first derivative, has been fitted against data taken from all quality classes of each yield table (figure A11.2), to calculate a set of variables' values for each forest inventory typology.

The curves have been derived from a collection of around 100 Italian yield tables


Figure A11.2: For-est model fitting



A12.2a Trentino, *larches*



A12.2b Lombardia, *norway spruce*



A12.2c Piemonte, *other conifers*

A12.2d Campania, *European beech*

The per hectare growing stock and associated gain and losses are converted into aboveground biomass stock applying the following equation:

$$\text{Aboveground tree biomass (d.m.)} = GS \cdot BEF \cdot WBD \cdot A$$

where:

GS = volume of growing stock (MAF/ISAF, 1988) [$\text{m}^3 \text{ha}^{-1}$] of specific forest inventory typology;

BEF = Biomass Expansion Factors which expands growing stock volume to volume of aboveground woody biomass (ISAF, 2004);

WBD = Wood Basic Density for conversions from fresh volume to dry weight (d.m.) [t m^{-3}] (Giordano, 1980);

A = forest area of specific forest inventory typology [ha].

The BEFs and WBDs have been estimated for each forest inventory typology and are reported in following Table A11.4.

Table A11.4 Biomass Expansion Factors and Wood Basic Densities

Inventory typology		BEF <i>aboveground biomass / growing stock</i>	WBD <i>Dry weight t/ fresh volume</i>
Stands	norway spruce	1.29	0.38
	silver fir	1.34	0.38
	larches	1.22	0.56
	mountain pines	1.33	0.47
	mediterranean pines	1.53	0.53
	other conifers	1.37	0.43
	european beech	1.36	0.61
	turkey oak	1.45	0.69
	other oaks	1.42	0.67
	other broadleaves	1.47	0.53
Coppices	european beech	1.36	0.61
	sweet chestnut	1.33	0.49
	hornbeams	1.28	0.66
	other oaks	1.39	0.65
	turkey oak	1.23	0.69
	evergreen oaks	1.45	0.72
	other broadleaves	1.53	0.53
	conifers	1.38	0.43
	eucalyptuses coppices	1.33	0.54
	other broadleaves coppices	1.45	0.53
Plantations	poplars stands	1.24	0.29
	other broadleaves stands	1.53	0.53
	conifers stands	1.41	0.43
	others	1.46	0.48
Protective	rupicolous forest	1.44	0.52
	riparian forest	1.39	0.41

Applying a Root/Shoot ratio (R) to the aboveground volume and the same WBDs the belowground biomass is derived for each forest inventory typology. The Rs have been estimated for each forest inventory typology and are reported in Table A11.5. Data on root to shoot ratios have been taken from the following European projects: CANIF⁶⁸ (*Carbon and Nitrogen cycling in Forest ecosystems*), CARBODATA⁶⁹ (*Carbon Balance Estimates and Resource Management - Support with Data from Project Networks Implemented at European Continental Scale*), CARBOINVENT⁷⁰ (*Multi-source inventory methods for quantifying carbon stocks and stock changes in European forests*) and COST⁷¹ Action E21- Contribution of forests and forestry to mitigate greenhouse effects.

$$\text{Belowground tree biomass (d.m.)} = \text{Aboveground tree biomass} \cdot R$$

where:

R = Root/Shoot ratio dimensionless of each specific forest inventory typology.

⁶⁸ CANIF-*Carbon and Nitrogen cycling in Forest ecosystems* http://www.bgc-jena.mpg.de/bgc-processes/research/Schulze_Euro_CANIF.html; Scarascia Mugnozza G., Bauer G., Persson H., Matteucci G., Masci A. (2000). Tree biomass, growth and nutrient pools. In: Schulze E.-D. (edit.) *Carbon and Nitrogen Cycling in European forest Ecosystems*, Ecological Studies 142, Springer Verlag, Heidelberg. Pp. 49-62. ISBN 3-540-67239-7

⁶⁹ CARBODATA - Carbon Balance Estimates and Resource Management - Support with Data from Project Networks Implemented at European Continental Scale: http://afoludata.jrc.it/carbodatat/proj_desc.html

⁷⁰ CARBOINVENT - Multi-source inventory methods for quantifying carbon stocks and stock changes in European forests; <http://www.joanneum.at/carboinvent/>

⁷¹ COST Action E21 - Contribution of forests and forestry to mitigate greenhouse effects: http://www.cost.eu/domains_actions/fps/Actions/E21; http://www.afs-journal.org/index.php?option=com_article&access=standard&Itemid=129&url=/articles/forest/pdf/2005/08/F62800f.pdf

Table A11.5 Root/Shoot ratio and Wood Basic Densities

Inventory typology		R Root/shoot ratio
Stands	norway spruce	0.29
	silver fir	0.28
	Larches	0.29
	mountain pines	0.36
	mediterranean pines	0.33
	other conifers	0.29
	european beech	0.20
	turkey oak	0.24
	other oaks	0.20
	other broadleaves	0.24
Coppices	european beech	0.20
	sweet chestnut	0.28
	Hornbeams	0.26
	other oaks	0.20
	turkey oak	0.24
	evergreen oaks	1.00
	other broadleaves	0.24
	Conifers	0.29
Plantations	eucalyptuses coppices	0.43
	other broadleaves coppices	0.24
	poplars stands	0.21
	other broadleaves stands	0.24
	conifers stands	0.29
	others	0.28
Protective	rupicolous forest	0.42
	riparian forest	0.23

The biomass stocks and stock changes are converted to carbon units by applying the IPCC default carbon fraction (CF) value of 0.47 t C (t d.m.)⁻¹.

Following the recommendation raised in the framework of the 2025 Comprehensive review of Member States greenhouse gas inventories under the Governance Regulation 2018/1999 and the LULUCF Regulation 2018/841, the estimate of carbon stock changes from dead organic matter and litter pools have been significantly modified. Litter pool, for forest land remaining forest land, has been assumed to be in equilibrium, applying the IPCC default methodology. The litter carbon stock changes have been estimated for land converted to forest land based on the default litter stocks from the 2006 IPCC Guidelines used to derive a weighted average stock (i.e., 2.67 t C ha⁻¹) and the 2006 IPCC equation 2.23.

The annual deadwood carbon stock changes have been calculated using a decay model based on the harvest wood product methodology (IPCC 2006, chapter 12, Eq. 12.1), as described in equations 6.1. The deadwood model reflects the impacts of C inflows from harvest residues, mortality and fires on forest deadwood dynamics. The resulting deadwood stock and stock changes are consistent with the measured stocks derived from the Italian NFI.

Equation 6.1

$$DW_{i+1} = (e^{-k} * DW_i) + \frac{1 - e^{-k}}{k} * DW\_Inflow_i$$

$$DW\_Inflow_i = DW\_mortality + Harvest\_inflow + Fire\_biomass$$

$$\Delta DW_i = DW_{i+1} - DW_i$$

where

i = year

DW_i = deadwood carbon stock in the beginning of year i , kt C

k = decay constant of first order

$DW_{mortality}$ = input to deadwood pool from tree mortality, kt C

$Harvest_{inflow}$ = input to deadwood pool from harvest, kt C

$Fire_{biomass}$ = input to the deadwood from biomass killed but not fully combusted during fire, kt C.

$DW_{mortality}$ has been estimated by dividing the tree mortality by an average national BEF (Table A11.6). The $Harvest_{inflow}$ has been estimated by multiplying the harvest residues for the average national wood basic density (Table A11.6) and the carbon ratio 0.47 g C/g d.m. (IPCC, 2006). $Fire_{biomass}$ has been estimated by applying the complement of a mean national combustion factor to the total carbon stock affected by fire and dividing the result by the BEF, included in Table 6.7. The combustion factor, derived from the For-Fires model, indicates the share of biomass fully burned, while its complement represents the portion affected but not combusted. Dividing by the BEF isolates the fraction of killed biomass attributable to stems and large branches, which is the component that can realistically become deadwood. Biomass gains and losses have been calculated with the model For-est, while harvest residue inputs were derived from the annual harvest volumes, as documented before.

In Table A11.6, the abovementioned factors and parameters, used in the estimation of deadwood carbon stock changes, are reported.

Table A11.6 Factors and parameters used to estimate deadwood carbon stock changes

Factor	Value	unit	Source
Mortality per standing biomass	0.0116	fraction of standing biomass per year	2003 IPCC GPGs for LULUCF - Page 3.37, table 3.2.2 Biome: Evergreen Forest
BEF	1.4	ratio of volume	Average of national BEFs reported in Table A11.4, Annex 11
Wood Basic Density	0.523	t m ³	Average of national wood basic densities reported in Table A11.4, Annex 11
Harvest residue	0.05	ratio of harvest	Expert judgment
C ratio	0.47	g C/g d.m.	IPCC 2006
Complement of combustion factor	0.336250314	ratio of biomass	For-fires model (linked to revised estimate of mean combustion factor)
k	0.159966167	t C ha ⁻¹	Country specific value, estimated from NFIs values

ANNEX 12: FOR-FIRES MODEL

For-fires is a bookkeeping model that calculates the non-CO₂ emissions from fires affecting forest categories. The model is based on the approach developed by Bovio (2007); to this aim, the template used by Carabinieri Force⁷², for each forest event, was modified in 2007 to collect the data needed to implement this approach.

A12.1 Method description

For-fires model is based on the on the equation 2.27 of the 2006 IPCC Guidelines (vol. 4, ch. 2):

$$L_{fire} = A \times M_B \times C_f \times G_{ef} \times 10^{-3}$$

where

L_{fire} amount of greenhouse gas emissions released from fire;

A burned area (hectares - ha);

M_B mass of fuel available for combustion (t ha⁻¹);

C_f combustion factor (dimensionless);

G_{ef} emission factors (g kg⁻¹ dry matter burnt).

Both living biomass and dead organic matter (deadwood and litter) are included in the mass of fuel available (M_B) term. Biomass and dead organic matter values for each region and forest typology are derived from the 2nd and 3rd National Forest Inventories (NFI 2005 and NFI 2015). Data from NFI 2015 are used for years from 2019 onward, as its field phase was completed in that year. Any missing (e.g., biomass and dead organic matter in temporarily unstocked forests, and carbon stock in litter) data from NFI 2015 were assumed to be the same as those estimated in NFI 2005.

Since NFI 2005 and NFI 2015 do not disaggregate deadwood and litter mass (or carbon stock) by forest management practice (stands and coppices), the values from the general forest category were assigned to both management types where necessary. A similar issue arose with NFI 2015 living biomass volume. To address this, the proportions of stands and coppices volumes to that of the general forest category were derived from NFI 2005 and then applied to the NFI 2015 volume of each general forest category per region.

The key driver for fires emissions release is the assessment of the burned and oxidized mass in each fire event. The combustion factor (C_f) term is the most critical to be estimated, representing the fraction of pre-disturbance mass that is combusted during the fire event. Its estimation has been carried out based on the abovementioned approach, which assess forest fire damage in Italy, considering two main elements: the burned forest typology, and the fire intensity (assessed through the scorch height).

The approach groups the forest typologies into 9 forest vegetation classes considering the possible effect that a fire event can have on them because of specific forest characteristics and their distribution over the country (Table A12.1).

⁷² the Armed Forces and Police Authority where the State Forestry Service is embedded, following the legislative decree 19/08/2016, n. 177

Table A12.1: Bovio (2007) forest vegetation classes and forest typologies: correspondence matrix

Forest vegetation class	forest typology
A	european beech stands
	sweet chestnut stands
	hornbeam stands
	riparian forests
	other broadleaves
B	turkey oak stands
	other oak stands
	evergreen oak stands
	cork oaks
C	Larches
	norway spruce
	silver fir
	mountain pines above 500 m a.s.l.
	black pine above 500 m a.s.l.
D	mountain pines below 500 m asl
	black pine below 500 m asl
	mediterranean pines
	other conifers
E	european beech coppices
	sweet chestnut coppices
F	turkey oak coppices
	other oak coppices
	evergreen oak coppices
	hornbeam coppices
G	other broadleaves with a mean height lower than 3.5m (temporary unstocked broadleaves forests)
H	other conifers with a mean height than 3.5m (temporary unstocked conifer forests)

Bovio (2007) assumed that, in each forest vegetation class, the damage level depends on the fire intensity, which, in turn, can be estimated as a function of scorch height. In table A12.2, the damage level as a function of scorch height (and fire intensity), for each forest vegetation class, is shown.

Table A12.2: Damage level of forest typologies as a function of fire intensity and forest vegetation class

Forest vegetation class	Scorch height (m)				
	<1	1-2.5	2.5-3.5	3.5-4.5	>4.5
A	0.10	0.15	0.30	0.60	0.90*
B	0.08	0.20	0.30	0.80	0.90
C	0.10	0.25	0.50	0.80	0.90
D	0.08	0.30	0.55	0.85	0.95
E	0.05	0.15	0.40	0.65	0.90*
F	0.05	0.20	0.35	0.60	0.95
G	0.30	0.70	0.80	0.90	1.00
H	0.25	0.40	0.70	0.90*	1.00*

* values not included in Bovio (2007); they have been assumed based on the damage levels assigned to the other forest vegetation classes for the corresponding scorch height categories

A12.2 Activity data

The activity data needed to estimate the annual loss of mass (burned) caused by forest fires are:


- year;
- burned area [ha];
- forest typology (26 NFI typologies) to assess the available combustion fuel and the combustion factor;
- mean scorch height [m] to assess the combustion factor.

A detailed database, annually provided by Carabinieri Force, has been used; the database collects data, from 2008 onward, related to any fire event occurred in 15 administrative Italian regions⁷³ (the 5 autonomous regions are not included), reporting, for each fire event, the following information:

- *year*;
- *administrative region name*;
- *burned area [ha]*;
- *forest typology (26 classes in line with the NFI nomenclature)*;
- *scorch height [m]*;
- *fire's type (e.g., crown, surface or ground fire)*.

The database was checked to select only the observations with known scorch height (and corresponding damage level), and the assignation of the fire event to a forest category that does exist in the corresponding region according to the NFI⁷⁴. For these observations, the burned biomass per hectare is estimated according to the logical pathway summarized in Figure A12.1.

Figure A12.1: Logical pathway to estimate the burned biomass on hectare basis caused by forest fires



The same approach is applied to estimate burned dead organic matter; however, there is no evidence that crown fires have a significant impact on this carbon pool. As a result, the combustion factor (C_f) for dead organic matter in crown fire events is assumed to be zero.

Data and information on fire occurrences in the 5 remaining autonomous regions are collected at regional level, with different level of disaggregation and details.

For the period 1990-2007, national statistics on areas affected by fire per region and aggregated forest types are available for (ISTAT, several years [a]). The aggregated forest types are stand (conifers, broadleaves, mixed) and coppice (simple, compound and degraded).

Therefore, the data used in the estimation process may be subdivided into the following groups with similar characteristics:

- a. time series from 2008 onward for the 15 Regions: data related to burned area, divided into different forest types, scorch height and fire's type;
- b. time series from 2008 onward for the 5 autonomous regions/provinces: data related to burned area;
- c. time series from 1990 to 2007 for the 20 Italian regions: data related to burned area.

A12.3 Methodological issues

Based on three different datasets identified in the previous section A12.2, different approaches and assumptions have been followed to estimate non-CO₂ emissions from fires.

⁷⁴ It is possible that some forest categories have been erroneously assigned to a specific administrative region because of problems in the forest identification on the field (e.g. due to the important damage caused by the fire event).

available. This choice, i.e., use of 2008-2016 data to deduce average values, estimation is due to the fact that:

- the year 2017 was not included in the dataset because the 2017 was not representative, since it was characterized by an extremely dry summer period, in which the overall surface covered by fires was anomalous compared to the past (on average +263% over the period 1990-2016) and in which the damage caused by the fires themselves was significantly more important than in the previous period (2008-2016);
- a possible annual extension of this period from 2008 to the last reported year constantly affects the gap-filling procedure causing annually recalculations of the relative GHG emissions along the whole time-series.

Finally, it has to be noted that the average values, instead of the maximum average ones, have been applied to implement the gap-filling procedure, addressing the 2019 UNFCCC review process's recommendation. Finally, the total burned mass is estimated multiplying the burned (lost) mass per hectare by the burned area of the corresponding fire event.

b. Time series from 2008 onward for the 5 autonomous regions/provinces

The emissions from fires have been estimated based on the average values assessed for the 15 regions from 2008 on. The burnt mass per hectare for fires has been estimated by applying the above-described gap filling procedure. The implementation consists in the following:

- clustering the 15 regions (those considered in the full dataset 2008-2016) into three groups with similar climatic conditions and forest types (Northern, Central and Southern Italy);
- estimating, for each cluster, the burnt mass per hectare as the mean of burnt volume per hectare of the related regions;
- classifying the 5 autonomous regions based on the clusters identified at step A;
- assigning to each of the 5 autonomous regions the burnt mass per hectare of the corresponding cluster estimated at step B.

Finally, the total burned mass is estimated multiplying the estimated burned (lost) mass per hectare by the total annual burned area for each year of the time-series (1990-2024), a datum that is available from ISTAT (several years [a]), regional websites and direct contacts with regional forestry corps⁷⁵.

c. Time series from 1990 to 2007 for the 20 Italian regions

The emissions from fires for the period 1990-2007 for the 20 Italian regions have been estimated based on the average values computed among 2008 and 2016, considering the fire's type and each region. The average values, instead of the maximum average values adopted in the previous submissions, have been implemented to address the 2019 UNFCCC review process's recommendation. The selected value of released carbon is then multiplied by the burned area of the region in each year from 1990 to 2007.

CH₄, N₂O, CO and NO_x have been estimated following the IPCC 2006 methodology (eq. 2.27, vol. 4, ch. 2), multiplying the burned mass, estimated as described above, by the 2006 IPCC Table 2.5 (IPCC, 2006) emission factors related to extra tropical forest category, as shown in table A12.3; in the same table emission ratios for NMVOC, NH₃ and SO₂ also reported (as described in the EMEP/EEA Guidebook 2023, chapter 11.B, Table 3-3 (EMEP/EEA, 2023)).

⁷⁵ Alto Adige (<https://www.provincia.bz.it/agricoltura-foreste/servizio-forestale-forestali/autorizzazioni-controlli/statistica-incendi-boschivi.asp>); Friuli – Venezia Giulia (<https://eagle.fvg.regione.fvg.it/eagle/main.aspx?configuration=guest>); Sardegna (https://www.sardegnageoportale.it/webgis2/sardegna-mappe/?map=aree_tutela); Sicilia (data shared by the regional forest corp upon specific request); Trento (https://siat.provincia.tn.it/geonetwork/srv/ita/catalog.search#/metadata/p_TN:04856367-56db-4f44-bb06-09bf75ad8689); Valle d'Aosta (<https://mappe.partout.it/pub/GeoNavSCT/?metadato=MTD34N2204>)

Table A12.3: CO, CH₄, NMVOC, NO_x, NH₃, N₂O, SO₂ emission factors

Pollutant/GHG	emission factor / emission ratio	unit	reference
CO	107	<i>g X/kg dry matter burned</i>	IPCC 2006 (Table 2.5)
CH₄	4.7	<i>g X/kg dry matter burned</i>	IPCC 2006 (Table 2.5)
NMVOC	21	<i>g X/kg C emitted as CO₂</i>	EMEP/EEA 2023 (Table 3-3)
NO_x	3.0	<i>g X/kg dry matter burned</i>	IPCC 2006 (Table 2.5)
NH₃	1.8	<i>g X/kg C emitted as CO₂</i>	EMEP/EEA 2023 (Table 3-3)
N₂O	0.26	<i>g X/kg dry matter burned</i>	IPCC 2006 (Table 2.5)
SO₂	1.6	<i>g X/kg C emitted as CO₂</i>	EMEP/EEA 2023 (Table 3-3)

PM₁₀, PM_{2.5}, dioxin, and polycyclic aromatic hydrocarbon (PAH) emissions have been also estimated, by multiplying the burnt mass (dry matter) by the emission factors reported in table A12.4. For black carbon, emissions have been estimated considering a percentage, i.e., 9%, of the PM_{2.5} emissions, in line with the EMEP/EEA Guidebook 2023, chapter 5.C.2, Table 3-5 (for temperate forest).

Table A12.4: PM₁₀, PM_{2.5}, dioxin, and polycyclic aromatic hydrocarbon (PAH) emission factors

pollutant	emission factor	unit	reference
PM₁₀	11	<i>g X/kg dry matter burned</i>	EMEP/EEA 2023 (Table 3-5)
PM_{2.5}	9	<i>g X/kg dry matter burned</i>	EMEP/EEA 2023 (Table 3-5)
Dioxin	10	<i>ng C/kg C</i>	EMEP/EEA 2023 (Table 3-1)
PAH	14.75	<i>g/t</i>	EMEP/EEA 2023 (Table 3-2)

